



May 30, 2025

Mr. Shane Phelps
State of North Carolina
Department of Insurance
Manufactured Building Division
1202 Mail Service Center
Raleigh, NC 27699-1202

RE: Cavco-Crouse
Model: 2025-1006204-NC

Mr. Shane Phelps:

Enclosed, you will find one (1) copy of the project mentioned above for your files.

Please get in touch with me at your earliest convenience if you have any questions or comments.

Sincerely,

Kip Whitehead

Kip Whitehead
Account Manager
ICC NTA, LLC

Adopted Codes: State of North Carolina

2018 North Carolina Residential Code
2017 North Carolina Electrical Code (2017 NEC)
2018 North Carolina Energy Conservation Code
2018 North Carolina Mechanical Code
2018 North Carolina Plumbing Code
2018 North Carolina Fuel Gas Code

Project Location:

461 MCNEILL ROAD
BROADWAY, NC 27505
HARNETT County

Occupancy:

Occupancy:IRC - Single Family Dwelling
Construction Type:5B (Wood Frame - Unprotected)
Number of Stories:One Story Cape

Design Load:

Floor Area 2280 Sq.Ft
 Ground Snow Load 20 psf
 Top Chord Dead Load 10 psf
 Ultimate Wind Speed 120 mph
 Seismic Design Category B
 Floor Live Load 40 psf
 Floor Dead Load 10 psf
 Bottom Chord Live Load: See Truss Diagram
 Wind Exposure Category: B
 IFCC Geographical Code: 4A

Insulation


Reference RESCheck for Requirements.

Attention Local Inspection Departments:

1. Set-up instructions for this modular unit are included by attachment to these plans. Any plans set that does not include an attachment entitled "MODULAR HOME INSTALLATION MANUAL," is incomplete.
2. The following items must be completed by the home manufacturer, are not inspected by in-factory third party inspectors, and are not certified by the modular compliance label: (A) Components or connections for heating or air conditioning systems which are NOT part of the factory compliance label. (C) Electrical service disconnect. (D) Foundation designs and attachments. In order to verify that all required systems connections are complete, refer to the "Inspection Check Sheet" in the manufacturer's modular home installation manual. Regardless of factory or site installation, the furnace, water heater, and all elements of heating system must be per applicable codes, (refer to ResCheck if applicable). (E) Furnace vented, HVAC completed on-site by others.
3. Site installed furnace must meet IECC Energy Efficiency Certificate if applicable.
4. This unit must be connected to a public water supply and sewer system if these are available.
5. If this structure is in a thermal zone more stringent than that listed on these plans, is set on pilings, or is installed at a mountain region or coastal high hazard site such that wind or other design parameters are increased, the design must be determined to be adequate for actual site conditions. Alterations may be required to bring the home into compliance with the more stringent conditions.
6. Soffit materials for this unit assume that the building face will be 10 feet or greater from the property line when installed on site. Where the building face is less than 10 feet from the property line, underlayment materials and ventilation in accordance with Section R302.1.1, NC Residential Code, must be provided and installed at the site and inspected by the local jurisdiction.
7. If after installation of this home, the lowest part of the clear opening of any window is more than 72" above the finished grade, guards will be required to be installed onsite in accordance with Section R312; subject to local inspection.
8. Partial plumbing installation (subbed in) requires full DWV testing in field. Testing of factory portion of DWV is not required unless partial testing is mandated by code.
9. Smoke detectors required by code that are not shown on the plan will be site installed by others and are subject to inspection by the authority having jurisdiction.
- Where required, window protection designed and provided on site by others to meet applicable local codes.

Drawing Index

Title	Page
Cover	CV
Floor Plan	FP
Proposed Cape Floor Plan	PCFP
Electrical Plan	EP
Schedules and General Notes	NG
Elevations	EL
Cross Section	XS
Hot Water Lines	WH
Cold Water Lines	WC
DWV System	DL
DWV Notes	DN
Supply Air Ducts - Perimeter Registers	SP
Ceiling Return Air System	HR
Braced Walls-Prescriptive	BWP
Foundation 2x10 Marriage Line without Stair	FD20#
Manual J Calculations	ATTACHED
ResCheck	ATTACHED
UPF Rigid Collar Tie Connection Details	UPF-EB05-02
Truss Diagram	ATTACHED



Plan: 2025-1006204

Customer: Griffin

Builder: NC Custom Mods

Manufacturer:

530 Cayco-Crouse

235 Anthony Grove Rd.

Crouse, NC 28033

APPROVED BY
NTA
Approval of this document does not authorize
approval or disapproval of deviations from the
requirements of applicable State Laws
K. M. Whiteland


Note: Window fall protection must be provided on-site where required in accordance with applicable code.

Smoke detectors required by code, that are not shown on the plan, must be site installed by others and are subject to inspection by the authority having jurisdiction.

Note:

* LVLs noted must extend past column on at least one end 24" minimum and be overlaid with OSB sheathing.

NOTES: 30' 12/12 cape



Proposed Second Floor:
All design materials and work to be the responsibility of the builders on site to local codes. Light, vent, egress, heating and plumbing are the responsibility of the builder.

Area: 1363 sq. ft.

Notes:

1. Exterior opening headers and jack studs are SPF #2 unless otherwise noted.
2. Sidelwall headers may use alternate construction per section B-10 of Systems Manual.
3. LVL's where specified to be minimum of 1 1/2" wide, M.O.E. = 2.0 and fb = 2900 PSI.
4. See C-10-45 for stair opening framing.
5. See C-10-105 for dormer opening framing.

See Schedules and General Notes Page

Column Support Location

Attic Access

Buildings: 530 Cayton-Cruise

The Proposed Cape Floor Plan

APPROVED BY


Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Engineer seal applies ONLY to FACTORY MANUFACTURED portions of the building. Seal does not apply to site installed elements or portions built on site such as, but not limited to, foundations, connections to foundation, exterior steps, smoke detectors, or other site works. Site work must be designed BY OTHERS for safe conditions, under local jurisdiction. COMPLIANCE WITH ALL APPLICABLE CODES PER LOCAL AUTHORITY. MAKE A RECORDATION DRAWING INSTALLED IN THIS SET OR NOT, MAKE A SET.

Scale	DATE	Cust: Griffin	Number	Order/Plan Number
3/16" = 1'-0"	05/27/2025	DR: NC Custom Molds	32763B	2025-1006204
By	Plumber/Arch	Pos.	PCPD	Run:
	1022023.V			

Address	235 Anthony Grove Rd Crouse, NC 28033	Revised	
		Drawn	SAJ

5. See C-10-105 for dormer opening framing.



APPROVED BY
NIA
 5/30/2025
 Approval of the document does not authorize or
 constitute a warranty or representation of the
 requirements of applicable State Laws
 Kip Whitehead

See Schedules and General Notes Page

Builder: 530 Cavco-Crouse


Title: Electrical Plan

Address: 235 Anthony Grove Rd. CROSS, NC 28033	Drawn By: SM	Scale: 3/16" = 1'-0"	DATE: 05/29/2025	Customer: Cavco-Griffin	Product Code: D9	Order Plan Number: 2025-1006204
	Reference: RZ2025-V			For: MC Custom Models		
				SN: 44874		


120000-020200-020200

Note: Window fall protection must be provided on-site where required in accordance with applicable code.

THE ELEVATIONS SHOWN ON THIS PAGE REPRESENT BASIC COMPONENTS AND ARE NOT INTENDED TO BE ALL INCLUSIVE, NOR DO THESE ELEVATIONS DETAIL EVERY CODE REQUIRED ASPECT OF THIS BUILDING. SITE BUILT STAIRS, STOPS, STEPS, DECKS, PORCHES, HANDRAILS AND/OR SIMILAR ITEMS MUST BE PROVIDED BY OTHERS ON SITE FOR COMPLIANCE WITH APPLICABLE CODES. COMPLIANCE WITH ALL APPLICABLE CODES PER LOCAL AUTHORITY HAVING JURISDICTION, WHETHER DETAILED IN THIS SET OR NOT, MUST BE MET.



FRONT VIEW



REAR VIEW

- NOTES:**
FOUNDATION SHALL BE DESIGNED AND CONSTRUCTED BY OTHERS WHERE "OTHERS" REFERS TO THE DEALER BUILDER.
GUTTERS AND LEADERS SHALL BE INSTALLED BY OTHERS.
TYPICAL 12" OR 15" VINYL SHUTTERS PROVIDED BY MANUFACTURERS.
ALL FOOTINGS, RAILINGS AND STEPS SHALL BE FIELD INSTALLED IN COMPLIANCE WITH APPLICABLE STATE AND LOCAL CODES.
SIDING SHALL BE VINYL SIDING WITH VINYL TRIM, AND MAY BE PARTIALLY INSTALLED ON SITE.
EXTERIOR LIGHTS MAY BE SHIPPED LOOSE FOR INSTALLATION ON SITE.
ROOFING SHINGLES MAY BE PARTIALLY SITE INSTALLED.
PORCH RAILINGS ARE PVC. TREATED LUMBER PORCH POSTS MAY BE COVERED WITH VINYL PORCH DECKING SHALL BE TREATED.
ALL EXTERIOR COVERINGS SHALL BE WEATHER AND DECAY RESISTIVE TO PROVIDE PROPER PROTECTION FOR UNTREATED MATERIALS.

APPROVED BY

NTA

Approval of this document does not authorize
repetitive any deviation or deviations from the
requirements of applicable State Laws

5/30/2025

Kim Whitehead

NOTE: HOMES WITH ATTIC SPACE QUALIFYING AS HABITABLE, MUST BE EQUIPPED WITH EMERGENCY ESCAPE AND RESCUE OPENINGS REGARDLESS OF WHETHER ATTIC AREA IS FINISHED OR UNFINISHED. OPENINGS MAY OCCUR AT END WALL OF ATTIC AND/OR AT ROOF DORMERS IN WHATEVER ARRANGEMENT NECESSARY TO INSURE THAT ANY SLEEPING ROOM HAS AT LEAST ONE EGRESS OPENING.

Order/Rate Number		2025-1006204	
Member		32763B	
Prod Code		D9	
Society		Cauc Griffin	
NLS		Dr NC Custom Mops	
References		S/N 66894	
Bearing		107703-AY	
Bearing By		SN	
Address		235 Anthony Grove Rd Crouse, NC 28033	
Number: 530 Cayco-Crouse Date: Elevations			

LEGEND

- 1 JACK POST, PIER OR CONCRETE FILLED POST THAT MEETS OR EXCEEDS REQUIRED SUPPORT CAPACITY PER FOUNDATION DESIGN.
- 2 EXTERIOR WALL INSULATION (SEE INSULATION R-VALUES).
- 3 2x6 #3 SPF EXTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
- 4 2x6 #3 SPF SIDEWALL BOTTOM PLATE
- 5 7/16" RATED SHEATHING.
- 6 VINYL OR HARDBOARD SIDING (RAIN VERT. OR HORIZ.) INSTALLED PER MFG.'S INSTRUCTIONS.
- 7 AIR INFILTRATION AND WATER RESISTANT BARRIER.
- 8 2x6 #3 SPF SINGLE OR DOUBLE TOP PLATE.
- 9 2x6 TREATED SILL PLATE. FASTENING OF SILL AND HOME TO FOUNDATION ON SITE PER CODES OR BY LOCAL ENGINEER WHEN APPLICABLE.
- 10 2x4 #3 SPF INTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
- 11 2x4 #3 SPF BOTTOM PLATE INTERIOR WALLS. TYP.
- 12 ENGINEERED TRUSSES SPACED TO MEET DESIGNED GROUND LOAD/SNOW LOAD.
- 13 VAPOR BARRIER.
- 14 CEILING BOARD 1/2" GIPSUM.
- 15 7/16" x 1/4" RATED ROOF DECKING MIN. TYP.
- 16 2x4 #3 SPF MIN. VERT. RAIL CONT. ON BOTH SECTIONS OVER MALE WALL. USE APPLICABLE BEAM OVER OPEN SPANS (TYP.) PER PGS C-10 OF SYSTEM DOCUMENT.
- 17 RIDGE VENT TYP. 50% VENTILATION OF ROOF CAVITY (UPPER PORTION). INSTALLED PER CODE REQUIREMENTS.

- 18 TYPICAL SHINGLES. INSTALLED PER MFG.'S INSTRUCTIONS.
- 19 SHINGLE UNDERLAMENT TYP.
- 20 JOIST HANGERS AT WALL LINES.
- 21 7" MIN. SPACE FOR ATTIC VENTILATION.
- 22 TYPICAL ICE BARRIER PER SECTION 905 OF APPLICABLE CODE.
- 23 CEILING INSULATION TYP. (SEE INSULATION R-VALUES).
- 24 2x3/8" (0.53) BOARD DECKING.
- 25 ALUM. VINYL OR HARD BOARD FASCIA AND Drip EDGE.
- 26 FLOOR CAVITY OR PERIMETER WALL MUST BE INSULATED ON SITE OR AT THE FACTORY (SEE "INSULATION R-VALUES")

- 27 PERIMETER DOW JOIST MUST BE INSULATED TO R-VALUE LISTED FOR EXTERIOR WALLS
- 28 INSULATION INSTALLED ON SITE BY OTHERS PER THERMAL REQUIREMENTS AND/OR STATE AND LOCAL CODES

- 29 VENTED SPLIT 50% OF LOWER ROOF VENTILATION.
- 30 Baffle REQUIRED
- 31 DRIFT BLOCKER
- 32 VAPOR RETARDER (AS REQUIRED PER CLIMATE ZONE).
- 33 FLOOR DECKING RATED FOR 19.2" O.C. JOIST SPACING MAX
- 34 MIN. 2X10 #2 SPF FLOOR JOIST 16" O.C.
- 35 2x6 #3 SPF DOUBLE TOP PLATE
- 36 WALL COVERING (MIN. 1/2" GIPSUM).

IMPORTANT!

MAIN LEVEL FLOORS, OVER ENCLOSED FOUNDATIONS, CONSTRUCTED WITH OPTIONAL ENGINEERED WEB FLOOR JOISTS (OR WITH JOISTS OF NOMINAL LUMBER LESS THAN 2X10, MAY BE SUBJECT TO SPECIAL FIRE PROTECTIVE REQUIREMENTS TO BE PERFORMED BY OTHERS ON SITE. CONSULT ADAPTED LOCAL CODES FOR COMPLIANCE WITH FIRE PROTECTION OF FLOORS. REFERENCE THE APPROVED SYSTEMS PACKAGE FOR ADDITIONAL AND SPECIFIC CROSS SECTION INFORMATION

TRIMLINE RIDGE VENT: ALLOWS 13" OF NET FREE AIR PER LINEAL FOOT

FULL LENGTH OF HOUSE AIR FLOW SUFFICIENT: FULL VENTED 5.89 SQ IN PER LINEAL FOOT

FULL LENGTH OF HOUSE 2280/2100 = 7.60 VENT REQUIRED

Builder: 530 Cavco-Crouse


Title: Cross Section

Truss Data		
Truss #	Spacing	Side Wall Centerline
R30C12F	24"	127 1/2"
		903"

STUD O.C. SPACING
EXTERIOR WALL: 16"
INTERIOR WALL: 16"

INSULATION R-VALUES
CEILING: 44

CEILING (Between Knee Walls: 30
EXTERIOR WALLS (continuous): -
EXTERIOR WALLS (cavity): 21
FLOOR: 30
FOUNDATION WALLS (continuous): 0
FOUNDATION WALLS (cavity): 0



NOTES:
FOLLOW RECOMMENDED ATTACHMENTS FOR FASTENING OF HOME TO FOUNDATION.
FOUNDATIONS TO BE BUILT AND CONSTRUCTED BY OTHERS ON SITE.
FOUNDATIONS (BY OTHERS) MUST MEET ALL APPLICABLE CODES.
NOTES AND/OR ILLUSTRATIONS SHOWN ARE TYPICAL AND MAY NOT APPLY TO ALL HOMES CONSTRUCTED.
CONSTRUCTION & SPECIFICATIONS MAY VARY PER PLAN.
REFER TO INSTALLATION MANUAL FOR MODULE CONNECTIONS.
REFER TO INSTALLATION MANUAL AND TRUSS MFG. DIAGRAM FOR ROOF TRUSS BRACING.



Address: 235 Anthony Grove Rd. Cress, NC 28033	Revolution Drawn By: SM	Scale 1/4" = 1'-0"	Date/Revision 05/29/2025	Case/Detail For: NC Custom Molds	Prod. Code D9	Number: 32763B	Order/Plan Number: 2025-1006204	Page: XS
---	----------------------------	-----------------------	-----------------------------	-------------------------------------	------------------	-------------------	------------------------------------	-------------




ALL DIMENSIONS FROM REAR
AND MARRIAGE EDGE

- NOTE:
1. 3/4" GALVANIZED OR COPPER RELIEF DRAIN (NOT SHOWN) THRU FLOOR W/WHOLE AIR CAP
 2. INLET WITH 1" CAP & O-RING
 3. DIMENSIONS EXPRESSED IN PARENTHESES (A x B) INDICATE: (DIST. FROM REAR END OF HOME FLOOR x DIST. FROM HOME WATE LINE).
 4. ANTI-SCALD DEVICE ON ALL SHOWER, AND TUB SHOWER COMBINATIONS.
 5. WATER-HAMMER ARRESTORS AT BATTERY OF FIXTURES INSTALLED WHEREVER THERE IS A QUICK-CLOSING VALVE CORRESPONDING TO ASSE 800.6
 6. SHUT-OFF VALVE IS REQUIRED AT EACH FIXTURE
 7. BATHTUBS WITH DOUBLE LAYS ARE FED FROM THE SAME RISER
 8. ANY LINE NOT LABELED IS 1/2"
 9. WATER HEATER TEMPERATURE & PRESSURE RELIEF VALVE AND RELIEF DRAIN PIPE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 10. SHUT-OFF VALVE AT WATER HEATER IS FULL OPEN VALVE INSTALLED ON COLD WATER SUPPLY PIPE AT EACH WATER HEATER, PER CODE.
 11. FULLWAY SHUT-OFF VALVE WITH BLEED ORFEE INSTALLED AT MAIN INLET SERVICE VALVE INSTALLED ON-SITE PER CODE.
 12. SEE SYSTEMS PACKAGE PLUMBING SECTION PAGES FOR ADDITIONAL PLUMBING NOTES AND DETAILS

SITE NOTES FOR DIAGRAM EXPLANATION:

- A. WHEN VERTICAL EXPOSED WATER SUPPLY RISERS ONLY ARE SHOWN ON THIS PLAN, RISERS ONLY ARE FACTORY INSTALLED AS SHOWN AND TERMINATED BELOW THE FLOOR AT THE INDICATED LOCATIONS. MATERIAL PROVISIONS, SYSTEM CONNECTIONS, TESTING, AND INSPECTION FOR ALL BELOW-FLOOR CONNECTIONS ARE ON SITE BY OTHERS IN ACCORDANCE WITH ALL STATE AND LOCAL CODES.
- B. WHEN BELOW-FLOOR SYSTEM CONNECTIONS TO RISERS ARE SHOWN ON PLAN BY SOLID LINES, THESE ARE COMPLETED, TESTED, AND INSPECTED IN THE FACTORY TO THE TERMINATION POINT SHOWN ON ILLUSTRATED PLAN.
- C. DOTTED LINES ON PLAN (IF PRESENT), ARE INTENDED ONLY TO ILLUSTRATE TYPICAL ON-SITE CONNECTIONS. THESE ARE FOR ILLUSTRATION ONLY AND ARE NOT PROVIDED, INSTALLED, TESTED, OR INSPECTED BY THE FACTORY.
- D. ALL BELOW FLOOR WATER LINES MUST BE SIZED, INSTALLED, AND TESTED ON SITE PER APPLICABLE LOCAL AND STATE CODES.

ELECTRIC WATER HEATER-RHEEM MODEL #82V40-2
ELECTRIC WATER HEATER-RHEEM MODEL #82V52-2
ELECTRIC WATER HEATER-RHEEM MODEL #83VR52-2
GAS WATER HEATER-RHEEM MODEL #22V40FI
GAS WATER HEATER-RHEEM MODEL #22V50FI



ALL DIMENSIONS FROM REAR
AND MARRIAGE EDGE

HANGER SPACING - PEX PIPE (SUPPLY)	
MAX HORIZONTAL SPACING (FT.)	4'-0"
MAX VERTICAL SPACING (FT.)	4'-0"

Builder	\$30 Cavo-Crouse		Address	235 Anthony Grove Rd Crouse, NC 28033		Scale	CUSTOM	Date	05/29/2025	Client	Griffin	Project	D9	Product	WC	Order/Plan Number	2025-1006204
Title	Cold Water Lines		Revision	SM		Reference	R2203-Y	Drawn By	SM	For	NC Custom Made	Sheet	44894	Rev.			



PLUMBING ABOVE THE FLOOR IS FACTORY INSTALLED. PLUMBING BELOW THE FLOOR INCLUDING CONNECTIONS SHALL BE INSTALLED ON SITE BY OTHERS ACCORDING TO SITE CONDITIONS. SUBJECT TO APPROVAL OF LOCAL INSPECTION. ON SITE PLUMBING SHOWN IS SUGGESTIVE ONLY.



APPROVED BY

5/30/2025

OWN FITTING IDENTIFICATION	
XL TL	LONG TURN UP ELBOW
XL SL	LONG TURN UP STREET ELBOW
4SL	45° ELBOW
4SL	45° STREET ELBOW
27.5L	22.12° ELBOW
40SL	22.70° STREET ELBOW
	45 WYE
	45° WYE
	LONG RADIOSITY
	SANITARY TEE
	DOUBLE WYE ELBOW
	90° CLOSET ELBOW

HANGER SPACING - DRAIN PIPE (DWM)	
MAX HORIZONTAL SPACING (FT.)	VERTICAL SPACING
4'-0"	Vertical piping shall be supported at each story or floor level.

530 Cayco-Crouse

the DWV System

Revisions	Scale	Date	Cast Griffin	Prod. Code	Number	Order/Plan Number
	CUSTOM	05/29/2025	Dr: INC Custom Molds	D9	32763B	2025-1006204
Drawn By:	Reference:			Pg.	OL	Run:
SM	1R2703-V					

494

PIPE SUPPORT:

VERTICAL PIPING:

SUPPORTS AT 10' O.C. MAX.

FOR BETWEEN FLOOR LEVELS.
HORIZONTAL PIPING:

HORIZONTAL PIPING:
SUPPORTS AT 6' O.C. MAX.

ENDS OF BRANCHES, AND


AT CHANGES IN ELEVATION AND/OR DIRECTION

TRAP ARMS:

SUPPORT LOCATED AS

CLOSE TO TRAP AS POSSIBLE WHEN TRAP TO

POSSIBLE WHEN THAT TO
VENT EXCEEDS 3".



OPTIONAL GARBAGE DISPOSAL PLUMBING ILLINOIS
MODELS ONLY - USE DETAIL ABOVE FOR OPTIONAL
GARBAGE DISPOSAL

NOTES:

ALL BELOW FLOOR PLUMBING BY OTHERS. ALL FITTINGS BELOW BOTTOM CAN BE SHIPPED LOOSE.

ALL BELOW FLOOR PLUMBING ILLUSTRATIONS ARE RECOMMENDATIONS ONLY. ON-SITE CONDITIONS AND/OR RESTRICTIONS MAY REQUIRE SOME MODIFICATIONS.

OPT. GARBAGE DISPOSAL TO BE LOCATED ON KITCHEN SINK WASTE ASSEMBLY. ALL VENTS THRU ROOF TO BE 3" 1/2" MIN. ABOVE AND BELOW ROOF PENETRATION.

ALL P-TRAPS TO BE 1/2" UNLESS NOTED.

APPROVED BY


NTA

5/30/2025

Approval of this document does not authorize
approval or disapproval or deviations from the
requirements of Applicable State Laws

Kim Whitehead

[illegible]




**FURNACE AND HEAT DUCTS ARE
OMITTED AND WILL BE INSTALLED
ON-SITE BY OTHERS**

HVAC MUST BE INSTALLED BY LICENSED HVAC TECHNICIAN
TOTAL LENGTH OF 6" FLEX REQUIRED = 228'-0"



Builder:	530 Cavco-Crouse						Order Date:	2025-10-06
Address:	235 Anthony Grove Rd CROUSE, NC 28033						Sheet Code:	D9
Drawings:							Number:	32763B
Scales:	3/16" = 1'-0"						Rev:	NC Custom Mods
Drawn By:	SM						Rate Mod:	\$/K 44894
IR2023-V							Pg:	SP
Take Supply Air Ducts - Perimeter Registers								




Return Air Material/Quantity List	
Storage Box (13x13x9)	6
10x6 Ceiling Grille	6
8" Insulated Flex Duct 6"	6'
8" Start Collar	6
20x25 Wall Grille	2

RETURNS IN CEILING IN ADDITION TO AIR THRU GRILLES/OPENINGS



Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC, 28033	Scale: 3/16" = 1'-0"	DATE: 05/29/2025	Case: Griffin	Prod. Code: D9	Number: 32763B	Order/Plan Number: 2025-1006204
File: Ceiling Return Air System		Reference: RZ203-V	Drawn By: SM	For: NC Custom Mode		HR	Page: 13 of 36



VERTICAL BML 1	
REQUIRED	10.64
PROVIDED	22.00
MEETS REQ	YES
% SHEATHED	73%

NORC BRACED WALL CONSTRUCTION DETAILS	
WALL TYPE	CONSTRUCTION
EXTERIOR	7/16" SHEATHING ONE SIDE WITH 0.131 PD WALLS AT 6" O/C EDGE SPACING AND 12" O/C FIELD SPACING.

HORIZONTAL BML 1	
REQUIRED	4.42
PROVIDED	145.93
MEETS REQ	YES
% SHEATHED	64%

HORIZONTAL BML 2	
REQUIRED	4.42
PROVIDED	148.50
MEETS REQ	YES
% SHEATHED	63%

Braced Wall													
Unit	Method	Wind Load	Wind Load Method	Width	Length	Exposure	Roof Pitch	Sidewall Height	Seismic	Max. Mean Roof Height			
MAIN	2018 NC RC	120 mph	Ultimate	30'	76'	B	12/12	9'	B	IRC			

Bracing per prescriptive North Carolina 2018 Residential code.

In conjunction with the wall bracing requirements of Section 602.10, all exterior walls are sheathed with wood structural sheathing panels in accordance with 4506.2 for 140 to 150 MPH structural bracing.



FOUNDATION TIE-DOWN MUST BE CONNECTED ON-SITE BY POINT LOAD LOCATIONS AS NOTED (BY OTHERS).
ALTERNATIVE TIE DOWN CONNECTION METHODS APPROVED BY A LOCAL ENGINEER MAY BE USED. REFER TO THE IRC FOR FOUNDATION TIE DOWN REQUIREMENTS FOR 130 MPH OR LESS WIND ZONES

Factory Installed Hold-Down Device with a Minimum Uplift Design Value of 800 LB.

530 Cavco-Crouse		Braced Walls- Prescriptive	
Address	235 Anthony Grove Rd.	City	Crouse, NC 28033
Scale	0.014000	Drawn By	SM
Reference	102003-1	Check/Griffin	Dir. NC Custom Made
Product Code	D9	Number	32763B
Order/Plan Number	2025-1006204	Rev.	BWP

FOUNDATION SHOWN MUST BE DESIGNED BY OTHERS TO THE SITE CONDITIONS. THIS INCLUDES SEISMIC DESIGN AND ATTACHING THE HOME TO THE FOUNDATION, ALONG WITH RESISTANCE TO LATERAL, LONGITUDINAL, SHEAR, UPLIFT AND DOWNLIFT FORCES IN BOTH DIRECTIONS.

FOR CONNECTION OF THE HOME TO FOUNDATION AT BRACING WALLS, REFER TO "BRACED WALLS-CALCULATED" PAGE. IF APPLICABLE, WHEN THIS PAGE IS PRESENT, HORIZONTAL AND OVERTURNING (RACKING) LOADS AT BRACING WALL LOCATIONS ARE INDICATED FOR THESE FOUNDATION CONNECTIONS. THESE LOADS MAY BE RECALCULATED AND REDESIGNED PER LOCAL CODES TO CONFORM TO SITE CONDITIONS AS REQUIRED. REFER TO CHAPTER 3 (3.9 TIE DOWN TO FOUNDATION) OF THE "MODULAR HOME INSTALLATION MANUAL" FOR ADDITIONAL INFORMATION.
REFER TO APPLICABLE CODES FOR CONNECTION OF HOME TO FOUNDATION WHEN "BRACED WALLS-PREScriptive" PAGE IS APPLICABLE.

COLUMNS & FOOTINGS MUST BE RATED TO MEET THE CENTER LINE LOADS LISTED

Feeding Size (in.)	1200 PSF	2000 PSF	2500 PSF
4" x 6"	2.5K	3.4K	4.3K
6" x 8"	4.0K	5.2K	6.7K
8" x 10"	5.4K	7.1K	9.4K
10" x 12"	6.8K	9.1K	11.8K
12" x 14"	8.2K	11.1K	14.4K
14" x 16"	9.6K	13.1K	17.0K
16" x 18"	11.0K	15.1K	19.6K
18" x 20"	12.4K	17.1K	22.2K
20" x 22"	13.8K	19.1K	24.8K
22" x 24"	15.2K	21.1K	27.4K
24" x 26"	16.6K	23.1K	30.0K
26" x 28"	18.0K	25.1K	32.6K
28" x 30"	19.4K	27.1K	35.2K
30" x 32"	20.8K	29.1K	37.8K
32" x 34"	22.2K	31.1K	40.4K
34" x 36"	23.6K	33.1K	43.0K
36" x 38"	25.0K	35.1K	45.6K
38" x 40"	26.4K	37.1K	48.2K
40" x 42"	27.8K	39.1K	50.8K
42" x 44"	29.2K	41.1K	53.4K
44" x 46"	30.6K	43.1K	56.0K
46" x 48"	32.0K	45.1K	58.6K
48" x 50"	33.4K	47.1K	61.2K
50" x 52"	34.8K	49.1K	63.8K
52" x 54"	36.2K	51.1K	66.4K
54" x 56"	37.6K	53.1K	69.0K
56" x 58"	39.0K	55.1K	71.6K
58" x 60"	40.4K	57.1K	74.2K
60" x 62"	41.8K	59.1K	76.8K
62" x 64"	43.2K	61.1K	79.4K
64" x 66"	44.6K	63.1K	82.0K
66" x 68"	46.0K	65.1K	84.6K
68" x 70"	47.4K	67.1K	87.2K
70" x 72"	48.8K	69.1K	89.8K
72" x 74"	50.2K	71.1K	92.4K
74" x 76"	51.6K	73.1K	95.0K
76" x 78"	53.0K	75.1K	97.6K
78" x 80"	54.4K	77.1K	100.2K
80" x 82"	55.8K	79.1K	102.8K
82" x 84"	57.2K	81.1K	105.4K
84" x 86"	58.6K	83.1K	108.0K
86" x 88"	60.0K	85.1K	110.6K
88" x 90"	61.4K	87.1K	113.2K
90" x 92"	62.8K	89.1K	115.8K
92" x 94"	64.2K	91.1K	118.4K
94" x 96"	65.6K	93.1K	121.0K
96" x 98"	67.0K	95.1K	123.6K
98" x 100"	68.4K	97.1K	126.2K
100" x 102"	69.8K	99.1K	128.8K
102" x 104"	71.2K	101.1K	131.4K
104" x 106"	72.6K	103.1K	134.0K
106" x 108"	74.0K	105.1K	136.6K
108" x 110"	75.4K	107.1K	139.2K
110" x 112"	76.8K	109.1K	141.8K
112" x 114"	78.2K	111.1K	144.4K
114" x 116"	79.6K	113.1K	147.0K
116" x 118"	81.0K	115.1K	149.6K
118" x 120"	82.4K	117.1K	152.2K
120" x 122"	83.8K	119.1K	154.8K
122" x 124"	85.2K	121.1K	157.4K
124" x 126"	86.6K	123.1K	160.0K
126" x 128"	88.0K	125.1K	162.6K
128" x 130"	89.4K	127.1K	165.2K
130" x 132"	90.8K	129.1K	167.8K
132" x 134"	92.2K	131.1K	170.4K
134" x 136"	93.6K	133.1K	173.0K
136" x 138"	95.0K	135.1K	175.6K
138" x 140"	96.4K	137.1K	178.2K
140" x 142"	97.8K	139.1K	180.8K
142" x 144"	99.2K	141.1K	183.4K
144" x 146"	100.6K	143.1K	186.0K
146" x 148"	102.0K	145.1K	188.6K
148" x 150"	103.4K	147.1K	191.2K
150" x 152"	104.8K	149.1K	193.8K
152" x 154"	106.2K	151.1K	196.4K
154" x 156"	107.6K	153.1K	199.0K
156" x 158"	109.0K	155.1K	201.6K
158" x 160"	110.4K	157.1K	204.2K
160" x 162"	111.8K	159.1K	206.8K
162" x 164"	113.2K	161.1K	209.4K
164" x 166"	114.6K	163.1K	212.0K
166" x 168"	116.0K	165.1K	214.6K
168" x 170"	117.4K	167.1K	217.2K
170" x 172"	118.8K	169.1K	219.8K
172" x 174"	120.2K	171.1K	222.4K
174" x 176"	121.6K	173.1K	225.0K
176" x 178"	123.0K	175.1K	227.6K
178" x 180"	124.4K	177.1K	230.2K
180" x 182"	125.8K	179.1K	232.8K
182" x 184"	127.2K	181.1K	235.4K
184" x 186"	128.6K	183.1K	238.0K
186" x 188"	130.0K	185.1K	240.6K
188" x 190"	131.4K	187.1K	243.2K
190" x 192"	132.8K	189.1K	245.8K
192" x 194"	134.2K	191.1K	248.4K
194" x 196"	135.6K	193.1K	251.0K
196" x 198"	137.0K	195.1K	253.6K
198" x 200"	138.4K	197.1K	256.2K
200" x 202"	139.8K	199.1K	258.8K
202" x 204"	141.2K	201.1K	261.4K
204" x 206"	142.6K	203.1K	264.0K
206" x 208"	144.0K	205.1K	266.6K
208" x 210"	145.4K	207.1K	269.2K
210" x 212"	146.8K	209.1K	271.8K
212" x 214"	148.2K	211.1K	274.4K
214" x 216"	149.6K	213.1K	277.0K
216" x 218"	151.0K	215.1K	279.6K
218" x 220"	152.4K	217.1K	282.2K
220" x 222"	153.8K	219.1K	284.8K
222" x 224"	155.2K	221.1K	287.4K
224" x 226"	156.6K	223.1K	290.0K
226" x 228"	158.0K	225.1K	292.6K
228" x 230"	159.4K	227.1K	295.2K
230" x 232"	160.8K	229.1K	297.8K
232" x 234"	162.2K	231.1K	300.4K
234" x 236"	163.6K	233.1K	303.0K
236" x 238"	165.0K	235.1K	305.6K
238" x 240"	166.4K	237.1K	308.2K
240" x 242"	167.8K	239.1K	310.8K
242" x 244"	169.2K	241.1K	313.4K
244" x 246"	170.6K	243.1K	316.0K
246" x 248"	172.0K	245.1K	318.6K
248" x 250"	173.4K	247.1K	321.2K
250" x 252"	174.8K	249.1K	323.8K
252" x 254"	176.2K	251.1K	326.4K
254" x 256"	177.6K	253.1K	329.0K
256" x 258"	179.0K	255.1K	331.6K
258" x 260"	180.4K	257.1K	334.2K
260" x 262"	181.8K	259.1K	336.8K
262" x 264"	183.2K	261.1K	339.4K
264" x 266"	184.6K	263.1K	342.0K
266" x 268"	186.0K	265.1K	344.6K
268" x 270"	187.4K	267.1K	347.2K
270" x 272"	188.8K	269.1K	349.8K
272" x 274"	190.2K	271.1K	352.4K
274" x 276"	191.6K	273.1K	355.0K
276" x 278"	193.0K	275.1K	357.6K
278" x 280"	194.4K	277.1K	360.2K
280" x 282"	195.8K	279.1K	362.8K
282" x 284"	197.2K	281.1K	365.4K
284" x 286"	198.6K	283.1K	368.0K
286" x 288"	200.0K	285.1K	370.6K
288" x 290"	201.4K	287.1K	373.2K
290" x 292"	202.8K	289.1K	375.8K
292" x 294"	204.2K	291.1K	378.4K
294" x 296"	205.6K	293.1K	381.0K
296" x 298"	207.0K	295.1K	383.6K
298" x 300"	208.4K	297.1K	386.2K
300" x 302"	209.8K	299.1K	388.8K
302" x 304"	211.2K	301.1K	391.4K
304" x 306"	212.6K	303.1K	394.0K
306" x 308"	214.0K	305.1K	396.6K
308" x 310"	215.4K	307.1K	399.2K
310" x 312"	216.8K	309.1K	401.8K
312" x 314"	218.2K	311.1K	404.4K
314" x 316"	219.6K	313.1K	407.0K
316" x 318"	221.0K	315.1K	409.6K
318" x 320"	222.4K	317.1K	412.2K
320" x 322"	223.8K	319.1K	414.8K
322" x 324"	225.2K	321.1K	417.4K
324" x 326"	226.6K	323.1K	420.0K
326" x 328"	228.0K	325.1K	422.6K
328" x 330"	229.4K	327.1K	425.2K
330" x 332"	230.8K	329.1K	427.8K
332" x 334"	232.2K	331.1K	430.4K
334" x 336"	233.6K	333.1K	433.0K
336" x 338"	235.0K	335.1K	435.6K
338" x 340"	236.4K	337.1K	438.2K
340" x 342"	237.8K	339.1K	440.8K
342" x 344"	239.2K	341.1K	443.4K
344" x 346"	240.6K	343.1K	446.0K
346" x 348"	242.0K	345.1K	448.6K
348" x 350"	243.4K	347.1K	451.2K
350" x 352"	244.8K	349.1K	453.8K
352" x 354"	246.2K	351.1K	456.4K
354" x 356"	247.6K	353.1K	459.0K
356" x 358"	249.0K	355.1K	461.6K
358" x 360"	250.4K	357.1K	464.2K
360" x 362"	251.8K	359.1K	466.8K
362" x 364"	253.2K	361.1K	469.4K
364" x 366"	254.6K	363.1K	472.0K
366" x 368"	256.0K	365.1K	474.6K
368" x 370"	257.4K	367.1K	477.2K
370" x 372"	258.8K	369.1K	479.8K
372" x 374"	260.2K	371.1K	482.4K
374" x 376"	261.6K	373.1K	485.0K
376" x 378"	263.0K	375.1K	487.6K
378" x 380"	264.4K	377.1K	490.2K
380" x 382"	265.8K	379.1K	492.8K
382" x 384"	267.2K	381.1K	495.4K
384" x 386"	268.6K	383.1K	498.0K
386" x 388"	270.0K	385.1K	500.6K
388" x 390"	271.4K	387.1K	503.2K
390" x 392"	272.8K	389.1K	505.8K
392" x 394"	274.2K	391.1K	508.4K
394" x 396"	275.6K	393.1K	511.0K
396" x 398"	277.0K	395.1K	513.6K
398" x 400"	278.4K	397.1K	516.2K
400" x 402"	279.8K	399.1K	518.8K
402" x 404"	281.2K	401.1K	521.4K
404" x 406"	282.6K	403.1K	524.0K
406" x 408"	284.0K	405.1K	526.6K
408" x 410"	285.4K	407.1K	529.2K
410" x 412"	286.8K	409.1K	531.8K
412" x 414"	288.2K	411.1K	534.4K
414" x 416"	289.6K	413.1K	537.0K
416" x 418"	291.0K	415.1K	539.6K
418" x 420"	292.4K	417.1K	542.2K
420" x 422"	293.8K	419.1K	544.8K
422" x 424"	295.2K	421.1K	547.4K
424" x 426"	296.6K	423.1K	550.0K
426" x 428"	298.0K	425.1K	552.6K
428" x 430"	299.4K	427.1K	555.2K
430" x 432"	300.8K	429.1K	557.8K
432" x 434"	302.2K	431.1K	560.4K
434" x 436"	303.6K	433.1K	563.0K
436" x 438"	305.0K	435.1K	565.6K
438" x 440"	306.4K	437.1K	568.2K
440" x 442"	307.8K	439.1K	570.8K
442" x 444"	309.2K	441.1K	573.4K
444" x 446"	310.6K	443.1K	576.0K
446" x 448"	312.0K	445.1K	578.6K
448" x 450"	313.4K	447.1K	581.2K
450" x 452"	314.8K	449.1K	583.8K
452" x 454"	316.2K	451.1K	586.4K
454" x 456"	317.6K	453.1K	589.0K
456" x 458"	319.0K	455.1K	591.6K
458" x 460"	320.4K	457.1K	594.2K
460" x 462"	321.8K	459.1K	596.8K
462" x 464"	323.2K	461.1K	599.4K
464" x 466"	324.6K	463.1K	602.0K
466" x 468"	326.0K	465.1K	604.6K
468" x 470"	327.4K	467.1K	607.2K
470" x 472"	328.8K	469.1K	609.8K
472" x 474"	330.2K	471.1K	612.4K
474" x 476"	331.6K	473.1K	615.0K
476" x 478"	333.0K	475.1K	617.6K
478" x 480"	334.4K	477.1K	620.2K
480" x 482"	335.8K	479.1K	622.8K



Load Short Form
Entire House
AMS of Indiana, Inc.

Job: 2025-1006204
 Date: 5/29/25
 By: AMS of Indiana, Inc.

3933 E. Jackson Blvd., Elkhart, IN 46516 Phone: 574-293-5526 Fax: 574-294-1366 Email: eng-ams@comcast.net

Project Information

For: The Commodore Corporation
 2025-1006204

Design Information

	Htg	Clg	Infiltration	
Outside db (°F)	10	99	Method	Simplified
Inside db (°F)	70	75	Construction quality	Average
Design TD (°F)	60	24	Fireplaces	1 (Average)
Daily range	-	M		
Inside humidity (%)	50	50		
Moisture difference (gr/lb)	48	42		

HEATING EQUIPMENT

Make	Generic
Trade	
Model	AFUE 100
AHRI ref	
Efficiency	100 AFUE
Heating input	9.8 kW
Heating output	33519 Btuh
Temperature rise	34 °F
Actual air flow	916 cfm
Air flow factor	0.031 cfm/Btuh
Static pressure	0.50 in H2O
Space thermostat	

COOLING EQUIPMENT

Make	Generic
Trade	
Cond	SEER 14.0
Coil	
AHRI ref	
Efficiency	12.2 EER, 14 SEER
Sensible cooling	25255 Btuh
Latent cooling	10823 Btuh
Total cooling	36078 Btuh
Actual air flow	916 cfm
Air flow factor	0.040 cfm/Btuh
Static pressure	0.50 in H2O
Load sensible heat ratio	0.84

ROOM NAME	Area (ft²)	Htg load (Btuh)	Clg load (Btuh)	Htg AVF (cfm)	Clg AVF (cfm)
BA1	129	2406	1078	74	43
T	21	84	57	3	2
WIC	72	926	391	28	16
STAIR	38	0	0	0	0
G/R-KIT-D/R-FOY	878	10625	9183	326	369
B2	166	1515	936	46	38
B3	166	2990	1637	92	66
B1	227	3820	3607	117	145
PAN	81	1319	1348	40	54
FR	263	2920	3159	89	127
U	156	2664	1135	82	46
BA	55	624	271	19	11
A	19	0	0	0	0

APPROVED BY

 5/30/2025
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
Kip Whitehead

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



wrightsoft®
 AIAA® Building Software Company

Right-Size® Universal 2025 25.0.02 RSU56435

K:\Engineering\AMS\DS\Commodore\2025-1006204.rup Calc = MJ8 Front Door faces: W

2025-May-29 09:37:09

Page 1

Entire House	d	2271	29894	22801	916	916
Other equip loads			3625	1458		
Equip. @ 1.04 RSM				25254		
Latent cooling				4676		
TOTALS		2271	33519	29930	916	916

APPROVED BY



5/30/2025

Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws

Kip Whitehead

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.




Right-Suite® Universal 2025 25.0.02 RSU56435

2025-May-29 09:37:09

Page 2

K:\Engineering AMS\DS\Commodore\2025-1006204.rup Calc = MJ8 Front Door faces: W



Component Constructions
Entire House
AMS of Indiana, Inc.

Job: 2025-1006204
 Date: 5/29/25
 By: AMS of Indiana, Inc.

3933 E. Jackson Blvd., Elkhart, IN 46516 Phone: 574-293-5526 Fax: 574-294-1366 Email: erg-ams@comcast.net

Project Information

For: The Commodore Corporation
 2025-1006204

Design Conditions

Location:			Indoor:		Heating	Cooling
Raleigh Executive, NC, US			Indoor temperature (°F)		70	75
Elevation: 247 ft			Design TD (°F)		60	24
Latitude: 36°N			Relative humidity (%)		50	50
Outdoor:			Moisture difference (gr/lb)		47.8	41.6
Heating			Cooling			
Dry bulb (°F)			10		99	
Daily range (°F)			-		21 (M)	
Wet bulb (°F)			-		77	
Wind speed (mph)			15.0		7.5	
			Infiltration:			
			Method		Simplified	
			Construction quality		Average	
			Fireplaces		1 (Average)	

Construction descriptions

	Or	Area ft²	U-value Btu/h-ft²-F	Insul R ft²-F/Btu	Htg HTM Btu/h-ft²	Loss Btu/h	Clg HTM Btu/h-ft²	Gain Btu/h
Walls								
12F-0sw: Frm wall, vnl ext, 3/8" wood shth, r-21 cav ins, 1/2" gypsum	n	264	0.065	21.0	3.89	1029	1.55	409
board int fnsh, 2"x4" wood frm, 16" o.c. stud	e	581	0.065	21.0	3.89	2261	1.55	898
	s	253	0.065	21.0	3.89	983	1.55	391
	w	536	0.065	21.0	3.89	2087	1.55	829
	all	1634	0.065	21.0	3.89	6361	1.55	2527
Partitions								
(none)								
Windows								
2 glazing, clr out, air gas, wd frm mat, clr innr, 1/4" gap, 1/8" thk; 2 glazing,	n	6	0.320	0	19.2	107	13.3	75
clr out, air gas, wd frm mat, clr innr, 1/4" gap, 1/8" thk; 6.67 ft head ht	e	59	0.320	0	19.2	1131	34.4	2030
	s	17	0.320	0	19.2	334	17.6	307
	w	125	0.320	0	19.2	2392	34.4	4293
	all	207	0.320	0	19.2	3964	32.4	6704
Doors								
11D0: Door, wd sc type	e	42	0.390	0	23.4	981	13.6	573
	w	21	0.390	0	23.4	491	13.6	287
	all	63	0.390	0	23.4	1472	13.6	860
Ceilings								
16B-30ad: Attic ceiling, asphalt shingles roof mat, r-30 cell ins		1225	0.032	30.0	1.92	2349	1.87	2294
16B-44ad: Attic ceiling, asphalt shingles roof mat, r-44 cell ins		1045	0.022	44.0	1.32	1378	1.29	1345
Floors								
19A-30cstp: Fir floor, frm flr, 10" thkns, r-30 cav ins, tight cowl ovr		2271	0.034	30.0	1.71	3881	0.69	1561

APPROVED BY

NIA

5/30/2025

Approval of this document does not authorize or
 approve any deviation or deviations from the
 requirements of applicable State Laws

Kip Whitehead



wrightsoft®
 A BalaTech® / BalaTech® Hardware Company

Right-Suite® Universal 2025 25.0.02 RSU56435

K:\Engineering\AMS\DS\Commodore\2025-1006204.rup Calc = MJ8 Front Door faces: W

2025-May-29 09:37:09

Page 1



Project Summary
Entire House
AMS of Indiana, Inc.

Job: 2025-1006204
 Date: 5/29/25
 By: AMS of Indiana, Inc.

3933 E. Jackson Blvd., Elkhart, IN 46516 Phone: 574-293-5526 Fax: 574-294-1366 Email: eng-ams@comcast.net

Project Information

For: The Commodore Corporation
 2025-1006204

Notes:

APPROVED BY



5/30/2025

Approval of this document does not authorize or
 approve any deviation or deviations from the
 requirements of applicable State Laws

Kip Whitehead

Design Information

Weather: Raleigh Executive, NC, US

Winter Design Conditions

Outside db 10 °F
 Inside db 70 °F
 Design TD 60 °F

Ventilation Method MJ8

Heating Summary

Structure 27827 Btuh
 Ducts (R-8.0) 2067 Btuh
 Central vent (56 cfm) 3625 Btuh
 Outside air
 Humidification 0 Btuh
 Piping 0 Btuh
 Equipment load 33519 Btuh

Infiltration

Method Simplified
 Construction quality Average
 Fireplaces 1 (Average)

	Heating	Cooling
Area (ft²)	2271	2271
Volume (ft³)	20436	20436
Air changes/hour	0.38	0.16
Equiv. AVF (cfm)	129	54

Heating Equipment Summary

Make Generic
 Trade
 Model AFUE 100
 AHRI ref

Efficiency 100 AFUE
 Heating input 9.8 kW
 Heating output 33519 Btuh
 Temperature rise 34 °F
 Actual air flow 916 cfm
 Air flow factor 0.031 cfm/Btuh
 Static pressure 0.50 in H2O
 Space thermostat

Summer Design Conditions

Outside db 99 °F
 Inside db 75 °F
 Design TD 24 °F
 Daily range M
 Relative humidity 50 %
 Moisture difference 42 gr/lb

Sensible Cooling Equipment Load Sizing

Structure 19971 Btuh
 Ducts (R-8.0) 2830 Btuh
 Central vent (56 cfm) 1458 Btuh
 Outside air
 Blower 0 Btuh
 Use manufacturer's data n
 Rate/swing multiplier 1.04
 Equipment sensible load 25254 Btuh

Latent Cooling Equipment Load Sizing

Structure 2729 Btuh
 Ducts 389 Btuh
 Central vent (56 cfm) 1558 Btuh
 Outside air
 Equipment latent load 4676 Btuh

Equipment Total Load (Sen+Lat) 29930 Btuh
 Req. total capacity at 0.70 SHR 3.0 ton

Cooling Equipment Summary

Make Generic
 Trade
 Cond SEER 14.0
 Coil

AHRI ref
 Efficiency 12.2 EER, 14 SEER
 Sensible cooling 25255 Btuh
 Latent cooling 10823 Btuh
 Total cooling 36078 Btuh
 Actual air flow 916 cfm
 Air flow factor 0.040 cfm/Btuh
 Static pressure 0.50 in H2O
 Load sensible heat ratio 0.84

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Side® Universal 2025 25.0.02 RSU56435

Right-Side® Universal 2025 25.0.02 RSU56435


K:\Engineering\AMS\DS\Commodore\2025-1006204.rup Calc = MJ8 Front Door faces: W

2025-May-29 09:37:09

Page 1



1ST FLOOR



APPROVED BY



5/30/2025

Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws

Kip Whitehead

Job #: 2025-1006204
Performed by AMS of Indiana, Inc. for:
 The Commodore Corporation
 2025-1006204

AMS of Indiana, Inc.
 3933 E. Jackson Blvd.
 Elkhart, IN 46516
 Phone: 574-293-5526 Fax: 574-294-1366
 eng-ams@comcast.net

Scale: 1 : 126
 Page 1
 Right-Suite® Universal 2025
 25.0.02 RSU56435
 2025-May-29 09:37:24
 ...MS\DS\Commodore\2025-100620...



Manual S Compliance Report

Entire House

AMS of Indiana, Inc.

Job: 2025-1006204
 Date: 5/29/25
 By: AMS of Indiana, Inc.

3933 E. Jackson Blvd., Elkhart, IN 46516 Phone: 574-293-5526 Fax: 574-294-1366 Email: eng-ams@comcast.net

Project Information

For: The Commodore Corporation
 2025-1006204

Cooling Equipment

Design Conditions

Outdoor design DB:	99.1 °F	Sensible gain:	24260	Btuh	Entering coil DB:	79.4 °F
Outdoor design WB:	77.1 °F	Latent gain:	4676	Btuh	Entering coil WB:	64.9 °F
Indoor design DB:	75.0 °F	Total gain:	28935	Btuh		
Indoor RH:	50%	Estimated airflow:	916	cfm		

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Split AC		
Manufacturer:	Generic	Model:	SEER 14.0
Actual airflow:	916	cfm	
Sensible capacity:	25255	Btuh	104% of load
Latent capacity:	10823	Btuh	231% of load
Total capacity:	36078	Btuh	125% of load SHR: 70%

Heating Equipment

Design Conditions

Outdoor design DB:	10.1 °F	Heat loss:	33519	Btuh	Entering coil DB:	64.2 °F
Indoor design DB:	70.0 °F					

Manufacturer's Performance Data at Actual Design Conditions

Equipment type:	Elec furnace		
Manufacturer:	Generic	Model:	AFUE 100
Actual airflow:	916	cfm	
Output capacity:	33519	Btuh	100% of load
			Temp. rise: 0 °F

APPROVED BY



5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

Meets all requirements of ACCA Manual S.



wrightsoft®

A McAfee / Blackstone Software Company

Right-Size® Universal 2025 25.0.02 RSU56435

K:\Engineering\AMS\DS\Commodore\2025-1006204.rup Calc = MJ8 Front Door faces: W

2025-May-29 09:37:09

Page 1



Duct System Summary

Entire House

AMS of Indiana, Inc.



Job: 2025-1006204
Date: 5/29/25
By: AMS of Indiana, Inc.

3933 E. Jackson Blvd., Elkhart, IN 46516 Phone: 574-293-5526 Fax: 574-294-1366 Email: eng-ams@comcast.net

Project Information

For: The Commodore Corporation
2025-1006204

	Heating	Cooling
External static pressure	0.50 in H ₂ O	0.50 in H ₂ O
Pressure losses	0.41 in H ₂ O	0.41 in H ₂ O
Available static pressure	0.09 in H ₂ O	0.09 in H ₂ O
Supply / return available pressure	0.045 / 0.045 in H ₂ O	0.045 / 0.045 in H ₂ O
Lowest friction rate	0.143 in/100ft	0.143 in/100ft
Actual air flow	916 cfm	916 cfm
Total effective length (TEL)	63 ft	

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
B1	c 1803	59	72	0	0	0x0	VIFx	0	0	
B1-A	c 1803	59	72	0	0	0x0	VIFx	0	0	
B2	h 936	46	38	0	0	0x0	VIFx	0	0	
B3	h 1637	92	66	0	0	0x0	VIFx	0	0	
BA	h 271	19	11	0	0	0x0	VIFx	0	0	
BA1	h 1078	74	43	0	0	0x0	VIFx	0	0	
FR	c 1579	45	63	0	0	0x0	VIFx	0	0	
FR-A	c 1579	45	63	0	0	0x0	VIFx	0	0	
G/R-KIT-DR-FOY	c 1837	65	74	0	0	0x0	VIFx	0	0	
G/R-KIT-DR-FOYA	c 1837	65	74	0	0	0x0	VIFx	0	0	
G/R-KIT-DR-FOYB	c 1837	65	74	0	0	0x0	VIFx	0	0	
G/R-KIT-DR-FOYFOZ	c 1837	65	74	0	0	0x0	VIFx	0	0	
G/R-KIT-DR-FOYFPA	c 1837	65	74	0	0	0x0	VIFx	0	0	
PAN	c 1348	40	54	0	0	0x0	VIFx	0	0	
T	h 57	3	2	0	0	0x0	VIFx	0	0	
U	h 1135	82	46	0	0	0x0	VIFx	0	0	
WIC	h 391	28	16	0	0	0x0	VIFx	0	0	

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb2	0x0	916	916	62.8	0.143	656	16.0	0x0		ShMt	



Generated by REScheck-Web Software

Compliance Certificate

Project 2025-1006204

Energy Code: **2018 IECC**
 Location: **Harnett County, North Carolina**
 Construction Type: **Single-family**
 Project Type: **New Construction**
 Project SubType: **None**
 Orientation: **Unspecified**
 Conditioned Floor Area: **2,280 ft²**
 Glazing Area: **11%**
 Climate Zone: **4 (3499 HDD)**
 Permit Date:
 Permit Number:
 All Electric: **true**
 Is Renewable: **false**
 Has Charger: **false**
 Has Battery: **false**
 Has Heat Pump: **false**

APPROVED BY



5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
Kip Whitehead

Construction Site:
 461 McNeill Road
 Broadway, North Carolina 27505

Owner/Agent:
 Griffin
 NC Custom Mods

Designer/Contractor:
 Cavco-Crouse
 235 Anthony Grove Rd.
 Crouse, NC 28033

Compliance: Passes using UA trade-off

Compliance: **5.6% Better Than Code** Maximum UA: **393** Your UA: **371** Maximum SHGC: **0.40** Your SHGC: **0.23**

The % Better or Worse Than Code Index reflects how close to compliance the house is based on code trade-off rules. It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home.

Slab-on-grade tradeoffs are no longer considered in the UA or performance compliance path in REScheck. Each slab-on-grade assembly in the specified climate zone must meet the minimum energy code insulation R-value and depth requirements.

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Ceiling 1: Flat Ceiling or Scissor Truss	1,077	44.0	0.0	0.027	0.026	29	28
Ceiling 2 [Between knee walls]: Flat Ceiling or Scissor Truss	1,203	30.0	0.0	0.035	0.026	42	31
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Right side	293	21.0	0.0	0.057	0.060	14	15
Door - Hinged - Exterior - Craftsman - 3 Lite {Qty 1}: null Orientation: Right side	22			0.240	0.320	5	7
Window - Lippert SH 3668 {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Right side	17			0.340	0.320	6	5

Project Title: 2025-1006204
 Data filename:

Report date: 05/29/25
 Page 1 of 10

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Left side	293	21.0	0.0	0.057	0.060	16	17
Window - Lippert 7112 Transom {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.26 Orientation: Left side	6			0.310	0.320	2	2
Window - Lippert SH 2427 {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Left side	5			0.340	0.320	2	2
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Back	743	21.0	0.0	0.057	0.060	36	38
Door - Sliding Patio {Qty 1}: null Orientation: Back	40			0.230	0.320	9	13
Window - Lippert SH 3668 {Qty 4}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Back	69			0.340	0.320	23	22
Window - Lippert 6012 Transom {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.26 Orientation: Back	5			0.310	0.320	2	2
Window - Lippert 3612 Transom {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.26 Orientation: Back	3			0.310	0.320	1	1
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Front	743	21.0	0.0	0.057	0.060	33	35
Door - Hinged - Exterior - Craftsman - 3 Lite {Qty 1}: null Orientation: Front	22			0.240	0.320	5	7
Window - Lippert SH 3668 {Qty 2}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Front	35			0.340	0.320	12	11
Window - (2) Lippert SH 3668 {Qty 3}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Front	104			0.340	0.320	35	33
Wall [Cape Close Off Kit]: Wood Frame, 16" o.c. Orientation: Unspecified	200	11.0	0.0	0.089	0.060	16	11
Attic Door: Solid Orientation: Unspecified	18			0.460	0.320	8	6
Floor 1: All-Wood Joist/Truss:Over Outside Air	2,280	30.0	0.0	0.033	0.047	75	107

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the 2018 IECC requirements in REScheck Version : REScheck-Web and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

Stephane Manigat - Draftsman
Name - Title

Stephane Manigat
Signature

5/29/2025
Date





REScheck Software Version : REScheck-Web

Inspection Checklist

Energy Code: 2018 IECC

Requirements: 0.0% were addressed directly in the REScheck software

Text in the "Comments/Assumptions" column is provided by the user in the REScheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Pre-Inspection/Plan Review	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
103.1, 103.2 [PR1] ¹ 	Construction drawings and documentation demonstrate energy code compliance for the building envelope. Thermal envelope represented on construction documents.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
103.1, 103.2, 403.7 [PR3] ¹ 	Construction drawings and documentation demonstrate energy code compliance for lighting and mechanical systems. Systems serving multiple dwelling units must demonstrate compliance with the IECC Commercial Provisions.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
302.1, 403.7 [PR2] ² 	Heating and cooling equipment is sized per ACCA Manual S based on loads calculated per ACCA Manual J or other methods approved by the code official.	Heating: Btu/hr____ Cooling: Btu/hr____	Heating: Btu/hr____ Cooling: Btu/hr____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

Additional Comments/Assumptions:

APPROVED BY

NIA

5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Project Title: 2025-1006204

Data filename:

Report date: 05/29/25

Page 3 of 10

Section # & Req.ID	Foundation Inspection	Complies?	Comments/Assumptions
303.2.1 [FO11] ² 	A protective covering is installed to protect exposed exterior insulation and extends a minimum of 6 in. below grade.	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.9 [FO12] ² 	Snow- and ice-melting system controls installed.	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

Additional Comments/Assumptions:

APPROVED BY



5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
402.1.1, 402.3.4 [FR1] ¹ 	Door U-factor.	U-____	U-____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	See the Envelope Assemblies table for values.
402.1.1, 402.3.1, 402.3.3, 402.5 [FR2] ¹ 	Glazing U-factor (area-weighted average).	U-____	U-____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	See the Envelope Assemblies table for values.
303.1.3 [FR4] ¹ 	U-factors of fenestration products are determined in accordance with the NFRC test procedure or taken from the default table.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.4.1.1 [FR23] ¹ 	Air barrier and thermal barrier installed per manufacturer's instructions.	APPROVED BY  5/30/2025 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws Kip Whitehead		☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.4.3 [FR20] ¹ 	Fenestration that is not site built is listed and labeled as meeting AAMA /WDMA/CSA 101/I.S.2/A440 or has infiltration rates per NFRC 400 that do not exceed code limits.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.4.5 [FR16] ²	IC-rated recessed lighting fixtures sealed at housing/interior finish and labeled to indicate ≤2.0 cfm leakage at 75 Pa.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.1 [FR12] ¹ 	Supply and return ducts in attics insulated ≥ R-8 where duct is ≥ 3 inches in diameter and ≥ R-6 where < 3 inches. Supply and return ducts in other portions of the building insulated ≥ R-6 for diameter ≥ 3 inches and R-4.2 for < 3 inches in diameter.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.2 [FR13] ¹ 	Ducts, air handlers and filter boxes are sealed with joints/seams compliant with International Mechanical Code or International Residential Code, as applicable.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.5 [FR15] ³ 	Building cavities are not used as ducts or plenums.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.4 [FR17] ² 	HVAC piping conveying fluids above 105 °F or chilled fluids below 55 °F are insulated to ≥ R-3.	R-____	R-____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.4.1 [FR24] ¹ 	Protection of insulation on HVAC piping.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.3 [FR18] ² 	Hot water pipes are insulated to ≥ R-3.	R-____	R-____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

1 High Impact (Tier 1)

2 Medium Impact (Tier 2)

3 Low Impact (Tier 3)

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
403.6 [FR19] ²	Automatic or gravity dampers are installed on all outdoor air intakes and exhausts.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

Additional Comments/Assumptions:

APPROVED BY



5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
---	----------------------	---	------------------------	---	---------------------

Section # & Req.ID	Insulation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
303.1 [IN13] ² 	All installed insulation is labeled or the installed R-values provided.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.1.1, 402.2.6 [IN1] ¹ 	Floor insulation R-value.	R-_____ ☐ Wood ☐ Steel	R-_____ ☐ Wood ☐ Steel	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	See the Envelope Assemblies table for values.
303.2, 402.2.8 [IN2] ¹ 	Floor insulation installed per manufacturer's instructions and in substantial contact with the underside of the subfloor, or floor framing cavity insulation is in contact with the top side of sheathing, or continuous insulation is installed on the underside of floor framing and extends from the bottom to the top of all perimeter floor framing members.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.1.1, 402.2.5, 402.2.6 [IN3] ¹ 	Wall insulation R-value. If this is a mass wall with at least ½ of the wall insulation on the wall exterior, the exterior insulation requirement applies (FR10).	R-_____ ☐ Wood ☐ Mass ☐ Steel	R-_____ ☐ Wood ☐ Mass ☐ Steel	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	See the Envelope Assemblies table for values.
303.2 [IN4] ¹	Wall insulation is installed per manufacturer's instructions.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

Additional Comments/Assumptions:

APPROVED BY

NIA

5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
---	----------------------	---	------------------------	---	---------------------

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
402.1.1, 402.2.1, 402.2.2, 402.2.6 [FI1] ¹	Ceiling insulation R-value.	R- _____ ☐ Wood ☐ Steel	R- _____ ☐ Wood ☐ Steel	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	See the Envelope Assemblies table for values.
303.1.1.1, 303.2 [FI2] ¹	Ceiling insulation installed per manufacturer's instructions. Blown insulation marked every 300 ft ² .			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.2.3 [FI22] ²	Vented attics with air permeable insulation include baffle adjacent to soffit and eave vents that extends over insulation.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.2.4 [FI3] ¹	Attic access hatch and door insulation ≥ R-value of the adjacent assembly.	R- _____	R- _____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
402.4.1.2 [FI17] ¹	Blower door test @ 50 Pa. ≤ 5 ach in Climate Zones 1-2, and ≤ 3 ach in Climate Zones 3-8.	ACH 50 = _____	ACH 50 = _____	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.3 [FI27] ¹	Ducts are pressure tested to determine air leakage with either: Rough-in test: Total leakage measured with a pressure differential of 0.1 inch w.g. across the system including the manufacturer's air handler enclosure if installed at time of test. Postconstruction test: Total leakage measured with a pressure differential of 0.1 inch w.g. across the entire system including the manufacturer's air handler enclosure.	_____ cfm/100 ft ²	_____ cfm/100 ft ²	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.4 [FI4] ¹	Duct tightness test result of ≤ 4 cfm/100 ft ² across the system or ≤ 3 cfm/100 ft ² without air handler @ 25 Pa. For rough-in tests, verification may need to occur during Framing Inspection.	_____ cfm/100 ft ²	_____ cfm/100 ft ²	☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.3.2.1 [FI24] ¹	Air handler leakage designated by manufacturer at ≤ 2% of design air flow.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.1.1 [FI9] ²	Programmable thermostats installed for control of primary heating and cooling systems and initially set by manufacturer to code specifications.	APPROVED BY  5/30/2025 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws Kip Whitehead		☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.1.2 [FI10] ²	Heat pump thermostat installed on heat pumps.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.1 [FI11] ²	Circulating service hot water systems have automatic or accessible manual controls.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
403.6.1 [FI25] ²	All mechanical ventilation system fans not part of tested and listed HVAC equipment meet efficacy and air flow limits per Table R403.6.1.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.2 [FI26] ²	Hot water boilers supplying heat through one- or two-pipe heating systems have outdoor setback control to lower boiler water temperature based on outdoor temperature.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.1.1 [FI28] ²	Heated water circulation systems have a circulation pump. The system return pipe is a dedicated return pipe or a cold water supply pipe. Gravity and thermosyphon circulation systems are not present. Controls for circulating hot water system pumps start the pump with signal for hot water demand within the occupancy. Controls automatically turn off the pump when water is in circulation loop is at set-point temperature and no demand for hot water exists.	APPROVED BY  5/30/2025 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws Kip Whitehead		☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.1.2 [FI29] ²	Electric heat trace systems comply with IEEE 515.1 or UL 515. Controls automatically adjust the energy input to the heat tracing to maintain the desired water temperature in the piping.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.2 [FI30] ²	Demand recirculation water systems have controls that manage operation of the pump and limit the temperature of the water entering the cold water piping to $\leq 104^{\circ}\text{F}$.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
403.5.4 [FI31] ²	Drain water heat recovery units tested in accordance with CSA B55.1. Potable water-side pressure loss of drain water heat recovery units < 3 psi for individual units connected to one or two showers. Potable water-side pressure loss of drain water heat recovery units < 2 psi for individual units connected to three or more showers.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
404.1 [FI6] ¹	90% or more of permanent fixtures have high efficacy lamps.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
404.1.1 [FI23] ³	Fuel gas lighting systems have no continuous pilot light.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	
401.3 [FI7] ²	Compliance certificate posted.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
303.3 [FI18] ³	Manufacturer manuals for mechanical and water heating systems have been provided.			☐ Complies ☐ Does Not ☐ Not Observable ☐ Not Applicable	

Additional Comments/Assumptions:

APPROVED BY



5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

Kip Whitehead

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
---	----------------------	---	------------------------	---	---------------------



2018 IECC Energy Efficiency Certificate

Insulation Rating	R-Value
Above-Grade Wall	21.00
Below-Grade Wall	0.00
Floor	30.00
Ceiling / Roof	30.00
Ductwork (unconditioned spaces):	_____

Glass & Door Rating	U-Factor	SHGC
Window	0.34	0.23
Door	0.23	

Heating & Cooling Equipment	Efficiency
Heating System: _____	_____
Cooling System: _____	_____
Water Heater: _____	_____

Name: _____ Date: _____








Comments _____

APPROVED BY

5/30/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws



Kip Whitehead

Job	Truss	Truss Type	Qty	Ply	UFP ENGINEERING 1 Bulletin 05-02 REF # 2001072
32802	A098601	RIGID COLLAR TIE CONNECTION DETAILS 1			
Universal Forest Products Inc., Grand Rapids, MI 49525.					
2x4 Collar Tie Nailed to 2x6 Chord		2x6 Collar Tie Nailed to 2x6 Chord		2x6 Collar Tie Nailed to 2x8 Chord	
Attach Collar Tie with (6) nails & 100% Structural & 100% Adhesive Coverage  1" Edge Distance, Typ. On All Sides Nail This Face Detail (A)		Attach Collar Tie with (8) nails & 100% Structural & 100% Adhesive Coverage  1" Edge Distance, Typ. On All Sides Nail This Face Detail (B)		Attach Collar Tie with (10) nails & 100% Structural & 100% Adhesive Coverage  1" Edge Distance, Typ. On All Sides Nail This Face Detail (C)	
2x8 Collar Tie Nailed to 2x6 Chord		2x8 Collar Tie Nailed to 2x8 Chord		Acceptable Alternate Applications See truss print for which detail is actually used *  Typical Side View	
Attach Collar Tie with (10) nails & 100% Structural & 100% Adhesive Coverage  1" Edge Distance, Typ. On All Sides Nail This Face Detail (D)		Attach Collar Tie with (12) nails & 100% Structural & 100% Adhesive Coverage  1" Edge Distance, Typ. On All Sides Nail This Face Detail (E)		1 or 2 Ply Truss  Collar Tie (Both Faces) Section A-A	
Power Driven Nails Rigid Collar Tie Connection Details A) Side member shall be fastened with structural adhesive that meets the requirements of ASTM-2559. Maximum wood to wood gap = 1/16". B) Bostitch .131" Dia. x 3" nails (or equal)					
APPROVED BY NTA 9/30/2015 Approval of this document does not authorize or approve any deviation or variations from the requirements of applicable State Laws Kip Whitehead Universal Forest Products, Inc. PHONE (414) 544-4444 FAX (414) 544-4204 2801 EAST 96TH AVE. PO. BOX 45 GRAND RAPIDS, MI 49503 WARNING - Verify design parameters and READ NOTES This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional permanent bracing to ensure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding design/constructability control, storage, delivery, erection and bracing, consult DSI-28 Quality Standard, DCS-49 Bracing Specification, and HHS-11 Handling, Installing and Bracing. Recommendations available from Truss Plate Institute, 580 D'Oroville Drive, Madison, WI 53719. Copyright 2004, by Universal Forest Products, Inc.					

**UFP INDUSTRIES**

Job	Truss	MFG	Customer
111603	CCB32853	315	COMMODORE

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



APPROVED BY
NIA 5/30/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
Kip Whitehead

NORTH CAROLINA MODULAR PLANS REVIEW CHECKLIST	
	PAGE 1 of 3 REVISED 1-30-2025
Manufacturer	R-Anell Housing Group
Model number/name	2025-1006204
3rd Party	NTA
Review Date	5/30/2025
Reviewer	Kip Whitehead
	Plan Sheet Page # and NOTES
QC MANUAL (current and complete)	OK
APPENDIX B (required and attached)	N/A - Does Not Apply to Residential Modulares
PLAN SHEETS	
Each plan sheet third-party stamped with approver's name	YES
Each plan sheets is numbered and/or indexed	YES
GENERAL (cover sheet)	
Code References	Cover sheet
Statement regarding connection to public utilities	Cover sheet
Statement regarding bathrooms if not included	NA
Construction type	Cover sheet - 5B (Wood Frame - Unprotected)
Occupancy classification	Cover sheet - Single Family Residential
Fire resistance ratings (if required)	NA
Floor live load	Cover sheet
Roof live load	Cover sheet
Design wind velocity	Cover sheet
Seismic information (commercial projects)	NA
Thermal zones	Cover sheet
Notice to inspections department regarding items to be site inspected	Cover sheet
FLOOR PLANS	
Interior and exterior wall layouts	Page FP
Door and window schedule	Schedules and General Notes Page
Light and Ventilation requirements	Schedules and General Notes Page
Attic access (size and location)	Page FP
Non-prescriptive headers	N/A
Safety glazing requirements	Shown on floor plan with "S" symbol
Fire rating of Exterior walls (if applicable)	NA
EXTERIOR ELEVATIONS	
Exterior materials	Page EL
Attic ventilation requirements	Page XS
PLUMBING	
Plan	Pages WH, WC, DL, DN, & GA
All fixtures furnished by mfg. shown on plans	Pages WH, WC, DL, DN, GA (references design manual
Materials (water supply & distribution, DWV, storm drainage)	Pages WH, WC, DL, DN, & GA
Supply and waste risers, <u>including DWV system (generic) beneath the building.</u>	Pages WH, WC, DL, DN, & GA
Water heater (type and capacity)	Electric 50 gal

NORTH CAROLINA **MODULAR PLANS REVIEW CHECKLIST**

PAGE 2 of 3

REVISED 1-30-2025

Plan Sheet Page # and NOTES

MECHANICAL

Design calculations	N/A
Installed unit capacity	ResCheck
Supply and returns (locations and sizes)	Pages HS & HR
Duct sizes	Page HS
Specifications (units, ducts)	Page HS (reference design manual)
All appliances furnished by mfg. shown on plans	Page HS (reference design manual)

ELECTRICAL

Plan	Page EP
Location of all electrical boxes	Page EP
Electrical panel location	Page EP
Note regarding main disconnect (if applicable)	Page NG
Exterior lighting and receptacles	Page EP
Ground level receptacles (if applicable)	Page EP
Smoke detector location(s)	Page EP
Electrical load calculations	Page NG
Electrical panel layout (breaker and wire sizes, circuit schedule)	Page NG
Panel and service entrance sizes	Page NG
All fixtures furnished by mfg. shown on plans	Page EP

ACCESSIBILITY

(for other than 1 & 2 family dwellings)

Entrances and means of egress	N/A
Doors, doorways, and door hardware	N/A
Stairs and handrails	N/A
Toilet rooms, plumbing fixtures, grab bars, etc	N/A
Bathrooms and shower rooms	N/A
Occupancy specific requirements	N/A
Multi-family dwellings: Type A and B units	N/A

FLOOR X-SECTION

Joists and beam sizes and spacing	Page XS
Materials species and grade	Page XS
Sheathing, decking, and concrete as applicable	Page XS
Fastening instructions	Page XS
Insulation	ResCheck
Details as required for clarification	N/A

WALL X-SECTION

Stud and column sizes and spacing	Page XS
Materials species and grade	Page XS
Sheathing and bracing	Page XS
Headers and lintels	Page XS
Finishes	Page XS
Fastening instructions	Cover Sheet (references Installation Manual)
Insulation	ResCheck
Details as required for clarification	ResCheck

NORTH CAROLINA

MODULAR PLANS REVIEW CHECKLIST

PAGE 3 of 3

REVISED 1-30-2025

Plan Sheet Page # and NOTES

CEILING / ROOF X-SECTION

Truss, rafter, and beam spacing

Page XS, Cover Sheet, truss dwgs.

Lumber species and grade

Design Manual

Sheathing and decking

Page XS

Finishes

Page XS

Fastening instructions

Installation Manual

Insulation

ResCheck

Details including NC sealed truss designs or manual reference

Design Manual

FOUNDATION PLAN

Footings, pier, and curtain wall locations and specifications

Page FD20# & Installation Manual

X-sections with dimensions

Page FD20# & Installation Manual

Anchorage - sill plate to piers and curtain wall

Page FD20# & Installation Manual

Anchorage - building to sill plate

Page FD20# & Installation Manual

Anchorage - tie downs (lateral and longitudinal)

Page FD20# & Installation Manual

Soil bearing capacity

Page FD20# & Installation Manual

Minimum concrete compressive strength

Page FD20# & Installation Manual

Mortar type

Page FD20# & Installation Manual

Ventilation requirements (with and without vapor barrier)

Page FD20# & Installation Manual

Crawl space access requirements

Page FD20# & Installation Manual

ENERGY COMPLIANCE

Demonstrated compliance

ResCheck

SET-UP INSTRUCTIONS

Floor and ceiling connections

Chapter 5 of Installation Manual

Marriage wall connections

Chapter 5 of Installation Manual

Roof set-up and connection

Chapter 5 of Installation Manual

Plumbing connections

Chapter 8.2 of Installation Manual

Mechanical connections

Chapter 8.5 of Installation Manual

Electrical connections

Chapter 8.1 of Installation Manual

Fire stopping

not specifically addressed in installation manual (inherent in design)

Air infiltration elimination

not specifically addressed in installation manual (part IRC requirements)

Notice to inspections department attachment if set-up instructions are by attachment

Cover Sheet

ITEMS NOT INSPECTED IN PLANT

List of items not inspected by 3rd. Party

Cover Sheet

Notice to inspections department

Code page