
BLUE: INDICATES STICK FRAMED

RED : INDICATES TRUSSES

BLACK: INDICATES REQUIREMENTS FOR BOTH



24"X24"X8" FOOTINGS,

(2) H2.5A CLIPS AT TOPS

TO HEADER (TYP UNO)

- W/ ABU66 BASE AND

THIS POST 6X6 POSTS ON

36"X36"12" FOOTINGS,

(2) H6 CLIPS AT TOPS TO

HEADER

- W/ ABU66 BASE AND



ENGINEERS SEAL APPLIES ONLY TO STRUCTURA COMPONENTS ON THIS DOCUMENT. SEAL DOES NOT INCLUDE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES, OR SAFETY PRECAUTIONS. ANY DEVIATIONS OR DISCREPANCIES ON PLANS ARE TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF A. A. TAKLA ENGINEERING, PLLC. FAILURE TO DO SO WILL VOID LIABILITY. SEAL IS VALID FOR ONE YEAR FROM THE DATE OF SEAL. PLEASE REFERENCE STRUCTURAL NOTES PROVIDED BY A. A. TAKLA ENGINEERING FOR ADDITIONAL INFORMATION.

arina Company >Design Fuquay Building Or. \geq ami \vdash \sim

[] For Construction [X] Not for Construction PROJ# 0086-21 DATE: 1/23/21

REVISIONS: 1 OF 1

SHEET TITLE:

FOUNDATION

& FRAMING

SCALE: 4":1' S1

Design Loads: (Exceeds minimum requirements per code)

	Live Load (PSF)	Dead Load (PSF)	Deflection
All Floors	40	10	L/360
Attic Platforms	25	10	L/360
Ceiling	10	10	L/360
Decks/Balconies	60	10	L/240
Roof	20	15	L/240
Wind Load	115 MPH (UON)	115 MPH (UON)	L/240

General Plan Reading Notes:

- 1. If any handwritten notes are provided plans must be printed in color or read digitally.
- Handwritten notes in Red and Blue ink shall take priority over all printed texts.
- 3. Noted dimensions shall take priority over scaled drawings.
- 4. These general notes shall apply unless otherwise noted in handwriting.

Foundation Notes:

- 1. Assumed soil load bearing capacity = 2000 PSF
- Minimum 28 day f'c of concrete = 3000 PSI
- 3. Foundations to be built in accordance with NCRC 2018,
- "Tie-In"s shall be (2) 16" long #4 epoxy bonded dowels half embedded mid-depth into existing footings. If no footing exists, omit Tie-in
- Install anchor bolts per R403.1.6.
- All slabs shall be 4" thick, 3000 psi concrete slab on 4" of #57 sub-base w/ a 6 mil vapor barrier (if used in an interior or garage application) w/10/10 6x6 welded wire fabric UON.
- 7. All slabs shall be on compacted fill or full depth self consolidated structural fill (#57) (at porches, garages and stem wall slabs UON.
- 8. All suspended slabs on metal pans shall utilize 16GA type B UON.
- 9. Max unreinforced, unbalanced condition of any CMU wall shall be 36". Any foundation wall subjected to 24" of unbalanced fill or more shall be fully grouted. Top course of all foundation walls shall be fully grouted.
- 10. Max CMU pier height to be 4x its least horizontal dimension. All piers shall be fully grouted.
- 11. All piers shall be in the middle 1/3rd of the footing. Min 2" footing projection at each side. Max projection shall be the depth of the footing.

Footing Schedule:

- $A = 16" \times 16" \times 8"$ E = 36"x36"x12"
- B = 20''x20''x8''F = 40"x40"x12" w/ (3) #4 EW @ bottomsC = 24''x24''x10'' $G = 48" \times 48" \times 12" \text{ w/ } (4) \# 4 \text{ EW } 0$
- bottoms. D = 30"x30"x12"*All rebar in footings to

have 3" cover. Header Schedule

- King Stud Schedule: 0'-3' wide = (1)2x4 @ EE A = (2)2x6 w/ (1) 2x4 Jack @ EEB = (2)2x8 w/(2) 2x4 Jack @ EE3'-6' wide = (2)2x4 @ EE C = (2)2x10 w/ (2) 2x4 Jack 06'-9' wide = (3)2x4 @ EE EE D = (2)2x12 w/(3) 2x4 Jack* If wall is 2x6,
- @ EE E = (2) 9 1/4" LVL w/ (3) 2x4 Js @ EE
- king studs shall be 2x6. Use 2x6 studs in 2x6 walls. In 2x6 walls use 3 plv headers

Stud Schedule for Walls 10' or Taller (supporting 1 + roof)

(Max)	Interior (Load Bearing)	Exterior (Load Bearing or Non-Bearing)	Non-Bearing (INT)
10'	2x4@ 16" O.C.	2x4@ 16" O.C.	2x4@ 24" O.C.
11'	2x4@ 12" O.C. 2x6 @ 16" O.C.	2x4@ 12" O.C. w/ B&S 2x6 @ 16" O.C.	2x4@ 24" O.C.
12'	2x4@ 12" O.C. 2x6 @ 16" O.C.	2x4@ 12" O.C. w/ B&S 2x6 @ 12" O.C.	2x4@ 16" O.C.
13'	(2)2x4@ 16" O.C. 2x6 @ 16" O.C.	(2)2x4@12"O.C.w/ B&S 2x6 @ 12" O.C. w/ B&S	2x4@ 16" O.C. w/ B
14'	2x4@ 12" O.C. w/B 2x6 @ 12" O.C.	(2)2x4@12"O.C.w/ B&S 2x6 @ 12" O.C. w/ B&S	2x6 @ 16" O.C.
15'	(2)2x4@ 12" O.C. w/B 2x6 @ 12" O.C. w/B	(2)2x6 @16"O.C. w/ B&S	2x6 @ 16" O.C. w/B (2)2x4@ 16" O.C. w/B
16'	(2)2x4@ 12" O.C. w/B 2x6 @ 12" O.C. w/B		2x6 @ 12" O.C. (2)2x4@ 16" O.C. w/B
		d2.48ne,1Exposure B, L/2	

B= Blbt/Ring-x6x Horizontal blocking at 6' o.c. vert. with (2)

- 10d nails @ EE
- S= Strapping: CS22 strapping to the interior face of the center 2/3rd height of every other stud. Half populate with 10d x 1.5"
- If wall supports 2 stories and a roof, $\ \underline{add}\ 2\,{}^{\prime}$ to the actual wall height and apply the table.
- If wall supports only roof, <u>subtract</u> 2' to the wall actual wall height and apply the table.

Framing Notes:

- All dimensional lumber to be Spruce Pine Fir No.2 or better.
- 2. Engineered Beams single ply = 1.75" wide w/ Fb of: LVL= 2600 psi, LSL = 2325 psi. PSL (columns) shall be 3.5" wide w/ F'b = 1344 psi
- 3. All floor framing per NCRC 2018 CH 5. All Wall framing per NCRC 2018 CH6.
- All I-joists and floor truss framing per supplier's specifications and layout.
- All structural steel shall be ASTM A-36; Fy= 36 KSI.
- All weld material shall be 70 KSI material.
- All welds to be installed by a certified AWS welder.
- Install double joist under all walls parallel with joists.
- Typically, load bearing walls (LBW) are shown hatched in red. Nearby girders and beams should be assumed to be directly supporting these

LBWs, UON.

- All LVL beams of 3 ply or more shall be fastened with ½" dia
 - at 16" o.c. staggered w/ 2" min edge distance from top/bottom edge UON. 2 ply LVLs shall be fastened with (4) #9 3" long wood screws UON
- Circled numbers indicate number of 2x4/2x6 studs in a stud column. Strap all stud columns of 4 or more with (3) horizontal CS22 straps.
- All beam bearings shall be no less than 3". All other bearing to
- 13. All hangers shall be standard, appropriately sized face mounted UON. Consult Simpson catalog or local supplier. High capacity hangers will be load rated on plans.
- 14. Install all hardware per manufacturer's guidelines.

Lateral Bracing:

- 1. Unless otherwise noted, lateral bracing is found sufficient and compliant with minimum requirements set forth in NCRC 2018 Table R602.10.2 provided all exterior walls are sheathed at the exterior per CS-WSP, R602.10.3 which includes 2x4 (min) studs at 16" o.c. sheathed with 7/16" OSB w/ (1)8d nail at 6"
 - o.c. edge and (1)8d nail at 12" o.c. field. Typically, required length of CS-WSP at each designated shear walls are shown on plans.
- 2. All noted Portal Frame (P-F) shall be compliant with R602.10.1
- 3. All locations noted with "HD" shall be 800 lbs min capacity. Options include 36" long CS16 straps fully populated with 10d nails, centered at interface, Simpson MSTC66B3Z or Simpson LSTA21. Install CS16 strap from top plate to 16" below top of
- 4. Minimum corner return in each direction shall be 24" of wood structural panel unless otherwise noted.
- 5. Walls noted as GB2 shall be framed in accordance with R602.10.2

- 1. All lumber to be pressure treated Spruce Pine Fir No.2 or better.
- Band attachments to be installed per NCRC 2018, Appendix M (AM 104.1(1))
- Install lateral bracing AM109.1
- 4. Install handrails per AM111.1 5. Max Post Heights per AM 108.1
- 6. Stair Stringers per AM 110.1

Screened in and Covered Porch Notes:

- 1. All wood deck notes apply.
- 2. Posts to be attached to footings, slab or CMU piers using ABU44 or ABU66 post base (or applicable size).
- 3. Uplift for posts to headers may be either (2) Simpson LCE4, (2) Simpson GA1 clips with 3" long #9 screws or (4) ¼" diameter, 5" long LedgerLoks driven
 - at a 45" degree angle to each side of posts or notched 50% width w/ (2) LedgerLoks.
- 4. Uplift for posts to floor framing may be either (2) Simpson GA1
 - clips with 3" long #9
 - screws
 - or (4) ¼" diameter, 5" long LedgerLoks driven
 - at a 45" degree angle to each side.

Roof Framing Notes:

- 1. All roof framing shall be in accordance with NCRC 2018 CH 9.
- 2. All dimensional lumber to be Spruce Pine Fur No.2 or better.
- 3. All flat valleys for over-framed roofs shall
 - attached using (3) 3" long #9 screws at each main rafter.
- 4. Sheath with 7/16" OSB w/8d nails at 6" o.c. edge and 12" o.c. field.
- 5. All rafter ties to be installed no higher
 - 1/3rd height eave to ridge up from eave nailed with (5) 10d nails at each end, UON
- 6. Roof trusses per others; installation per supplier guidelines.

General Construction Notes

- 1. All temporary shoring, means and methods are the responsibility of the contractor.
- 2. All dimensions to be verified by the contractor in the field.
- 3. Takla Engineering assumes no responsibility for safety of project delivery.
- 4. Any questions pertaining to structural components
 - should be immediately brought to the attention of Takla Engineering.
- 5. Limitations: Services provided are in accordance with the standard of practice for structural engineering and within the limits imposed by scope, schedule and budget. The determinations contained in this report are based on conditions observed at the time of the evaluation. No quarantees or warranties, expressed or implied, under this Agreement or otherwise, shall be construed in connection with services provided. Sequencing, shoring, means and methods of construction are considered beyond the scope of this design. Takla Engineering shall not be responsible for any safety aspect of Work.

Abbreviations:

ADDIC V	Tactons.	
•	CONC	Concrete
•	CONT.	Continuous
•	C.J	Ceiling Joists
•	CMU	Conc Masonry
	CS-WSP	Unit
	DIA	Sheathing per
•	DBL	R602.10.3 Diameter
	DJ / DR	Double
•	EO	Double Joist /

ΕQ Rafter Equal ΕE Each End FJ FND Floor • FT Joist

FTG Foundation GB Floor GRT HGR Truss

HD Footing T.BW Gypsum Board (shear

MANUF wall) Girder Roof Truss NTS

Hanger O.C. Holddowns O.F. Load Bearing PF Wall

PLManufacturer P.T. Not To R.T. Scale On SC

Center SIM Over-framed STGR (roof) Portal

SUP Frame TYP.

Point Load Pressure Treated Roof Truss

Stud Column Similar

Staggered Supplier [ypical

J<mark>hless Oth</mark> Harnett

RTH CARO SEAL 050695

₽

Takla, Paklano Andy

 α \Box --Company Ы α >аy ndn Ŋ ng $\check{\Box}$ ĹΤΙ D \vdash Н --0 0 щ ma \geq en ami \vdash

 \sim

] For Construction [X] Not for Construction PROJ# 0086-21

DATE: 1/23/21

REVISIONS: 1 OF 1 SHEET TITLE:

STRUCTURAL NOTES

HEET:

SD-1