

B L E G E N R E M O D E L


PROJECT #
DRB2001-0046
DATE
11/30/20
DESIGNED BY
KR
CHECKED BY
DRB
SCALE
1/4" = 1'-0"

PROJECT NAME
ATTIC
REMODEL


HEATED/HABITABLE SQUARE FOOTAGE	
Remodel	855
TOTAL HEATED	855

NOTE:
ALL INTERIOR WALLS
ARE NOMINAL 4" UNO

NOTE:
ALL DIMENSIONS ARE
FRAME TO FRAME



ATTIC REMODEL
1/4" = 1'-0" CLG HGT. = EXIST.



reidbyrd@drbhomedesign.com 919.631.5979
250 Shipwash Dr Suite 105 Garner, NC 27529


1. DRB DESIGN assumes no liability for any home constructed from this plan.
2. All construction shall conform to the latest requirements of "North Carolina State 2018 residential building code" in addition to all local codes and regulations.
3. Should these plans require structural calculations for permitting the contractor shall be required to obtain the services of a structural engineer after notifying DRB DESIGN that such services are required.
4. Release of these plans requires further cooperation among the owner, his/her contractor, and DRB DESIGN.
5. Design and construction are complex and, although the designer performed his services with due care and diligence, perfection is not a guarantee.
6. Communication is imperfect and every contingency cannot be anticipated.
7. Any ambiguity or discrepancy discovered by the use of these plans shall be reported immediately to DRB DESIGN. Failure to notify the DRB DESIGN compounds misunderstandings and increases construction costs.
8. A failure to cooperate by a simple notice to DRB DESIGN shall relieve the designer from any and all responsibilities for all consequences.
9. Changes made to these plans without the consent of the designer are unauthorized and shall relieve DRB DESIGN of responsibility for any and all consequences arising out of such changes.
10. Written dimensions on these plans always have precedence over scaled dimensions.
11. It is the contractors responsibility to verify and be responsible for all dimensions and square footage prior to construction, as well as conditions on the job site. DRB DESIGN is not responsible for dimension and square footage errors once construction has begun.
12. DRB DESIGN must be notified of any variations from the dimensions and conditions shown on these drawings.

CLIENT NAME
Dana Blegen
188 Saddle Ln Lillington, NC 27546
910-322-4925
dsblegen@gmail.com

SHEET NAME
FLOOR PLAN
SHEET #

A1
of 1

Engineers seal does not include construction means, methods, techniques, sequences, procedures or safety precaution.
 Any deviations or discrepancies on plans are to be brought to the immediate attention of Tyndall Engineering & Design, P.A. Failure to do so will void Tyndall Engineering & Design, P.A. liability.
 Please review these documents carefully. Tyndall Engineering & Design, P.A. will interpret that all dimensions, recommendations, etc. presented in these documents were deemed acceptable once construction begins.



TYNDALL
ENGINEERING & DESIGN, P.A.



T 919 773-3200 • F 919 774-9488
 280 Shipwash Drive • Garner • North Carolina • 27529
 www.tyndallengineering.com


Client: DANA BLEGEN
 Title: ATTIC REMODEL

**1ST FLR. HEADER
 2ND FLR. FRMG.**

Project #: DRB2001-0046
 Date: 12/30/20
 Drawn/Design By: JTT
 DWG. Checked By: PAT
 Scale: SEE PLAN

REVISIONS		
No.	Date	Remarks

Sheet Number
S1
 2 of 4



STRUCTURAL NOTES:
 1.- VERIFY ALL OPENINGS <4'-0" HAVE MIN. (2) 2 X 8 HEADER W/2SC E/E, TYP. @ALL LOAD BEARING WALLS
 2.- VERIFY (3) 2X10 GIRDERS @CRAWL SPACE UNDER LOAD BEARING WALLS DO NOT SPAN OVER 6'-3". IF SO, ADD 16" X 16" MASONRY PIER ON A 30" X 30" X 10" CONC. FTG. @MID-POINT. BETWEEN EXISTING SUPPORT PIERS.

FIRST FLOOR PLAN
 1/4" = 1'-0"

FILENAME: Z:\DRB_2001\DRB2001-0046_DANA_BLEGEN\DWG_FILES\DRB2001-0046_1 - RENOVATED SHED BY JOHNNY LAST PLOT DATE: 12/29/2021 11:40 AM


DESIGN LOADS

	LIVE LOAD (PSF)	DEAD LOAD (PSF)	DEFLECTION	
			LL	TL
FLOOR (primary)	40	10	L/360	L/240
FLOOR (secondary)	40	10	L/360	L/240
ATTIC (w/ storage)	20	10	L/240	L/180
ATTIC (no access)	10	5	L/240	L/180
EXTERNAL BALCONY	40	10	L/360	L/240
ROOF	20	10	L/240	L/180
ROOF TRUSS	20	20	L/240	L/180
WIND LOAD	BASED ON 120 MPH (EXPOSURE B)			
SEISMIC	BASED ON SEISMIC ZONES A, B & C			

STRUCTURAL NOTES:

- ALL CONSTRUCTION SHALL CONFORM TO THE LATEST REQUIREMENTS OF "NORTH CAROLINA STATE 2018 RESIDENTIAL BUILDING CODE", IN ADDITION TO ALL LOCAL CODES AND REGULATIONS.
- IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND SQUARE FOOTAGE PRIOR TO CONSTRUCTION. TYNDALL ENGINEERING & DESIGN, PA IS NOT RESPONSIBLE FOR DIMENSIONS AND SQUARE FOOTAGE ERRORS ONCE CONSTRUCTION BEGINS.
- ALL LUMBER SHALL BE SYP #2 (UNO)
ALL LVL LUMBER TO BE 1.75" WIDE NOMINAL EACH SINGLE MEMBER AND Fb = 2600 PSI, E = 1.9M PSI
(I.E. I LEVEL MICROLAM)
ALL LSL LUMBER IS TO BE 1.55E (Fb = 2325 PSI)

- ALL LOAD BEARING EXTERIOR WINDOW HEADERS WITH MAXIMUM SPAN OF 5'-6" SHOULD BE A (2) 2x10 w/ (1) 2x4 KING STUD AND (1) 2x4 JACK STUD NAILED TOGETHER w/ (2) 10d @ 8" O.C. PROVIDED THAT THE TOP OF THE WINDOW HEIGHT IS 6'-3" MINIMUM BOTTOM OF THE WINDOW HEIGHT IS 1'-6", OTHERWISE REFER TO TABLE R502.5(1).
- ALL INTERIOR LOAD BEARING HEADERS TO BE (2) 2x10 (U.N.O.) REFER TO TABLE R502.5(1) FOR JACK STUD REQUIREMENTS FOR HEADER SPANS FOR INTERIOR AND EXTERIOR LOAD CONDITIONS (UNO)
- REFER TO 2018 NC BUILDING CODE SECTION R602 FOR CONSTRUCTION OF ALL WALLS OVER 10'-0" IN HEIGHT.
- ALL STRUCTURAL STEEL SHALL BE ASTM A992 GRADE 50
Fy = 50 KSI MIN. (UNO)
- ALL EXTERIOR LUMBER TO BE #2 SYP PT
- ALL CONCRETE, fc = 3000 PSI MIN.
- PRESUMPTIVE BEARING CAPACITY = 2000 PSF
- 1/2" ANCHOR BOLTS SPACED AT MAXIMUM OF 6'-0" O.C. AND NOT MORE THAN 12" FROM THE CORNER. THERE SHALL BE A MINIMUM OF (2) BOLTS PER PLATE SECTION. ANCHOR BOLTS SHALL BE SPACED AT 3'-0" O.C. FOR BASEMENTS. ANCHOR BOLT SHALL EXTEND 7" INTO CONCRETE OR MASONRY.
- PSL COLUMNS DESIGNED WITH MAX. HEIGHT OF 9'-0" (UNO)
- PROVIDE A MINIMUM OF 500# UPLIFT & LATERAL CONNECTION AT TOP AND BOTTOM OF PORCH COLUMNS. (U.N.O.)
- PROVIDE CONTINUOUS SHEATHING PER SECTION 602.10.4 OF THE 2018 IRC. MAXIMUM MASONRY PIER HEIGHT SHALL NOT EXCEED FOUR TIMES ITS LEAST HORIZONTAL DIMENSION.
- UPLIFT LOADS GREATER THAN 500# SHALL BE CONTINUOUSLY ANCHORED TO THE FOUNDATION.
- METAL HANGERS SHALL BE SIMPSON OR APPROVED EQUAL.



ATTIC REMODEL
1/4" = 1'-0" CLG HGT. = EXIST.

* Engineers seal does not include construction means, methods, techniques, sequences, procedures or safety precaution.
* Any deviations or discrepancies on plans are to be brought to the immediate attention of Tyndall Engineering & Design, P.A.
* Failure to do so will void Tyndall Engineering & Design, P.A. liability.
* Please review these documents carefully.
Tyndall Engineering & Design, P.A. will interpret that all dimensions, recommendations, etc. presented in these documents were deemed acceptable once construction begins.



TYNDALL ENGINEERING & DESIGN, P.A.
 280 Shipwash Drive • Garner • North Carolina • 27839
 T 919 773-3200 • F 919 773-9488
 www.tyndallengineering.com

Client: **DANA BLEGEN**
 Title: **ATTIC REMODEL**

2ND FLR. HDR. 2ND FLR. CLG.

Project #:	DRB2001-0046
Date:	12/30/20
Drawn/Design By:	JTT
DWG. Checked By:	PAT
Scale:	SEE PLAN

REVISIONS		
No.	Date:	Remarks

Sheet Number
S2
3 of 4

STRUCTURAL NOTES

1) ALL CONSTRUCTION SHALL CONFORM TO THE LATEST REQUIREMENTS OF "NORTH CAROLINA STATE 2018 RESIDENTIAL BUILDING CODE", IN ADDITION TO ALL LOCAL CODES AND REGULATIONS.

DESIGN LOADS	LIVE LOAD (PSF)	DEAD LOAD (PSF)	DEFLECTION	
			LL	TL
ALL FLOORS	40	10	L/360	L/240
ATTIC (w/ walk up stairs)	30	10	L/360	L/240
ATTIC (w/ no access)	20	10	L/240	L/180
ATTIC (w/ access)	10	5	L/240	L/180
EXTERNAL BALCONY	40	10	L/360	L/240
ROOF	20	10	L/240	L/180
ROOF TRUSS	20	20	L/240	L/180
WIND LOAD	BASED ON 120 MPH (EXPOSURE B)			
SEISMIC	SEISMIC ZONES A, B & C			

- 3) MINIMUM ALLOWABLE SOIL BEARING PRESSURE = 2000 PSF
- 4) CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI AND A MAXIMUM SLUMP OF FIVE INCHES UNLESS NOTED OTHERWISE. (U.N.D.)
- 5) MAXIMUM DEPTH OF UNBALANCED FILL AGAINST FOUNDATION WALLS TO BE LESS THAN 4'-0" WITHOUT USING SUFFICIENT WALL BRACING. REFER TO SECTION 904.4 OF 2018 NC BUILDING CODE FOR BACKFILL LIMITATIONS BASED ON WALL HEIGHT, WALL THICKNESS, SOIL TYPE, AND UNBALANCED BACKFILL HEIGHT.
- 6) ALL FRAMING LUMBER SHALL BE SYP #2 (F_b = 900 PSI, BASED ON 2x10) UNO. ALL FRAMING LUMBER EXPOSED TO THE ELEMENTS SHALL BE TREATED MATERIAL. ALL LV LUMBER TO BE 1 1/2" WIDE NOMINAL EACH SINGLE MEMBER AND F_b = 2000 PSI, E = 1.9M PSI (U.N.D.). ALL LS LUMBER TO BE 3" WIDE NOMINAL EACH SINGLE MEMBER AND F_b = 2200 PSI, E = 1.9M PSI (U.N.D.). ALL PSL LUMBER TO BE 3" WIDE NOMINAL EACH SINGLE MEMBER AND F_b = 2400 PSI, E = 1.9M PSI (U.N.D.).
- 7) ALL LOAD BEARING EXTERIOR HEADERS SHALL BE AT (2) 2x10 (U.N.D.) REFER TO TABLE R602.7(1) & (2) FOR JACK STUD REQUIREMENTS FOR HEADER SPANS FOR INTERIOR AND EXTERIOR LOAD CONDITIONS UNLESS SPECIFICALLY NOTED ON PLANS.
- 8) ALL STRUCTURAL STEEL W-SHAPES (I-BEAMS) SHALL BE ASTM A992 GRADE 50. ALL STEEL ANGLES, PLATES, AND C-CHANNELS SHALL BE ASTM A36. ALL STEEL PIPE SHALL BE ASTM A53 GRADE B.
- 9) STEEL BEAMS SHALL BE SUPPORTED AT EACH END WITH A MINIMUM BEARING LENGTH OF 3'-12" AND FULL FLANGE WIDTH. PROVIDE SOLID BEARING FROM BEAM SUPPORT TO FOUNDATION. BEAMS SHALL BE ATTACHED TO EACH SUPPORT WITH TWO (2) LAG SCREWS (1 1/2" x 4" LONG). LATERAL SUPPORT IS CONSIDERED ADEQUATE FOR THE JOISTS ARE TOE NAIL TO THE SOLE PLATES, AND THE SOLE PLATES ARE NAILED OR BOLTED TO THE BEAM FLANGES @ 48" O.C.
- 10) PROVIDE ANCHOR BOLT PLACEMENT PER SECTION 403.1.6: 1/2" Ø ANCHOR BOLTS SPACED AT 6'-0" O.C. AND PLACED 12" FROM THE END OF EACH PLATE SECTION. ANCHOR BOLTS SHALL BE SPACED AT 3'-0" O.C. FOR BASEMENTS. ANCHOR BOLT SHALL EXTEND 7" INTO CONCRETE OR MASONRY. THE BOLTS SHALL BE LOCATED THE MIDDLE THIRD OF THE WIDTH OF THE PLATE. THERE SHALL BE A MINIMUM TWO ANCHOR BOLTS PER PLATE SECTION.
- 11) FOUNDATION DRAINAGE DAMP PROOFING OR WATERPROOFING PER SECTION 405 AND 406 OF NC BUILDING CODE.
- 12) WALL AND ROOF CLADDING VALUES:
WALL CLADDING SHALL BE DESIGNED FOR 28.0 POUNDS PER SQUARE FOOT (LBS/SQFT) OR GREATER POSITIVE AND NEGATIVE PRESSURE. ROOF VALUES BOTH POSITIVE AND NEGATIVE SHALL BE AS FOLLOWS:
38.0 LBS/SQFT FOR ROOF PITCHES 0/12 TO 1/12
36.0 LBS/SQFT FOR ROOF PITCHES 1 1/2 TO 6/12
18.0 LBS/SQFT FOR ROOF PITCHES 6/12 TO 12/12
"MEAN ROOF HEIGHT" 30" OR LESS
- 13) FOR ROOF SLOPES FROM 2/12 THROUGH 4/12, BUILDER TO INSTALL 2 LAYERS OF 15# FELT PAPER.
- 14) REFER TO SECTION R602.3 FOR FRAMING OF ALL WALLS OVER 10'-0" IN HEIGHT.
- 15) PROVIDE CONTINUOUS SHEATHING PER SECTION 602.10.3 OF THE 2018 NRC.
- 16) UPLIFT LOADS GREATER THAN 500# SHALL BE CONTINUOUSLY ANCHORED TO THE FOUNDATION.
- 17) REFER TO TABLE N1102.1 FOR PRESCRIPTIVE BUILDING ENVELOPE THERMAL COMPONENT CRITERIA.
- 18) PSL COLUMNS DESIGNED WITH MAXIMUM HEIGHT OF 9'-0" (U.N.D.)
- 19) PROVIDE A MINIMUM OF 500# UPLIFT & LATERAL CONNECTION AT TOP AND BOTTOM OF PORCH COLUMNS. (U.N.D.)
- 20) MAXIMUM MASONRY PER HEIGHT SHALL NOT EXCEED FOUR TIMES ITS LEAST HORIZONTAL DIMENSION.
- 21) IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND SQUARE FOOTAGE PRIOR TO CONSTRUCTION. TYNDALL ENGINEERING & DESIGN, P.A. IS NOT RESPONSIBLE FOR DIMENSION OR SQUARE FOOTAGE ERRORS ONCE CONSTRUCTION BEGINS.

DEFINITIONS FOR COMMON ABBREVIATIONS

ALT = ALTERNATE	MAX = MAXIMUM
CANT = CANTILEVER	MIN = MINIMUM
CJ = CEILING JOIST	NOM = NOMINAL
CMU = CONCRETE MASONRY UNIT	O.C. = ON CENTER
COL = COLUMN	PL = POINT LOAD
CONC = CONCRETE	PT = PRESSURE TREATED
CONT = CONTINUOUS	RENF = REINFORCED
CT = COLLAR TIE	REQD = REQUIRED
DBL = DOUBLE	RJ = ROOF JOIST
DA = DIAMETER	RS = ROOF SUPPORT
DJ = DOUBLE JOIST	SC = STUD COLUMN
DR = DOUBLE RAFTER	SCH = SCHEDULE
EA = EACH	SPEC = SPECIFIED
EE = EACH END	THK = THICK
FJ = FLOOR JOIST	TJ = TRIPLE JOIST
FND = FOUNDATION	TRTD = TREATED
FTD = FOOTING	TYP = TYPICAL
GALV = GALVANIZED	UNO = UNLESS NOTED OTHERWISE
HORIZ = HORIZONTAL	W = WIDE FLANGE BEAM
HT = HEIGHT	WWF = WELDED WIRE FABRIC
MANUF = MANUFACTURER	XJ = EXTRA JOIST

1) MAXIMUM HEIGHT OF DECK SUPPORT POSTS AS FOLLOWS:


POST SIZE	MAX. POST HEIGHT**
4 x 4	8'-0"
6 x 6	20'-0"
***	OVER 20'-0"

* THIS TABLE IS BASED ON NO. 2 TREATED SOUTHERN PINE POSTS. MAXIMUM TRIBUTARY AREA IS BASED ON 128 TOTAL SQUARE FEET WHICH MAY BE LOCATED AT DIFFERENT LEVELS.
FROM TOP OF FOOTING TO BOTTOM OF GIRDER
** DECKS WITH POST HEIGHTS OVER 20'-0" SHALL BE DESIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR REGISTERED ARCHITECT.


- 2) DECKS SHALL BE BRACED TO PROVIDE LATERAL STABILITY BY ONE OF THESE METHODS:
- A. THE DECK FLOOR HEIGHT IS LESS THAN 4'-0" AND THE DECK IS ATTACHED TO THE STRUCTURE IN ACCORDANCE WITH SECTION (H) ABOVE. LATERAL BRACING IS NOT REQUIRED.
- B. 4 x 4 WOOD KNEE BRACES MAY BE PROVIDED ON EACH COLUMN IN BOTH DIRECTIONS. THE KNEE BRACES SHALL ATTACH TO EACH POST AT A POINT NOT LESS THAN 1/3 OF THE POST LENGTH FROM THE TOP OF THE POST, AND THE BRACES SHALL BE ANGLED BETWEEN 45° AND 60° FROM THE HORIZONTAL. KNEE BRACES SHALL BE BOLTED TO THE POST AND GIRDER WITH ONE 5/8" Ø HOT DIPPED GALVANIZED BOLT AT EACH END OF THE BRACE.
- C. FOR FREESTANDING DECKS WITHOUT KNEE BRACES OR DIAGONAL BRACING, LATERAL STABILITY MAY BE PROVIDED BY EMBEDDING THE POSTS IN ACCORDANCE WITH THE FOLLOWING:

POST SIZE	MAX. TRIBUTARY AREA	MAX. POST HEIGHT	EMBEDMENT DEPTH	CONCRETE DIAMETER
4 x 4	48 SQ. FT.	4'-0"	2'-6"	1'-0"
6 x 6	120 SQ. FT.	8'-0"	3'-6"	1'-8"

- D. 2 x 6 DIAGONAL VERTICAL CROSS BRACING MAY BE PROVIDED IN TWO (2) PERPENDICULAR DIRECTIONS FOR FREESTANDING DECKS OR PARALLEL TO THE STRUCTURE AT THE EXTERIOR COLUMN LINE FOR ATTACHED DECKS. THE 2 x 6s SHALL BE ATTACHED TO THE POSTS WITH ONE 5/8" Ø HOT DIPPED GALVANIZED BOLT AT EACH END OF EACH BRACING MEMBER.
- E. FOR EMBEDMENT OF PILES IN COASTAL REGIONS, SEE CHAPTER 46.



NO SCALE
ONE-STORY ON CRAWL
TYPICAL WALL DETAIL



NO SCALE
DROPPED GIRDER DETAIL

HARDWARE CROSS-REFERENCE CHART

SIMPSON STRONG-TIE	USP STRUCTURAL CONNECTORS
PRODUCT NUMBER	PRODUCT NUMBER
A35	MPA1
ABE	PAE
CBSQ	CBSQ
CCQ	KCCQ
CMSTC16	CMSTC16
CS	RS
HT	RT15
H2-SA	RTTA
H10	RT16
HDDR-SDS3	UPHDB
HDDR-SDS2.5	PHD2
HDS-SDS2.5	PHD5
HETA	HTA
HGAM10KTA	HGAM
HDDQ14-SDS2.5	UPHD14
HHS	HTW
HTT	HTT
HUS	HUS
LTA1	LPTA
LTAH26	NCH26
LTA	NCH
LUS	AUS
MAS	FA3
MSTAM	MSTAM
PC	PCM
PHD-SD3	PHD
SSP	RSP16
STC	TRI
STHD	STAD

CLIMATE ZONES	FENESTRATION U-FACTOR ^a	SKYLIGHT U-FACTOR ^b	GLAZED FENESTRATION SHGC ^c	CEILING R-VALUE ^d	WOOD FRAMED WALL R-VALUE ^e	MASS WALL R-VALUE ^f	FLOOR R-VALUE ^g	BASEMENT ^h WALL R-VALUE	SLAB ⁱ R-VALUE AND DEPTH	CRAWL SPACE ^j WALL R-VALUE
3	0.35	0.55	0.30	38 or 30 cont.	15 or 13 + 2.5 n	5/13 or 5/13 cont.	19	5/13 ¹	0	5/13
4	0.35	0.55	0.30	38 or 30 cont. j	15 or 13 + 2.5 n	5/13 or 5/13 cont.	19	10/15	10	10/15
5	0.35	0.55	NR	38 or 30 (cont. j)	19 or 13 + 5 or 15 + 3	13/17 or 13/12.5 cont.	30 ⁹	10/15	10	10/15

TABLE N1102.1 CLIMATE ZONES 3-5

NO SCALE

a. R-VALUES ARE MINIMUM U-FACTORS AND SHGC ARE MAXIMUMS. WHEN INSULATION IS INSTALLED IN A CAVITY WHICH IS LESS THAN THE LABEL OR DESIGN THICKNESS OF THE INSULATION, THE INSTALLED R-VALUE OF THE INSULATION SHALL NOT BE LESS THAN THE VALUE SPECIFIED IN THE TABLE.

b. THE FENESTRATION U-FACTOR TO BE USED FOR UNGLAZED SKYLIGHTS, THE SOLAR HEAT GAIN COEFFICIENT (SHGC) COLUMN APPLIES TO ALL GLAZED FENESTRATION.

c. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.

d. FOR MASONRY WALLS, INSULATION SHALL BE APPLIED FROM THE EXTERIOR (WALL POINTING) TO THE BOTTOM OF THE COURSE OF MASONRY. FOR BRICK OR BLOCK, INSULATION SHALL BE APPLIED TO THE EXTERIOR OF THE COURSE OF MASONRY OR TO THE INTERIOR OF THE COURSE OF MASONRY. INSULATION SHALL EXTEND TO THE BOTTOM OF THE COURSE OF MASONRY OR TO THE INTERIOR OF THE COURSE OF MASONRY.

e. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.


f. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.

g. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.

h. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.


i. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.

j. 100% MEANS IS CONTINUOUS INSULATION BRACING ON THE EXTERIOR OR INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE DECK OR IS GLAZED INSULATION AT THE INTERIOR OF THE EXTERIOR WALL OR WINDOW.



NO SCALE
FLUSH GIRDER DETAIL

* Engineers seal does not include construction means, methods, techniques, sequences, procedures or safety precautions.
* Any deviations or discrepancies on plans are to be brought to the immediate attention of Tyndall Engineering & Design, P.A. Failure to do so will void Tyndall Engineering & Design, P.A. liability.
* Please review these documents carefully. Tyndall Engineering & Design, P.A. will interpret that all dimensions, recommendations, etc. presented in these documents were deemed acceptable once construction begins.



TYNDALL ENGINEERING & DESIGN, P.A.

199 773-1200 • F 919-774-9488
www.tyndalldesign.com

280 Shipwash Drive • Garner • North Carolina • 27839

CLIMATE: DANA BLEGEN
DATE: ATTIC REMODEL

STANDARD DETAILS

Project #: DRB2001-0046
Date: 12/30/20
Drawn/Design By: JTT
DWG. Checked By: PAT
Scale: NOT TO SCALE

No.	Date:	Remarks

Sheet Number
D1
4 of 4