



4055 HIGHWAY 401 SOUTH
LILLINGTON, NC 27546

"23-3276-16 061720"
3 BEDROOM 3 BATH
2305 SQ. FT.

A HOME DESIGNED FOR:

5/12, 130 Vult MAX

SHEET INDEX

- CP-101 COVER SHEET
- GE-101 GENERAL NOTES
- L-101 LITERATURE PLAN
- EV-101 ELEVATIONS
- EV-102 ELEVATIONS
- EV-103 ELEVATIONS
- EV-104 ELEVATIONS
- AP-101 FLOOR PLAN
- AP-201 STRUCTURAL BRACING
- AP-202 STRUCTURAL BRACING DETAILS
- AP-203 STRUCTURAL BRACING DETAILS
- EP-101 ELECTRICAL PLAN
- PP-101 DWV PLAN OFF-FRAME

SHEET INDEX-CONT.

- W-101 WATER LINE PLAN
- SE-101 SECTION PLAN OFF-FRAME
- F-101 PERIMETER FOUNDATION PLAN
- F-102 PERIMETER FOUNDATION DETAILS
- F-103 PERIMETER FOUNDATION DETAILS
- APPENDIX E
- WORK SHEET 1 VENT CALCS
- WORK SHEET 2 BRACEWALL CALCS
- SHEARWALL CALCULATIONS SHEETS SECTION 6 PAGES 1-30 (PFS REVIEW ONLY)
- HVAC CALCULATIONS PGS 1-7



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Swale*
Title: Staff Plan Reviewer
Date: 8/18/21

APPROVED FOR THE PROJECT TO COVER THE DESIGN AND CONSTRUCTION OF THE FACTORY BUILT PORTION OF THE PROJECT.
APPROVED BY: *Tim Swale*
DATE: 02/07/2022



**Harnett
COUNTY**
NORTH CAROLINA

THIS MODEL NOT DESIGNED FOR OCEAN HIGH HAZARD AREAS OR SPECIAL MOUNTAIN REGIONS OR FLOOD ZONES OR SPECIAL WIND REGIONS.



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

| |
|----------------------------------|
| TITLE |
| COVER SHEET |
| MODEL: |
| 23-3276-16 061720 |
| 30'-0" x 75'-0" 3 BEDROOM 3 BATH |
| DATE: 8-17-20 |
| SCALE: |
| DRAWN BY: TT |
| REVISED: |
| REVISIONS: |

| |
|-----------|
| SHEET NO: |
| CP-101 |
| PAGE: |

| | | | | | |
|----------|--------------------------|-------------------------|-----------------------|-------------------------|---|
| STATE | GENERAL: | ELECTRICAL: | PLUMBING: | MECHANICAL: | ENERGY: |
| NC CODES | 2018 NC RESIDENTIAL CODE | 2017 NC ELECTRICAL CODE | 2018 NC PLUMBING CODE | 2018 NC MECHANICAL CODE | 2018 NORTH CAROLINA ENERGY CONSERVATION CODE N1102.1.2 and Appendix E used for code compliance |

GENERAL NOTES

- ALL GLAZING WITHIN 24 INCH ARC OF DOORS, WHOSE BOTTOM EDGE IS LESS THAN 80 INCHES ABOVE THE FLOOR, AND ALL GLAZING IN DOORS SHALL BE SAFETY, TEMPERED OR ACRYLIC PLASTIC SHEET.
- OCCUPANT LOAD IS BASED ON 1 PERSON PER 200 SQUARE FEET OF FLOOR AREA.
- ALL STEEL STRAPS REFERENCED ON FLOOR PLAN SHALL BE 1/2 INCH X 28 GA. MIN.
- CEILING FANS SHALL BE 80 INCHES MIN. FROM BOTTOM OF BLADES TO FINISH FLOOR.
- MINIMUM CORRIDOR WIDTH IS 36 INCHES.
- ALL WINDOWS SHALL BE DOUBLE GLAZED.
- EXTERIOR DOORS SHALL HAVE AN INSULATION VALUE OF R-1.66 MINIMUM.
- FIRE STOPPING AND AIR INFILTRATION BARRIER BETWEEN UNITS SHALL BE PROVIDED BY DRAFTSTOP BRAND NONCOMBUSTIBLE FILLER COMPOUND OR EQUAL MEETING ASTM-E136, R902.8
- HOMES GOING INTO RADON AREAS WILL HAVE A 3 VTR AND SWITCH LEG TO SWITCH LABELED "RADON" ON TRIM PLATE.
- LOCATION MAY VARY PER MODEL.
- THIS HOME DESIGNED FOR JUP TO, CLIMATE ZONE 4 FOR VA
- FOR NC & SC AND CLIMATE ZONE 4A FOR VA
- THE MANUFACTURER MUST BE INFORMED IF HOME IS TO BE LOCATED IN HIGHER CLIMATE ZONE.
- THE MANUFACTURER MUST BE INFORMED IF THE HOME IS TO BE LOCATED IN THE CITY OF CHARLESTON, S.C.
- THE MANUFACTURER MUST BE INFORMED IF THE HOME IS TO BE LOCATED IN ANY SPECIAL MOUNTAIN REGION.
- THIS PLAN MAY BE FLIPPED END TO END AND/OR MIRRORED

PLUMBING NOTES

- THIS UNIT MUST BE CONNECTED TO PUBLIC WATER SUPPLY AND SEWAGE SYSTEM IF THESE SERVICES ARE AVAILABLE
- ALL PLUMBING FIXTURES SHALL HAVE SEPARATE SHUT-OFF VALVES.
- WATER HEATER SHALL HAVE A SAFETY PAN WITH 1 INCH DRAIN TO EXTERIOR.
- WATER PIPES INSTALLED IN A WALL, EXPOSED TO THE EXTERIOR SHALL BE LOCATED ON THE HEATED SIDE OF THE WALL INSULATION. WATER PIPING INSTALLED IN AN UNCONDITIONED ATTIC SHALL BE INSULATED WITH AN INSULATION OF R-5.5 MINIMUM.
- DWV SYSTEM SHALL EITHER ABS OR PVC-DWV
- WATER SUPPLY LINES SHALL BE POLYETHYLENE (PEX), CPVC, OR COPPER. WHEN POLYETHYLENE (PEX) SUPPLY LINES ARE INSTALLED THE MAXIMUM WATER HEATER SETTING IS 180 DEG F. THE POLYETHYLENE PIPE SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS LIMITATIONS AND INSTRUCTIONS.
- BUILDING DRAIN AND CLEANOUTS ARE DESIGNED AND SITE INSTALLED BY OTHERS, SUBJECT TO LOCAL JURISDICTION APPROVAL.
- TUB ACCESS PROVIDED UNDER HOME UNLESS OTHERWISE NOTED.
- SHOWER STALLS SHALL BE COVERED W/ NON-ABSORBANT MATERIAL TO A HEIGHT OF 72 INCHES ABOVE FINISH FLOOR.
- T&B RELIEF VALVE W/DRAIN TO EXTERIOR AND SHUT-OFF WITHIN 3' OF WATER SUPPLY AT WATER HEATER
- WATER HAMMERS ARRESTERS SHALL BE INSTALLED AT EACH QUICK CLOSING VALVE I.e. ICE MAKERS, DISH WASHERS, AND CLOTHES WASHERS (WHEN REQUIRED).
- WATER HEATERS LIST ON Q.C. 04.01.01
- ALL PLUMBING FIXTURES/DRIPING SHALL COMPLY WITH SECTIONS: P2206, P2701 & TABLES P2701.1, P2904.1 & P2904.5 OF INTERNATIONAL RESIDENTIAL CODE OR SECTIONS 303, 402 & TABLES 603.3, 605.4, 605.5 OF NORTH CAROLINA PLUMBING.
- ALL TUBS AND SHOWER SHALL HAVE TEMPERATURE LIMITING VALVES PER IRC AND NC PLUMBING.
- ELECTRICAL NOTES
- ALL CIRCUITS AND EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH THE APPROPRIATE ARTICLES OF THE NATIONAL ELECTRIC CODE (NEC).
- WHEN LIGHT FIXTURES ARE INSTALLED IN CLOSELY OR RECESSED, INCANDESCENT FIXTURES SHALL HAVE COMPLETELY ENCLOSED LAMPS. SURFACE MOUNTED INCANDESCENT FIXTURES SHALL HAVE A MINIMUM OF 12 INCHES AND ALL OTHER FIXTURES SHALL HAVE A CLEARANCE OF 6 INCHES FROM "STORAGE" AREA AS DEFINED BY NEC 410-16(C)
- WHEN WATER HEATERS, DISH WASHERS, AND WASH OVERS ARE INSTALLED, THEY SHALL BE PROVIDED WITH READILY ACCESSIBLE DISCONNECTS. THE BRANCH CIRCUIT SWITCH OR CIRCUIT BREAKER SHALL BE PERMITTED TO SERVE AS THE DISCONNECTING MEANS ONLY WHERE THE SWITCH OR CIRCUIT BREAKER IS WITHIN SIGHT FROM THE APPLIANCE OR IS CAPABLE OF BEING LOCKED IN THE OPEN POSITION.
- HVAC EQUIPMENT SHALL BE PROVIDED W/ READILY ACCESSIBLE DISCONNECTS ADJACENT TO THE EQUIPMENT SERVED. A UNIT SWITCH WITH A MARKED "OFF" POSITION THAT IS PART OF THE HVAC EQUIPMENT AND DISCONNECTS ALL UNGROUNDED CONDUCTORS SHALL BE PERMITTED AS THE DISCONNECTING MEANS WHERE OTHER DISCONNECTING MEANS ARE ALSO PROVIDED BY A READILY ACCESSIBLE CIRCUIT BREAKER.
- PRIOR TO ENERGIZING THE ELECTRICAL SYSTEM THE INTERRUPTING RATING OF THE MAIN BREAKER MUST BE DESIGNED AND VERIFIED AS BEING IN COMPLIANCE WITH SECTION 110-9 OF THE NEC BY LOCAL ELECTRICAL CONSULTANT.
- THE MAIN ELECTRICAL PANEL(DISCONNECT) AND FEEDERS ARE DESIGNED BY OTHERS, SITE INSTALLED AND SUBJECT TO LOCAL JURISDICTION APPROVAL.
- SMOKE DETECTORS SHALL BE WIRED SO THAT THE OPERATION OF ANY ONE SMOKE DETECTOR WILL CAUSE SIMULTANEOUS ACTIVATION OF ALL OTHERS.
- ALL CIRCUITS CROSSING OVER MODULE MATING LINES(S) SHALL BE SITE CONNECTED IN APPROVED ACCESSIBLE JUNCTION BOXES OR WITH APPROVED CABLE CONNECTIONS.
- ALL WIRING SHALL BE NMC
- ANY STRIP RECEPT MOUNTED BENEATH A COUNTER SHALL BE WITHIN 6" OF THE EDGE
- ALL BRANCH CIRCUITS SUPPLYING 15 & 20 AMPRE OUTLETS IN LIVING AREAS ARE PROTECTED BY AN ARCH-FULT CIRCUIT INTERRUPTER IN ACCORDANCE WITH SECTION 210.12, NEC
- ALL ELECTRICAL FIXTURES/WIRING SHALL COMPLY WITH SECTION E3303.3 (9C & VA)
- IT IS THE BUILDERS RESPONSIBILITY TO PROVIDE ELECTRICAL PROVISIONS FOR ANY "MOBILE" WORKSTATION IF IT IS PERMANENTLY MOUNTED.

MECHANICAL NOTES

- FACTORY INSTALLED SUB-PANEL BOX SHALL HAVE 2" MIN. CONDUIT FOR WIRE FEEDERS
- ALL AIR SUPPLY REGISTERS ARE ADJUSTABLE EXCEPT WHERE OTHERWISE SPECIFIED
- INTERIOR DOORS SHALL BE UNDERCUT 1" MIN ABOVE FINISHED FLOOR FOR AIR RETURN
- BATHROOMS SHALL BE PROVIDED WITH A WINDOW OR A MIN. 60 CFM VENT FAN. VA. REQUIRES A MINIMUM OF .35 AIR CHANGE EVERY HOUR.
- BATH VENT FANS SHALL BE DUCTED TO THE EXTERIOR AND TERMINATE AT AN APPROVED VENT CAP
- HVAC EQUIPMENT SHALL BE EQUIPPED WITH OUTSIDE FRESH AIR INTAKES BY OTHERS.
- HVAC SUPPLY DUCTS AND CALCULATIONS DESIGNED AND INSTALLED BY OTHERS
- ALL DUCTS SHALL HAVE A MIN. OF R-8 INSULATION
- ALL REGISTER BOOTS SHALL BE TAPED OR SEALED OTHERWISE
- ALL RETURN GRILLS BY FACTORY UNLESS SPECIFIED OTHERWISE
- OPTIONAL FURNACE TO BE FACTORY INSTALLED. OPTIONAL FURNACE KW SIZING TO BE VERIFIED BY OTHERS WITH SITE PROVIDED MANUAL D & L
- *OPTIONAL FURNACE USED FOR SUPPLEMENTAL HEATING ONLY. FOR OPTIMAL EFFICIENCY, A HEAT PUMP SHOULD BE INSTALLED.
- ON-SITE CONNECTIONS
- ON-SITE STRUCTURAL CONNECTIONS: FOR SITE CONNECTIONS REFER TO SECTION DRAWINGS, FOUNDATION PLANS, AND THE DOWN PLAN (ON-FRAME)
- ON-SITE ELECTRICAL CONNECTIONS: MULTIPLE SECTIONS UNITS WILL HAVE THE ELECTRICAL CROSSOVERS LOCATED EITHER IN THE FLOOR NEAR THE MARRIAGE LINE OR IN THE ENDWALLS NEAR THE CENTER OF THE UNIT. LOCATE THE JUNCTION BOXES AND CONNECT THE CONDUCTORS TOGETHER. THE CONDUCTORS SHOULD BE COLOR CODED OR MARKED FOR EASY IDENTIFICATION. DO NOT INTERCONNECT CIRCUITS OR CROSS CONDUCTORS.
- ON-SITE PLUMBING CONNECTIONS: WATER LINES: LOCATE AND CONNECT WATER LINE CROSS-OVERS LOCATED UNDER THE FLOOR AT THE MARRIAGE LINE. TURN THE WATER ON AND CHECK FOR LEAKS. DRAIN LINES: CONNECT DRAIN DROP-OUTS TO THE MAIN DRAIN. BE SURE ALL CONNECTIONS ARE MADE TO COMPLY WITH LOCAL PLUMBING CODES. TWO STORY DESIGNS: SOME 2 STORY MODELS WILL REQUIRE ADDITIONAL VERTICAL CONNECTIONS SEE PLAN SHEETS FOR LOCATIONS AND ACCESS POINTS
- INTEGRITY OF MARRIAGE LINE RIDGE BEAM SHALL NOT BE COMPROMISED UNLESS SPECIFICALLY DESIGNED FOR AND SHOWN ON APPROVED PLANS.
- ON-SITE GAS CONNECTIONS (IF APPLICABLE): LOCATE "QUICK DISCONNECT" AND CONNECT THE "QUICK DISCONNECT" IS LOCATED UNDER THE FLOOR AT THE MARRIAGE LINE. VERIFY THAT ALL CONNECTIONS ARE TIGHT AND HAVE BEEN CHECKED FOR LEAKS.

ATTENTION LOCAL INSPECTIONS DEPARTMENT

THE FOLLOWING ITEMS HAVE NOT BEEN COMPLETED BY CHAMPION HOMES. HAVE NOT BEEN INSPECTED BY P.F.S., AND ARE NOT CERTIFIED BY THE STATE MODULAR CERTIFICATION LABEL. CODE COMPLIANCE MUST BE DETERMINED AT THE LOCAL LEVEL.

- SITE CONNECTION OF ROOFS, FLOORS, WALLS (setup manual pages 11-13, pages AP-101, SE-101-102, CALCULATION SHEETS in plan set)
- ELECTRICAL CONNECTIONS ON SITE (pages 26-28 setup manual), PLUMBING CONNECTIONS ON SITE (pages 23-25 setup manual), TRUNKLINE, MANUAL D & J BY OTHERS ON SITE. DRYER VENTING BY OTHERS (page 20 setup manual).
- * BLOWER DOOR TEST TO BE COMPLETED BY OTHERS ON SITE.
- * ON BASEMENT ENTRY HOMES, FLOOR INSULATION IS NOT PROVIDED BY FACTORY.
- ALL BASEMENT WORK, INCLUDING FOUNDATION DESIGN, STAIRS, HVAC AND CONNECTION OF SMOKE DETECTOR AND REQUIRED OUTLETS, DONE BY OTHERS.
- PROVISIONS FOR EGRESS FROM BASEMENT MUST BE PROVIDED ON SITE BY OTHERS.
- ALL ENERGY COMPLIANCE FOR BASEMENTS MUST BE DONE ON SITE BY OTHERS
- * RODENT PROOFING TO BE COMPLETED ON-SITE BY OTHERS PER RP-101 (IN HOME OWNERS PACKET) IN WINDBORNE DEBRIS AREAS, WINDOW/DOOR PROTECTION PROVIDED BY OTHERS PER LOCAL CODE
- ANY SITE INSTALLED ATTIC ACCESS SHOWN ON AP-101
- NO SPRINKLER SYSTEMS REQUIRED FOR UNIT. A FIRE EXTINGUISHER TO BE PROVIDED ON SITE BY OTHERS
- **SEE ENERGY CODE INSPECTION CHECKLIST FOR FACTORY COMPLETED ITEMS AND SITE COMPLETED ITEMS**
- **ALL FALL PROTECTION DEVICES REQUIRED PER R312.2. MUST BE INSTALLED ON SITE BY OTHERS

ATTENTION LOCAL INSPECTIONS DEPARTMENT

SET-UP INSTRUCTIONS ARE INCLUDED ON THE PLAN SHEETS & IN SET-UP MANUAL INCLUDED IN HOMES. SEE NOTES, CROSS SECTION AND FOUNDATION PAGES (ITEMS NOT COMPLETE AT FACTORY MARKED WITH * ON CROSS SECTION) IF CHAMPION HOMES INSTALLATION MANUAL IS NOT INCLUDED THESE PLANS ARE INCOMPLETE.

ATTENTION LOCAL INSPECTIONS DEPARTMENT
IF THIS STRUCTURE IS IN A THERMAL ZONE MORE STRINGENT THAN THAT LISTED ON THESE PLANS, IS SET ON PILING, OR IS INSTALLED AT A MOUNTAIN REGION OR COASTAL HIGH HAZARD SITE SUCH THAT WIND OR OTHER DESIGN PARAMETERS ARE INCREASED, THE DESIGN MUST BE DETERMINED TO BE ADEQUATE FOR ACTUAL SITE CONDITIONS. ALTERATIONS MAY BE REQUIRED TO BRING THE HOME INTO COMPLIANCE WITH THE MORE STRINGENT CONDITIONS.

ANY MODEL DESIGNED FOR 150 MPH WIND MAY BE LOCATED IN AREAS OF 4500 FT OR ABOVE

ALL OPERABLE WINDOWS TO INCLUDE INSECT SCREENS.
ALL PATIO AND ATRIUM DOORS TO INCLUDE INSECT SCREENS.

IF HOME IS EQUIPPED WITH WOOD BURNING FIREPLACE, SEE PAGE 22 OF SET UP MANUAL AND MANUFACTURERS INSTALLATION MANUAL FOR REQUIRED SITE INSTALLATION.

VIRGINIA MODS TO HAVE ICE DAM PROTECTION AS REQUIRED BY STATE/LOCAL CODES.

APPROVAL STAMP

PFS CORPORATION
Approval Limited to Factory Built Portion Only

North Carolina

Signature: *Tim Blumke*
Staff Plan Reviewer

Date: 8/18/21

DESIGN INFORMATION

| | |
|--|----------------------|
| OCCUPANCY | SINGLE FAMILY |
| CONSTRUCTION TYPE | VB UNP |
| MAXIMUM WIND SPEED | 130 MPH W/IT |
| WIND EXPOSURE | C |
| SEISMIC CATEGORY | C |
| FLOOR LIVE LOAD | 40 PSF |
| 2ND FLOOR LIVE LOAD (for homes with fixed walkup stairs) | 30 PSF |
| FLOOR DEAD LOAD | 10 PSF |
| ROOF LIVE LOAD | 20 PSF STANDARD |
| ROOF DEAD LOAD | 10 PSF |
| GROUND SNOW LOAD | 30 PSF STD(24" O.C.) |
| FIRE RATING EXT WALL | 0 HRS. |
| TENANT SEPARATION | 0 HRS. |
| MAX MEAN ROOF HT. | 20.00' |



4055 HWY. 401 SOUTH LILLINGTON, NC 27548


| | |
|------------|--------------|
| TITLE: | NOTES |
| MODEL: | ANY MODEL |
| DATE: | 04-15-08 |
| SCALE: | NOT TO SCALE |
| DRAWN BY: | COB |
| REVISIONS: | |
| REVISIONS: | |

| | |
|------------|--------|
| SHEET NO.: | GE-101 |
| PAGE: | |

NOTE: ALL HIGH WIND DESIGNS, CONSTRUCTION, FASTENING, ETC, BUILT PER CALCULATION MANUAL OR SPECIFIC ENGINEERING (MEETING OR EXCEEDING CHAPTER 45- NC)

76'

30'-4"



23-3276-16 061720
 4 BEDROOM 3 BATH
 76'-0" X 30'-4"
 2305 SQ. FT.


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Swale*
 Title: Staff Plan Reviewer
 Date: 8/18/21



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

| | |
|-----------|-------------------|
| PROJECT | |
| TITLE | LITERATURE PLAN |
| MODEL | 23-3276-16 061720 |
| DATE | 8/17/20 |
| SCALE | 3/4" = 1'-0" |
| DRAWN BY | TT |
| REVISED | REVISIONS |
| SHEET NO. | L-101 |
| PAGE | |


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swindle*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**



SHOWN WITH 5/12 PITCH
 SHOWN WITH STANDARD DOOR & WINDOW CONFIGURATION

FRONT ELEVATION

FOUNDATIONS, STEPS, PORCHES
 AND RAILS DONE ON SITE BY OTHERS


 4055 HWY. 401 SOUTH LILLINGTON, NC 27546


PROJECT

TITLE

ELEVATIONS


MODEL: 23-3276-16 061720
30'-4" x 75'-0" BEDROOM & BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS

SHEET NO:
EV-101
 PAGE:


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swade*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**

RIDGE VENT

COMPOSITE SHINGLE



FOUNDATIONS, STEPS, PORCHES
AND RAILS DONE ON SITE BY OTHERS

REAR ELEVATION

CHAMPION 
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT


TITLE
 ELEVATIONS

MODEL: 23-3276-16 061720
 30' x 78'-0" BEDROOM 3 BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS

SHEET NO:
EV-102

PAGE


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swale*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**





CHAMPION 
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE:
 ELEVATIONS
 MODEL:
 23-3276-16 061720
 30'-4" x 18'-0" BEDROOM & BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS:

SHEET NO:
EV-103
 PAGE:


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Swale*
 Title: Staff Plan Reviewer
 Date: 8/18/21



RIGHT ELEVATION

CHAMPION 
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE

ELEVATIONS

MODEL: 23-3276-16 061720
 30'-0" x 75'-0" 3 BEDROOM 3 BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS:
 SHEET NO: EV-104
 PAGE:

PFS CORPORATION
 Approval Limited to Factory Built Partion Only
 North Carolina
State:
Signature: *Tim Brucke*
Title: Staff Plan Reviewer
Date: 8/18/21

WIND VELOCITY SHEARWALLS
 REFERENCED TO ATTACHED CALCULATIONS
 FROM BARLOW ENGINEERING


TRUSSES LOCATED IN CALCULATION MANUAL, SECTION 6 PAGES 1-3
 ALL BEAMS REFERENCED TO CHAMPION HOMES OF LILLINGTON
 SYSTEM PACKAGE U/180, "UNIFORM BEAM CHARTS" SECTION 8, PAGE 15
 WITH U/240, "UNIFORM BEAM CHARTS" SECTION 8, PAGE 15
 AS PREPARED BY BARLOW ENGINEERING
 MATERIAL TOTAL LOAD (U/180) = 367 PLF
 LIVE LOAD (U/240) = 198 PLF

ATTIC VENTILATION:
 SEE WORKSHEET #1 CALCULATIONS
 DRYER VENT TO BE INSTALLED ONSITE

| DESCRIPTION | GLAZED SQ. FT. | VENTING PRESSURE | SECTION | U-VALUE | MANUFACTURER |
|--|----------------|------------------|---------|---------|--------------|
| WINDOWS (9750 SERIES) | 132 | 644 | DP 50 | 0.1 | LIPPERT |
| 36" x 61" EGRESS OPT. SAFETY GLAZED | 856 | 585 | DP 50 | 0.29 | LIPPERT |
| 30" x 61" EGRESS OPT. SAFETY GLAZED | 555 | 276 | DP 50 | 0.29 | LIPPERT |
| 30" x 36" OPT. SAFETY GLAZED | 1607 | 801 | DP 50 | 0.29 | LIPPERT |
| 16" x 61" EGRESS OPT. SAFETY GLAZED | 131 | 0 | DP 50 | 0.29 | LIPPERT |
| 24" x 48" OPT. SAFETY GLAZED | 485 | 244 | DP 50 | 0.29 | LIPPERT |
| 14" x 40" OPT. SAFETY GLAZED | 628 | 0 | DP 50 | 0.29 | LIPPERT |
| 42" x 34" BLACK GLASS | 1429 | 611 | DP 50 | 0.28 | LIPPERT |
| 42" x 40" PICTURE | 826 | 288 | DP 50 | 0.28 | LIPPERT |
| 46" x 38" ARCH SAFETY GLAZED | 17 | 0 | DP 50 | 0.28 | LIPPERT |
| 36" x 87" TRANSLUCENT GLAZED | 0 | 0 | DP 50 | 0.28 | LIPPERT |
| 46" x 87" TRANSLUCENT GLAZED | 0 | 0 | DP 50 | 0.28 | LIPPERT |
| 36" x 80" EXTERIOR DOOR WITH Y LITE | 440 | 1945 | DP 50 | 0.29 | LIPPERT |
| 36" x 80" EXTERIOR DOOR WITH Y LITE | 1468 | 1945 | DP 50 | 0.29 | LIPPERT |
| WINDOWS OPT. SLIDING GLASS | 3437 | 1945 | DP 50 | 0.30 | LIPPERT |
| 74" x 80" ALUMINUM DOOR WITH 15 LITE WINDOWS | 2496 | 1945 | DP 50 | 0.30 | LIPPERT |

DATA PLATE
 ENERGY CERTIFICATION LABEL
 LABEL LOCATIONS (STATE & PFS)

| COLUMN SUPPORT | AREA |
|----------------|-------------|
| 1-2x4's | 1st FLOOR |
| 2-2x4's | 2305 SQ. FT |
| 3-2x4's | 2nd FLOOR |
| | N/A |
| | GLAZING |



NOTE: ALL WINDOWS AND DOORS TO HAVE SCREENS FOR VENTILATION AND INSECTS.

CHAMPION
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE: FLOOR PLAN

MODEL: 23-3276-16 061720

DATE: 8-17-20

SCALE: 3/16" = 1'-0"

DRAWN BY: TT

REVISIONS:

SHEET NO: AP-101

PAGE:

MODEL No.: 23-3276-16 061720
 SERIAL No.:
 WIND SPEED.: 130 VULT
 ROOF 5/12

PFS CORPORATION
 SHEAR CALCULATIONS

Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Jim Duncanson*
 Title: Staff Plan Reviewer
 Date: 8/18/21

SIGNED BY: CHAMPION HOMES
 DATE: 8/9/2021
 CHECKED BY: JPT

| By | CHK'D | LOCATION | EDGE FASTENING* | FIELD FASTENING* | 16 GA. | 19/32" OSB MIN. | NOTES | CONN. # |
|----|-------|------------------------|-----------------|------------------|--------|---|----------------------------|---------|
| | | ENDWALL #1 (HITCH) | 4.0 | 4.0 | 8.0 | 7/16" OSB BLOCKED | 71 FHS (MASTER BED / BATH) | F/S1 |
| | | ENDWALL #2 (REAR) | 6.0 | 6.0 | 12.0 | 7/16" OSB BLOCKED | 90 FHS (BEDROOM 2 & 3) | F/S2 |
| | | SIDEWALL #1 (A MODULE) | 6.0 | 6.0 | 12.0 | 7/16" OSB BLOCKED | 71 FHS (LIVING) | F3 |
| | | SIDEWALL #2 (B MODULE) | 6.0 | 6.0 | 12.0 | 7/16" OSB BLOCKED | 59 FHS (KITCHEN / DINING) | F4 |
| | | ROOF SHEATHING | 6.0 | 6.0 | 12.0 | 7/16" OSB UNBLOCKED | | F5 |
| | | INCREASE TO | 6.0 | 6.0 | 8.0 | 7/16" OSB BLOCKED | | F6 |
| | | WITH | 6.0 | 3.0 | | O.C. FASTENERS AT PERIMETER | | F7 |
| | | BLOCKING DISTANCE | 0' | 0' | | FROM ENDWALLS (ROOF DIAPHRAGM SHEATHING CONNECTION : 170 PLF) | | F8 |
| | | CEILING SHEATHING | 7.0 | 7.0 | 7.0 | 1/2" GWB UNBLOCKED (FOAM ADHESIVE MEETS REQUIRED FASTENING) | | F9 |
| | | FLOOR SHEATHING | 6.0 | 2.0 | 12.0 | 15 GA. | | F10 |

| By | CHK'D | LOCATION | FASTENING * | ALT. FASTENER† | NOTES |
|----|-------|--------------------|-------------|----------------|-------|
| | | ROOF ZONE 1 | 12 | 5 | |
| | | ROOF ZONE 2 | 11 | 5 | |
| | | ROOF ZONE 3 | 7 | 3 | |
| | | ROOF ZONE 3 O/H | 6 | 2 | |
| | | WALL ZONE 4 | 12 | 5 | |
| | | WALL ZONE 5 | 12 | 5 | |
| | | EDGE DIMENSION (Z) | 4 | 4 | |

* 8D COMMON NAILS (.131" x 2.5")
 * Roof (16 GA. STAPLES)
 * Floor (8D COMMON NAILS (.131" x 2.5"))
 † 16 GA. STAPLE (REF. SEC 16 PG. 14 8D TO 16GA. (Z))
 † Roof (16 GA. STAPLE (REF. SEC 16 PG. 15 14GA. TO 16GA. (Z))
 † Floor (15 GA. STAPLE (REF. SEC 16 PG. 14 10D TO 15GA. (Z))



| By | CHK'D | LOCATION | UPLIFT # FASTENING * | ALT. FASTENING * | NOTES | CONN. # |
|----|-------|-----------------------------------|----------------------|------------------|---|---------|
| | | TRUSS THE DOWN | 148 | | (1) SIMPSON SDWC 15600 | F9 |
| | | TRUSS THE DOWN (FLAT STRAP) | 148 | | (1) 1/2" x 20GA STRAP W/ (4) 0.113 NAILS | F10 |
| | | STUD TO TOP PLATE/CEILING BAND | 99 | | (1) 1/2" x 20GA STRAP W/ (2) 0.113 NAILS | F11 |
| | | STUD TO TOP PLATE (ALTERNATE) | 99 | | 16 GA STAPLES EA. STUD | F12 |
| | | STUD TO FLOOR BAND | 13 | | (1) 1/2" x 20GA STRAP W/ (4) 0.113 NAILS | F13 |
| | | STUD TO FLOOR BAND (ALTERNATE) | 13 | | 16 GA STAPLES EA. STUD | F14 |
| | | PLATE TO STUD | 248 | | (6) 15GA. X 2 1/2" STAPLES EACH END | F15 |
| | | PLATE TO PLATE | 248 | | 15GA. X 2 1/2" STAPLES AT 5" O.C. | F16 |
| | | TRUSS TO TOP PLATE | 248 | | (6) .131 TOE NAIL OR (3) #10 X 5" TSCREW EA TRUSS | F17 |
| | | LOAD (PLF) AT IN. O.C. LOAD (LBS) | 496 | | | F18 |
| | | TRUSS TO TOP PLATE | 248 | | (3) #10 X 5" TSCREW EA TRUSS | F19 |
| | | FACE NAILED | | | | F20 |
| | | END NAILED | | | | F21 |
| | | FACE NAILED | | | | F22 |
| | | END NAILED | | | | F23 |

* QUANTITIES ARE EACH END
 ** C-2019-2021 ED. SIMPSON CATALOG
 (REF. SEC 18 PG. 17 20GA. STRAP/NAILS)
 (REF. SEC 18 PG. 17 20GA. STRAP/NAILS)
 ALT. FASTENING *
 UPLIFT # FASTENING *
 UPLIFT CONNECTIONS

| By | CHK'D | LOCATION | FASTENING | NOTES | CONN. # |
|----|-------|----------------|--|---------------------------|---------|
| | | PLATE TO PLATE | (2) ROWS 15GA. X 2 1/2" STAPLES AT 1" O.C. | FACE NAILED 3" MIN SPLICE | F16 |

TOP PLATE SPLICES
 (SUBSTITUTION REF. SEC 16 PG. 14 .131 TO 15 GA. (Z))
 (SUBSTITUTION REF. SEC 16 PG. 15 .162 TO 15 GA. (Z))

| By | CHK'D | LOCATION | FASTENING | NOTES | CONN. # |
|----|-------|---------------------------------|---|------------------------|---------|
| | | ENDWALLS | SHEATHING UPLIFT CONN. TO FLOOR BAND AND BOTTOM CHORD W/ (1) ROWS OF 16GA. STAPLES AT (2) IN O.C. | | F17 |
| | | ENDWALLS | SHEATHING UPLIFT CONN. TO FLOOR BAND AND BOTTOM CHORD W/ (1) ROWS OF 16GA. STAPLES AT (2) IN O.C. | | F18 |
| | | ENDWALLS | BOTTOM CHORD TO TOP PLATE W/ .131 X 3" TOENAILS AT 6" IN O.C. | | F19 |
| | | ENDWALLS | SHEATHING SHEAR CONN. TO FLOOR BAND W/ (1) ROWS OF 16GA. STAPLES AT (6) IN O.C. | | F20 |
| | | SIDEWALLS | SHEATHING UPLIFT CONN. TO FLOOR BAND W/ (1) ROWS OF 16GA. STAPLES AT (6) IN O.C. | | F21 |
| | | LOCATION / LOAD | | | F22 |
| | | ALL EXTERIOR WALL INTERSECTIONS | (1) ROW(S) #8 SCREWS AT 6.2" O.C. | FACE NAILED/SCREWED | F23 |
| | | ALTERNATE FASTENER | (1) ROW(S) 3/8" LAG AT 9.3" O.C. | | F24 |
| | | LOCATION | FASTENING * | CORNER HOLDOWNS | F25 |
| | | ALL EXTERIOR WALL CORNERS | 4600 LBS MAX UPLIFT MINUS 6650 LBS 2 OF DEAD LOAD = 0 LBS | NO HOLD DOWNS REQUIRED | F26 |

CORNER CONNECTIONS
 (SUBSTITUTION REF. SEC 16 PG. 14 .131 TO 16 GA. (Z))
 (SUBSTITUTION REF. SEC 20 PG. 14 .162 TO .113 (Z))

SIDEWALL/ENDWALL DETAIL





PLATE TO PLATE
F16


TOP PLATE SPLICE DETAIL



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: **North Carolina**
Signature: *Tim Swale*
Title: **Staff Plan Reviewer**
Date: **8/18/21**

ROOF ASSEMBLY DETAILS




SEE Q/A MANUAL FOR APPROVED ELECTRICAL FIXTURES SECTION 4 PAGE 4

NC NOTE:
PER NC ECC 404.1, A MINIMUM OF 75% OF LAMPS INSTALLED IN PERMANENTLY INSTALLED FIXTURES MUST BE HIGH-EFFICIENT LAMPS (EXAMPLE: CFL'S)

ALL BULBS TO BE PROVIDED ON SITE BY OTHERS.

PFS CORPORATION
Approval Limited to: Factory Built Portion Only

State: **North Carolina**
Signature: *Tim Brubaker*
Title: **Staff Plan Reviewer**
Date: **8/18/21**



FURNACE NOTE: 17KW NORDYNE E6 FURNACE WITH 57,000 BTUH PROVIDED BY CHAMPION HOMES.

ELECTRICAL LEGEND

| | | | |
|---|---------------------------------------|---------------------------|-------------------------------------|
| GENERAL RECEPTACLE 120 VOLT - 15 AMP | CEILING LIGHT | FLUORESCENT LIGHT | PHONE JACK |
| G.F.I. PROTECTED RECEPT. 120 VOLT-15 AMP | WALL LIGHT | DIRECTLY WIRED CONNECTION | TV/CABLE JACK |
| 120 VOLT - 20 AMP G.F.I. PROTECTED | CEILING VENT FAN W/LIGHT (2 SWITCHES) | THERMOSTAT | HEAT TAPE RECEPT 120 VOLT-15 AMP |
| 220 VOLT RECEPT. EXTERIOR LIGHT | EXHAUST FAN | SMOKE DETECTOR | JUNCTION BOX |
| WATERPROOF EXTERIOR LIGHT | SINGLE POLE SWITCH | MAIN PANEL | RECESSED LIGHT |
| | FLOOD LIGHT | TRACK LIGHTING | SMOKE DETECTOR/CO COMBINATION |

NOTE:

1. CIRCUIT NUMBERS MAY VARY AND NOT ALL CIRCUITS ARE IN USE
2. ARC-FAULT CIRCUIT INTERRUPTERS SHALL BE IN ACCORDANCE WITH SECTION 210.12 (A) OF THE CURRENT NEC.
3. OPTIONAL 220 VOLT RECEPTACLE PROVIDED FOR RANGE AND DRYER.
4. POWER RANGE HOOD STANDARD.
5. ALL CLOSET LIGHTS TO BE A MIN. 12" OFF OF SHELF.
6. DWELLING UNIT RECEPTACLE MUST BE RATED AS TAMPER RESISTANT ACCORDANCE WITH SECTION 408.12, NEC
7. WATER PROOF COVERS REQUIRED FOR OUTDOOR SWITCHES AND RECEPTACLE ACCORDANCE WILL SECTION 404.4 AND 404.9, NEC
8. OUTLET, DEVICE, PULL, AND JUNCTION ARE IN ACCORDANCE TO ARTICLE 314
9. ATTIC LIGHT TO BE INSTALLED, IF ATTIC TO BE USED FOR STORAGE, ON SITE

- RECEPT TO BE INSTALLED FOR WHIRLPOOL TUB WITHIN 12" OF ACCESS IN DIRECT VIEW FOR DISCONNECT OF APPLIANCE.
- BREAKER LOCKOUT TO BE INSTALLED FOR DISHWASHER, WATER HEATER
- RANGE HOOD EXHAUST FAN IS A NON VENTED RECIRCULATION TYPE (CHARCOAL)
- CO/SMOKE DETECTOR COMPLIES WITH UL 217 AND UL 2034
- FIRST ALERT MODEL #SC9120B (NC, SC)

| ELECTRICAL SCHEDULE - CONT - | | | ELECTRICAL SCHEDULE - CONT - | | | PANEL SIZING | | |
|------------------------------|------------------------|------------|------------------------------|-------------|------------|--------------|-------|--|
| BREAKER CIR # | DESCRIPTION | VOLTS WIRE | BREAKER CIR # | DESCRIPTION | VOLTS WIRE | DESCRIPTION | KVA | |
| 20 A11 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A12 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A13 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A14 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A15 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A16 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A17 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A18 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A19 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A20 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A21 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A22 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A23 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A24 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A25 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A26 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A27 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A28 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A29 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A30 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A31 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A32 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A33 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A34 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A35 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A36 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A37 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A38 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A39 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A40 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A41 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A42 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A43 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A44 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A45 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A46 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A47 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A48 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A49 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A50 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A51 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A52 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A53 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A54 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A55 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A56 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A57 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A58 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A59 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A60 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A61 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A62 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A63 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A64 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A65 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A66 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A67 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A68 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A69 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A70 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A71 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A72 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A73 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A74 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A75 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A76 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A77 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A78 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A79 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A80 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A81 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A82 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A83 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A84 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A85 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A86 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A87 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A88 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A89 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A90 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A91 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A92 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A93 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A94 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A95 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A96 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A97 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A98 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A99 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |
| 20 A100 | GFI PORTABLE APPLIANCE | 120 12/2 | 15 | 24 | 12/2 | 1500VA, 1000 | 3 KVA | |



4055 HWY. 401 SOUTH LILLINGTON, NC 27548

PROJECT

TITLE
ELECTRICAL PLAN

MODEL:
23-3276-16 061720

DATE: 6-17-20
SCALE: 3/16" = 1'-0"

DRAWN BY: TT
REVISIONS:

SHEET NO:
EP-101

PAGE:

PROJECT

DWW PLUMBING PLAN

NOTES:


- 1- ALL PIPE SIZES ARE 1/2" UNLESS OTHERWISE SPECIFIED.
- 2- ONE FIXTURE IN "BATHROOM GROUP" MAY BE ELIMINATED WITHOUT AFFECTING PIPE SIZING.
- 3- ALL PIPES SHOWN IN DASHED LINE ARE FIELD INSTALLED BY OTHERS SUBJECT TO LOCAL JURISDICTION.
- 4- AUTO VENTS TO BE INSTALLED ON SITE AFTER COMPLETE PLUMBING SYSTEM TEST.
- 5- WATER STAND TEST MUST BE DONE ON SITE AFTER COMPLETION OF PLUMBING SYSTEM.
- 6- ALL VENT PIPES MUST TERMINATE MIN. 6' ABOVE ROOF, WITH APPROVED WATER TIGHT FLASHING. (P904.1 & P904.3)
- 7- IF HOME LOCATED IN AREA WHERE 97.5% FOR OUTSIDE DESIGN TEMPERATURE IS 0° OR LESS, EVERY VENT EXTENSION SHALL BE MIN. 3". THIS TO BE DONE ON SITE BY OTHERS. (P904.2)
- 8- RODENT PROOFING AT ALL SHOWERS, TUBS, TUB/SHOWER TO BE COMPLETED ON SITE BY OTHERS AFTER PLUMBING TEST COMPLETED.

SEE Q/A MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 5

| |
|--------------------------------|
| PIPE SUPPORT TO BE AS FOLLOWS: |
| MAX HORIZONTAL SPACING = 4' |
| MAX VERTICAL SPACING = 10' |
| REFERENCE: IPC TABLE 308.5 |

ATTN. LOCAL BUILDING OFFICIAL *

ALL P-TRAPS AT TUBS, SHOWERS & TUB/SHOWERS MUST BE RODENT PROOFED AND FINAL FIRE BLOCKING COMPLETED ON SITE BY OTHERS AFTER COMPLETION OF ALL PLUMBING TESTS. ALL OTHER RODENT PROOFING AND FIRE BLOCKING AT FLOOR LEVEL DONE AT FACTORY. (REFERENCE IRC R302.11 FOR CORRECT METHODS) SEE PAGE AE-101 IN SETUP MANUAL IN HOME FOR DETAILS (SECTION 5, PG 36 QA MANUAL). SEE Q/A MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 5



PFS CORPORATION

Approval Limited to Factory Built Portion Only

State:

North Carolina

Signature:

Tim Brudke

Title:

Staff Plan Reviewer

Date:

8/18/21

| | |
|-----|-------------------|
| ① | 1 1/2" PVC OR ABS |
| ② | 2" PVC OR ABS |
| ③ | 3" PVC OR ABS |
| ⊙ | APPROVED AUTOVENT |
| ⊖ | STUB OUT |
| VTR | VENT THROUGH ROOF |
| --- | INSTALLED ON SITE |

TITLE: DWV PLAN OFF-FRAME

MODEL:

DATE: 6-17-20

SCALE: NTS

DRAWN BY: TT

REVISIONS:

SHEET NO:

PP-101

PAGE:


23-3276-16 061720

30'-4" x 75'-0" BATHROOM 3 BATH

PROJECT

STATE WATER HEATER
 MODEL # SC 152 PORTE 3 (ELECTRIC)
 CO#1094 IM 50 NHDST 2 (GAS)
 MANUF. INFORMATION LOCATED
 IN O.A. MANUAL, SECTION 4,
 PAGE 04.01.01

WATER HEATER SECURED IN PLACE FOR TRANSIT WITH METAL SHIPPING STRAPS FROM WALL TO WALL




1" DRAIN TO EXTERIOR

SUPPLY AT WATER HEATER

1. ALL PLUMBING FIXTURES HAVE SEPARATE SHUTOFF VALVES.
 2. WATER HEATER SHALL HAVE A SAFETY PAN WITH 1 INCH DRAIN TO EXTERIOR.
 3. WATER PIPES INSTALLED IN A WALL EXPOSED TO THE EXTERIOR SHALL BE LOCATED ON THE HEATED SIDE OF THE WALL INSULATION. WATER PIPING INSTALLED IN AN UNCONDITIONED ATTIC OR CRAWL SPACE SHALL BE INSULATED WITH AN INSULATION OF R-30 MINIMUM ON SITE BY OTHERS.
 4. DWV SYSTEM SHALL EITHER ASB or PVC-DWV ENTIRELINE (PVC, CPVC, OR COPPER, WHEN NOTIFIED BY THE MANUFACTURER).
 5. THE MAXIMUM WATER HEATER SETTING IS 180 DEG F. THE POLYETHYLENE PIPE SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S LIMITATIONS AND INSTRUCTIONS.
 6. BUILDING DRAIN AND CLEANOUTS ARE DESIGNED AND SITE INSTALLED BY OTHERS. SUBJECT TO LOCAL JURISDICTION APPROVAL.
 7. TUB ACCESS PROVIDED UNDER HOME.
 8. UNLESS OTHERWISE NOTED, COVERED UP SHOWER STALLS SHALL BE COVERED UP 72 INCHES ABOVE FINISH FLOOR.
 9. TAP RELIEF VALVE W/RAIN TO EXTERIOR OR PAN SHUT-OFF WITHIN 3' OF WATER SUPPLY AT WATER HEATER.
 10. THIS UNIT MUST BE CONNECTED TO PUBLIC WATER SUPPLY AND SEWAGE SYSTEM.
 11. THESE ARE PERFORMED FOR MAXIMUM INLET PRESSURE OF 80 PSI. SEE SETUP MANUAL, SECTION 4.1
- SEE O.A. MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 9

WATER PLUMBING PLAN

NOTES:
 -ALL PIPE SIZES ARE 1/2" UNLESS OTHERWISE SPECIFIED.



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

North Carolina

Staff Plan Reviewer

Signature: *Tim Brade*
 Title: Staff Plan Reviewer
 Date: 8/18/21

TITLE
 WATER LINE PLAN

MODEL:
 23-3276-16 061720
 30'-4" x 78'-0" 1/2" BDRROOM 3 BATH

DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISIONS:
 REVISIONS


SHEET NO.
 WP-101

PAGE:

*** ATTN LOCAL BUILDING OFFICIAL:
SEE INSULATION CERTIFICATE AT PANEL BOX FOR ACTUAL INSULATION VALUE USED.
APPENDIX E IS USED.**

Soft materials for this work assume that the building face will be 30 feet or greater from the property line when installed on site. Where the building face is less than 30 feet from the property line, underlayment materials and ventilation in accordance with Section R703.11.3, IRC Residential Code, must be provided and installed at the site and inspected by the local jurisdiction.

FOR RIDGE BEAMS ABOVE BOTTOM CHORD REQUIRING TENSION CONNECTIONS



(PAINTED HARDI, WOOD OR METAL COVERED)

CONNECTION DETAILS FASTENED PER AP-202.

VINYL EXTERIOR SIDING PER ORDER

SHEATHING PAPER OR APPROVED WATERPROOF MEMBRANE MUST BE INSTALLED UNDER EXTERIOR SIDING (EX. HOUSE WRAP, all seams taped). EXTERIOR SIDING MAY BE SITE INSTALLED WITH LOCAL INSPECTION

CONNECTIONS FASTENED PER AP-202.

ON SITE CONNECTION

ON SITE CONNECTION

ON SITE CONNECTION

ON SITE CONNECTION SEE TRUSS SETUP & GABLE ENDWALL PAGES.

FASTENING OF ROOF SHEATHING SEE PAGE AP-202

SHINGLE OVER RIDGE VENT INSTALL PER MANUFACTURERS INSTRUCTIONS
SHINGLES - SHINGLES INSTALLED PER MANUF. LOCATED ON EACH VENT FOR INSTALLATION INSTRUCTIONS - (NO CAMBRIDGE OR TRAWCO HERITAGE ARCHITECTURAL OR EQUAL - (HIGH WIND REQUIRES 6 FASTENERS PER SHINGLE))

ATTIC VENTILATION REQUIREMENT OF 1/600th OF TOTAL ROOF AREA IS ACCOMPLISHED WITH 50% OR MORE OF THE NET VENT AREA PROVIDED THROUGH ROOF VENTILATORS, RIDGE VENTS OR GABLE VENTS LOCATED IN THE UPPER 1/3 OF THE TRUSS HEIGHT AND THE REMAINDER OF THE NET VENT AREA PROVIDED BY SOFFIT VENTS. SEE NOTE ON AP-101 AND WORKSHEET 1

APPROVED TRUSS (SEE AP-101 FOR REFERENCE) 24" O.C. STANDARD, 18" O.C. OPTIONAL

ROOF COVERING OVER APA RATED SHEATHING

1 x 4 BLOCKING BETWEEN TRUSSES FOR FIELD FASTENING OF SHEATHING (PER TRUSS DESIGN)

BAFFLE TO PROVIDE 1" AIR SPACE.

DOUBLE 2x6 #3 GRADE SPF TOP PLATE

1/2" GYPSUM CL.G. FIN. WOOD COMPRESSION STRIP (1 1/2" x 1 1/2" PLYWOOD OR EQUAL AS REQUIRED)

NOTE: GYPSUM WALLBOARD USED IN DAMP LOCATIONS (TUB ENCLOSURES WITH SHOWER HEAD) MUST BE WATER RESISTANT BOARD. WATER RESISTANT BOARD NOT REQUIRED WITH ONE PIECE FIBERGLASS TUB ENCLOSURE 6 FT HIGH OR HIGHER.

WALL INSULATION KRAFT FACED WARM SIDE FIBERGLASS BATT INSULATION (R-18 2X6) SEE APPENDIX E

2X6 SPF #2 STUDS @ 16" O.C.

1/2" GYPSUM

2X6 BOTTOM PLATE TYPICAL HEAT REGISTER INSTALLED IN EACH ROOM ANY ADDITIONAL REGISTER REQUIRED BY OTHERS IS TO BE DONE ONSITE

8' TO 9' MAX

MEAN ROOF HEIGHT

20.00'

WOOD COMPRESSION STRIP (1 1/2" x 1 1/2" PLYWOOD OR EQUAL AS REQUIRED) CONTINUOUS VINYL VENTED SOFFIT

7/8" OSB SHEATHING SHALL BE INSTALLED ON THE ENTIRE EXTERIOR OF THE HOME ALL SHEATHING TO BE FASTENED WITH 6d BOX NAILS OR EQUAL FASTENED PER AP-202.

VINYL SIDING - 4 1/2" VENT TRUE WALL BRAND "OR EQUAL" (FASTENER SPACING: 16" O.C. HORIZONTAL VINYL 12" O.C. VERTICAL VINYL AND ACCESSORIES AT 8" TO 10" O.C. ALL WIND SPEEDS) INSTALLED PER MANUF. INSTALLATION INSTRUCTIONS FASTENED PER AP-202.

FLOOR DECKING IS TO BE CONTINUOUS OVER JOIST PER AP-202.

19/32" OSB FLOOR DECKING FASTENED PER AP-202.

FLOOR INSULATION R-30 FIBERGLASS BATT INSULATION SEE APPENDIX E

For floor joist size and grade, see FL-02.01A in QA manual

CONTINUOUS TO FLOOR DECKING


SEE FOUNDATION DESIGN FOR PERIMETER WALL AND FOOTING DETAILS

FASTEN TRUSS TOGETHER IN THE FIELD WITH 3/8" X 6" LAG SCREWS AT 32" O.C. ALTERNATE DIRECTIONS

REFERENCE: ATTACHED CALC PAGE 24, sect 6 76'-0" / 13 = 5'-10" X 0.575 = 3'-4"

SEE FOUNDATION DESIGN FOR COLUMN/JACKPOST DESIGN, SIZE, AND SPACING. SEE FT101-103

GROUND LEVEL VAPOR BARRIER TO BE INSTALLED BY OTHERS



- NOTES:
1. ALL FINISH MATERIAL TO HAVE CLASS "C" FIRE RATING.
 2. ALL PENETRATIONS THROUGH FLOOR OR CEILING FIRE STOPPED
 3. SEE FOUNDATION PLAN FOR SUPPORT AND THE DOWN REQUIREMENTS.

PFS CORPORATION
Approval Limited to Factory Built Portion Only
North Carolina
Staff Plan Reviewer
Tim Swade
8/18/21



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE:
OFF FRAME
CROSS SECTION

MODEL:
23-3276-16 061720
30'-4" x 76'-0" 3 BEDROOM 3 BATH

DATE: 10/7/03

SCALE: 1/8" = 1'-0"

DRAWN BY: JPT

REVISIONS: 04-13-04

CDB ADDED DORMER INFORMATION

SFA ADDED P-TRAP RODENT PROOF

SHEET NO:

SE-101


PAGE:

FOUNDATION VENT TO PROVIDE 1st OF VENT PER EACH 150sf OF CRAWL SPACE AREA
 2305 SF / 150 SF = 15.4
 8"x16" (TYP) VENT = APPROX. 5 SF
 15.4 / .5 = APPROX. 31 VENTS

- NOTES:
1. SPLICES IN MATE LINE GIRDERS MUST FALL ON A SUPPORT PIER.
 2. PIERS OR POSTS TO BE SPACED PER CHART AND LOCATED UNDER OPENING COLUMN SUPPORTS WHEN OPENING WIDTH IS 4' OR GREATER.
 3. FOR SEISMIC DESIGN CATEGORY D0, D1 & D2 FOUNDATION DESIGNED BY OTHERS

OFF FRAME LIFTING NOTES:

1. IF LIFTING POINTS ARE MORE THAN 32 FEET APART (TYPICAL OF UNIT LENGTHS GREATER THAN 64'), A THIRD AND FOURTH LIFTING POINT IS REQUIRED. THIRD AND FOURTH LIFTING POINT IS TO BE BETWEEN OUTER LIFTING POINTS AND MEET THE REQUIREMENTS OF NOTE 2.
2. PICK UP POINT MUST NOT BE LOCATED UNDER A WALL OPENING. IF AN OPENING CANNOT BE AVOIDED, A TEMPORARY WALL MUST BE INSTALLED.



NOTE:
 1" ADDED TO OVERALL WIDTH TO ACCOMMODATE LIFT STRAPS


PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim B. Swalle*
 Title: Staff Plan Reviewer
 Date: 8/18/21


| | |
|------------|---------------------------|
| TITLE: | PERIMETER FOUNDATION PLAN |
| MODEL: | 23-3276-16 061720 |
| DATE: | 8-17-20 |
| SCALE: | NTS |
| DRAWN BY: | TT |
| REVISIONS: | |
| SHEET NO.: | F-101 |
| PAGE: | |

CHAMPION


4055 HWY. 401 SOUTH LILLINGTON, NC 27546




SECTION A-A BLOCK WALL



SECTION A-A BRICK VENEER WALL



SECTION A-A PIER & CURTAIN WALL



SECTION A-A CONTINUOUS 8" MASONRY WALL

C:\Users\jtyndal\Desktop\23-3276-16 061720 DWG, 8/9/21 07:30 AM

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: **North Carolina**

Signature: *Tim Swale*
Staff Plan Reviewer

Date: 8/18/21

TYPICAL FOUNDATION NOTES :

- Foundation and its structural elements shall be capable of accommodating all superimposed live, dead, and other loads in accordance with applicable codes and all lateral loads in accordance with accepted design practices.
- Lots shall be provided with adequate drainage and shall be graded so as to drain surface water away from foundation walls - by lot owner.
- Materials shall conform to applicable standards and codes.
- Concrete subject to weathering shall have a minimum compressive strength and air content in accordance with code - 2500 psi concrete minimum.
- All exterior walls, bearing walls, columns, and piers shall be supported on continuous solid concrete footings which shall be of sufficient design to support safely the loads imposed as determined from the character of the soil, and shall in all cases, extend below the frost line. Top surface shall be level and bottom not exceeding 1 in 40 slope. Footings shall be not less than shown on drawings for 2000 psf soil.
- Foundation walls shall be constructed in accordance with the code and not less than as shown on the Drawings.
- Foundations shall extend not less than 12 inches below the finished natural grade or engineered fill and in no case less than the frost line depth. Footings on soil with a lower allowable soil pressure shall be designed in accordance with accepted engineering practice. However, where there is evidence that the groundwater table can rise to within 6 inches of the finished grade at the building perimeter or where there is evidence that the surface water does not readily drain from the building site, the building official may require that the grade in the under-floor space be as high as the outside finished grade, unless an approved drainage system is provided. Termite shields and/or protection shall be provided as per code. Local and state requirements for footings may exceed that shown on drawings. If there are any questions, contact your local building inspections department.
- Crawl space ventilation and access space shall be by openings in the foundation walls {cross-ventilation as required by code and/or as follows}. Provide 1 sq. Ft. of ventilation area for each 150 sq. Ft. of crawl space floor area. Use 8"x16" foundation vents with corrosion resistant wire mesh (1/8" mesh) or equal.
- Mortar shall be type "m" or "s".
- Minimum soil bearing capacity shall be 2000 psf.
- Anchorbolt length to be: masonry wall-20",
- Poured concrete footing w/two #5 rebar (120 & 130 only) continuous w/ a minimum 25" lap. Place bars 3" from bottom.
- This foundation plan is provided for reference as a typical. Actual foundation conditions must be evaluated for applicability if this plan is to be used. Alternate foundation plans may be designed by others in accordance with the requirements of the jurisdiction having authority.

* Vertical wall reinforcement or continuous anchorage is as follows:

- Sidewall anchor bolt spacing see F-101
- Endwall anchor bolt spacing see F-101

PFS CORPORATION
Approval Limited to Factory Built Portion Only


State: North Carolina

Signature: *Tim B. Swade*
Staff Plan Reviewer


Title: Staff Plan Reviewer

Date: 8/18/21

There shall be a minimum of (2) bolts per sill plate section, with one bolt located not more than 12" from each end of the plate section.



SECTION B-B BASEMENT WALL



SECTION B-B

PIER & CURTAIN WALL, BLOCK WALL
& BRICK VENEER WALL
(where required on module mate lines)

BUILDER MUST FINISH APPENDIX, FACTORY DONE MARKED IN RED

APPENDIX E

(E-1 THROUGH E-4)

RESIDENTIAL REQUIREMENTS FOR ENERGY CONSERVATION

This appendix is a North Carolina addition and not part of the 2015 International Residential Code.

There will be no underlined text.

(The provisions contained in this appendix are adopted as part of this code.)

APPENDIX E-1 Energy Efficiency Certificate (Section N1101.14)

ENERGY EFFICIENCY CERTIFICATE (N1101.14)

| | | |
|---|--|---|
| Builder, Permit Holder or Registered Design Professional PFS CORPORATION Approval Limited to Factory Built Portion Only  | | Print Name: Signature: Property Address: State: North Carolina Signature: <i>Jim Dwork</i> Title: Staff Plan Reviewer Date: 8/18/21 |
|---|--|---|


| | | |
|---|--|---|
| Insulation Rating – List the value covering largest area to all that apply Ceiling/roof: R-38 Wall: R-18 Floor: R-30 Closed crawl space wall: R- Closed crawl space floor: R- Slab: R- Basement wall: R- | | Fenestration: U-Factor: 0.34 Solar Heat Gain Coefficient (SHGC): 0.29 Building Air Leakage: Visually inspected according to N1102.4.2.1 OR <input type="checkbox"/> Building air leakage test results (Sec. N1102.4.2.2) ACH50 [Target: 5.0] or CFM50/SFSA [Target: 0.30] |
| Name of Tester/Company: Date: Phone: | | Ducts: Insulation: R- |
| Total duct leakage test result (Sect. N1103.3.3) Circle one: Total duct leakage test (CFM25 Total/100SF) [Target: 5] or Duct leakage to the outside test (CFM25 Total/100SF) [Target: 4] | | Name of Tester or Company: Date: Phone: |

Certificate to be displayed permanently

APPENDIX E-2
INSULATION AND AIR SEALING DETAILS


APPENDIX E-2.1

N1102.2.1 Ceilings with attic spaces: Exception for fully enclosed attic floor systems



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Jim Drake*
 Title: Staff Plan Reviewer
 Date: 8/18/21




N1102.2.11 Closed crawl space walls. Insulation illustrations

APPENDIX E-2.2


APPENDIX E-2.3

N1102.2.14 Framed cavity walls. Insulation enclosure—1. Tubs



FACTORY COMPLETED

N1102.2.14 Framed cavity walls. Insulation enclosure—2. Showers



FACTORY COMPLETED


PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tom Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

PFS CORPORATION
Approval Limited to Factory Built Portion Only


State: North Carolina
Signature: *Jim Coward*
Title: Staff Plan Reviewer
Date: 8/18/21

SECTION VIEW OF INTERIOR STAIRCASE FOR WALL (OPTION 2)



N1102.2.14 Framed cavity walls. Insulation enclosure—3. Stairs

SECTION VIEW OF INTERIOR STAIRCASE ON EXTERIOR WALL (OPTION 1)




N1102.2.14 Framed cavity walls. Insulation enclosure—3. Stairs

FACTORY COMPLETED, IF APPLICABLE

N/A BY FACTORY

N1102.2.14 Framed cavity wall. Insulation enclosure—4. Direct vent gas fireplace



SECTION VIEW OF DIRECT VENT GAS FIREPLACE

PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

2018 NORTH CAROLINA RESIDENTIAL CODE

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). Order Number #10066317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with ICC. No further reproduction or distribution authorized. Single user only, copying and networking prohibited. ANY UNAUTHORIZED REPRODUCTION OR DISTRIBUTION IS A VIOLATION OF THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

N1102.2.15 Framed cavity walls. Insulation enclosure—5. Walls that adjoin attic spaces


N/A BY FACTORY



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21


ISOMETRIC VIEW OF DIMENSIONAL LUMBER FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems
 N/A BY FACTORY

APPENDIX E-2.4


SECTION VIEW OF WALL ADJOINING ATTIC SPACE WITH TRUSS ROOF



N/A BY FACTORY

N1102.2.15 Framed cavity walls. Insulation enclosure.—5. Walls that adjoin attic spaces


ISOMETRIC VIEW OF I-JOIST FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 State: _____
 Signature: _____
 Title: _____
 Date: 8/18/21
 Staff Plan Reviewer
 8/18/21

N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems N/A BY FACTORY


ISOMETRIC VIEW OF WOOD TRUSS FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems N/A BY FACTORY

N1102.4.1 Building thermal envelope—2. Cap and seal shafts and chases

BY OTHERS IF APPLICABLE



SECTION VIEWS OF DUCT PENETRATING INTO ATTIC

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 Jim Clarke
 Staff Plan Reviewer
 Date: 8/18/21


2018 NORTH CAROLINA RESIDENTIAL CODE

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). (-) Order Number #10069317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
Signature: *Tim Duerke*
Title: Staff Plan Reviewer
Date: 8/18/21

SECTION VIEW OF SOFFIT OVER CABINET




N1102.4.1 Building thermal envelope.—3. Cap and seal soffit or dropped ceiling. N/A


N1102.4.1 Building thermal envelope.—4. Seal HVAC boot penetration—floor




PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
Jim Currie
 Staff Plan Reviewer
 8/18/21
Title: HVAC SUPPLY
Date:

N1102.4.1 Building thermal envelope.—4. Seal HVAC boot penetration—ceiling





N1102.4.1 Building thermal envelope.—5. Sealed exterior air barrier with sheathing



air barrier with housewrap

N1102.4.1 Building thermal envelope.—5. Sealed exterior

Follow manufacturer's instructions for sealing air barrier-rated housewrap, including choice of materials, to provide an exterior air barrier at the following locations:


MUST BE INSPECTED ON SITE BY OTHERS FOR TEARS

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). (-) Order Number #100636317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with ICC. No further reproduction or distribution authorized. Single user only, copying and networking prohibited. ANY UNAUTHORIZED REPRODUCTION OR DISTRIBUTION IS A VIOLATION OF THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.


2018 NORTH CAROLINA RESIDENTIAL CODE

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tom Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21



N1102.4.2.1 Visual inspection option. — Table N1102.4.2 Seal ceiling electrical box penetrations **FACTORY COMPLETED**



N1102.4.2.1 Visual inspection option. — Table N1102.4.2 Seal ceiling mechanical box penetrations **FACTORY COMPLETED**

MUST BE COMPLETED BY BUILDER ON SITE

APPENDIX E

APPENDIX E-3: SAMPLE WORKSHEETS FOR RESIDENTIAL AIR AND DUCT LEAKAGE TESTING

APPENDIX E-3A

AIR SEALING: VISUAL INSPECTION OPTION (Section N1102.4.2.1)

SAMPLE WORKSHEET

air sealing in Section N1102.2.15 and air sealing in Section N1102.4.1 are addressed and when the items listed in Table N1102.4.2, applicable to the method of construction, are certified by the builder, permit holder or registered design professional via the certificate in Appendix E-1.

N1102.4.2 Air sealing. Building envelope air tightness shall be demonstrated by Section N1102.4.2.1 or N1102.4.2.2. N1102.4.2.1 Visual inspection option. Building envelope tightness shall be considered acceptable when items providing insulation enclosure in Section N1102.2.14 and enclosure and

**TABLE N1102.4.2
AIR BARRIER INSPECTION**

| COMPONENT | CRITERIA |
|---|---|
| Ceiling/attic | factory done Sealants or gaskets provide a continuous air barrier system joining the top plate of framed walls with either the ceiling drywall or the top edge of wall drywall to prevent air leakage. Top plate penetrations are sealed. For ceiling finishes that are not air barrier systems such as tongue-and-groove planks, air barrier systems (for example, taped house wrap), shall be used above the finish. Note: It is acceptable that sealants or gaskets applied as part of the application of the drywall will not be observable by the code official. |
| Walls | Sill plate is gasketed or sealed to subfloor or slab. factory done |
| Windows and doors | Space between window and exterior door jambs and framing is sealed. factory done |
| Floors (including above-garage and cantilevered floors) | Air barrier system is installed at any exposed edge of insulation. factory done |
| Penetrations | Utility penetrations through the building thermal envelope, including those for plumbing, electrical wiring, ductwork, security and fire alarm wiring, and control wiring, shall be sealed. factory done |
| Garage separation | Air sealing is provided between the garage and conditioned spaces. An air barrier system shall be installed between the ceiling system above the garage and the ceiling system of interior spaces. |
| Ceiling penetrations | Ceiling electrical box penetrations and ceiling mechanical boxes shall be caulked, gasketed, or sealed at the penetration of the ceiling finish. See Appendix E-2.4. factory done Exception: Ceiling electrical boxes and ceiling mechanical boxes not penetrating the building thermal envelope |
| Recessed lighting | Recessed light fixtures are air tight, IC rated, and sealed to drywall. factory done Exception: Fixtures in conditioned space. |

Attic Access insulated and weatherstripped per N1102.2.2.4

Property Address:

N1102.4.2.1 Visual Inspection Option. The inspection information including tester name, date, and contact shall be included on the certificate described in Section N1101.14.

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Date: _____
Signature: *Jim Dumble*
Title: Staff Plan Reviewer
Date: 8/18/21

Signature

2018 NORTH CAROLINA RESIDENTIAL CODE

INTERNATIONAL CODE COUNCIL

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). (-) Order Number #10066317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with ICC. No further reproduction or distribution authorized. Single user only, copying and networking prohibited. ANY UNAUTHORIZED REPRODUCTION OR DISTRIBUTION IS A VIOLATION OF THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

MUST BE COMPLETED BY BUILDER ON SITE

APPENDIX E-3B

Air sealing: Testing option (Section N1102.4.2.2)

Sample Worksheet

tor, a North Carolina licensed HVAC contractor, a North Carolina licensed Home Inspector, a registered design professional, a certified BPI Envelope Professional or a certified HERS rater.

During testing:

- 1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed;
2. Dampers shall be closed, but not sealed, including exhaust, backdraft, and flue dampers;
3. Interior doors shall be open;
4. Exterior openings for continuous ventilation systems, air intake ducted to the return side of the conditioning system, and energy or heat recovery ventilators shall be closed and sealed;
5. Heating and cooling system(s) shall be turned off; and
6. Supply and return registers shall not be sealed.

The air leakage information, including building air leakage result, tester name, date, and contact information, shall be included on the certificate described in Section N1101.14.

N1102.4.2 Air sealing. Building envelope air tightness shall be demonstrated by Section N1102.4.2.1 or N1102.4.2.2:

N1102.4.2.2 Testing option. Building envelope tightness shall be considered acceptable when items providing insulation enclosure in Section N1102.2.14 and enclosure and air sealing in Section N1102.2.15 and air sealing in Section N1102.4.1 are addressed and when tested air leakage is less than or equal to one of the two following performance measurements:

- 1. 0.30 CFM50/Square Foot of Surface Area (SFA) or 2. Five (5) air changes per hour (ACH50) or

When tested with a blower door fan assembly, at a pressure of 33.5 psf (50 Pa). A single point depressurization, not temperature corrected, test is sufficient to comply with this provision, provided that the blower door fan assembly has been certified by the manufacturer to be capable of conducting tests in accordance with ASTM E779-03. Testing shall occur after rough in and after installation of penetrations of the building envelope, including penetrations for utilities, plumbing, electrical, ventilation and combustion appliances. Testing shall be reported by the permit holder, a North Carolina licensed general contractor

For Test Criteria 1 in this section, the report shall be produced in the following manner: Perform the blower door test and record the CFM50. Calculate the total square feet of surface area for the building thermal envelope, all floors, cellings, and walls (this includes windows and doors) and record the area. Divide CFM50 by the total square feet and record the result below. If the result is less than or equal to [0.30 CFM50/SFA] the envelope tightness is acceptable; or For Test Criteria 2, the report shall be produced in the following manner: Perform a blower door test and record the CFM50. Multiply the CFM50 by 60 minutes to create CFHour50 and record. Divide the CFHour50 by the total conditioned volume of the home and record. If the result is less than or equal to [5 ACH50] the envelope tightness is acceptable.

Property Address:
Fan attachment location
Company Name
Contact Information:
Signature of Tester
Date

Permit Holder, NC Licensed General Contractor,
NC Licensed Home Inspector, Registered
Certified BPI Envelope Professional, or
Approved HERS Rater
PFS CORPORATION
Approved Limited to Factory Built Portion Only

State: North Carolina
Signature: [Handwritten Signature]
Title: Staff Plan Reviewer
Date: 8/18/21

MUST BE COMPLETED BY BUILDER ON SITE

record the result. If the result is less than or equal to 5 CFM25/100SF for the "Total duct leakage test" or less than or equal to 4 CFM25/100SF for the "Duct leakage to the outside" test, then the HVAC system air tightness is acceptable.

Complete one duct leakage report for each HVAC system serving the home:

Property Address: _____

Test Performed: Total duct leakage or Duct leakage to the outside (circle one)

HVAC System Number: _____ Describe area of home served: _____

CFM25 Total _____ Conditioned Floor Area (CFA) served by system: _____ s.f.
CFM25 x 100 divided by CFA = _____ CFM25/100SF (e.g. 100 CFM25 x 100/2,000 CFA = 5 CFM25/100SF)

Fan attachment location _____

Company Name _____

Contact Information: _____

Signature of Tester _____
Date _____

Permit Holder, NC Licensed General Contractor, NC Licensed HVAC Contractor,
NC Licensed Home Inspector, Registered Design Professional,
Certified BPI Envelope Professional, or Certified HERS Rater
(circle one)

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Duvall*
Title: Staff Plan Reviewer
Date: 8/18/21

2018 NORTH CAROLINA RESIDENTIAL CODE

**E-4D.2
DUCT SEALING, Duct air leakage test
(Section N1103.3.3)
Sample Worksheet for Alternative Residential
Energy Code for Higher Efficiency**

N1103.3.3 Duct leakage (Prescriptive) and duct testing (Mandatory). Duct testing and duct leakage shall be verified by compliance with either Section N1103.3.3.1 or N1103.3.3.2. Duct testing shall be performed and reported by the permit holder, a NC licensed general contractor, a NC licensed HVAC contractor, a NC licensed Home Inspector, a registered design professional, a certified BPI Envelope Professional or a certified HERS rater. A single point depressurization, not temperature corrected, test is sufficient to comply with this provision, provided that the duct testing fan assembly(s) has been certified by the manufacturer to be capable of conducting tests in accordance with ASTM E1554-07.

The duct leakage information, including duct leakage test selected and result, tester name, date, and contact information, shall be included on the certificate described in Section N1101.3.

For the Test Criteria, the report shall be produced in the following manner: perform the HVAC system air leakage test and record the CFM25. Calculate the total square feet of Conditioned Floor Area (CFA) served by that system. Multiply CFM25 by 100, divide the result by the CFA and record the result. If the result is less than or equal to 4 CFM25/100SF for the "Total duct leakage test or less than or equal to 3 CFM25/100SF for the Duct leakage to the outside" test, then the HVAC system air tightness is acceptable.

Exceptions to testing requirements:


1. Duct systems or portions thereof inside the building thermal envelope shall not be required to be leak tested.
2. Installation of a partial system as part of replacement, renovation or addition does not require a duct leakage test.

1103.3.3.1 Total duct leakage. Total duct leakage less than or equal to 4 CFM (113 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, including the manufacturer's air handler enclosure. During testing:

1. Block, if present, ventilation air duct(s) connected to the conditioning system.
2. The duct air leakage testing equipment shall be attached to the largest return in the system or to the air handler.
3. The filter shall be removed and the air handler power shall be turned off.
4. Supply boots or registers and return boxes or grilles shall be taped, plugged, or otherwise sealed air tight.
5. The hose for measuring the 25 Pascals of pressure differential shall be inserted into the boot of the supply that is nominally closest to the air handler.

6. Specific instructions from the duct testing equipment manufacturer shall be followed to reach duct test pressure and measure duct air leakage.
- 1103.3.3.2 Duct leakage to the outside.** Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leak. Duct leakage to the outside shall be less than or equal to 3 CFM (85 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.
- During testing:
1. Block, if present, the ventilation air duct(s) connected to the conditioning system.
 2. The duct air leakage testing equipment shall be attached to the largest return in the system or to the air handler.
 3. The filter shall be removed and the air handler power shall be turned off.
 4. Supply boots or registers and return boxes or grilles shall be taped, plugged, or otherwise sealed air tight or as tight as possible.
 5. The hose for measuring the 25 Pascals of pressure differential shall be inserted into the boot of the supply that is nominally closest to the air handler.
 6. Open all interconnecting doors in the building, close dampers for fireplaces and other operable dampers.
 7. Set up an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door, following the manufacturer's prescribed procedure.
 8. Specific instructions from the duct testing equipment manufacturer shall be followed to reach duct test pressure and measure duct air leakage used in combination with a blower door. Typical steps are as follows:

- a. Depressurize the ductwork system to 25 Pa using the measurement hose in Step 5 above.
- b. Depressurize the house to 25 Pa using an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door.
- c. Correct the duct pressure to measure 0 Pa of pressure differential between the house and the ductwork system.
- d. Read the CFM of duct leakage using the procedure for the manufacturer's equipment being used. (Note that most automatically calculating pressure gauges cannot compute the CFM25 automatically with a duct-to-house difference in pressure of 0 Pa, so the final step, manual set to read



PFS CORPORATION
Approval Limited to Factory Built Potholes Only

State: North Carolina
Signature: Jim D'Amico
Title: Staff Plan Reviewer
Date: 8/18/21

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Permit Holder, NC Licensed General Contractor, NC Licensed HVAC Contractor, NC Licensed Home Inspector, Registered Design Professional, Certified BPI Envelope Professional, or Certified HERs Rater
 (circle one)

Property Address: _____
 HVAC System Number: _____ Describe area of home served: _____
 CFM25 Total _____ Conditioned Floor Area (CFA) served by system: _____ s.f.
 CFM25 x 100 divided by CFA = _____ CFM25/100 SF
 (e.g. 50 CFM25 x 100/2,000 CFA = 2.5 CFM25/100SF)
 Fan attachment location _____
 Company Name _____
 Contact Information: _____

 Signature of Tester _____
 Date _____

Complete one duct leakage report for each HVAC system serving the home:

APPENDIX E

MUST BE COMPLETED BY BUILDER ON SITE

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 State:
 Signature: *Jim Dussle*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Code can be found at R806.2 in the NC Residential and the IRC

Ventilation in House

| | |
|-----|---------|
| 874 | sq. in. |
| 576 | sq. in. |
| 8 | pc. |

32 ft. of Ridge Vent
 52.05% through Ridge Vent

Soffit Ventilation in house:
 Ridge Ventilation in house:
 Number of Ridge Vents in house:

House Required Ventilation

| | |
|----------|---------|
| 1106.56 | sq. in. |
| 553.28 | sq. in. |
| 553.28 | sq. in. |
| 7.684444 | pc. |

30.73778 ft. of Ridge Vent

Required Ventilation for House:
 Inches Required for Soffit Ventilation:
 Inches Required for Ridge Ventilation:
 Number of Ridge Vents Required:

Floor Type: 28 Wide 32 Wide Triple Wide T-Ranch Check if pod

Manufacturer Specifications
 Ridge Vent: 18 sq. in. per ft.
 Soffit Vent: 5.89 sq. in. per ft.

Required Ventilation
 Model Number: 23-3276-16
 Floor Length: 76 ft.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim D'Amico*
Title: Staff Plan Reviewer
Date: 8/18/21




| | | | |
|-----------------|------------|----|----------------|
| Front Sidelwall | USE PG. 55 | 71 | % of Sheathing |
| Rear Sidelwall | USE PG. 55 | 59 | % of Sheathing |
| Right Endwall | USE PG 41 | 71 | % of Sheathing |
| Left Endwall | USE PG 38 | 90 | % of Sheathing |

USE 32.083 FOR 32 WIDES
 USE 26.417 FOR 28 WIDES
 (Calculation sheet referenced to structural package)

House meets all applicability limits.

| | | |
|---|----------|---|
| a) House Mean Roof Height | 20' | Max. Mean Roof Height = 33'-0" |
| b) Number of Stores | 1 | Max. Number of Stores = 3 |
| c) House Length | 76 | Max. Length = 80'-0" |
| d) House Width | 30.3 | Min. Width = Mean Roof Height 20' |
| e) House Aspect Ratio | 2.508251 | Min. Ratio = 1:4 |
| = L / W | | |
| f) House Vertical Offset | 2.508251 | |
| g) Floor Diaphragm Aspect Ratio = L / W | | |
| h) House Floor Diaphragm Opening Width | 0 | Max. = 12'-0" |
| House Floor Diaphragm Opening Length | 0 | Max. = 12'-0" |
| i) Max. Shearwall Plan Offset | 0 | (If wall offset is more than 4'-0", count as 2 different shear walls) |
| j) Min. Shearwall Segment = h/3.5 | 2.571429 | |
| k) Wall Height | 9 | Max. Wall Height = 10' |
| l) Roof Diaphragm Aspect Ratio | 2.508251 | Max. Ratio = 4:1 |
| = L / W | | |
| m) Roof Slope | 5/12 | Min. 0/12 Max. 12/12 |

07/22/19



- P1 - P3
- P4 - P5
- P6
- P7 - P12
- P13
- P14
- P15
- P16
- P17
- P18
- P19 - P58

- TRUSS HM773855
- TRUSS SHEET (FOR REFERENCE ONLY)
- TRUSS CONNECTIONS
- TRUSS LOAD SUMMARY
- EXTERIOR WALL STUDS
- EXTERIOR WALL HEADER / JACKSTUDS
- MATING WALL STUDS
- MATING WALL HEADER / JACKSTUDS
- PERIMETER BANDS
- FLOOR JOISTS
- CENTER GIRDER
- SHEARWALL CALCULATIONS

SECTION 6


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

| | | | | | | | | | |
|-----|-------|-------|----------|------------|-----|---|-----|---|-----------------------|
| Job | 89373 | Truss | HM773855 | HINGE MONO | Qty | 1 | Ply | 1 | Champion Homes 315 NC |
| | | | | | | | | | Ref. #3157316 |

Universal Forest Products Inc., Grand Rapids, MI 49525, Weston Gorby 8.030 e Apr 8 2017 MITek Industries, Inc. Fri Sep 22 13:38:30 2017 Page 2 of 2

Copyright © 2017 Universal Forest Products, Inc. All Rights Reserved

- 3) TLL: ASCE 7-10; Pg=30.0 psf (ground snow); Ps=23.1 psf (roof snow); Category II; Exp C; Partially Exp.; Ct=1.1
- 4) Root design snow load has been reduced to account for slope.
- 5) Unbalanced snow loads have been considered for this design.
- 6) This truss has been designed for greater or min roof live load of 19.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- 7) All plates are MT20 plates unless otherwise indicated.
- 8) See HINGE PLATE DETAILS for plate placement.
- 9) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
- 10) All additional member connections shall be provided by others for forces as indicated.
- 11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 392 lb uplift at joint 8.
- 13) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TP1 1.
- 14) This truss is designed in accordance with the 2012 IBC Sec 2306.1 and referenced standard ANSI/TP1 1
- 15) Take precaution to keep the chords in plane, any bending or twisting of the hinge plate must be repaired before the building is put into service.
- 16) The field-installed members are an integral part of the truss design. Retain a design professional to specify final field connections and temporary supports. All field-installed members must be properly fastened prior to applying any loading to the truss. This design anticipates the final set position.
- 17) Based on: HM773854
- 18) Revision: IBC2015/2012 Version



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Jim Duvall*

Title: Staff Plan Reviewer

Date: 8/18/21

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

WARNING - Verify design parameters and READ NOTES
 Universal Forest Products, Inc. 2801 EAST BELTLINE RD, NE GRAND RAPIDS, MI 49525
 PHONE (616)-364-6161 FAX (616)-365-0060



Truss shall not be cut or modified without approval of the truss design engineer. Construction and lifting forces have not been considered. The builder is responsible for lifting methods and system design. Builder responsibilities are defined under TP1. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult BCSI 1-06 from the Wood Truss Council of America and Truss Plate Institute Recommendation available from WTCA, 6300 Enterprise LN, Madison, WI 53719. J:\support\Mittek\suppl templates\trp;pe

190284

SECTION 6/ pp. 2

Corporate Engineering
 2801 East Beltline, NE Grand Rapids, MI 49525-9736 (616) 364-6161 Fax (616) 365-0060
 SECTION 6/ pp. 3
 190288
 ufpi.com

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim D'Amico*
 Title: Staff Plan Reviewer
 Date: 8/18/21



The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

| | | | | |
|-----|-------|----------|----------|----------------|
| Job | 89373 | HM773855 | 315 | CHAMPION HOMES |
| | Truss | MFG | Customer | |

Universal Forest Products




TRUSS CALCULATIONS

CHAMPION HOMES OF NC

TRUSS CONNECTIONS

TRUSS NUMBER : HM773855
 PROJECT NUMBER : 190127
 TRUSS PITCH : 5/12
 TRUSS SPAN : 15'-2"
 UNIT WIDTH : 30'-4"



UPLIFT CONNECTIONS (MWFRS LOADS):

| CONDITION "A" - EXTERIOR WALL: | UPLIFT (lbs) | CASE | WIND | CD | 1 1/2" x 26ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 16 ga STAPLE | QTY / END | QTY / END | QTY / END | QTY / END | CHECK ALT. STRAP | CHECK ALT. STRAP | |
|---|--------------------------|------|------|---------|---------------------|------------|--------------|----------------------|------------|--------------|----------------------|------------|--------------|------------------------|-----------|-----------|-----------|-----------|------------------|------------------|--|
| 150 / 119 mph | 392 | CD | 1.6 | OK | OK | 3 | 4 | OK | 2 | 4 | OK | 2 | 4 | SIMPSON H8 TWIST STRAP | 4 | 2 | 4 | 2 | OK | OK | |
| ALTERNATE: (5) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (1) SIMPSON SDWC15600 SCREW | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION | | | | | | | | | | | | | | | | | | | | | |
| CONDITION "B" - MATING WALL (PER SIDE): | UPLIFT (lbs) / PER SIDE) | CASE | WIND | CD | 1 1/2" x 26ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 16 ga STAPLE | QTY / END | QTY / END | QTY / END | QTY / END | CHECK ALT. STRAP | CHECK ALT. STRAP | |
| 130 / 101 mph (ADJUSTED) | 497 | CD | 1.6 | NO GOOD | NO GOOD | N/A | N/A | OK | 2 | 5 | OK | 2 | 5 | SIMPSON CS20 STRAP | 5 | 2 | 5 | 2 | OK | OK | |
| ALTERNATE: (6) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (4) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (1) SIMPSON SDWC15600 SCREW | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION | | | | | | | | | | | | | | | | | | | | | |
| CONDITION "A" - EXTERIOR WALL: | UPLIFT (lbs) | CASE | WIND | CD | 1 1/2" x 26ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 16 ga STAPLE | QTY / END | QTY / END | QTY / END | QTY / END | CHECK ALT. STRAP | CHECK ALT. STRAP | |
| 115 / 90 mph (ADJUSTED) | 294 | CD | 1.6 | OK | OK | 2 | 3 | OK | 2 | 3 | OK | 2 | 3 | SIMPSON H3 TWIST STRAP | 3 | 2 | 3 | 2 | OK | OK | |
| ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (1) SIMPSON SDWC15600 SCREW | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION | | | | | | | | | | | | | | | | | | | | | |
| CONDITION "B" - MATING WALL (PER SIDE): | UPLIFT (lbs) / PER SIDE) | CASE | WIND | CD | 1 1/2" x 26ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 16 ga STAPLE | QTY / END | QTY / END | QTY / END | QTY / END | CHECK ALT. STRAP | CHECK ALT. STRAP | |
| 115 / 90 mph (ADJUSTED) | 231 | CD | 1.6 | OK | OK | 2 | 3 | OK | 2 | 3 | OK | 2 | 3 | SIMPSON H3 TWIST STRAP | 3 | 2 | 3 | 2 | OK | OK | |
| ALTERNATE: (3) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (2) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (1) SIMPSON SDWC15600 SCREW | | | | | | | | | | | | | | | | | | | | | |
| ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION | | | | | | | | | | | | | | | | | | | | | |
| CONDITION "B" - MATING WALL (PER SIDE): | UPLIFT (lbs) / PER SIDE) | CASE | WIND | CD | 1 1/2" x 26ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STAPLE | 16 ga STAPLE | QTY / END | QTY / END | QTY / END | QTY / END | CHECK ALT. STRAP | CHECK ALT. STRAP | |
| 292 | 292 | CD | 1.6 | OK | OK | 2 | 3 | OK | 2 | 3 | OK | 2 | 3 | SIMPSON H3 TWIST STRAP | 3 | 2 | 3 | 2 | OK | OK | |
| ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD | | | | | | | | | | | | | | | | | | | | | |


PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Duvall*
Title: Staff Plan Reviewer
Date: 8/18/21

| CONDITION "C" - KNEEWALL TO WEB MEMBER: | | | | | | | | | |
|--|------------|----------------------|------------|------------------|-------------|------------------|-------------|------------------|-------------|
| 1 1/2" x 26ga STRAP | 10 d NAILS | 1 1/2" x 20 ga STRAP | 10 d NAILS | 16 ga STRAP | 16 ga STRAP | 10 d NAILS | 16 ga STRAP | 10 d NAILS | 16 ga STRAP |
| OK | 4 | OK | 5 | OK | 5 | OK | 5 | OK | 5 |
| CHECK STRAP | QTY / END | CHECK ALT. STRAP | QTY / END | CHECK ALT. STRAP | QTY / END | CHECK ALT. STRAP | QTY / END | CHECK ALT. STRAP | QTY / END |
| 443 | 1.15 | 443 | 1.15 | 443 | 1.15 | 443 | 1.15 | 443 | 1.15 |
| TENSION (lbs) | CASE | TENSION (lbs) | CASE | TENSION (lbs) | CASE | TENSION (lbs) | CASE | TENSION (lbs) | CASE |
| 157 | SNOW | 157 | SNOW | 157 | SNOW | 157 | SNOW | 157 | SNOW |
| 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD |
| CONDITION "D" - TOP CHORD FLIP: | | | | | | | | | |
| 55 | SNOW | 55 | SNOW | 55 | SNOW | 55 | SNOW | 55 | SNOW |
| 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD |
| 38 | SNOW | 38 | SNOW | 38 | SNOW | 38 | SNOW | 38 | SNOW |
| 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD | 1.15 | CD |
| ALTERNATE: USE (2) 16 ga STRAP THROUGH SHEATHING EACH SIDE | | | | | | | | | |
| USE (2) 16 d NAILS TOENAILED EACH END PLUS USE 10 d NAILS AT 24 in O.C. THROUGH PLATES | | | | | | | | | |



TRUSS NUMBER : HM773855
 PROJECT NUMBER : 190127
 TRUSS PITCH : 5/12
 TRUSS SPAN : 15'-2"
 UNIT WIDTH : 30'-4"

TRUSS CONNECTIONS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Burke*
Title: Staff Plan Reviewer
Date: 8/18/21

| | | | | |
|------------------------|-----|-----|-----|-----|
| LOCATION | 1 | 2 | 3 | 4 |
| UPLIFT (0.6) DEAD LOAD | 105 | 103 | 223 | 196 |
| 150 / 119 mph UPLIFT | 196 | 249 | - | -53 |
| 130 / 101 mph UPLIFT | 147 | 187 | - | - |
| 115 / 90 mph UPLIFT | 116 | 146 | - | - |

C & C UPLIFT

| | | | | |
|------------|-----|-----|-----|-----|
| LOCATION | 1 | 2 | 3 | 4 |
| DEAD LOAD | 175 | 171 | 371 | 327 |
| LIVE LOAD | 201 | 196 | 505 | 500 |
| TOTAL LOAD | 376 | 367 | 876 | 827 |

30 psf GROUND SNOW (MATING WALL LOADS ARE PER SIDE OF LINE)

COMPONENT LOADS (lbs/ft)


TRUSS HM773855, 5/12 PITCH, 15'-2" WIDTH

| |
|--|
| LOCATION 1 = EXT. WALL HEADER & EXT. WALL STUD |
| LOCATION 2 = M. WALL HEADER & M. WALL STUD |
| LOCATION 3 = PERIMETER BAND |
| LOCATION 4 = CENTER GIRDER |
| LOCATIONS 3 & 4 MAY BE USED TO GENERATE FOUNDATION LOADS |

| | | | | | | | | |
|---------------------------|----|-----|---|-------|--------|---|-------|-----|
| EXTERIOR WALL DEAD LOAD = | 12 | psf | x | 10 | ft | = | 120 | plf |
| MATING WALL DEAD LOAD = | 8 | psf | x | 10 | ft | = | 80 | plf |
| FLOOR DEAD LOAD = | 10 | psf | x | 15.16 | ft / 2 | = | 75.8 | plf |
| FLOOR LIVE LOAD = | 40 | psf | x | 15.16 | ft / 2 | = | 303.2 | plf |
| CEILING DEAD LOAD = | 5 | psf | x | 15.16 | ft / 2 | = | 37.9 | plf |

COMPONENT LOAD SUMMARY

* CROSS SECTION IS FOR REFERENCE ONLY
 AND MAY NOT REFLECT ACTUAL TRUSS



EXTERIOR WALL STUD TABLES



PFS CORPORATION
Approval Limited to Factory Built Portion Only

CHAMPION HOMES of NC

State: North Carolina
Signature: *Tim Swade*
Title: Staff Plan Reviewer
Date: 8/18/21

101/130 mph WIND, 5/12 PITCH, FIELD PRESSURE (27.47 psf)

| HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | | | | | | | |
|----------------------|----------------------|--------------|------------|--------------|----------------------|----------------------|---------|--------------|-----------|----------------------|----------------------|---------|------------|--------------|--------------|--------|--------|--------|--------|--------|-------|
| 8 ft | 2 x 4 SPF STUD GRADE | 12 | 755 | 0.227 | 9 ft | 2 x 4 SPF STUD GRADE | 12 | 295 | 0.372 | 10 ft | 2 x 4 SPF STUD GRADE | 12 | **NG** | - | | | | | | | |
| | | 16 | 295 | 0.303 | | | 16 | **NG** | - | | | 16 | **NG** | - | | | | | | | |
| | | 19.2 | 295 | 0.364 | | | 19.2 | **NG** | - | | | 19.2 | **NG** | - | | | | | | | |
| | 2 x 4 SPF #2 | 24 | **NG** | - | | 2 x 4 SPF #2 | 24 | **NG** | - | | 2 x 4 SPF #2 | 24 | **NG** | - | 24 | **NG** | - | | | | |
| | | | 12 | 1565 | | | | 0.195 | 12 | | | | 1035 | 0.319 | | 12 | 660 | 0.495 | | | |
| | | | 16 | 1265 | | | | 0.26 | 16 | | | | 740 | 0.426 | | 16 | **NG** | - | | | |
| | | 2 x 4 SYP #2 | 19.2 | 1035 | | | 0.312 | 2 x 4 SYP #2 | 19.2 | | | **NG** | - | 2 x 4 SYP #2 | 19.2 | **NG** | - | 19.2 | **NG** | - | |
| | | | | 24 | | | 685 | | | | | 0.39 | 24 | | | **NG** | - | | 24 | **NG** | - |
| | | | | 12 | | | 1395 | | | | | 0.195 | 12 | | | 865 | 0.319 | | 12 | 490 | 0.495 |
| | 2 x 4 SYP #2 | 16 | 1045 | 0.26 | | 2 x 4 SYP #2 | 16 | 510 | 0.426 | | 2 x 4 SYP #2 | 16 | **NG** | - | 2 x 4 SYP #2 | 16 | **NG** | - | | | |
| | | | 19.2 | 765 | | | | 0.312 | 19.2 | | | | **NG** | - | | | 19.2 | **NG** | - | | |
| | | | 24 | 320 | | | | 0.39 | 24 | | | | **NG** | - | | | 24 | **NG** | - | | |
| 2 x 6 SPF STUD GRADE | | 12 | 4790 | 0.059 | 2 x 6 SPF STUD GRADE | | 12 | 3605 | 0.096 | 2 x 6 SPF STUD GRADE | | 12 | 2610 | 0.149 | | 12 | 1915 | 0.198 | | | |
| | | | 16 | 4180 | | | | 0.078 | 16 | | | | 2940 | 0.128 | | | 16 | 1340 | 0.238 | | |
| | | | 19.2 | 3705 | | | | 0.094 | 19.2 | | | | 2420 | 0.154 | | | 19.2 | 375 | 0.298 | | |
| 2 x 6 SPF #2 | 24 | 2995 | 0.117 | 2 x 6 SPF #2 | 24 | 1605 | 0.192 | 2 x 6 SPF #2 | 24 | 4275 | 0.128 | 24 | 2685 | 0.255 | | | | | | | |
| | | 12 | 7380 | | | 0.05 | 12 | | | 5625 | 0.082 | | 12 | 4075 | 0.128 | | | | | | |
| | | 16 | 6810 | | | 0.067 | 16 | | | 5055 | 0.11 | | 16 | 3720 | 0.17 | | | | | | |
| | 2 x 6 SYP #2 | 19.2 | 6380 | | 0.08 | 2 x 6 SYP #2 | 19.2 | | 4625 | 0.132 | 2 x 6 SYP #2 | | 19.2 | 3300 | 0.204 | 19.2 | 2980 | 0.204 | | | |
| | | | 24 | | 5770 | | | | 0.1 | 24 | | | | 4010 | 0.164 | | 24 | 2685 | 0.255 | | |
| | | | 12 | | 7285 | | | | 0.05 | 12 | | | | 5450 | 0.082 | | 12 | 4075 | 0.128 | | |
| 2 x 6 SYP #2 | 16 | 6635 | 0.067 | 2 x 6 SYP #2 | 16 | 4815 | 0.11 | 2 x 6 SYP #2 | 16 | 3455 | 0.17 | 16 | 3455 | 0.17 | | | | | | | |
| | | 19.2 | 6150 | | | 0.08 | 19.2 | | | 4330 | 0.132 | | 19.2 | 2980 | 0.204 | | | | | | |
| | | 24 | 5455 | | | 0.1 | 24 | | | 3635 | 0.164 | | 24 | 2275 | 0.255 | | | | | | |

P:\2019\190284\HMT\738551EXVALLS

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
EVEN IF RATIO MEETS CODE REQUIREMENTS

190284

BARLOW ENGINEERING, P.C.
6312 SIX FORKS RD., SUITE 203-B
RALEIGH, NC 27615
SECTION 6/ pp. 9

EXTERIOR WALL STUD TABLES



PFS CORPORATION

Approval: Limited to Factory Built Portion Only

North Carolina

State:
Signature:

Tim Swade

Title: Staff Plan Reviewer

Date: 8/18/21

CHAMPION HOMES of NC

101/130 mph WIND, 5/12 PITCH, EDGE PRESSURE (33.35 psf)

| HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | | | | |
|----------------------|----------------------|---------|------------|--------------|--------------|----------------------|---------|--------------|-----------|--------------|----------------------|--------------|------------|-----------|--------------|------|--------|-------|
| 8 ft | 2 x 4 SPF STUD GRADE | 12 | 470 | 0.276 | 9 ft | 2 x 4 SPF STUD GRADE | 12 | **NG** | - | 10 ft | 2 x 4 SPF STUD GRADE | 12 | **NG** | - | | | | |
| | | 16 | 295 | 0.368 | | | 16 | **NG** | - | | | 16 | **NG** | - | | | | |
| | | 19.2 | **NG** | - | | | 19.2 | **NG** | - | | | 19.2 | **NG** | - | | | | |
| | 2 x 4 SPF #2 | 24 | **NG** | - | | 2 x 4 SPF #2 | 24 | **NG** | - | | 2 x 4 SPF #2 | 24 | **NG** | - | 2 x 4 SPF #2 | 24 | **NG** | - |
| | | 12 | 1370 | 0.237 | | | 12 | 845 | 0.387 | | | 12 | **NG** | - | | 12 | **NG** | - |
| | | 16 | 1020 | 0.316 | | | 16 | **NG** | - | | | 16 | **NG** | - | | 16 | **NG** | - |
| | 2 x 4 SYP #2 | 19.2 | 735 | 0.379 | | 2 x 4 SYP #2 | 19.2 | **NG** | - | | 2 x 4 SYP #2 | 19.2 | **NG** | - | 2 x 4 SYP #2 | 19.2 | **NG** | - |
| | | 24 | **NG** | - | | | 24 | **NG** | - | | | 24 | **NG** | - | | 24 | **NG** | - |
| | | 12 | 1170 | 0.237 | | | 12 | 640 | 0.387 | | | 12 | **NG** | - | | 12 | **NG** | - |
| | 2 x 4 SYP #2 | 16 | 745 | 0.316 | | 2 x 4 SYP #2 | 16 | **NG** | - | | 2 x 4 SYP #2 | 16 | **NG** | - | 2 x 4 SYP #2 | 16 | **NG** | - |
| | | 19.2 | 385 | 0.379 | | | 19.2 | **NG** | - | | | 19.2 | **NG** | - | | 19.2 | **NG** | - |
| | | 24 | **NG** | - | | | 24 | **NG** | - | | | 24 | **NG** | - | | 24 | **NG** | - |
| 2 x 6 SPF STUD GRADE | 2 x 6 SPF STUD GRADE | 12 | 4395 | 0.071 | 2 x 6 SPF #2 | 2 x 6 SPF STUD GRADE | 12 | 3175 | 0.116 | 2 x 6 SPF #2 | 2 x 6 SPF STUD GRADE | 12 | 2160 | 0.181 | | | | |
| | | 16 | 3670 | 0.095 | | | 16 | 2380 | 0.155 | | | 16 | 1300 | 0.241 | | | | |
| | | 19.2 | 3095 | 0.114 | | | 19.2 | 1725 | 0.186 | | | 19.2 | 530 | 0.289 | | | | |
| | 2 x 6 SPF #2 | 24 | 2205 | 0.142 | | 2 x 6 SPF #2 | 24 | 625 | 0.233 | | 2 x 6 SPF #2 | 24 | 295 | 0.361 | 2 x 6 SPF #2 | 24 | 295 | 0.361 |
| | | 12 | 7005 | 0.061 | | | 12 | 5250 | 0.1 | | | 12 | 3915 | 0.155 | | 12 | 3915 | 0.155 |
| | | 16 | 6350 | 0.081 | | | 16 | 4595 | 0.133 | | | 16 | 3265 | 0.206 | | 16 | 3265 | 0.206 |
| 2 x 6 SYP #2 | 19.2 | 5855 | 0.098 | 2 x 6 SYP #2 | 19.2 | 4095 | 0.16 | 2 x 6 SYP #2 | 19.2 | 2770 | 0.248 | 2 x 6 SYP #2 | 19.2 | 2770 | 0.248 | | | |
| | 24 | 5140 | 0.122 | | 24 | 3370 | 0.2 | | 24 | 2025 | 0.31 | | 24 | 2025 | 0.31 | | | |
| | 12 | 6860 | 0.061 | | 12 | 5035 | 0.1 | | 12 | 3670 | 0.155 | | 12 | 3670 | 0.155 | | | |
| 2 x 6 SYP #2 | 16 | 6115 | 0.081 | 2 x 6 SYP #2 | 16 | 4300 | 0.133 | 2 x 6 SYP #2 | 16 | 2945 | 0.206 | 2 x 6 SYP #2 | 16 | 2945 | 0.206 | | | |
| | 19.2 | 5555 | 0.098 | | 19.2 | 3735 | 0.16 | | 19.2 | 2375 | 0.248 | | 19.2 | 2375 | 0.248 | | | |
| | 24 | 4740 | 0.122 | | 24 | 2900 | 0.2 | | 24 | 1505 | 0.31 | | 24 | 1505 | 0.31 | | | |

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS

EVEN IF RATIO MEETS CODE REQUIREMENTS

EXTERIOR WALL HEADER - 1 STORY (LOCATION 1)

2x3 FOR (1) MEMBER HEADERS
2x4 FOR (2) MEMBER HEADERS
2x6 FOR (3) MEMBER HEADERS

TRUSS HM773855

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

| MEMBER | QUANTITY | HEADER | TL (pif) | HEADER | MAXIMUM | SPAN | LIMITED BY | DEFLECTION (in) | MID-SPAN | MIN. NUMBER OF JACKSTDS REQ'D EACH END | SYP #2 | SYP #2 | SPF STUD | UPLIFT (pif) | REACTION (lbs) |
|---------------|----------|--------|----------|--------|---------|------|------------|-----------------|----------|--|--------|--------|----------|--------------|----------------|
| 2x4 SPF #2 | 1 | 378 | 201 | 2 | 4'-2" | 378 | LB | 0.075 | 0.206 | 2 | 2 | 2 | 2 | 196 | 280 |
| 2x6 SPF #2 | 1 | 378 | 201 | 1 | 4'-2" | 378 | LB | 0.088 | 0.304 | 2 | 2 | 2 | 2 | 196 | 409 |
| 2x8 SPF #2 | 1 | 378 | 201 | 1 | 5'-3" | 378 | LB | 0.1 | 0.304 | 2 | 2 | 2 | 2 | 196 | 518 |
| 2x10 SPF #2 | 1 | 378 | 201 | 1 | 6'-5" | 378 | LB | 0.107 | 0.304 | 2 | 2 | 2 | 2 | 196 | 633 |
| 2x4 SYP #2 | 1 | 378 | 201 | 1 | 7'-5" | 378 | LB | 0.108 | 0.206 | 2 | 2 | 2 | 2 | 196 | 734 |
| 2x4 SYP #2 | 1 | 378 | 201 | 1 | 2'-7" | 378 | LB | 0.053 | 0.206 | 2 | 2 | 2 | 2 | 196 | 256 |
| 2x6 SYP #2 | 1 | 378 | 201 | 1 | 3'-10" | 378 | LB | 0.066 | 0.304 | 2 | 2 | 2 | 2 | 196 | 383 |
| 2x8 SYP #2 | 1 | 378 | 201 | 1 | 4'-11" | 378 | LB | 0.078 | 0.304 | 2 | 2 | 2 | 2 | 196 | 487 |
| 2x10 SYP #2 | 1 | 378 | 201 | 1 | 5'-10" | 378 | LB | 0.074 | 0.304 | 2 | 2 | 2 | 2 | 196 | 577 |
| 2x12 SYP #2 | 1 | 378 | 201 | 1 | 7'-1" | 378 | LB | 0.09 | 0.206 | 2 | 2 | 2 | 2 | 196 | 702 |
| 1.5x3.5 LVL | 1 | 378 | 201 | 1 | 4'-0" | 378 | LB | 0.206 | 0.206 | 2 | 2 | 2 | 2 | 196 | 393 |
| 1.5x5.5 LVL | 1 | 378 | 201 | 1 | 6'-2" | 378 | LB | 0.304 | 0.304 | 2 | 2 | 2 | 2 | 196 | 609 |
| 1.5x7.25 LVL | 1 | 378 | 201 | 1 | 8'-1" | 378 | LB | 0.387 | 0.387 | 2 | 2 | 2 | 2 | 196 | 795 |
| 1.5x9.25 LVL | 1 | 378 | 201 | 1 | 10'-3" | 378 | LB | 0.479 | 0.479 | 2 | 2 | 2 | 2 | 196 | 1007 |
| 1.5x11.25 LVL | 1 | 378 | 201 | 1 | 12'-4" | 378 | LB | 0.568 | 0.568 | 3 | 3 | 3 | 3 | 196 | 1217 |
| 1.5x12 LVL | 1 | 378 | 201 | 1 | 13'-2" | 378 | LB | 0.6 | 0.6 | 3 | 3 | 3 | 3 | 196 | 1295 |
| 1.5x14 LVL | 1 | 378 | 201 | 1 | 15'-4" | 378 | LB | 0.687 | 0.687 | 3 | 3 | 3 | 3 | 196 | 1503 |
| 1.5x16 LVL | 1 | 378 | 201 | 1 | 17'-5" | 378 | LB | 0.771 | 0.771 | 3 | 3 | 3 | 3 | 196 | 1711 |
| 1.5x18 LVL | 1 | 378 | 201 | 1 | 19'-6" | 378 | LB | 0.854 | 0.854 | 3 | 3 | 3 | 3 | 196 | 1917 |
| 1.5x20 LVL | 1 | 378 | 201 | 1 | 21'-7" | 378 | LB | 0.936 | 0.936 | 3 | 3 | 3 | 3 | 196 | 2123 |
| 1.5x22 LVL | 1 | 378 | 201 | 1 | 23'-7" | 378 | LB | 1.017 | 1.017 | 3 | 3 | 3 | 3 | 196 | 2328 |
| 1.5x24 LVL | 1 | 378 | 201 | 1 | 25'-7" | 378 | LB | 1.097 | 1.097 | 3 | 3 | 3 | 3 | 196 | 2532 |
| 2x4 SPF #2 | 2 | 378 | 201 | 2 | 4'-10" | 378 | LB | 0.177 | 0.177 | 1 | 1 | 1 | 1 | 196 | 396 |
| 2x6 SPF #2 | 2 | 378 | 201 | 2 | 7'-5" | 378 | LB | 0.214 | 0.214 | 1 | 1 | 1 | 1 | 196 | 578 |
| 2x8 SPF #2 | 2 | 378 | 201 | 2 | 9'-1" | 378 | LB | 0.215 | 0.215 | 1 | 1 | 1 | 1 | 196 | 733 |
| 2x10 SPF #2 | 2 | 378 | 201 | 2 | 10'-11" | 378 | LB | 0.215 | 0.215 | 1 | 1 | 1 | 1 | 196 | 896 |
| 2x4 SYP #2 | 2 | 378 | 201 | 2 | 3'-8" | 378 | LB | 0.106 | 0.106 | 2 | 2 | 2 | 2 | 196 | 362 |
| 2x6 SYP #2 | 2 | 378 | 201 | 2 | 5'-6" | 378 | LB | 0.136 | 0.136 | 2 | 2 | 2 | 2 | 196 | 542 |
| 2x8 SYP #2 | 2 | 378 | 201 | 2 | 7'-0" | 378 | LB | 0.155 | 0.155 | 2 | 2 | 2 | 2 | 196 | 688 |
| 2x10 SYP #2 | 2 | 378 | 201 | 2 | 8'-3" | 378 | LB | 0.148 | 0.148 | 2 | 2 | 2 | 2 | 196 | 817 |
| 2x12 SYP #2 | 2 | 378 | 201 | 2 | 10'-11" | 378 | LB | 0.18 | 0.18 | 2 | 2 | 2 | 2 | 196 | 993 |
| 1.5x3.5 LVL | 2 | 378 | 201 | 2 | 5'-8" | 378 | LB | 0.411 | 0.411 | 1 | 1 | 1 | 1 | 196 | 556 |
| 1.5x5.5 LVL | 2 | 378 | 201 | 2 | 8'-9" | 378 | LB | 0.609 | 0.609 | 1 | 1 | 1 | 1 | 196 | 861 |
| 1.5x7.25 LVL | 2 | 378 | 201 | 2 | 11'-5" | 378 | LB | 0.775 | 0.775 | 2 | 2 | 2 | 2 | 196 | 1125 |
| 1.5x9.25 LVL | 2 | 378 | 201 | 2 | 14'-6" | 378 | LB | 0.957 | 0.957 | 2 | 2 | 2 | 2 | 196 | 1424 |
| 1.5x11.25 LVL | 2 | 378 | 201 | 2 | 17'-6" | 378 | LB | 1.135 | 1.135 | 2 | 2 | 2 | 2 | 196 | 1721 |
| 1.5x12 LVL | 2 | 378 | 201 | 2 | 18'-8" | 378 | LB | 1.2 | 1.2 | 2 | 2 | 2 | 2 | 196 | 1831 |
| 1.5x14 LVL | 2 | 378 | 201 | 2 | 21'-8" | 378 | LB | 1.373 | 1.373 | 3 | 3 | 3 | 3 | 196 | 2126 |
| 1.5x16 LVL | 2 | 378 | 201 | 2 | 24'-8" | 378 | LB | 1.542 | 1.542 | 3 | 3 | 3 | 3 | 196 | 2419 |
| 1.5x18 LVL | 2 | 378 | 201 | 2 | 27'-7" | 378 | LB | 1.708 | 1.708 | 3 | 3 | 3 | 3 | 196 | 2711 |
| 1.5x20 LVL | 2 | 378 | 201 | 2 | 30'-7" | 378 | LB | 1.872 | 1.872 | 3 | 3 | 3 | 3 | 196 | 3002 |
| 1.5x22 LVL | 2 | 378 | 201 | 2 | 33'-7" | 378 | LB | 2.034 | 2.034 | 3 | 3 | 3 | 3 | 196 | 3292 |
| 1.5x24 LVL | 2 | 378 | 201 | 2 | 36'-6" | 378 | LB | 2.194 | 2.194 | 3 | 3 | 3 | 3 | 196 | 3581 |
| 2x4 SPF #2 | 3 | 378 | 201 | 3 | 4'-11" | 378 | LB | 0.226 | 0.226 | 1 | 1 | 1 | 1 | 196 | 485 |
| 2x6 SPF #2 | 3 | 378 | 201 | 3 | 7'-2" | 378 | LB | 0.265 | 0.265 | 1 | 1 | 1 | 1 | 196 | 708 |
| 2x8 SPF #2 | 3 | 378 | 201 | 3 | 9'-1" | 378 | LB | 0.3 | 0.3 | 1 | 1 | 1 | 1 | 196 | 898 |
| 2x10 SPF #2 | 3 | 378 | 201 | 3 | 11'-2" | 378 | LB | 0.321 | 0.321 | 1 | 1 | 1 | 1 | 196 | 1097 |
| 2x12 SPF #2 | 3 | 378 | 201 | 3 | 12'-11" | 378 | LB | 0.323 | 0.323 | 1 | 1 | 1 | 1 | 196 | 1272 |
| 2x4 SYP #2 | 3 | 378 | 201 | 3 | 4'-6" | 378 | LB | 0.159 | 0.159 | 1 | 1 | 1 | 1 | 196 | 444 |
| 2x6 SYP #2 | 3 | 378 | 201 | 3 | 6'-9" | 378 | LB | 0.205 | 0.205 | 1 | 1 | 1 | 1 | 196 | 664 |
| 2x8 SYP #2 | 3 | 378 | 201 | 3 | 8'-7" | 378 | LB | 0.233 | 0.233 | 1 | 1 | 1 | 1 | 196 | 843 |
| 2x10 SYP #2 | 3 | 378 | 201 | 3 | 10'-2" | 378 | LB | 0.222 | 0.222 | 1 | 1 | 1 | 1 | 196 | 1000 |
| 2x12 SYP #2 | 3 | 378 | 201 | 3 | 12'-4" | 378 | LB | 0.27 | 0.27 | 1 | 1 | 1 | 1 | 196 | 1216 |
| 1.5x3.5 LVL | 3 | 378 | 201 | 3 | 6'-11" | 378 | LB | 0.617 | 0.617 | 1 | 1 | 1 | 1 | 196 | 681 |
| 1.5x5.5 LVL | 3 | 378 | 201 | 3 | 10'-9" | 378 | LB | 0.913 | 0.913 | 1 | 1 | 1 | 1 | 196 | 1054 |
| 1.5x7.25 LVL | 3 | 378 | 201 | 3 | 14'-0" | 378 | LB | 1.162 | 1.162 | 1 | 1 | 1 | 1 | 196 | 1378 |
| 1.5x9.25 LVL | 3 | 378 | 201 | 3 | 17'-9" | 378 | LB | 1.436 | 1.436 | 1 | 1 | 1 | 1 | 196 | 1744 |
| 1.5x11.25 LVL | 3 | 378 | 201 | 3 | 21'-6" | 378 | LB | 1.703 | 1.703 | 1 | 1 | 1 | 1 | 196 | 2107 |
| 1.5x12 LVL | 3 | 378 | 201 | 3 | 22'-10" | 378 | LB | 1.801 | 1.801 | 1 | 1 | 1 | 1 | 196 | 2243 |
| 1.5x14 LVL | 3 | 378 | 201 | 3 | 26'-6" | 378 | LB | 2.06 | 2.06 | 1 | 1 | 1 | 1 | 196 | 2604 |
| 1.5x16 LVL | 3 | 378 | 201 | 3 | 30'-2" | 378 | LB | 2.313 | 2.313 | 1 | 1 | 1 | 1 | 196 | 2963 |
| 1.5x18 LVL | 3 | 378 | 201 | 3 | 33'-10" | 378 | LB | 2.561 | 2.561 | 2 | 2 | 2 | 2 | 196 | 3320 |
| 1.5x20 LVL | 3 | 378 | 201 | 3 | 37'-6" | 378 | LB | 2.808 | 2.808 | 2 | 2 | 2 | 2 | 196 | 3677 |
| 1.5x22 LVL | 3 | 378 | 201 | 3 | 41'-1" | 378 | LB | 3.052 | 3.052 | 2 | 2 | 2 | 2 | 196 | 4032 |
| 1.5x24 LVL | 3 | 378 | 201 | 3 | 44'-9" | 378 | LB | 3.291 | 3.291 | 2 | 2 | 2 | 2 | 196 | 4386 |

PFS CORPORATION
Approval Limited to Factory Built Portion Only
State: North Carolina
Signature: Jim Diwanke
Title: Staff Plan Reviewer
Date: 8/18/21

MATING WALL STUDS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

CHAMPION HOMES OF NC

State: North Carolina
Signature: *Tim Swade*
Title: Staff Plan Reviewer

ALL WINDS, ALL PITCHES, LATERAL PRESSURE (5 psf) **Date:** 8/18/21

| HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) | HEIGHT | SIZE | SPACING | LOAD (lbs) | DEF. (in) |
|-------------------------|-------------------------|---------|------------|-----------|-------------------------|-------------------------|---------|------------|-----------|-------------------------|-------------------------|---------|------------|-----------|
| 8 ft | 2 x 3 SPF STUD GRADE | 12 | 610 | 0.114 | 9 ft | 2 x 3 SPF STUD GRADE | 12 | 435 | 0.186 | 10 ft | 2 x 3 SPF STUD GRADE | 12 | 310 | 0.288 |
| | | 16 | 540 | 0.151 | | | 16 | 370 | 0.248 | | | 16 | 295 | 0.385 |
| | | 19.2 | 490 | 0.182 | | | 19.2 | 320 | 0.298 | | | 19.2 | 295 | 0.461 |
| 2 x 3 SPF #2 | 2 x 3 SPF #2 | 12 | 830 | 0.097 | 2 x 3 SPF #2 | 2 x 3 SPF #2 | 12 | 615 | 0.159 | 2 x 3 SPF #2 | 2 x 3 SPF #2 | 12 | 465 | 0.247 |
| | | 16 | 775 | 0.13 | | | 16 | 565 | 0.213 | | | 16 | 415 | 0.33 |
| | | 19.2 | 735 | 0.156 | | | 19.2 | 525 | 0.255 | | | 19.2 | 385 | 0.395 |
| 2 x 3 SYP #2 | 2 x 3 SYP #2 | 12 | 800 | 0.097 | 2 x 3 SYP #2 | 2 x 3 SYP #2 | 12 | 475 | 0.319 | 2 x 3 SYP #2 | 2 x 3 SYP #2 | 12 | 335 | 0.494 |
| | | 16 | 740 | 0.13 | | | 16 | 585 | 0.159 | | | 16 | 435 | 0.247 |
| | | 19.2 | 695 | 0.156 | | | 19.2 | 530 | 0.213 | | | 19.2 | 385 | 0.33 |
| 2 x 4 SPF STUD GRADE | 2 x 4 SPF STUD GRADE | 12 | 1920 | 0.041 | 2 x 4 SPF STUD GRADE | 2 x 4 SPF STUD GRADE | 12 | 1450 | 0.068 | 2 x 4 SPF STUD GRADE | 2 x 4 SPF STUD GRADE | 12 | 1110 | 0.105 |
| | | 16 | 1810 | 0.055 | | | 16 | 1345 | 0.09 | | | 16 | 1010 | 0.14 |
| | | 19.2 | 1725 | 0.066 | | | 19.2 | 1265 | 0.108 | | | 19.2 | 940 | 0.168 |
| 2 x 4 SPF #2 | 2 x 4 SPF #2 | 12 | 2495 | 0.035 | 2 x 4 SPF #2 | 2 x 4 SPF #2 | 12 | 1905 | 0.058 | 2 x 4 SPF #2 | 2 x 4 SPF #2 | 12 | 1485 | 0.09 |
| | | 16 | 2400 | 0.047 | | | 16 | 1815 | 0.077 | | | 16 | 1400 | 0.12 |
| | | 19.2 | 2330 | 0.057 | | | 19.2 | 1750 | 0.093 | | | 19.2 | 1340 | 0.144 |
| 2 x 4 SYP #2 | 2 x 4 SYP #2 | 12 | 2230 | 0.071 | 2 x 4 SYP #2 | 2 x 4 SYP #2 | 12 | 1660 | 0.116 | 2 x 4 SYP #2 | 2 x 4 SYP #2 | 12 | 1255 | 0.18 |
| | | 16 | 2450 | 0.035 | | | 16 | 1855 | 0.058 | | | 16 | 1440 | 0.09 |
| | | 19.2 | 2340 | 0.047 | | | 19.2 | 1755 | 0.077 | | | 19.2 | 1345 | 0.12 |
| 2 x 6 SPF STUD GRADE | 2 x 6 SPF STUD GRADE | 12 | 6495 | 0.011 | 2 x 6 SPF STUD GRADE | 2 x 6 SPF STUD GRADE | 12 | 5520 | 0.017 | 2 x 6 SPF STUD GRADE | 2 x 6 SPF STUD GRADE | 12 | 4600 | 0.027 |
| | | 16 | 6345 | 0.014 | | | 16 | 5340 | 0.023 | | | 16 | 4405 | 0.036 |
| | | 19.2 | 6230 | 0.017 | | | 19.2 | 5205 | 0.028 | | | 19.2 | 4260 | 0.043 |
| 2 x 6 SPF #2 | 2 x 6 SPF #2 | 12 | 9150 | 0.009 | 2 x 6 SPF #2 | 2 x 6 SPF #2 | 12 | 7445 | 0.015 | 2 x 6 SPF #2 | 2 x 6 SPF #2 | 12 | 6055 | 0.023 |
| | | 16 | 8980 | 0.012 | | | 16 | 7260 | 0.02 | | | 16 | 5870 | 0.031 |
| | | 19.2 | 8855 | 0.015 | | | 19.2 | 7125 | 0.024 | | | 19.2 | 5735 | 0.037 |
| 2 x 6 SYP #2 | 2 x 6 SYP #2 | 12 | 8670 | 0.018 | 2 x 6 SYP #2 | 2 x 6 SYP #2 | 12 | 6935 | 0.03 | 2 x 6 SYP #2 | 2 x 6 SYP #2 | 12 | 5545 | 0.046 |
| | | 16 | 9325 | 0.009 | | | 16 | 7490 | 0.015 | | | 16 | 6040 | 0.023 |
| | | 19.2 | 8970 | 0.015 | | | 19.2 | 7125 | 0.024 | | | 19.2 | 5685 | 0.037 |
| 24 | 2 x 6 SYP #2 | 12 | 8760 | 0.018 | 24 | 2 x 6 SYP #2 | 12 | 6910 | 0.03 | 24 | 2 x 6 SYP #2 | 12 | 5480 | 0.046 |
| | | 16 | 9125 | 0.012 | | | 16 | 7280 | 0.02 | | | 16 | 5835 | 0.031 |
| 19.2 | 8970 | 0.015 | 19.2 | 7125 | 0.024 | 19.2 | 5685 | 0.037 | | | | | | |
| 24 | 8760 | 0.018 | 24 | 6910 | 0.03 | 24 | 5480 | 0.046 | | | | | | |

*** LOADS AND QUANTITIES ARE PER SIDE OF MATING WALL

MATING WALL HEADER - 1 STORY (LOCATION 2)

2x3 FOR (1) MEMBER HEADERS
 2x4 FOR (2) MEMBER HEADERS
 2x6 FOR (3) MEMBER HEADERS

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

| MEMBER | QUANTITY | HEADER LL (plf) | HEADER TL (plf) | SPAN | LIMITED BY | DEFLECTION (in) | MID-SPAN | MIN. NUMBER OF JACKSTUDS REQ'D EACH END | SYP #2 | SYP #2 | SFP STUD | UPLIFT (plf) | UPLIFT REACTION (lbs) |
|-----------------|----------|-----------------|-----------------|---------|------------|-----------------|----------|---|--------|--------|----------|--------------|-----------------------|
| 2 x 4 SPF #2 | 1 | 198 | 367 | 2'-10" | LB | 0.078 | 0.078 | 1 | 1 | 1 | 1 | 249 | 361 |
| 2 x 6 SPF #2 | 1 | 198 | 367 | 4'-2" | LB | 0.091 | 0.091 | 2 | 2 | 2 | 2 | 249 | 527 |
| 2 x 8 SPF #2 | 1 | 198 | 367 | 5'-4" | LB | 0.103 | 0.103 | 2 | 2 | 2 | 2 | 249 | 668 |
| 2 x 10 SPF #2 | 1 | 198 | 367 | 6'-6" | LB | 0.111 | 0.111 | 2 | 2 | 2 | 2 | 249 | 816 |
| 2 x 4 SYP #2 | 1 | 198 | 367 | 2'-7" | LB | 0.055 | 0.055 | 1 | 1 | 1 | 1 | 249 | 330 |
| 2 x 6 SYP #2 | 1 | 198 | 367 | 3'-11" | LB | 0.07 | 0.07 | 2 | 2 | 2 | 2 | 249 | 494 |
| 2 x 8 SYP #2 | 1 | 198 | 367 | 5'-0" | LB | 0.08 | 0.08 | 2 | 2 | 2 | 2 | 249 | 627 |
| 2 x 10 SYP #2 | 1 | 198 | 367 | 5'-11" | LB | 0.076 | 0.076 | 2 | 2 | 2 | 2 | 249 | 744 |
| 2 x 12 SYP #2 | 1 | 198 | 367 | 7'-3" | LB | 0.093 | 0.093 | 2 | 2 | 2 | 2 | 249 | 905 |
| 1.5 x 3.5 LVL | 1 | 198 | 367 | 4'-0" | LB | 0.212 | 0.212 | 2 | 2 | 2 | 2 | 249 | 507 |
| 1.5 x 5.5 LVL | 1 | 198 | 367 | 6'-3" | LB | 0.314 | 0.314 | 2 | 2 | 2 | 2 | 249 | 785 |
| 1.5 x 7.25 LVL | 1 | 198 | 367 | 8'-2" | LB | 0.399 | 0.399 | 2 | 2 | 2 | 2 | 249 | 1025 |
| 1.5 x 9.25 LVL | 1 | 198 | 367 | 10'-5" | LB | 0.493 | 0.493 | 2 | 2 | 2 | 2 | 249 | 1298 |
| 1.5 x 11.25 LVL | 1 | 198 | 367 | 12'-7" | LB | 0.585 | 0.585 | 3 | 3 | 3 | 3 | 249 | 1569 |
| 1.5 x 12 LVL | 1 | 198 | 367 | 13'-4" | LB | 0.618 | 0.618 | 3 | 3 | 3 | 3 | 249 | 1670 |
| 1.5 x 14 LVL | 1 | 198 | 367 | 15'-6" | LB | 0.707 | 0.707 | 3 | 3 | 3 | 3 | 249 | 1938 |
| 1.5 x 16 LVL | 1 | 198 | 367 | 17'-8" | LB | 0.794 | 0.794 | 3 | 3 | 3 | 3 | 249 | 2205 |
| 1.5 x 18 LVL | 1 | 198 | 367 | 19'-10" | LB | 0.879 | 0.879 | 3 | 3 | 3 | 3 | 249 | 2471 |
| 1.5 x 20 LVL | 1 | 198 | 367 | 21'-11" | LB | 0.964 | 0.964 | 3 | 3 | 3 | 3 | 249 | 2737 |
| 1.5 x 22 LVL | 1 | 198 | 367 | 24'-1" | LB | 1.048 | 1.048 | 3 | 3 | 3 | 3 | 249 | 3001 |
| 1.5 x 24 LVL | 1 | 198 | 367 | 26'-2" | LB | 1.13 | 1.13 | 3 | 3 | 3 | 3 | 249 | 3265 |
| 2 x 4 SPF #2 | 2 | 198 | 367 | 4'-1" | LB | 0.155 | 0.155 | 1 | 1 | 1 | 1 | 249 | 510 |
| 2 x 6 SPF #2 | 2 | 198 | 367 | 5'-11" | LB | 0.182 | 0.182 | 1 | 1 | 1 | 1 | 249 | 745 |
| 2 x 8 SPF #2 | 2 | 198 | 367 | 7'-7" | LB | 0.206 | 0.206 | 1 | 1 | 1 | 1 | 249 | 945 |
| 2 x 10 SPF #2 | 2 | 198 | 367 | 9'-3" | LB | 0.221 | 0.221 | 1 | 1 | 1 | 1 | 249 | 1155 |
| 2 x 12 SPF #2 | 2 | 198 | 367 | 10'-9" | LB | 0.222 | 0.222 | 2 | 2 | 2 | 2 | 249 | 1339 |
| 2 x 4 SYP #2 | 2 | 198 | 367 | 3'-9" | LB | 0.109 | 0.109 | 1 | 1 | 1 | 1 | 249 | 467 |
| 2 x 6 SYP #2 | 2 | 198 | 367 | 5'-7" | LB | 0.141 | 0.141 | 1 | 1 | 1 | 1 | 249 | 699 |
| 2 x 8 SYP #2 | 2 | 198 | 367 | 7'-1" | LB | 0.16 | 0.16 | 1 | 1 | 1 | 1 | 249 | 887 |
| 2 x 10 SYP #2 | 2 | 198 | 367 | 8'-5" | LB | 0.152 | 0.152 | 1 | 1 | 1 | 1 | 249 | 1053 |
| 2 x 12 SYP #2 | 2 | 198 | 367 | 10'-3" | LB | 0.185 | 0.185 | 1 | 1 | 1 | 1 | 249 | 1280 |
| 1.5 x 3.5 LVL | 2 | 198 | 367 | 5'-9" | LB | 0.423 | 0.423 | 1 | 1 | 1 | 1 | 249 | 717 |
| 1.5 x 5.5 LVL | 2 | 198 | 367 | 8'-10" | LB | 0.627 | 0.627 | 1 | 1 | 1 | 1 | 249 | 1110 |
| 1.5 x 7.25 LVL | 2 | 198 | 367 | 11'-7" | LB | 0.798 | 0.798 | 2 | 2 | 2 | 2 | 249 | 1450 |
| 1.5 x 9.25 LVL | 2 | 198 | 367 | 14'-8" | LB | 0.986 | 0.986 | 2 | 2 | 2 | 2 | 249 | 1836 |
| 1.5 x 11.25 LVL | 2 | 198 | 367 | 17'-9" | LB | 1.169 | 1.169 | 2 | 2 | 2 | 2 | 249 | 2218 |
| 1.5 x 12 LVL | 2 | 198 | 367 | 18'-11" | LB | 1.236 | 1.236 | 2 | 2 | 2 | 2 | 249 | 2361 |
| 1.5 x 14 LVL | 2 | 198 | 367 | 22'-0" | LB | 1.474 | 1.474 | 3 | 3 | 3 | 3 | 249 | 2741 |
| 1.5 x 16 LVL | 2 | 198 | 367 | 25'-0" | LB | 1.588 | 1.588 | 3 | 3 | 3 | 3 | 249 | 3119 |
| 1.5 x 18 LVL | 2 | 198 | 367 | 28'-0" | LB | 1.759 | 1.759 | 3 | 3 | 3 | 3 | 249 | 3495 |
| 1.5 x 20 LVL | 2 | 198 | 367 | 31'-1" | LB | 1.928 | 1.928 | 3 | 3 | 3 | 3 | 249 | 3870 |
| 1.5 x 22 LVL | 2 | 198 | 367 | 34'-1" | LB | 2.095 | 2.095 | 3 | 3 | 3 | 3 | 249 | 4245 |
| 1.5 x 24 LVL | 2 | 198 | 367 | 37'-1" | LB | 2.26 | 2.26 | 3 | 3 | 3 | 3 | 249 | 4617 |
| 2 x 4 SPF #2 | 3 | 198 | 367 | 5'-0" | LB | 0.273 | 0.273 | 1 | 1 | 1 | 1 | 249 | 625 |
| 2 x 6 SPF #2 | 3 | 198 | 367 | 7'-3" | LB | 0.309 | 0.309 | 1 | 1 | 1 | 1 | 249 | 913 |
| 2 x 8 SPF #2 | 3 | 198 | 367 | 9'-3" | LB | 0.331 | 0.331 | 1 | 1 | 1 | 1 | 249 | 1158 |
| 2 x 10 SPF #2 | 3 | 198 | 367 | 11'-4" | LB | 0.333 | 0.333 | 1 | 1 | 1 | 1 | 249 | 1414 |
| 2 x 12 SPF #2 | 3 | 198 | 367 | 13'-2" | LB | 0.333 | 0.333 | 1 | 1 | 1 | 1 | 249 | 1640 |
| 2 x 4 SYP #2 | 3 | 198 | 367 | 4'-7" | LB | 0.164 | 0.164 | 1 | 1 | 1 | 1 | 249 | 572 |
| 2 x 6 SYP #2 | 3 | 198 | 367 | 6'-10" | LB | 0.211 | 0.211 | 1 | 1 | 1 | 1 | 249 | 856 |
| 2 x 8 SYP #2 | 3 | 198 | 367 | 8'-8" | LB | 0.24 | 0.24 | 1 | 1 | 1 | 1 | 249 | 1087 |
| 2 x 10 SYP #2 | 3 | 198 | 367 | 10'-4" | LB | 0.229 | 0.229 | 1 | 1 | 1 | 1 | 249 | 1289 |
| 2 x 12 SYP #2 | 3 | 198 | 367 | 12'-7" | LB | 0.278 | 0.278 | 1 | 1 | 1 | 1 | 249 | 1568 |
| 1.5 x 3.5 LVL | 3 | 198 | 367 | 7'-0" | LB | 0.635 | 0.635 | 1 | 1 | 1 | 1 | 249 | 878 |
| 1.5 x 5.5 LVL | 3 | 198 | 367 | 10'-11" | LB | 0.941 | 0.941 | 1 | 1 | 1 | 1 | 249 | 1359 |
| 1.5 x 7.25 LVL | 3 | 198 | 367 | 14'-3" | LB | 1.197 | 1.197 | 1 | 1 | 1 | 1 | 249 | 1776 |
| 1.5 x 9.25 LVL | 3 | 198 | 367 | 18'-0" | LB | 1.479 | 1.479 | 1 | 1 | 1 | 1 | 249 | 2248 |
| 1.5 x 11.25 LVL | 3 | 198 | 367 | 21'-9" | LB | 1.754 | 1.754 | 1 | 1 | 1 | 1 | 249 | 2717 |
| 1.5 x 12 LVL | 3 | 198 | 367 | 23'-2" | LB | 1.855 | 1.855 | 1 | 1 | 1 | 1 | 249 | 2892 |
| 1.5 x 14 LVL | 3 | 198 | 367 | 26'-11" | LB | 2.121 | 2.121 | 1 | 1 | 1 | 1 | 249 | 3357 |
| 1.5 x 16 LVL | 3 | 198 | 367 | 30'-8" | LB | 2.382 | 2.382 | 1 | 1 | 1 | 1 | 249 | 3820 |
| 1.5 x 18 LVL | 3 | 198 | 367 | 34'-4" | LB | 2.638 | 2.638 | 1 | 1 | 1 | 1 | 249 | 4281 |
| 1.5 x 20 LVL | 3 | 198 | 367 | 38'-0" | LB | 2.892 | 2.892 | 2 | 2 | 2 | 2 | 249 | 4740 |
| 1.5 x 22 LVL | 3 | 198 | 367 | 41'-9" | LB | 3.143 | 3.143 | 2 | 2 | 2 | 2 | 249 | 5198 |
| 1.5 x 24 LVL | 3 | 198 | 367 | 45'-5" | LB | 3.39 | 3.39 | 2 | 2 | 2 | 2 | 249 | 5655 |

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: Jim B...
 Title: Staff Plan Reviewer
 Date: 8/18/21

***LOADS AND QUANTITIES ARE PER SIDE OF MATING LINE

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS

EVEN IF RATIO MEETS CODE REQUIREMENTS

190284

PERIMETER BAND - 1 STORY (LOCATION 3)

TRUSS HM773855

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

| MEMBER | QUANTITY | HEADER LT (plf) | HEADER TL (plf) | MAXIMUM SPAN | LIMITED BY | DEFLECTION (in) | MID-SPAN UPLIFT (plf) | REACTION (lbs) |
|-----------------|----------|--------------------|--------------------|-----------------|------------|-----------------|--------------------------|----------------|
| 2 x 8 SPF #2 | 1 | 505 | 878 | 3'-5" | Lb | 0.043 | 0 | 0 |
| 2 x 10 SPF #2 | 1 | 505 | 878 | 4'-2" | Lb | 0.046 | 0 | 0 |
| 2 x 12 SPF #2 | 1 | 505 | 878 | 4'-11" | Lb | 0.046 | 0 | 0 |
| 2 x 8 SYP #2 | 1 | 505 | 878 | 3'-3" | Lb | 0.033 | 0 | 0 |
| 2 x 10 SYP #2 | 1 | 505 | 878 | 3'-10" | Lb | 0.032 | 0 | 0 |
| 2 x 12 SYP #2 | 1 | 505 | 878 | 4'-8" | Lb | 0.039 | 0 | 0 |
| 1.5 x 7.25 LVL | 1 | 505 | 878 | 5'-3" | Lb | 0.167 | 0 | 0 |
| 1.5 x 9.25 LVL | 1 | 505 | 878 | 6'-8" | Lb | 0.206 | 0 | 0 |
| 1.5 x 11.25 LVL | 1 | 505 | 878 | 8'-1" | Lb | 0.244 | 0 | 0 |
| 2 x 8 SPF #2 | 2 | 505 | 878 | 4'-10" | Lb | 0.086 | 0 | 0 |
| 2 x 10 SPF #2 | 2 | 505 | 878 | 5'-11" | Lb | 0.092 | 0 | 0 |
| 2 x 12 SPF #2 | 2 | 505 | 878 | 6'-11" | Lb | 0.093 | 0 | 0 |
| 2 x 8 SYP #2 | 2 | 505 | 878 | 4'-7" | Lb | 0.067 | 0 | 0 |
| 2 x 10 SYP #2 | 2 | 505 | 878 | 5'-5" | Lb | 0.064 | 0 | 0 |
| 2 x 12 SYP #2 | 2 | 505 | 878 | 6'-7" | Lb | 0.077 | 0 | 0 |
| 1.5 x 7.25 LVL | 2 | 505 | 878 | 7'-6" | Lb | 0.333 | 0 | 0 |
| 1.5 x 9.25 LVL | 2 | 505 | 878 | 9'-6" | Lb | 0.412 | 0 | 0 |
| 1.5 x 11.25 LVL | 2 | 505 | 878 | 11'-6" | Lb | 0.489 | 0 | 0 |
| 2 x 8 SPF #2 | 3 | 505 | 878 | 6'-0" | Lb | 0.129 | 0 | 0 |
| 2 x 10 SPF #2 | 3 | 505 | 878 | 7'-4" | Lb | 0.138 | 0 | 0 |
| 2 x 12 SPF #2 | 3 | 505 | 878 | 8'-6" | Lb | 0.139 | 0 | 0 |
| 2 x 8 SYP #2 | 3 | 505 | 878 | 5'-7" | Lb | 0.1 | 0 | 0 |
| 2 x 10 SYP #2 | 3 | 505 | 878 | 6'-8" | Lb | 0.096 | 0 | 0 |
| 2 x 12 SYP #2 | 3 | 505 | 878 | 8'-1" | Lb | 0.116 | 0 | 0 |
| 1.5 x 7.25 LVL | 3 | 505 | 878 | 9'-2" | Lb | 0.5 | 0 | 0 |
| 1.5 x 9.25 LVL | 3 | 505 | 878 | 11'-8" | Lb | 0.618 | 0 | 0 |
| 1.5 x 11.25 LVL | 3 | 505 | 878 | 14'-1" | Lb | 0.733 | 0 | 0 |

PFS CORPORATION
Approval Limited to Factory Built Portion Only


State: North Carolina
Signature: *Tim Duncanson*
Title: Staff Plan Reviewer
Date: 8/18/21

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
EVEN IF RATIO MEETS CODE REQUIREMENTS
190284
SECTION 6/ pp. 16
RALEIGH, NC 27615
6912 SIX FORKS RD., SUITE 203-B
BARROW ENGINEERING, P.C.

**CENTER GIRDER - 1 STORY (LOCATION 4)
TRUSS HM778355
5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD**

| MEMBER | QUANTITY | HEADER LL (plf) | HEADER TL (plf) | MAXIMUM SPAN | LIMITED BY | MID-SPAN DEFLECTION (in) | UPLIFT (plf) | REACTION (lbs) |
|-----------------|----------|--------------------|--------------------|-----------------|------------|-----------------------------|-----------------|----------------|
| 2 x 8 SPF #2 | 1 | 500 | 827 | 3'-6" | Lb | 0.046 | 53 | 95 |
| 2 x 10 SPF #2 | 1 | 500 | 827 | 4'-4" | Lb | 0.049 | 53 | 116 |
| 2 x 12 SPF #2 | 1 | 500 | 827 | 5'-0" | Lb | 0.049 | 53 | 134 |
| 2 x 8 SYP #2 | 1 | 500 | 827 | 3'-4" | Lb | 0.035 | 53 | 89 |
| 2 x 10 SYP #2 | 1 | 500 | 827 | 3'-11" | Lb | 0.034 | 53 | 106 |
| 2 x 12 SYP #2 | 1 | 500 | 827 | 4'-10" | Lb | 0.041 | 53 | 128 |
| 1.5 x 7.25 LVL | 1 | 500 | 827 | 5'-5" | Lb | 0.177 | 53 | 145 |
| 1.5 x 9.25 LVL | 1 | 500 | 827 | 6'-11" | Lb | 0.219 | 53 | 184 |
| 1.5 x 11.25 LVL | 1 | 500 | 827 | 8'-4" | Lb | 0.259 | 53 | 222 |
| 2 x 8 SPF #2 | 2 | 500 | 827 | 5'-0" | Lb | 0.091 | 53 | 134 |
| 2 x 10 SPF #2 | 2 | 500 | 827 | 6'-2" | Lb | 0.098 | 53 | 164 |
| 2 x 12 SPF #2 | 2 | 500 | 827 | 7'-1" | Lb | 0.098 | 53 | 190 |
| 2 x 8 SYP #2 | 2 | 500 | 827 | 4'-8" | Lb | 0.071 | 53 | 126 |
| 2 x 10 SYP #2 | 2 | 500 | 827 | 5'-7" | Lb | 0.068 | 53 | 149 |
| 2 x 12 SYP #2 | 2 | 500 | 827 | 6'-10" | Lb | 0.082 | 53 | 182 |
| 1.5 x 7.25 LVL | 2 | 500 | 827 | 7'-9" | Lb | 0.354 | 53 | 206 |
| 1.5 x 9.25 LVL | 2 | 500 | 827 | 9'-9" | Lb | 0.438 | 53 | 260 |
| 1.5 x 11.25 LVL | 2 | 500 | 827 | 11'-10" | Lb | 0.519 | 53 | 315 |
| 2 x 8 SPF #2 | 3 | 500 | 827 | 6'-2" | Lb | 0.137 | 53 | 164 |
| 2 x 10 SPF #2 | 3 | 500 | 827 | 7'-6" | Lb | 0.147 | 53 | 201 |
| 2 x 12 SPF #2 | 3 | 500 | 827 | 8'-9" | Lb | 0.148 | 53 | 233 |
| 2 x 8 SYP #2 | 3 | 500 | 827 | 5'-9" | Lb | 0.106 | 53 | 154 |
| 2 x 10 SYP #2 | 3 | 500 | 827 | 6'-10" | Lb | 0.101 | 53 | 183 |
| 2 x 12 SYP #2 | 3 | 500 | 827 | 8'-4" | Lb | 0.123 | 53 | 222 |
| 1.5 x 7.25 LVL | 3 | 500 | 827 | 9'-6" | Lb | 0.531 | 53 | 252 |
| 1.5 x 9.25 LVL | 3 | 500 | 827 | 12'-0" | Lb | 0.656 | 53 | 319 |
| 1.5 x 11.25 LVL | 3 | 500 | 827 | 14'-6" | Lb | 0.778 | 53 | 385 |

*** LOADS AND QUANTITIES ARE PER SIDE OF MATING LINE




PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tom Dwork*
Title: Staff Plan Reviewer
Date: 8/18/21

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
 EVEN IF RATIO MEETS CODE REQUIREMENTS
 190284
 SECTION 6/ pp. 18
 RALEIGH, NC 27615
 6512 SIX FORKS RD., SUITE 203-B
 RAYSON ENGINEERING, P.C.
 P:\2019\190284\HM778355\CENTER-GIRDER

| DESIGN INFORMATION: | | MEETS LIMITATIONS OF WFCM: | | WIND: | | EXPOSURE: | | WALL HEIGHT: | | FLOOR DEAD LOAD (FDL): | | WALL DEAD LOAD (WDL): | | ROOF & CEILING ASSEMBLY DEAD LOAD = | |
|---|--|---|--|--------------------------------------|--|----------------------------|--|--------------|--|------------------------|--|-----------------------|--|-------------------------------------|--|
| TRUSS BOTTOM CHORD TO TOP PLATE CONNECTION: | | V _{max} = | | 1605 | | 18 | | 18 | | 1873 | | 16 | | 15 | |
| AT 30 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 72 | | 72 | | 72 | | 72 | | 72 | |
| AT 35 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 1873 | | 16 | | 16 | | 16 | | 16 | |
| AT 40 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 2140 | | 14 | | 14 | | 14 | | 14 | |
| AT 45 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 2408 | | 12 | | 12 | | 12 | | 12 | |
| AT 50 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 2675 | | 11 | | 11 | | 11 | | 11 | |
| AT 55 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 2943 | | 10 | | 10 | | 10 | | 10 | |
| AT 60 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 3210 | | 7 | | 7 | | 7 | | 7 | |
| AT 65 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 3478 | | 8 | | 8 | | 8 | | 8 | |
| AT 70 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 3745 | | 8 | | 8 | | 8 | | 8 | |
| AT 75 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 4013 | | 55 | | 55 | | 55 | | 55 | |
| AT 80 ft SIDEWALL LENGTH: | | SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL): | | OR SPACING OF (1) SIMPSON LTP4 PLATE | | 4280 | | 52 | | 52 | | 52 | | 52 | |
| lbs AT 30 ft LENGTH | | 1725 | | 1725 | | 1725 | | 17 | | 17 | | 17 | | 17 | |
| lbs AT 35 ft LENGTH | | 2013 | | 2013 | | 2013 | | 15 | | 15 | | 15 | | 15 | |
| lbs AT 40 ft LENGTH | | 2300 | | 2300 | | 2300 | | 13 | | 13 | | 13 | | 13 | |
| lbs AT 45 ft LENGTH | | 2588 | | 2588 | | 2588 | | 11 | | 11 | | 11 | | 11 | |
| lbs AT 50 ft LENGTH | | 2875 | | 2875 | | 2875 | | 10 | | 10 | | 10 | | 10 | |
| lbs AT 55 ft LENGTH | | 3163 | | 3163 | | 3163 | | 9 | | 9 | | 9 | | 9 | |
| lbs AT 60 ft LENGTH | | 3450 | | 3450 | | 3450 | | 8 | | 8 | | 8 | | 8 | |
| lbs AT 65 ft LENGTH | | 3738 | | 3738 | | 3738 | | 6 | | 6 | | 6 | | 6 | |
| lbs AT 70 ft LENGTH | | 4025 | | 4025 | | 4025 | | 5 | | 5 | | 5 | | 5 | |
| lbs AT 75 ft LENGTH | | 4313 | | 4313 | | 4313 | | 7 | | 7 | | 7 | | 7 | |
| lbs AT 80 ft LENGTH | | 4600 | | 4600 | | 4600 | | 48 | | 48 | | 48 | | 48 | |
| YES | | YES | | YES | | YES | | 150 | | 150 | | 150 | | 150 | |
| C | | C | | C | | C | | 9 | | 9 | | 9 | | 9 | |
| ft | | ft | | ft | | ft | | 10 | | 10 | | 10 | | 10 | |
| psf | | psf | | psf | | psf | | 12 | | 12 | | 12 | | 12 | |
| psf | | psf | | psf | | psf | | 15 | | 15 | | 15 | | 15 | |
| 5/12 PITCH, 30.33 ft WIDTH | | 5/12 PITCH, 30.33 ft WIDTH | | 5/12 PITCH, 30.33 ft WIDTH | | 5/12 PITCH, 30.33 ft WIDTH | | 115 | | 115 | | 115 | | 115 | |



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Tim D'Amico*

Title: Staff Plan Reviewer

Date: 8/18/21



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Tim Duerle*

Title: Staff Plan Reviewer

Date: 8/18/21

| DESIGN INFORMATION: | | MEETS LIMITATIONS OF WFCM: | | WIND: | | EXPOSURE: | | WALL HEIGHT: | | FLOOR DEAD LOAD (FDL): | | WALL DEAD LOAD (WDL): | | ROOF & CEILING ASSEMBLY DEAD LOAD = | | SILL PLATE TO FOUNDATION CONNECTION: | |
|----------------------------|-------|----------------------------|-----|-------|----|-----------|----|--------------|----|------------------------|----|-----------------------|----|-------------------------------------|----|--------------------------------------|----|
| 5/12 PITCH, 30.33 ft WIDTH | 115 | YES | 115 | C | 9 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |
| 5/12 PITCH, 30.33 ft WIDTH | 130 | YES | 130 | C | 9 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |
| 5/12 PITCH, 30.33 ft WIDTH | 150 | YES | 150 | C | 9 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |
| lbs AT 30 ft LENGTH | 6113 | 4617 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 35 ft LENGTH | 7132 | 5387 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 40 ft LENGTH | 8150 | 6155 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 45 ft LENGTH | 9170 | 6925 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 50 ft LENGTH | 10198 | 7694 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 55 ft LENGTH | 11207 | 8464 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 60 ft LENGTH | 12225 | 9233 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 65 ft LENGTH | 13245 | 10003 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 70 ft LENGTH | 14263 | 10772 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 75 ft LENGTH | 15282 | 11542 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| lbs AT 80 ft LENGTH | 16300 | 12310 | 72 | 72 | 67 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 | 72 |
| | 33 | 42 | 30 | 30 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 | 22 |

| DESIGN INFORMATION: | PERFORATED SHEARWALL LENGTH REQUIREMENTS | WALL CONSTRUCTION: | WALL CONSTRUCTION: | DESIGN INFORMATION: |
|---|---|---|---|---|
| MEETS LIMITATIONS OF WFCM: WIND: EXPOSURE: WALL HEIGHT: FLOOR DEAD LOAD (FDL): WALL DEAD LOAD (WDL): ROOF & CEILING ASSEMBLY DEAD LOAD = | 15 12 10 9 C 130 YES | 15 12 10 9 C 130 YES | 15 12 10 9 C 130 YES | 5/12 PITCH, 30.33 ft WIDTH |
| PERFORATED SHEARWALL LENGTH REQUIREMENTS | 15 12 10 9 C 130 YES | 15 12 10 9 C 130 YES | 15 12 10 9 C 130 YES | 5/12 PITCH, 30.33 ft WIDTH |
| WALL CONSTRUCTION: | WALL CONSTRUCTION: | WALL CONSTRUCTION: | WALL CONSTRUCTION: | WALL CONSTRUCTION: |
| EXTERIOR: 7/16" OSB (BLOCKED) FASTENED w/ 16 ga. STAPLES 6" EDGE / 12" FIELD | EXTERIOR: 7/16" OSB (BLOCKED) FASTENED w/ 16 ga. STAPLES 6" EDGE / 12" FIELD | EXTERIOR: 7/16" OSB (BLOCKED) FASTENED w/ 16 ga. STAPLES 6" EDGE / 12" FIELD | EXTERIOR: 7/16" OSB (BLOCKED) FASTENED w/ 16 ga. STAPLES 6" EDGE / 12" FIELD | EXTERIOR: 7/16" OSB (BLOCKED) FASTENED w/ 16 ga. STAPLES 6" EDGE / 12" FIELD |
| INTERIOR: 1/2" GWB FASTENED w/ 5D NAILS 7" EDGE / 10" FIELD | INTERIOR: 1/2" GWB FASTENED w/ 5D NAILS 7" EDGE / 10" FIELD | INTERIOR: 1/2" GWB FASTENED w/ 5D NAILS 7" EDGE / 10" FIELD | INTERIOR: 1/2" GWB FASTENED w/ 5D NAILS 7" EDGE / 10" FIELD | INTERIOR: 1/2" GWB FASTENED w/ 5D NAILS 7" EDGE / 10" FIELD |
| SIDEWALL - FULL HEIGHT SHEATHING REQUIRED (ft): = ALLOW | SIDEWALL - FULL HEIGHT SHEATHING REQUIRED (ft): = ALLOW | SIDEWALL - FULL HEIGHT SHEATHING REQUIRED (ft): = ALLOW | SIDEWALL - FULL HEIGHT SHEATHING REQUIRED (ft): = ALLOW | SIDEWALL - FULL HEIGHT SHEATHING REQUIRED (ft): = ALLOW |
| FOR 30 PERCENT SIDEWALL SHEATHING: FOR 35 PERCENT SIDEWALL SHEATHING: FOR 40 PERCENT SIDEWALL SHEATHING: FOR 45 PERCENT SIDEWALL SHEATHING: FOR 50 PERCENT SIDEWALL SHEATHING: FOR 55 PERCENT SIDEWALL SHEATHING: FOR 60 PERCENT SIDEWALL SHEATHING: FOR 65 PERCENT SIDEWALL SHEATHING: FOR 70 PERCENT SIDEWALL SHEATHING: FOR 75 PERCENT SIDEWALL SHEATHING: FOR 80 PERCENT SIDEWALL SHEATHING: FOR 85 PERCENT SIDEWALL SHEATHING: FOR 90 PERCENT SIDEWALL SHEATHING: FOR 95 PERCENT SIDEWALL SHEATHING: FOR 100 PERCENT SIDEWALL SHEATHING: | FOR 30 PERCENT SIDEWALL SHEATHING: FOR 35 PERCENT SIDEWALL SHEATHING: FOR 40 PERCENT SIDEWALL SHEATHING: FOR 45 PERCENT SIDEWALL SHEATHING: FOR 50 PERCENT SIDEWALL SHEATHING: FOR 55 PERCENT SIDEWALL SHEATHING: FOR 60 PERCENT SIDEWALL SHEATHING: FOR 65 PERCENT SIDEWALL SHEATHING: FOR 70 PERCENT SIDEWALL SHEATHING: FOR 75 PERCENT SIDEWALL SHEATHING: FOR 80 PERCENT SIDEWALL SHEATHING: FOR 85 PERCENT SIDEWALL SHEATHING: FOR 90 PERCENT SIDEWALL SHEATHING: FOR 95 PERCENT SIDEWALL SHEATHING: FOR 100 PERCENT SIDEWALL SHEATHING: | FOR 30 PERCENT SIDEWALL SHEATHING: FOR 35 PERCENT SIDEWALL SHEATHING: FOR 40 PERCENT SIDEWALL SHEATHING: FOR 45 PERCENT SIDEWALL SHEATHING: FOR 50 PERCENT SIDEWALL SHEATHING: FOR 55 PERCENT SIDEWALL SHEATHING: FOR 60 PERCENT SIDEWALL SHEATHING: FOR 65 PERCENT SIDEWALL SHEATHING: FOR 70 PERCENT SIDEWALL SHEATHING: FOR 75 PERCENT SIDEWALL SHEATHING: FOR 80 PERCENT SIDEWALL SHEATHING: FOR 85 PERCENT SIDEWALL SHEATHING: FOR 90 PERCENT SIDEWALL SHEATHING: FOR 95 PERCENT SIDEWALL SHEATHING: FOR 100 PERCENT SIDEWALL SHEATHING: | FOR 30 PERCENT SIDEWALL SHEATHING: FOR 35 PERCENT SIDEWALL SHEATHING: FOR 40 PERCENT SIDEWALL SHEATHING: FOR 45 PERCENT SIDEWALL SHEATHING: FOR 50 PERCENT SIDEWALL SHEATHING: FOR 55 PERCENT SIDEWALL SHEATHING: FOR 60 PERCENT SIDEWALL SHEATHING: FOR 65 PERCENT SIDEWALL SHEATHING: FOR 70 PERCENT SIDEWALL SHEATHING: FOR 75 PERCENT SIDEWALL SHEATHING: FOR 80 PERCENT SIDEWALL SHEATHING: FOR 85 PERCENT SIDEWALL SHEATHING: FOR 90 PERCENT SIDEWALL SHEATHING: FOR 95 PERCENT SIDEWALL SHEATHING: FOR 100 PERCENT SIDEWALL SHEATHING: | FOR 30 PERCENT SIDEWALL SHEATHING: FOR 35 PERCENT SIDEWALL SHEATHING: FOR 40 PERCENT SIDEWALL SHEATHING: FOR 45 PERCENT SIDEWALL SHEATHING: FOR 50 PERCENT SIDEWALL SHEATHING: FOR 55 PERCENT SIDEWALL SHEATHING: FOR 60 PERCENT SIDEWALL SHEATHING: FOR 65 PERCENT SIDEWALL SHEATHING: FOR 70 PERCENT SIDEWALL SHEATHING: FOR 75 PERCENT SIDEWALL SHEATHING: FOR 80 PERCENT SIDEWALL SHEATHING: FOR 85 PERCENT SIDEWALL SHEATHING: FOR 90 PERCENT SIDEWALL SHEATHING: FOR 95 PERCENT SIDEWALL SHEATHING: FOR 100 PERCENT SIDEWALL SHEATHING: |
| 277 | 277 | 277 | 277 | 277 |
| ** NG ** | ** NG ** | ** NG ** | ** NG ** | ** NG ** |
| 10.463 | 10.463 | 10.463 | 10.463 | 10.463 |
| 9.765 | 9.765 | 9.765 | 9.765 | 9.765 |
| 9.45 | 9.45 | 9.45 | 9.45 | 9.45 |
| 8.745 | 8.745 | 8.745 | 8.745 | 8.745 |
| 8.37 | 8.37 | 8.37 | 8.37 | 8.37 |
| 8.026 | 8.026 | 8.026 | 8.026 | 8.026 |
| 7.659 | 7.659 | 7.659 | 7.659 | 7.659 |
| 7.324 | 7.324 | 7.324 | 7.324 | 7.324 |
| 6.934 | 6.934 | 6.934 | 6.934 | 6.934 |
| 6.583 | 6.583 | 6.583 | 6.583 | 6.583 |
| 6.2 | 6.2 | 6.2 | 6.2 | 6.2 |
| 5.859 | 5.859 | 5.859 | 5.859 | 5.859 |
| 10.948 | 10.948 | 10.948 | 10.948 | 10.948 |
| 11.389 | 11.389 | 11.389 | 11.389 | 11.389 |
| 11.769 | 11.769 | 11.769 | 11.769 | 11.769 |
| ** NG ** | ** NG ** | ** NG ** | ** NG ** | ** NG ** |
| ** NG ** | ** NG ** | ** NG ** | ** NG ** | ** NG ** |
| ** NG ** | ** NG ** | ** NG ** | ** NG ** | ** NG ** |
| ** NG ** | ** NG ** | ** NG ** | ** NG ** | ** NG ** |
| 13.972 | 13.972 | 13.972 | 13.972 | 13.972 |
| 14.513 | 14.513 | 14.513 | 14.513 | 14.513 |
| 13.373 | 13.373 | 13.373 | 13.373 | 13.373 |
| 12.823 | 12.823 | 12.823 | 12.823 | 12.823 |
| 12.237 | 12.237 | 12.237 | 12.237 | 12.237 |
| 11.701 | 11.701 | 11.701 | 11.701 | 11.701 |
| 11.076 | 11.076 | 11.076 | 11.076 | 11.076 |
| 10.518 | 10.518 | 10.518 | 10.518 | 10.518 |
| 9.906 | 9.906 | 9.906 | 9.906 | 9.906 |
| 9.361 | 9.361 | 9.361 | 9.361 | 9.361 |

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Duvall*
Title: Staff Plan Reviewer
Date: 8/18/21



Load Short For...

Entire House

AMS Of Indiana, In



PFS CORPORATION

Approval Limited to Factory Built Portion Only

Job: 23-3276-16 061720

Date: 8/5/21

By: AMS of Indiana, Inc.

North Carolina

Signature: *Jim D... [Signature]*

Title: Staff Plan Reviewer

8/18/21

3933 East Jackson Blvd., Elkhart, IN 46516

For: Champion Home Builders
Lillington, NC

Design Information

| | | | |
|-----------------------------|----|----------------------|--------------|
| Outside db (°F) | 10 | Method | Infiltration |
| Inside db (°F) | 70 | Construction quality | |
| Design TD (°F) | 61 | Fireplaces | |
| Daily range | - | | |
| Inside humidity (%) | 50 | | |
| Moisture difference (gr/lb) | 49 | | |

HEATING EQUIPMENT

| | | | | |
|------------------|----------------|--------------------------|-------------------|----------|
| Make | Generic | Trade | AFUE 100 | AHRI ref |
| Model | AFUE 100 | Cond | SEER 14.0 | Coil |
| AHRI ref | | AHRI ref | | |
| Efficiency | 100 AFUE | Efficiency | 12.2 EER, 14 SEER | |
| Heating input | 11.6 kW | Sensible cooling | 23454 Btuh | |
| Heating output | 39658 Btuh | Latent cooling | 10052 Btuh | |
| Temperature rise | 31 °F | Total cooling | 33505 Btuh | |
| Actual air flow | 1191 cfm | Actual air flow | 1191 cfm | |
| Air flow factor | 0.034 cfm/Btuh | Air flow factor | 0.056 cfm/Btuh | |
| Static pressure | 0.50 in H2O | Static pressure | 0.50 in H2O | |
| Space thermostat | | Load sensible heat ratio | 0.75 | |

COOLING EQUIPMENT

| | | | | |
|------------------|-------------------|--------------------------|-------------------|------|
| Make | Generic | Trade | SEER 14.0 | Coil |
| Model | SEER 14.0 | Cond | SEER 14.0 | Coil |
| AHRI ref | | AHRI ref | | |
| Efficiency | 12.2 EER, 14 SEER | Efficiency | 12.2 EER, 14 SEER | |
| Heating input | 11.6 kW | Sensible cooling | 23454 Btuh | |
| Heating output | 39658 Btuh | Latent cooling | 10052 Btuh | |
| Temperature rise | 31 °F | Total cooling | 33505 Btuh | |
| Actual air flow | 1191 cfm | Actual air flow | 1191 cfm | |
| Air flow factor | 0.034 cfm/Btuh | Air flow factor | 0.056 cfm/Btuh | |
| Static pressure | 0.50 in H2O | Static pressure | 0.50 in H2O | |
| Space thermostat | | Load sensible heat ratio | 0.75 | |

| ROOM NAME | Area (ft²) | Htg load (Btuh) | Cig load (Btuh) | Htg AVF (cfm) | Cig AVF (cfm) |
|-----------|------------|-----------------|-----------------|---------------|---------------|
| B4 | 158 | 3788 | 1953 | 130 | 108 |
| C4 | 49 | 0 | 0 | 0 | 0 |
| BA3 | 45 | 691 | 292 | 24 | 16 |
| DEN | 154 | 3744 | 2635 | 128 | 146 |
| H | 126 | 0 | 0 | 0 | 0 |
| DRKLT | 476 | 5961 | 3842 | 204 | 213 |
| U | 140 | 3266 | 1251 | 112 | 69 |
| BA1 | 138 | 2942 | 1154 | 101 | 64 |
| LR | 324 | 4417 | 3247 | 151 | 180 |
| B2 | 160 | 2086 | 1678 | 71 | 93 |
| BA2 | 48 | 742 | 271 | 25 | 15 |
| B3 | 160 | 3282 | 1946 | 112 | 108 |
| C1 | 70 | 837 | 311 | 29 | 17 |
| B1 | 244 | 3083 | 2878 | 105 | 160 |

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

Calculations approved by ACGA to meet all requirements of Manual J 8th Ed.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

| | | | | | | |
|------|------|-------|-------|------|------|-------------------|
| 1191 | 1191 | 21456 | 34839 | 2291 | 2291 | Entire House |
| 1191 | 1191 | 1697 | 4819 | | | Other equip loads |
| | | 23453 | | | | Equip. @ 1.01 RSM |
| | | 7801 | | | | Latent cooling |
| 1191 | 1191 | 31254 | 39658 | 2291 | 2291 | TOTALS |

Job: 23-3276-16 061720
 Date: 8/5/21
 By: AMS of Indiana, Inc.

Project Summary
Entire House
 AMS Of Indiana, Inc.



3933 East Jackson Blvd, Elkhart, IN 46516

| | | | |
|--|--|----------------------------|--|
| PFS CORPORATION | | Project Information | |
| Approval Limited to Factory Built Portion Only | | For: | Champion Home Builders Lillington, NC |
| State: North Carolina | | Notes: | |
| Signature: <i>Tom Duvall</i> | | | |
| Title: Staff Plan Reviewer | | | |
| Date: 8/18/21 | | | |

Weather: Winston-Salem Reynolds AP, NC, US

Summer Design Conditions

| | |
|---------------------|----------|
| Outside db | 96 °F |
| Inside db | 75 °F |
| Design TD | 21 °F |
| Daily range | M |
| Relative humidity | 50 % |
| Moisture difference | 51 gr/lb |

Sensible Cooling Equipment Load Sizing

| | |
|-------------------------|------------|
| Structure | 19861 Btuh |
| Ducts | 1594 Btuh |
| Central vent (75 cfm) | 1697 Btuh |
| Outside air | 0 Btuh |
| Blower | 0 Btuh |
| Use manufacturer's data | 1.01 n |
| Rate/swing multiplier | 23453 Btuh |
| Equipment sensible load | 23453 Btuh |

Latent Cooling Equipment Load Sizing

| | |
|---------------------------------|------------|
| Structure | 3259 Btuh |
| Ducts | 2006 Btuh |
| Central vent (75 cfm) | 2536 Btuh |
| Outside air | 7801 Btuh |
| Equipment latent load | 7801 Btuh |
| Equipment Total Load (Sen+Lat) | 31254 Btuh |
| Req. total capacity at 0.70 SHR | 2.8 ton |

Cooling Equipment Summary

| | |
|--------------------------|-------------------|
| Make | Generic |
| Trade | Generic |
| Cond | SEER 14.0 |
| AHRI ref | |
| Efficiency | 12.2 EER, 14 SEER |
| Sensible cooling | 23454 Btuh |
| Latent cooling | 10052 Btuh |
| Total cooling | 33505 Btuh |
| Actual air flow | 1191 cfm |
| Air flow factor | 0.056 cfm/Btuh |
| Static pressure | 0.50 in H2O |
| Load sensible heat ratio | 0.75 |

Winter Design Conditions

| | |
|------------|-------|
| Outside db | 10 °F |
| Inside db | 70 °F |
| Design TD | 61 °F |

Heating Summary

| | |
|-----------------------|------------|
| Structure | 31459 Btuh |
| Ducts | 3380 Btuh |
| Central vent (75 cfm) | 4819 Btuh |
| Outside air | 0 Btuh |
| Humidification | 0 Btuh |
| Piping | 0 Btuh |
| Equipment load | 39658 Btuh |

Infiltration

| | |
|----------------------|-------------|
| Method | Simplified |
| Construction quality | 1 (Average) |
| Fireplaces | |

| | |
|---------------------------|-------|
| Area (ft ²) | 2291 |
| Volume (ft ³) | 20623 |
| Air changes/hour | 0.38 |
| Equip. AVF (cfm) | 130 |

Heating Equipment Summary


| | |
|------------------|----------------|
| Make | Generic |
| Trade | Generic |
| Model | AFUE 100 |
| AHRI ref | |
| Efficiency | 100 AFUE |
| Heating input | 11.6 kW |
| Heating output | 39658 Btuh |
| Temperature rise | 31 °F |
| Actual air flow | 1191 cfm |
| Air flow factor | 0.034 cfm/Btuh |
| Static pressure | 0.50 in H2O |
| Space thermostat | |

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

Job #: 23-3276-16 061720
 Performed by AMS of Indiana, Inc. for:
 Champion Home Builders
 Lillington, NC

AMS Of Indiana, Inc.
 3933 East Jackson Blvd.
 Elkhart, IN 46516

Scale: 1 : 131
 Page 1
 Right-Suite@ Universal 2021
 21.0.03 RSU02009
 2021-Aug-05 16:54:36
 ...23-3276-16 061720(MOD-floor).rup



Sheet 1

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim Duerke*
 Title: Staff Plan Reviewer
 Date: 8/18/21



Project Information

For: Champion Home Builders
 Lillington, NC

| | | | |
|------------------------------------|----------------------|---------|----------------------|
| External static pressure | 0.50 in H2O | Heating | 0.50 in H2O |
| Pressure losses | 0.26 in H2O | | 0.26 in H2O |
| Available static pressure | 0.24 in H2O | | 0.24 in H2O |
| Supply / return available pressure | 0.170 / 0.070 in H2O | | 0.170 / 0.070 in H2O |
| Lowest friction rate | 0.079 in/100ft | | 0.079 in/100ft |
| Actual air flow | 1191 cfm | | 1191 cfm |
| Total effective length (TEL) | 303 ft | | 303 ft |

Supply Branch Detail Table

| Name | Design (Btuh) | Htg (cfm) | Cig (cfm) | Design FR | Diam (in) | H x W (in) | Duct Matl | Actual Ln (ft) | Fig.Eqv Ln (ft) | Trunk |
|---------|---------------|-----------|-----------|-----------|-----------|------------|-----------|----------------|-----------------|-------|
| B1 | 1439 | 53 | 80 | 0.094 | 6.0 | 0x0 | VIFX | 56.5 | 125.0 | st1A |
| B1-A | 1439 | 53 | 80 | 0.106 | 6.0 | 0x0 | VIFX | 46.3 | 115.0 | st1 |
| B2 | 1678 | 71 | 93 | 0.105 | 6.0 | 0x0 | VIFX | 16.5 | 145.0 | st1 |
| B3 | 3282 | 112 | 108 | 0.107 | 6.0 | 0x0 | VIFX | 23.5 | 135.0 | st2A |
| B4 | 3788 | 130 | 108 | 0.112 | 8.0 | 0x0 | VIFX | 26.8 | 125.0 | st2A |
| BA1 | 2942 | 101 | 64 | 0.083 | 6.0 | 0x0 | VIFX | 55.8 | 150.0 | st1B |
| BA2 | 742 | 25 | 15 | 0.110 | 6.0 | 0x0 | VIFX | 14.5 | 140.0 | st2A |
| BA3 | 691 | 24 | 16 | 0.109 | 6.0 | 0x0 | VIFX | 11.0 | 145.0 | st2A |
| C1-A | 837 | 29 | 17 | 0.088 | 6.0 | 0x0 | VIFX | 57.3 | 135.0 | st1B |
| DEN | 1318 | 64 | 73 | 0.104 | 6.0 | 0x0 | VIFX | 18.5 | 145.0 | st1 |
| DEN-A | 1318 | 64 | 73 | 0.099 | 6.0 | 0x0 | VIFX | 27.8 | 145.0 | st1 |
| DRKVT | 1281 | 68 | 71 | 0.100 | 6.0 | 0x0 | VIFX | 30.8 | 140.0 | st1 |
| DRKVT-A | 1281 | 68 | 71 | 0.100 | 6.0 | 0x0 | VIFX | 40.5 | 130.0 | st1 |
| DRKVT-B | 1281 | 68 | 71 | 0.092 | 6.0 | 0x0 | VIFX | 49.0 | 135.0 | st1A |
| LR | 1623 | 76 | 90 | 0.104 | 6.0 | 0x0 | VIFX | 28.5 | 135.0 | st1 |
| LR-A | 1623 | 76 | 90 | 0.104 | 6.0 | 0x0 | VIFX | 38.3 | 125.0 | st1 |
| U | 3266 | 112 | 69 | 0.079 | 6.0 | 0x0 | VIFX | 69.8 | 145.0 | st1B |

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tom Duncanson*
 Title: Staff Plan Reviewer
 Date: 8/18/21



Bold/italic values have been manually overridden

PFS CORPORATION

Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Jim Duvall*

Title: Staff Plan Reviewer


Date: 8/18/21

| Name | Grille Size (in) | Htg (cfm) | Cig (cfm) | TEL (ft) | Design FR | Veloc (fpm) | Diam (in) | H x W (in) | Stud/Joist Opening (in) | Duct Matl | Trunk |
|------|------------------|-----------|-----------|----------|-----------|-------------|-----------|------------|-------------------------|-----------|-------|
| rb2 | 0x0 | 565 | 562 | 88.1 | 0.079 | 529 | 14.0 | 0x0 | | VIFx | |
| rb1 | 0x0 | 626 | 629 | 61.8 | 0.113 | 589 | 14.0 | 0x0 | | VIFx | |

Return Branch Detail Table

| Name | Trunk Type | Htg (cfm) | Cig (cfm) | Design FR | Veloc (fpm) | Diam (in) | H x W (in) | Duct Material | Trunk |
|------|------------|-----------|-----------|-----------|-------------|-----------|------------|---------------|-------|
| st2A | Peak AVF | 291 | 248 | 0.107 | 872 | 9.0 | 8 x 6 | RectFbg | st2 |
| st1A | Peak AVF | 362 | 302 | 0.079 | 620 | 10.4 | 14 x 6 | RectFbg | st1 |
| st1B | Peak AVF | 241 | 151 | 0.079 | 723 | 8.9 | 8 x 6 | RectFbg | st1A |
| st1 | Peak AVF | 900 | 944 | 0.079 | 1132 | 14.9 | 20 x 6 | RectFbg | |
| st2 | Peak AVF | 291 | 248 | 0.107 | 436 | 9.0 | 16 x 6 | RectFbg | |

Supply Trunk Detail Table



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Swacke*
Title: Staff Plan Reviewer
Date: 8/18/21

| | |
|--------------------------------------|------------------------------------|
| | CUSTOMER: CHAMPION HOME BUILDER |
| | |
| MODEL: 23-3276-16 | SCALE: |
| DRAWN: BPW | DATE: 8/5/21 |
| CAD FILENAME: DS\CHAMPION LILLINGTON | |



PFS Corporation d/b/a PFS TECO

An Employee-Owned Company

August 18, 2021

Mr. Mike Hamm, P.E.
Chief Building Code Consultant
North Carolina Department of Insurance - OSFM
325 North Salisbury Street
Raleigh, NC 27603

RE: Champion Home Builders #23
Lillington, NC
Model: 23-3276-16 (061720)

Dear Mr. Hamm:

Enclosed is one set of PFS accepted documents for the above referenced manufacturer. PFS has reviewed these documents and to the best of our knowledge have found them to conform to the North Carolina codes:

2018 NC Residential Code w/Amendments (includes plumbing, mechanical, & energy codes – Chapter 11)
2017 NC Electrical Code w/Amendments

If you have any questions, please contact us.

Sincerely,

A handwritten signature in black ink, appearing to read 'Ian Lehrer'.

Ian Lehrer, P.E.
Agency Engineer

Enclosure: As Stated

cc: Ryan Duke
File

Mr. Mike Hamm, P.E.
August 18, 2021
Page Two

PFS Corporation has reviewed and approved the above referenced material and to the best of our knowledge these documents conform to the referenced codes.



Construction Review
Ian Lehrer, P.E.



Structural Review
Ian Lehrer, P.E.



Plumbing Review
Ian Lehrer, P.E.



Mechanical Review
Ian Lehrer, P.E.



Electrical Review
Ian Lehrer, P.E.

N//A

Quality Control Review
Ian Lehrer, P.E.



Date Received at PFS: 8-10-2021
 IBC Transmittal No. (by PFS): _____
 Project No. (by PFS): 21005336

ADDITIONAL OR MODIFIED ACCEPTANCE (MODULARS/PANELIZED)

This form is to be used only when the manufacturer is seeking acceptance of an additional model, modified model or model name change which uses a previously accepted building system.

Current PFS Building System Acceptance #: _____
 Model Name/ No. 23-3276-16 061720
 Manufacturer's Name: CHAMPION HOME BUILDERS
 Plant(s) at which model will be produced PLANT #23 LILLINGTON, NC

Check One: Y NEW MODEL _____ Revised Model*

| TECHNICAL DATA | | Conforms | | |
|---|--|----------|----|-----|
| | | Yes | No | N/A |
| Floor Plan Showing: | | | | |
| Braced Wall Method or Shearwalls | | Y | | |
| Building Size (LxW Dimensions) | | Y | | |
| Room Sizes, Light & Ventilation Schedule | | Y | | |
| Exit Requirements | | Y | | |
| Electrical Outlet Spacing & Smoke Detector | | Y | | |
| Location of Labels & Data Plates | | Y | | |
| Use Group, Type Const., Total Sq.Ft. Area | | Y | | |
| Plumbing System Design or Reference No. (<u>PROVIDED ON PP-101</u>) | | Y | | |
| Heat Loss Calculations or Reference No. (<u>PROVIDED ON RS-101</u>) | | Y | | |
| HVAC/Furnace Size/Model No. (<u>BY OTHERS</u>) | | Y | | |
| Thermal Performance Calculations or Reference No. (<u>PROVIDED ON RS-101</u>) | | Y | | |
| Electrical Load Calculations or Reference No. (<u>PROVIDED ON EP-101</u>) | | Y | | |
| Service Size and Location (<u>200A/UTILITY</u>) | | Y | | |
| Applicable Building Codes <u>SEE GE-101</u> | | Y | | |
| Submit model to the following states: <u>NC</u> | | | | |
| *Description of Modification: _____ | | | | |
| Requested by: <u>JON TYNDALL</u> Date: <u>8-9-21</u> | | | | |
| (designer) | | | | |

For PFS Use

Staff Plan Reviewer Tim Busche Certification #: B5002446-R3 Date: 8-18-2021

Structural Calculation(s) Reviewed By: _____ P.E. #: _____ Date: _____

Remarks: _____

**** (1) copy sent to IBC within 15 days of approval.**

VERBAL APPROVAL GIVEN By Whom: _____ To Whom: _____ Date: _____

MODEL WAS DEVIATED Revision Number: _____

THIS FORM SHALL BE FILLED OUT COMPLETELY WITH EACH MODEL ACCEPTANCE OR MODIFICATION PRIOR TO SUBMITTAL TO PFS.

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 1 of 3

revised May 2011

Manufacturer CHAMPION HOME BUILDERS

Model number/name 23-3276-16 061720

3rd Party PFS Corporation

Review Date

Reviewer

Plan Sheet Page # and NOTES

QC MANUAL (current and complete)

APPROVED ON 2-28-12

APPENDIX B (required and attached)

N/A

PLAN SHEETS

Each plan sheet third-party stamped with approver's name

Each plan sheets is numbered and/or indexed

GENERAL (cover sheet)

Code References

GE-101

Statement regarding connection to public utilities

GE-101

Statement regarding bathrooms if not included

N/A

Construction type

GE-101

Occupancy classification

GE-101

Fire resistance ratings (if required)

GE-101

Floor live load

GE-101

Roof live load

GE-101

Design wind velocity

GE-101

Seismic information (commercial projects)

GE-101

Thermal zones

RS-101/GE-101 UNDER GENERAL NOTES

Notice to inspections department regarding items to be site inspected

GE-101

FLOOR PLANS

Interior and exterior wall layouts

AP-101

Door and window schedule

AP-101

Light and Ventilation requirements

AP-101

Attic access (size and location)

AP-101

Non-prescriptive headers

AP-101, SECTION 9, PAGES 1-12

Safety glazing requirements

AP-101

Fire rating of Exterior walls (if applicable)

N/A

EXTERIOR ELEVATIONS

Exterior materials

EV-101-104/SE-101

Attic ventilation requirements

SE-101/AP-101/ WORKSHEET 1

PLUMBING

Plan

PP-101/ WP-101

All fixtures furnished by mfg. shown on plans

PP-101/WP-101/GE-101(REFERENCE TO COMPLIANCE)

Materials (water supply & distribution, DWV, storm drainage)

PP-101/ WP-101

Supply and waste risers, including DWV system (generic) beneath the building.

PP-101/ WP-101

Water heater (type and capacity)

QA MANUAL 04.01.01

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 2 of 3

revised May 2011

Plan Sheet Page # and NOTES

MECHANICAL

| | |
|---|----------------------------------|
| Design calculations | BY OTHERS |
| Installed unit capacity | BY OTHERS |
| Supply and returns (locations and sizes) | AP-101 (RETURNS BY MANUFACTURER) |
| Duct sizes | BY OTHERS |
| Specifications (units, ducts) | BY OTHERS |
| All appliances furnished by mfg. shown on plans | QA MANUAL 04.01.01 |

ELECTRICAL

| | |
|--|---------------|
| Plan | EP-101 |
| Location of all electrical boxes | EP-101 |
| Electrical panel location | EP-101 |
| Note regarding main disconnect (if applicable) | GE-101 |
| Exterior lighting and receptacles | EP-101 |
| Ground level receptacles (if applicable) | BY OTHERS |
| Smoke detector location(s) | EP-101 |
| Electrical load calculations | EP-101 |
| Electrical panel layout (breaker and wire sizes, circuit schedule) | EP-101 |
| Panel and service entrance sizes | GE-101/EP-101 |
| All fixtures furnished by mfg. shown on plans | EP-101 |

ACCESSIBILITY

(for other than 1 & 2 family dwellings)

| | |
|---|-----|
| Entrances and means of egress | N/A |
| Doors, doorways, and door hardware | N/A |
| Stairs and handrails | N/A |
| Toilet rooms, plumbing fixtures, grab bars, etc | N/A |
| Bathrooms and shower rooms | N/A |
| Occupancy specific requirements | N/A |
| Multi-family dwellings: Type A and B units | N/A |

FLOOR X-SECTION

| | |
|--|---|
| Joists and beam sizes and spacing | SE-101/ STRUCT. MANUAL SECTION 20 PGS 1-2 |
| Materials species and grade | SE-101 STRUCT. MANUAL SECTION 20 PGS 1-2 |
| Sheathing, decking, and concrete as applicable | SE-101 |
| Fastening instructions | SE-101/ STRUCT. MANUAL SECTION 20 PGS 1-2 |
| Insulation | SE-101 |
| Details as required for clarification | SE-101 |

WALL X-SECTION

| | |
|---------------------------------------|--|
| Stud and column sizes and spacing | SE-101 |
| Materials species and grade | SE-101 |
| Sheathing and bracing | AP-101/SE-101 |
| Headers and lintels | AP-101/SE-101 |
| Finishes | SE-101 |
| Fastening instructions | SE-101/SEE AP-101 FOR SHEARWALL SECTION-PAGE REFERENCE |
| Insulation | SE-101 |
| Details as required for clarification | SE-101 |

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 3 of 3

revised May 2011

Plan Sheet Page # and NOTES

CEILING / ROOF X-SECTION

| | |
|---|--|
| Truss, rafter, and beam spacing | AP-101/SE-101/ STRUCT. MANUAL SECTION 3 PAGES 1-38 |
| Lumber species and grade | SE-101/ STRUCT. MANUAL SECTION 3 PAGES 1-38 |
| Sheathing and decking | SE-101/ STRUCT. MANUAL SECTION 4 PAGES 1-36 |
| Finishes | SE-101 |
| Fastening instructions | SE-101/ STRUCT. MANUAL SECTION 4 PAGES 1-36 |
| Insulation | SE-101 |
| Details including NC sealed truss designs or manual reference | STRUCT. MANUAL SECTION 3 PAGES 1-38 |

FOUNDATION PLAN

| | |
|---|-----------|
| Footings, pier, and curtain wall locations and specifications | F-101 |
| X-sections with dimensions | F-101 |
| Anchorage - sill plate to piers and curtain wall | F-102-103 |
| Anchorage - building to sill plate | F-102-103 |
| Anchorage - tie downs (lateral and longitudinal) | N/A |
| Soil bearing capacity | F-103 |
| Minimum concrete compressive strength | F-103 |
| Mortar type | F-103 |
| Ventilation requirements (with and without vapor barrier) | F-101 |
| Crawl space access requirements | F-101 |

ENERGY COMPLIANCE

| | |
|-------------------------|--------|
| Demonstrated compliance | RS-101 |
|-------------------------|--------|

SET-UP INSTRUCTIONS

| | |
|--|--|
| Floor and ceiling connections | GE-101/SE-101/SETUP MANUAL PAGES 12-13 |
| Marriage wall connections | N/A |
| Roof set-up and connection | GE-101/SE-101/SETUP MANUAL PAGES 12-13 |
| Plumbing connections | GE-101/SE-101/SETUP MANUAL PAGES 23-24 |
| Mechanical connections | GE-101/SE-101/SETUP MANUAL PAGES 21,25,28,29 |
| Electrical connections | GE-101/SE-101/SETUP MANUAL PAGES 25-28 |
| Fire stopping | GE-101/SE-101/SETUP MANUAL |
| Air infiltration elimination | GE-101/SE-101/SETUP MANUAL PAGE 11 |
| Notice to inspections department attachment if set-up instructions are by attachment | GE-101/SE-101 |

ITEMS NOT INSPECTED IN PLANT

| | |
|---|--------|
| List of items not inspected by 3rd. Party | GE-101 |
| Notice to inspections department | GE-101 |