



4055 HIGHWAY 401 SOUTH
LILLINGTON, NC 27546

"23-3276-16 061720"
3 BEDROOM 3 BATH
2305 SQ. FT.

A HOME DESIGNED FOR:

5/12, 130 Vult MAX

SHEET INDEX

- CP-101 COVER SHEET
- GE-101 GENERAL NOTES
- L-101 LITERATURE PLAN
- EV-101 ELEVATIONS
- EV-102 ELEVATIONS
- EV-103 ELEVATIONS
- EV-104 ELEVATIONS
- AP-101 FLOOR PLAN
- AP-201 STRUCTURAL BRACING
- AP-202 STRUCTURAL BRACING DETAILS
- AP-203 STRUCTURAL BRACING DETAILS
- EP-101 ELECTRICAL PLAN
- PP-101 DWV PLAN OFF-FRAME

SHEET INDEX-CONT.

- W-101 WATER LINE PLAN
- SE-101 SECTION PLAN OFF-FRAME
- F-101 PERIMETER FOUNDATION PLAN
- F-102 PERIMETER FOUNDATION DETAILS
- F-103 PERIMETER FOUNDATION DETAILS
- APPENDIX E
- WORK SHEET 1 VENT CALCS
- WORK SHEET 2 BRACEWALL CALCS
- SHEARWALL CALCULATIONS SHEETS SECTION 6 PAGES 1-30 (PFS REVIEW ONLY)
- HVAC CALCULATIONS PGS 1-7



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Swale*
Title: Staff Plan Reviewer
Date: 8/18/21

THIS MODEL NOT DESIGNED FOR OCEAN HIGH HAZARD AREAS OR SPECIAL MOUNTAIN REGIONS OR FLOOD ZONES OR SPECIAL WIND REGIONS.



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE
COVER SHEET
MODEL:
23-3276-16 061720
30'-0" x 75'-0" 3 BEDROOM 3 BATH
DATE: 8-17-20
SCALE:
DRAWN BY: TT
REVISED:
REVISIONS:

SHEET NO:
CP-101
PAGE:

STATE	GENERAL:	ELECTRICAL:	PLUMBING:	MECHANICAL:	ENERGY:
NC CODES	2018 NC RESIDENTIAL CODE	2017 NC ELECTRICAL CODE	2018 NC PLUMBING CODE	2018 NC MECHANICAL CODE	2018 NORTH CAROLINA ENERGY CONSERVATION CODE N1102.1.2 and Appendix E used for code compliance

GENERAL NOTES

- ALL GLAZING WITHIN 24 INCH ARC OF DOORS, WHOSE BOTTOM EDGE IS LESS THAN 80 INCHES ABOVE THE FLOOR, AND ALL GLAZING IN DOORS SHALL BE SAFETY, TEMPERED OR ACRYLIC PLASTIC SHEET.
- OCCUPANT LOAD IS BASED ON 1 PERSON PER 200 SQUARE FEET OF FLOOR AREA.
- ALL STEEL STRAPS REFERENCED ON FLOOR PLAN SHALL BE 1/2 INCH X 28 GA. MIN.
- CEILING FANS SHALL BE 80 INCHES MIN. FROM BOTTOM OF BLADES TO FINISH FLOOR.
- MINIMUM CORRIDOR WIDTH IS 36 INCHES.
- ALL WINDOWS SHALL BE DOUBLE GLAZED.
- EXTERIOR DOORS SHALL HAVE AN INSULATION VALUE OF R-1.66 MINIMUM.
- FIRE STOPPING AND AIR INFILTRATION BARRIER BETWEEN UNITS SHALL BE PROVIDED BY DRAFTSTOP BRAND NONCOMBUSTIBLE FILLER COMPOUND OR EQUAL MEETING ASTM-E136, R902.8
- HOMES GOING INTO RADON AREAS WILL HAVE A 3 VTR AND SWITCH LEG TO SWITCH LABELED "RADON" ON TRIM PLATE.
- LOCATION MAY VARY PER MODEL.
- THIS HOME DESIGNED FOR JUP TO, CLIMATE ZONE 4 FOR VA
- FOR NC & SC AND CLIMATE ZONE 4A FOR VA
- THE MANUFACTURER MUST BE INFORMED IF HOME IS TO BE LOCATED IN HIGHER CLIMATE ZONE.
- THE MANUFACTURER MUST BE INFORMED IF THE HOME IS TO BE LOCATED IN THE CITY OF CHARLESTON, S.C.
- THE MANUFACTURER MUST BE INFORMED IF THE HOME IS TO BE LOCATED IN ANY SPECIAL MOUNTAIN REGION.
- THIS PLAN MAY BE FLIPPED END TO END AND/OR MIRRORED

PLUMBING NOTES

- THIS UNIT MUST BE CONNECTED TO PUBLIC WATER SUPPLY AND SEWAGE SYSTEM IF THESE SERVICES ARE AVAILABLE
- ALL PLUMBING FIXTURES SHALL HAVE SEPARATE SHUT-OFF VALVES.
- WATER HEATER SHALL HAVE A SAFETY PAN WITH 1 INCH DRAIN TO EXTERIOR.
- WATER PIPES INSTALLED IN A WALL, EXPOSED TO THE EXTERIOR SHALL BE LOCATED ON THE HEATED SIDE OF THE WALL INSULATION. WATER PIPING INSTALLED IN AN UNCONDITIONED ATTIC SHALL BE INSULATED WITH AN INSULATION OF R-5.5 MINIMUM.
- DWV SYSTEM SHALL EITHER ABS OR PVC-DWV
- WATER SUPPLY LINES SHALL BE POLYETHYLENE (PEX), CPVC, OR COPPER. WHEN POLYETHYLENE (PEX) SUPPLY LINES ARE INSTALLED THE MAXIMUM WATER HEATER SETTING IS 180 DEG F. THE POLYETHYLENE PIPE SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS LIMITATIONS AND INSTRUCTIONS.
- BUILDING DRAIN AND CLEANOUTS ARE DESIGNED AND SITE INSTALLED BY OTHERS, SUBJECT TO LOCAL JURISDICTION APPROVAL.
- TUB ACCESS PROVIDED UNDER HOME UNLESS OTHERWISE NOTED.
- SHOWER STALLS SHALL BE COVERED W/ NON-ABSORBANT MATERIAL TO A HEIGHT OF 72 INCHES ABOVE FINISH FLOOR.
- T&B RELIEF VALVE W/DRAIN TO EXTERIOR AND SHUT-OFF WITHIN 3' OF WATER SUPPLY AT WATER HEATER
- WATER HAMMERS ARRESTERS SHALL BE INSTALLED AT EACH QUICK CLOSING VALVE I.e. ICE MAKERS, DISH WASHERS, AND CLOTHES WASHERS (WHEN REQUIRED).
- WATER HEATERS LIST ON Q.C. 04.01.01
- ALL PLUMBING FIXTURES/DRIPING SHALL COMPLY WITH SECTIONS: P2206, P2701 & TABLES P2701.1, P2904.1 & P2904.5 OF INTERNATIONAL RESIDENTIAL CODE OR SECTIONS 303, 402 & TABLES 603.3, 605.4, 605.5 OF NORTH CAROLINA PLUMBING.
- ALL TUBS AND SHOWER SHALL HAVE TEMPERATURE LIMITING VALVES PER IRC AND NC PLUMBING.
- ELECTRICAL NOTES
- ALL CIRCUITS AND EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH THE APPROPRIATE ARTICLES OF THE NATIONAL ELECTRIC CODE (NEC).
- WHEN LIGHT FIXTURES ARE INSTALLED IN CLOSELY OR RECESSED, INCANDESCENT FIXTURES SHALL HAVE COMPLETELY ENCLOSED LAMPS. SURFACE MOUNTED INCANDESCENT FIXTURES SHALL HAVE A MINIMUM OF 12 INCHES AND ALL OTHER FIXTURES SHALL HAVE A CLEARANCE OF 6 INCHES FROM "STORAGE" AREA AS DEFINED BY NEC 410-16(C)
- WHEN WATER HEATERS, DISH WASHERS, AND WASH OVERS ARE INSTALLED, THEY SHALL BE PROVIDED WITH READILY ACCESSIBLE DISCONNECTS. THE BRANCH CIRCUIT SWITCH OR CIRCUIT BREAKER SHALL BE PERMITTED TO SERVE AS THE DISCONNECTING MEANS ONLY WHERE THE SWITCH OR CIRCUIT BREAKER IS WITHIN SIGHT FROM THE APPLIANCE OR IS CAPABLE OF BEING LOCKED IN THE OPEN POSITION.
- HVAC EQUIPMENT SHALL BE PROVIDED W/ READILY ACCESSIBLE DISCONNECTS ADJACENT TO THE EQUIPMENT SERVED. A UNIT SWITCH WITH A MARKED "OFF" POSITION THAT IS PART OF THE HVAC EQUIPMENT AND DISCONNECTS ALL UNGROUNDED CONDUCTORS SHALL BE PERMITTED AS THE DISCONNECTING MEANS WHERE OTHER DISCONNECTING MEANS ARE ALSO PROVIDED BY A READILY ACCESSIBLE CIRCUIT BREAKER.
- PRIOR TO ENERGIZING THE ELECTRICAL SYSTEM THE INTERRUPTING RATING OF THE MAIN BREAKER MUST BE DESIGNED AND VERIFIED AS BEING IN COMPLIANCE WITH SECTION 110-9 OF THE NEC BY LOCAL ELECTRICAL CONSULTANT.
- THE MAIN ELECTRICAL PANEL(DISCONNECT) AND FEEDERS ARE DESIGNED BY OTHERS, SITE INSTALLED AND SUBJECT TO LOCAL JURISDICTION APPROVAL.
- SMOKE DETECTORS SHALL BE WIRED SO THAT THE OPERATION OF ANY ONE SMOKE DETECTOR WILL CAUSE SIMULTANEOUS ACTIVATION OF ALL OTHERS.
- ALL CIRCUITS CROSSING OVER MODULE MATING LINES(S) SHALL BE SITE CONNECTED IN APPROVED ACCESSIBLE JUNCTION BOXES OR WITH APPROVED CABLE CONNECTIONS.
- ALL WIRING SHALL BE NMC
- ANY STRIP RECEPT MOUNTED BENEATH A COUNTER SHALL BE WITHIN 6" OF THE EDGE
- ALL BRANCH CIRCUITS SUPPLYING 15 & 20 AMPRE OUTLETS IN LIVING AREAS ARE PROTECTED BY AN ARCH-FULT CIRCUIT INTERRUPTER IN ACCORDANCE WITH SECTION 210.12, NEC
- ALL ELECTRICAL FIXTURES/WIRING SHALL COMPLY WITH SECTION E3303.3 (9C & VA)
- IT IS THE BUILDERS RESPONSIBILITY TO PROVIDE ELECTRICAL PROVISIONS FOR ANY "MOBILE" WORKSTATION IF IT IS PERMANENTLY MOUNTED.

MECHANICAL NOTES

- FACTORY INSTALLED SUB PANEL BOX SHALL HAVE 2" MIN. CONDUIT FOR WIRE FEEDERS
- ALL AIR SUPPLY REGISTERS ARE ADJUSTABLE EXCEPT WHERE OTHERWISE SPECIFIED
- INTERIOR DOORS SHALL BE UNDERCUT 1" MIN ABOVE FINISHED FLOOR FOR AIR RETURN
- BATHROOMS SHALL BE PROVIDED WITH A WINDOW OR A MIN. 60 CFM VENT FAN. VA. REQUIRES A MINIMUM OF .35 AIR CHANGE EVERY HOUR.
- BATH VENT FANS SHALL BE DUCTED TO THE EXTERIOR AND TERMINATE AT AN APPROVED VENT CAP
- HVAC EQUIPMENT SHALL BE EQUIPPED WITH OUTSIDE FRESH AIR INTAKES BY OTHERS.
- HVAC SUPPLY DUCTS AND CALCULATIONS DESIGNED AND INSTALLED BY OTHERS
- ALL DUCTS SHALL HAVE A MIN. OF R-8 INSULATION
- ALL REGISTER BOOTS SHALL BE TAPED OR SEALED OTHERWISE
- ALL RETURN GRILLS BY FACTORY UNLESS SPECIFIED OTHERWISE
- OPTIONAL FURNACE TO BE FACTORY INSTALLED. OPTIONAL FURNACE KW SIZING TO BE VERIFIED BY OTHERS WITH SITE PROVIDED MANUAL D & L
- *OPTIONAL FURNACE USED FOR SUPPLEMENTAL HEATING ONLY. FOR OPTIMAL EFFICIENCY, A HEAT PUMP SHOULD BE INSTALLED.
- ON-SITE CONNECTIONS
- ON-SITE STRUCTURAL CONNECTIONS: FOR SITE CONNECTIONS REFER TO SECTION DRAWINGS, FOUNDATION PLANS, AND THE DOWN PLAN (ON-FRAME)
- ON-SITE ELECTRICAL CONNECTIONS: MULTI-SECTION UNITS WILL HAVE THE ELECTRICAL CROSSOVERS LOCATED EITHER IN THE FLOOR NEAR THE MARRIAGE LINE OR IN THE ENDWALLS NEAR THE CENTER OF THE UNIT. LOCATE THE JUNCTION BOXES AND CONNECT THE CONDUCTORS TOGETHER. THE CONDUCTORS SHOULD BE COLOR CODED OR MARKED FOR EASY IDENTIFICATION. DO NOT INTERCONNECT CIRCUITS OR CROSS CONDUCTORS.
- ON-SITE PLUMBING CONNECTIONS: WATER LINES: LOCATE AND CONNECT WATER LINE CROSS-OVERS LOCATED UNDER THE FLOOR AT THE MARRIAGE LINE. TURN THE WATER ON AND CHECK FOR LEAKS. DRAIN LINES: CONNECT DRAIN DROP-OUTS TO THE MAIN DRAIN. BE SURE ALL CONNECTIONS ARE MADE TO COMPLY WITH LOCAL PLUMBING CODES. TWO STORY DESIGNS: SOME 2 STORY MODELS WILL REQUIRE ADDITIONAL VERTICAL CONNECTIONS SEE PLAN SHEETS FOR LOCATIONS AND ACCESS POINTS
- INTEGRITY OF MARRIAGE LINE RIDGE BEAM SHALL NOT BE COMPROMISED UNLESS SPECIFICALLY DESIGNED FOR AND SHOWN ON APPROVED PLANS.
- ON-SITE GAS CONNECTIONS (IF APPLICABLE): LOCATE "QUICK DISCONNECT" AND CONNECT THE "QUICK DISCONNECT" IS LOCATED UNDER THE FLOOR AT THE MARRIAGE LINE. VERIFY THAT ALL CONNECTIONS ARE TIGHT AND HAVE BEEN CHECKED FOR LEAKS.

ATTENTION LOCAL INSPECTIONS DEPARTMENT

THE FOLLOWING ITEMS HAVE NOT BEEN COMPLETED BY CHAMPION HOMES. HAVE NOT BEEN INSPECTED BY P.F.S., AND ARE NOT CERTIFIED BY THE STATE MODULAR CERTIFICATION LABEL. CODE COMPLIANCE MUST BE DETERMINED AT THE LOCAL LEVEL.

- SITE CONNECTION OF ROOFS, FLOORS, WALLS (setup manual pages 11-13, pages AP-101, SE-101-102, CALCULATION SHEETS in plan set)
- ELECTRICAL CONNECTIONS ON SITE (pages 26-28 setup manual), PLUMBING CONNECTIONS ON SITE (pages 23-25 setup manual), TRUNKLINE, MANUAL D & J BY OTHERS ON SITE, DRYER VENTING BY OTHERS (page 20 setup manual).
- * BLOWER DOOR TEST TO BE COMPLETED BY OTHERS ON SITE.
- * ON BASEMENT ENTRY HOMES, FLOOR INSULATION IS NOT PROVIDED BY FACTORY.
- ALL BASEMENT WORK, INCLUDING FOUNDATION DESIGN, STAIRS, HVAC AND CONNECTION OF SMOKE DETECTOR AND REQUIRED OUTLETS, DONE BY OTHERS.
- PROVISIONS FOR EGRESS FROM BASEMENT MUST BE PROVIDED ON SITE BY OTHERS.
- ALL ENERGY COMPLIANCE FOR BASEMENTS MUST BE DONE ON SITE BY OTHERS
- * RODENT PROOFING TO BE COMPLETED ON-SITE BY OTHERS PER RP-101 (IN HOME OWNERS PACKET) IN WINDBORNE DEBRIS AREAS, WINDOW/DOOR PROTECTION PROVIDED BY OTHERS PER LOCAL CODE
- ANY SITE INSTALLED ATTIC ACCESS SHOWN ON AP-101
- NO SPRINKLER SYSTEMS REQUIRED FOR UNIT. A FIRE EXTINGUISHER TO BE PROVIDED ON SITE BY OTHERS
- **SEE ENERGY CODE INSPECTION CHECKLIST FOR FACTORY COMPLETED ITEMS AND SITE COMPLETED ITEMS**
- **ALL FALL PROTECTION DEVICES REQUIRED PER R312.2. MUST BE INSTALLED ON SITE BY OTHERS

ATTENTION LOCAL INSPECTIONS DEPARTMENT

SET-UP INSTRUCTIONS ARE INCLUDED ON THE PLAN SHEETS & IN SET-UP MANUAL INCLUDED IN HOMES. SEE NOTES, CROSS SECTION AND FOUNDATION PAGES (ITEMS NOT COMPLETE AT FACTORY MARKED WITH * ON CROSS SECTION) IF CHAMPION HOMES INSTALLATION MANUAL IS NOT INCLUDED THESE PLANS ARE INCOMPLETE.

ATTENTION LOCAL INSPECTIONS DEPARTMENT

IF THIS STRUCTURE IS IN A THERMAL ZONE MORE STRINGENT THAN THAT LISTED ON THESE PLANS, IS SET ON PILING, OR IS INSTALLED AT A MOUNTAIN REGION OR COASTAL HIGH HAZARD SITE SUCH THAT WIND OR OTHER DESIGN PARAMETERS ARE INCREASED, THE DESIGN MUST BE DETERMINED TO BE ADEQUATE FOR ACTUAL SITE CONDITIONS. ALTERATIONS MAY BE REQUIRED TO BRING THE HOME INTO COMPLIANCE WITH THE MORE STRINGENT CONDITIONS.

ALL OPERABLE WINDOWS TO INCLUDE INSECT SCREENS, ALL PATIO AND ATRIUM DOORS TO INCLUDE INSECT SCREENS. IF HOME IS EQUIPPED WITH WOOD BURNING FIREPLACE, SEE PAGE 22 OF SET UP MANUAL AND MANUFACTURERS INSTALLATION MANUAL FOR REQUIRED SITE INSTALLATION. VIRGINIA MODS TO HAVE ICE DAM PROTECTION AS REQUIRED BY STATE/LOCAL CODES.

APPROVAL STAMP

PFS CORPORATION
Approval Limited to Factory Built Portion Only

North Carolina
Tom Blumke
Staff Plan Reviewer
8/18/21

DESIGN INFORMATION

OCCUPANCY	SINGLE FAMILY
CONSTRUCTION TYPE	VB UNP
MAXIMUM WIND SPEED	130 MPH VILT
WIND EXPOSURE	C
SEISMIC CATEGORY	C
FLOOR LIVE LOAD	40 PSF
2ND FLOOR LIVE LOAD (for homes with fixed walkup stairs)	30 PSF
FLOOR DEAD LOAD	10 PSF
ROOF LIVE LOAD	20 PSF STANDARD
ROOF DEAD LOAD	10 PSF
GROUND SNOW LOAD	30 PSF STD(24" O.C.)
FIRE RATING EXT WALL	0 HRS.
TENANT SEPARATION	0 HRS.
MAX MEAN ROOF HT.	20.00'



4055 HWY. 401 SOUTH LILLINGTON, NC 27548

TITLE: NOTES

MODEL: ANY MODEL

DATE: 04-18-20
SCALE: NOT TO SCALE
DRAWN BY: CDB
REVISIONS

REVISIONS

SHEET NO:


GE-101

PAGE:

NOTE: ALL HIGH WIND DESIGNS, CONSTRUCTION, FASTENING, ETC, BUILT PER CALCULATION MANUAL OR SPECIFIC ENGINEERING (MEETING OR EXCEEDING CHAPTER 45- NC)

76'

30'-4"



23-3276-16 061720
 4 BEDROOM 3 BATH
 76'-0" X 30'-4"
 2305 SQ. FT.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Swale*
 Title: Staff Plan Reviewer
 Date: 8/18/21




4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT	
TITLE	LITERATURE PLAN
MODEL	23-3276-16 061720
DATE	6-17-20
SCALE	3/8" = 1'-0"
DRAWN BY	TT
REVISED	REVISIONS
SHEET NO.	L-101
PAGE	

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swindle*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**

CHAMPION
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546



SHOWN WITH 5/12 PITCH
 SHOWN WITH STANDARD DOOR & WINDOW CONFIGURATION

FRONT ELEVATION


FOUNDATIONS, STEPS, PORCHES
 AND RAILS DONE ON SITE BY OTHERS

PROJECT

TITLE
 ELEVATIONS


MODEL: 23-3276-16 061720
 30'-4" x 75'-0" BEDROOM & BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS

SHEET NO:
EV-101
 PAGE:


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swade*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**

RIDGE VENT

COMPOSITE SHINGLE



FOUNDATIONS, STEPS, PORCHES
AND RAILS DONE ON SITE BY OTHERS

REAR ELEVATION


CHAMPION 
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE

ELEVATIONS
 MODEL:
 23-3276-16 061720
30' x 78'-0" BEDROOM 3 BATH
 DATE 6-17-20
 SCALE NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS
 SHEET NO:
EV-102
 PAGE


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: **North Carolina**
 Signature: *Tim Swade*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**




CHAMPION
 4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE

ELEVATIONS

MODEL

23-3276-16 061720

30'-4" x 18'-0" BEDROOM & BATH

DATE 6-17-20

SCALE NTS

DRAWN BY: TT


REVISED:


REVISIONS

SHEET NO:

EV-103

PAGE:


PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Swale*
 Title: Staff Plan Reviewer
 Date: 8/18/21



RIGHT ELEVATION

CHAMPION 

4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE
ELEVATIONS

MODEL:
 23-3276-16 061720
 30'-0" x 7'-0" 3 BEDROOM 3 BATH
 DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISED:
 REVISIONS:

SHEET NO:

EV-104

PAGE:

PFS CORPORATION
 Approval Limited to Factory Built Parton Only
 North Carolina
State:
Signature: *Tim Brucke*
Title: Staff Plan Reviewer
Date: 8/18/21

WIND VELOCITY SHEARWALLS
 REFERENCED TO ATTACHED CALCULATIONS
 FROM BARLOW ENGINEERING


TRUSSES LOCATED IN CALCULATION MANUAL, SECTION 6 PAGES 1-3
 ALL BEAMS REFERENCED TO CHAMPION HOMES OF LILLINGTON
 SYSTEM PACKAGE U/180, "UNIFORM BEAM CHARTS" SECTION 8, PAGE 15
 WITH U/240, "UNIFORM BEAM CHARTS" SECTION 8, PAGE 15
 AS PREPARED BY BARLOW ENGINEERING
 MATERIAL TOTAL LOAD (U/180) = 367 PLF
 LIVE LOAD (U/240) = 198 PLF

ATTIC VENTILATION:
 SEE WORKSHEET #1 CALCULATIONS
 DRYER VENT TO BE INSTALLED ONSITE

DESCRIPTION	GLAZED SQ. FT.	VENTING PRESSURE	SECTION	U-VALUE	MANUFACTURER
WINDOWS (9750 SERIES)	132	644	DP 50	0.17	LIPPERT
36" x 61" EGRESS OPT. SAFETY GLAZED	856	585	DP 50	0.29	LIPPERT
30" x 61" EGRESS OPT. SAFETY GLAZED	555	276	DP 50	0.29	LIPPERT
30" x 36" OPT. SAFETY GLAZED	1607	801	DP 50	0.34	KINHO
16" x 61" EGRESS OPT. SAFETY GLAZED	131	0	DP 50	0.35	KINHO
24" x 48" OPT. SAFETY GLAZED	485	244	DP 50	0.34	KINHO
14" x 48" OPT. SAFETY GLAZED	628	0	DP 50	0.34	KINHO
42" x 34" BLACK GLASS	1429	611	DP 50	0.28	LIPPERT
42" x 40" PICTURE	826	288	DP 50	0.34	KINHO
46" x 38" ARCH SAFETY GLAZED	17	0	DP 50	0.34	KINHO
36" x 87" TRANSLUCENT GLAZED	0	0	DP 50	0.34	KINHO
46" x 87" TRANSLUCENT GLAZED	0	0	DP 50	0.34	KINHO
36" x 80" EXTERIOR DOOR WITH Y LITE	440	1945	DP 50	0.17	LIPPERT
36" x 80" EXTERIOR DOOR WITH Y LITE	1468	1945	DP 50	0.17	LIPPERT
WINDOWS OPT. SLIDING GLASS	3437	1945	DP 50	0.29	LIPPERT
74" x 80" ALUMINUM DOOR WITH 15 LITE WINDOWS	2496	1945	DP 50	0.30	LIPPERT

DATA PLATE
 ENERGY CERTIFICATION LABEL
 LABEL LOCATIONS (STATE & PFS)

COLUMN SUPPORT	AREA
1-2x4's	1st FLOOR
2-2x4's	2305 SQ. FT
3-2x4's	2nd FLOOR
	N/A
	GLAZING



NOTE: ALL WINDOWS AND DOORS TO HAVE SCREENS FOR VENTILATION AND INSECTS.

PROJECT

TITLE
 FLOOR PLAN

MODEL
 23-3276-16 061720

DATE
 8-17-20

SCALE
 3/16" = 1'-0"

DESIGNED BY
 TT

REVISIONS


SHEET NO.
 AP-101

PAGE

CHAMPION

4055 HWY. 401 SOUTH LILLINGTON, NC 27546

ENDWALL #2 CONNECTION SUMMARY # F/S 2



ENDWALL #1 CONNECTION SUMMARY # F/S 1

SIDEWALL # 1 CONNECTION SUMMARY # F3

SIDEWALL # 2 CONNECTION SUMMARY # F4

SEE STRUCTURAL BRACING SUMMARY AP202 FOR MORE DETAILS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 Signature: *Tim Swalle*
 Title: Staff Plan Reviewer
 Date: 8/18/21



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE:
STRUCTURAL
BRACING &
CONNECTIONS

MODEL:
23-3276-16 061720
30'-4" x 76'-0" BEDROOM 3 BATH
DATE: 6-17-20
SCALE: 1/8" = 1'-0"
DRAWN BY: TT
REVISIONS:

SHEET NO:
AP-201

PAGE:

MODEL No.: 23-3276-16 061720
 SERIAL No.:
 WIND SPEED.: 130 VULT
 ROOF 5/12

PFS CORPORATION
 SHEAR CALCULATIONS

Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Jim Duncanson*
 Title: Staff Plan Reviewer
 Date: 8/18/21

SIGNED BY: CHAMPION HOMES
 DATE: 8/9/2021
 CHECKED BY: JPT

By	CHK'D	LOCATION	EDGE FASTENING*	FIELD FASTENING*	16 GA.	19/32" OSB MIN.	NOTES	CONN. #
		ENDWALL #1 (HITCH)	4.0	4.0	8.0	7/16" OSB BLOCKED	71 FHS (MASTER BED / BATH)	F/S1
		ENDWALL #2 (REAR)	6.0	6.0	12.0	7/16" OSB BLOCKED	90 FHS (BEDROOM 2 & 3)	F/S2
		SIDEWALL #1 (A MODULE)	6.0	6.0	12.0	7/16" OSB BLOCKED	71 FHS (LIVING)	F3
		SIDEWALL #2 (B MODULE)	6.0	6.0	12.0	7/16" OSB BLOCKED	59 FHS (KITCHEN / DINING)	F4
		ROOF SHEATHING	6.0	6.0	12.0	7/16" OSB UNBLOCKED		F5
		INCREASE TO	6.0	6.0	8.0	7/16" OSB BLOCKED		F6
		WITH	6.0	3.0		O.C. FASTENERS AT PERIMETER		F7
		BLOCKING DISTANCE	0'	0'		FROM ENDWALLS (ROOF DIAPHRAGM SHEATHING CONNECTION : 170 PLF)		F8
		CEILING SHEATHING	7.0	7.0	7.0	1/2" GWB UNBLOCKED (FOAM ADHESIVE MEETS REQUIRED FASTENING)		F9
		FLOOR SHEATHING	6.0	2.0	12.0	15 GA.		F10

By	CHK'D	LOCATION	FASTENING *	ALT. FASTENER†	NOTES
		ROOF ZONE 1	12	5	
		ROOF ZONE 2	11	5	
		ROOF ZONE 3	7	3	
		ROOF ZONE 3 O/H	6	2	
		WALL ZONE 4	12	5	
		WALL ZONE 5	12	5	
		EDGE DIMENSION (Z)	4	4	

* 8D COMMON NAILS (.131" x 2.5")
 * Roof (16 GA. STAPLES)
 * Floor (8D COMMON NAILS (.131" x 2.5"))
 † 16 GA. STAPLE (REF. SEC 16 PG. 14 8D TO 16GA. (Z))
 † Roof (16 GA. STAPLE (REF. SEC 16 PG. 15 14GA. TO 16GA. (Z))
 † Floor (15 GA. STAPLE (REF. SEC 16 PG. 14 10D TO 15GA. (Z))



By	CHK'D	LOCATION	UPLIFT # FASTENING *	ALT. FASTENING *	NOTES
		TRUSS THE DOWN	148		(1) SIMPSON SDWC 15600
		TRUSS THE DOWN (FLAT STRAP)	148		(1) 1/2" x 20GA STRAP W/ (4) 0.113 NAILS
		STUD TO TOP PLATE/CEILING BAND	99		(1) 1/2" x 20GA STRAP W/ (2) 0.113 NAILS
		STUD TO TOP PLATE (ALTERNATE)	99		16 GA STAPLES EA. STUD
		STUD TO FLOOR BAND	13		(1) 1/2" x 20GA STRAP W/ (4) 0.113 NAILS
		STUD TO FLOOR BAND (ALTERNATE)	13		16 GA STAPLES EA. STUD
		PLATE TO PLATE	248		(6) 15GA. X 2 1/2" STAPLES EACH END
		PLATE TO STUD	248		15GA. X 2 1/2" STAPLES AT 5" O.C.
		BOTTOM PLATE TO FLOOR	248		15GA. X 2 1/2" STAPLES AT 5" O.C.

* QUANTITIES ARE EACH END
 ** C-2019-2021 ED. SIMPSON CATALOG
 (REF. SEC 18 PG. 17 20GA. STRAP/NAILS)
 (REF. SEC 18 PG. 17 20GA. STRAP/NAILS)
 ALT. FASTENING *
 CONN. #

By	CHK'D	LOCATION	FASTENING	NOTES
		PLATE TO PLATE	(2) ROWS 15GA. X 2 1/2" STAPLES AT 1" O.C.	
		FACE NAILED 3" MIN SPLICE		(SUBSTITUTION REF. SEC 16 PG. 15 .162 TO 15 GA. (Z))

By	CHK'D	LOCATION	FASTENING	NOTES
		ENDWALLS	SHEATHING UPLIFT CONN. TO FLOOR BAND AND BOTTOM CHORD W/ (1) ROWS OF 16GA. STAPLES AT (2) IN O.C.	
		ENDWALLS	SHEATHING UPLIFT CONN. TO FLOOR BAND AND BOTTOM CHORD W/ (1) ROWS OF 16GA. STAPLES AT (2) IN O.C.	
		ENDWALLS	BOTTOM CHORD TO TOP PLATE W/ .131 X 3" TOENAILS AT 6" IN O.C.	
		ENDWALLS	SHEATHING SHEAR CONN. TO FLOOR BAND W/ (1) ROWS OF 16GA. STAPLES AT (6) IN O.C.	
		SIDEWALLS	SHEATHING UPLIFT CONN. TO FLOOR BAND W/ (1) ROWS OF 16GA. STAPLES AT (6) IN O.C.	
		SIDEWALLS	SHEATHING UPLIFT CONN. TO FLOOR BAND W/ (1) ROWS OF 16GA. STAPLES AT (6) IN O.C.	
		LOCATION / LOAD		

UNIT SHEAR & UPLIFT CONNECTIONS
 (SUBSTITUTION REF. SEC 16 PG. 14 .131 TO 16 GA. (Z))
 (SUBSTITUTION REF. SEC 20 PG. 14 .162 TO .113 (Z))
 CONN. #


By	CHK'D	LOCATION	FASTENING	NOTES
		ALL EXTERIOR WALL INTERSECTIONS	(1) ROW(S) #8 SCREWS AT 6.2" O.C.	
		ALTERNATE FASTENER	(1) ROW(S) 3/8" LAG AT 9.3" O.C.	
		LOCATION		

CORNER HOLDOWNS *
 (SUBSTITUTION REF. SEC 16 PG. 13 LATERAL (Z))
 (3/8 LAG REF. SEC 2 PG. 2 LATERAL (Z-1.6 Cd))
 CONN. #

By	CHK'D	LOCATION	FASTENING	NOTES
		ALL EXTERIOR WALL CORNERS	4600 LBS MAX UPLIFT MINUS 6650 LBS Z OF DEAD LOAD = 0 LBS	
		NO HOLD DOWNS REQUIRED		

CONN. #


SIDEWALL/ENDWALL DETAIL




PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: **North Carolina**
 Signature: *Tim Swale*
 Title: **Staff Plan Reviewer**
 Date: **8/18/21**

ROOF ASSEMBLY DETAILS



TOP PLATE SPLICE DETAIL



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE
WALL FASTENING

MODEL:

23-3276-16 061720
 30'-4" x 76'-0" BEROOM 3 BATH

DATE: 6-17-20

SCALE: 1/8" = 1'-0"

DRAWN BY: TT

REVISIONS:

REVISIONS

SHEET NO:

AP-203

PAGE:


SEE Q/A MANUAL FOR APPROVED ELECTRICAL FIXTURES SECTION 4 PAGE 4

NC NOTE:
PER NC ECC 404.1, A MINIMUM OF 75% OF LAMPS INSTALLED IN PERMANENTLY INSTALLED FIXTURES MUST BE HIGH-EFFICIENT LAMPS (EXAMPLE: CFL'S)

ALL BULBS TO BE PROVIDED ON SITE BY OTHERS.

PFS CORPORATION
Approval Limited to: Factory Built Portion Only

State: **North Carolina**
Signature: *Tim Brubaker*
Title: **Staff Plan Reviewer**
Date: **8/18/21**



FURNACE NOTE: 17KW NORDYNE E6 FURNACE WITH 57,000 BTUH PROVIDED BY CHAMPION HOMES.

ELECTRICAL LEGEND

GENERAL RECEPTACLE 120 VOLT - 15 AMP	CEILING LIGHT	FLUORESCENT LIGHT	PHONE JACK
G.F.I. PROTECTED RECEPT. 120 VOLT-15 AMP	WALL LIGHT	DIRECTLY WIRED CONNECTION	TV/CABLE JACK
120 VOLT - 20 AMP G.F.I. PROTECTED	CEILING VENT FAN W/LIGHT (2 SWITCHES)	THERMOSTAT	HEAT TAPE RECEPT 120 VOLT-15 AMP
220 VOLT RECEPT. EXTERIOR LIGHT	EXHAUST FAN	SMOKE DETECTOR	JUNCTION BOX
	SINGLE POLE SWITCH	MAIN PANEL	RECESSED LIGHT
	FLOOD LIGHT	TRACK LIGHTING	SMOKE DETECTOR/ CO COMBINATION

NOTE:

1. CIRCUIT NUMBERS MAY VARY AND NOT ALL CIRCUITS ARE IN USE
2. ARC-FAULT CIRCUIT INTERRUPTERS SHALL BE IN ACCORDANCE WITH SECTION 210.12 (A) OF THE CURRENT NEC.
3. OPTIONAL 220 VOLT RECEPTACLE PROVIDED FOR RANGE AND DRYER.
4. POWER RANGE HOOD STANDARD.
5. ALL CLOSET LIGHTS TO BE A MIN. 12" OFF OF SHELF.
6. DWELLING UNIT RECEPTACLE MUST BE RATED AS TAMPER RESISTANT ACCORDANCE WITH SECTION 408.12, NEC
7. WATER PROOF COVERS REQUIRED FOR OUTDOOR SWITCHES AND RECEPTACLE ACCORDANCE WILL SECTION 404.4 AND 404.9, NEC
8. OUTLET, DEVICE, PULL, AND JUNCTION ARE IN ACCORDANCE TO ARTICLE 314
9. ATTIC LIGHT TO BE INSTALLED, IF ATTIC TO BE USED FOR STORAGE, ON SITE

- RECEPT TO BE INSTALLED FOR WHIRLPOOL TUB WITHIN 12" OF ACCESS IN DIRECT VIEW FOR DISCONNECT OF APPLIANCE.
- BREAKER LOCKOUT TO BE INSTALLED FOR DISHWASHER, WATER HEATER
- RANGE HOOD EXHAUST FAN IS A NON VENTED RECIRCULATION TYPE (CHARCOAL)
- CO/SMOKE DETECTOR COMPLIES WITH UL 217 AND UL 2034
- FIRST ALERT MODEL #SC9120B (NC, SC)

ELECTRICAL SCHEDULE - CONT -			ELECTRICAL SCHEDULE - CONT -			PANEL SIZING		
BREAKER CIR #	DESCRIPTION	VOLTS WIRE	BREAKER CIR #	DESCRIPTION	VOLTS WIRE	DESCRIPTION	KVA	
20 A11	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A12	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A13	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A14	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A15	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A16	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A17	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A18	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A19	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A20	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A21	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A22	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A23	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A24	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A25	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A26	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A27	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A28	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A29	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A30	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A31	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A32	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A33	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A34	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A35	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A36	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A37	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A38	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A39	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A40	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A41	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A42	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A43	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A44	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A45	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A46	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A47	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A48	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A49	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A50	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A51	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A52	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A53	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A54	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A55	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A56	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A57	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A58	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A59	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A60	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A61	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A62	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A63	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A64	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A65	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A66	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A67	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A68	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A69	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A70	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A71	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A72	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A73	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A74	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A75	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A76	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A77	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A78	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A79	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A80	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A81	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A82	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A83	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A84	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A85	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A86	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A87	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A88	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A89	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A90	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A91	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A92	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A93	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A94	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A95	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A96	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A97	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A98	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A99	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	
20 A100	GFI PORTABLE APPLIANCE	120 12/2	15	24	12/2	1500VA, 1000	3 KVA	



4055 HWY. 401 SOUTH LILLINGTON, NC 27548

PROJECT

TITLE
ELECTRICAL PLAN

MODEL: 23-3276-16 061720
DATE: 6-17-20
SCALE: 3/16" = 1'-0"
DRAWN BY: TT
REVISIONS:
SHEET NO: EP-101
PAGE:

PROJECT

TITLE:
DWV PLAN
OFF-FRAME

MODEL:

23-3276-16 061720
30" x 75" x 6" BATHROOM 3 BATH
DATE: 6-17-20
SCALE: NTS
DRAWN BY: TT
REVISIONS

SHEET NO:
PP-101

PAGE:

DWV PLUMBING PLAN

NOTES:


- 1- ALL PIPE SIZES ARE 1/2" UNLESS OTHERWISE SPECIFIED.
- 2- ONE FIXTURE IN "BATHROOM GROUP" MAY BE ELIMINATED WITHOUT AFFECTING PIPE SIZING.
- 3- ALL PIPES SHOWN IN DASHED LINE ARE FIELD INSTALLED BY OTHERS SUBJECT TO LOCAL JURISDICTION.
- 4- AUTO VENTS TO BE INSTALLED ON SITE AFTER COMPLETE PLUMBING SYSTEM TEST.
- 5- WATER STAND TEST MUST BE DONE ON SITE AFTER COMPLETION OF PLUMBING SYSTEM.
- 6- ALL VENT PIPES MUST TERMINATE MIN. 6' ABOVE ROOF, WITH APPROVED WATER TIGHT FLASHING. (P904.1 & P904.3)
- 7- IF HOME LOCATED IN AREA WHERE 97.5% FOR OUTSIDE DESIGN TEMPERATURE IS 0° OR LESS, EVERY VENT EXTENSION SHALL BE MIN. 3". THIS TO BE DONE ON SITE BY OTHERS. (P904.2)
- 8- RODENT PROOFING AT ALL SHOWERS, TUBS, TUB/SHOWER TO BE COMPLETED ON SITE BY OTHERS AFTER PLUMBING TEST COMPLETED.

SEE Q/A MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 5

PIPE SUPPORT TO BE AS FOLLOWS:
MAX HORIZONTAL SPACING = 4'
MAX VERTICAL SPACING = 10'
REFERENCE: IPC TABLE 308.5

ATTN. LOCAL BUILDING OFFICIAL *

ALL P-TRAPS AT TUBS, SHOWERS & TUB/SHOWERS MUST BE RODENT PROOFED AND FINAL FIRE BLOCKING COMPLETED ON SITE BY OTHERS AFTER COMPLETION OF ALL PLUMBING TESTS. ALL OTHER RODENT PROOFING AND FIRE BLOCKING AT FLOOR LEVEL DONE AT FACTORY. (REFERENCE IRC R302.11 FOR CORRECT METHODS) SEE PAGE AE-101 IN SETUP MANUAL IN HOME FOR DETAILS (SECTION 5, PG 36 QA MANUAL). SEE Q/A MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 5



PFS CORPORATION

Approval Limited to Factory Built Portion Only

State:

North Carolina

Signature:

Tim Brudke

Title:

Staff Plan Reviewer

Date:

8/18/21

① 1 1/2" PVC OR ABS

② 2" PVC OR ABS

③ 3" PVC OR ABS

⊙ APPROVED AUTOVENT

⊙ S/O STUB OUT


⊙ VTR VENT THROUGH ROOF

⊙ INSTALLED ON SITE

PROJECT

STATE WATER HEATER
 MODEL # SC 152 PORTE 3 (ELECTRIC)
 CO#1094 IM 50 NHDST 2 (GAS)
 MANUF. INFORMATION LOCATED
 IN O.A. MANUAL, SECTION 4,
 PAGE 04.01.01

WATER HEATER SECURED IN PLACE
 FOR TRANSIT WITH METAL SHIPPING
 STRAPS FROM WALL TO WALL




1" DRAIN
 TO EXTERIOR

SUPPLY AT WATER HEATER

1. ALL PLUMBING FIXTURES HAVE SEPARATE SHUTOFF VALVES.
2. WATER HEATER SHALL HAVE A SAFETY PAN WITH 1 INCH DRAIN TO EXTERIOR.
3. WATER PIPES INSTALLED IN A WALL EXPOSED TO THE EXTERIOR SHALL BE LOCATED ON THE HEATED SIDE OF THE WALL INSULATION. WATER PIPING INSTALLED IN AN UNCONDITIONED ATTIC OR CRAWL SPACE SHALL BE INSULATED WITH AN INSULATION OF R-3 MINIMUM ON SITE BY OTHERS.
4. DWV SYSTEM SHALL EITHER ASB or PVC-DWV ENTIRELINE (PVC, CPVC, OR COPPER, WHEN NOTIFIED BY THE MANUFACTURER).
5. THE MAXIMUM WATER HEATER SETTING IS 180 DEG F. THE POLYETHYLENE PIPE SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S LIMITATIONS AND INSTRUCTIONS.
6. BUILDING DRAIN AND CLEANOUTS ARE DESIGNED AND SITE INSTALLED BY OTHERS. SUBJECT TO LOCAL JURISDICTION APPROVAL.
7. TUB ACCESS PROVIDED UNDER HOME UNLESS OTHERWISE NOTED.
8. SHOWER STALLS SHALL BE COVERED UP TO A HEIGHT OF 72 INCHES ABOVE FINISH FLOOR.
9. TAP RELIEF VALVE W/RAIN TO EXTERIOR OR PAN SUPPLY AT WATER HEATER.
10. THIS UNIT MUST BE CONNECTED TO PUBLIC WATER SUPPLY AND SEWAGE SYSTEM.
11. THESE ARE PERFORMED FOR MAXIMUM INLET PRESSURE OF 80 PSI. SEE SETUP MANUAL SECTION 4.1
12. SEE O.A. MANUAL FOR APPROVED PLUMBING FIXTURES SECTION 4 PAGE 9

WATER PLUMBING PLAN

NOTES:
 -ALL PIPE SIZES ARE 1/2" UNLESS OTHERWISE SPECIFIED.



PFS CORPORATION
 Approval Limited to Factory Built Portion Only
North Carolina

State: _____
 Signature: *Tim Brade*
 Title: Staff Plan Reviewer
 Date: 8/18/21

TITLE
 WATER LINE PLAN

MODEL:
 23-3276-16 061720
 30'-4" x 78'-0" 1/2" BDRM 3 BATH


DATE: 6-17-20
 SCALE: NTS
 DRAWN BY: TT
 REVISIONS:
 REVISIONS

SHEET NO.
WP-101

*** ATTN LOCAL BUILDING OFFICIAL:
SEE INSULATION CERTIFICATE AT PANEL BOX FOR ACTUAL INSULATION VALUE USED.
APPENDIX E IS USED.**

Soft materials for this work assume that the building face will be 30 feet or greater from the property line when installed on site. Where the building face is less than 30 feet from the property line, underlayment materials and ventilation in accordance with Section R783.11.3, IRC Residential Code, must be provided and installed at the site and inspected by the local jurisdiction.

FOR RIDGE BEAMS ABOVE BOTTOM CHORD REQUIRING TENSION CONNECTIONS



(PAINTED HARDI, WOOD OR METAL COVERED)

CONNECTION DETAILS FASTENED PER AP-202.

VINYL EXTERIOR SIDING PER ORDER

SHEATHING PAPER OR APPROVED WATERPROOF MEMBRANE MUST BE INSTALLED UNDER EXTERIOR SIDING (EX. HOUSE WRAP, all seams taped). EXTERIOR SIDING MAY BE SITE INSTALLED WITH LOCAL INSPECTION

CONNECTIONS FASTENED PER AP-202.

ON SITE CONNECTION

ON SITE CONNECTION

ON SITE CONNECTION

ON SITE CONNECTION SEE TRUSS SETUP & GABLE ENDWALL PAGES.

FASTENING OF ROOF SHEATHING SEE PAGE AP-202

SHINGLE OVER RIDGE VENT INSTALL PER MANUFACTURERS INSTRUCTIONS
SHINGLES - SHINGLES INSTALLED PER MANUF. LOCATED ON EACH VENT FOR INSTALLATION INSTRUCTIONS - (NO CAMBRIDGE OR TRAWCO HERITAGE ARCHITECTURAL OR EQUAL - (HIGH WIND REQUIRES 6 FASTENERS PER SHINGLE))

ATTIC VENTILATION REQUIREMENT OF 1/600th OF TOTAL ROOF AREA IS ACCOMPLISHED WITH 50% OR MORE OF THE NET VENT AREA PROVIDED THROUGH ROOF VENTILATORS, RIDGE VENTS OR GABLE VENTS LOCATED IN THE UPPER 1/3 OF THE TRUSS HEIGHT AND THE REMAINDER OF THE NET VENT AREA PROVIDED BY SOFFIT VENTS. SEE NOTE ON AP-101 AND WORKSHEET 1

APPROVED TRUSS (SEE AP-101 FOR REFERENCE) 24" O.C. STANDARD, 18" O.C. OPTIONAL

ROOF COVERING OVER APA RATED SHEATHING

1 x 4 BLOCKING BETWEEN TRUSSES FOR FIELD FASTENING OF SHEATHING (PER TRUSS DESIGN)

BAFFLE TO PROVIDE 1" AIR SPACE.

DOUBLE 2x6 #3 GRADE SPF TOP PLATE

1/2" GYPSUM CL.G. FIN. WOOD COMPRESSION STRIP (1 1/2" x 1 1/2" PLYWOOD OR EQUAL AS REQUIRED)

NOTE: GYPSUM WALLBOARD USED IN DAMP LOCATIONS (TUB ENCLOSURES WITH SHOWER HEAD) MUST BE WATER RESISTANT BOARD. WATER RESISTANT BOARD NOT REQUIRED WITH ONE PIECE FIBERGLASS TUB ENCLOSURE 6 FT HIGH OR HIGHER.

WALL INSULATION KRAFT FACED WARM SIDE FIBERGLASS BATT INSULATION (R-18 2X6) SEE APPENDIX E

2X6 SPF #2 STUDS @ 16" O.C.

1/2" GYPSUM

2X6 BOTTOM PLATE TYPICAL HEAT REGISTER INSTALLED IN EACH ROOM ANY ADDITIONAL REGISTER REQUIRED BY OTHERS IS TO BE DONE ONSITE

8' TO 9' MAX

MEAN ROOF HEIGHT

20.00'

WOOD COMPRESSION STRIP (1 1/2" x 1 1/2" PLYWOOD OR EQUAL AS REQUIRED) CONTINUOUS VINYL VENTED SOFFIT

7/8" OSB SHEATHING SHALL BE INSTALLED ON THE ENTIRE EXTERIOR OF THE HOME. ALL SHEATHING TO BE FASTENED WITH 6d BOX NAILS OR EQUAL. FASTENED PER AP-202.

VINYL SIDING - 4 1/2" VENT TRUE WALL BRAND "OR EQUAL" (FASTENER SPACING: 16" O.C. HORIZONTAL VINYL 12" O.C. VERTICAL VINYL AND ACCESSORIES AT 8" TO 10" O.C. ALL WIND SPEEDS) INSTALLED PER MANUF. INSTALLATION INSTRUCTIONS FASTENED PER AP-202.

FLOOR DECKING IS TO BE CONTINUOUS OVER JOIST. FASTENED TO FLOOR RIM JOIST PER AP-202.

CONTINUOUS TO FLOOR DECKING


SEE FOUNDATION DESIGN FOR PERIMETER WALL AND FOOTING DETAILS

FASTEN TRUSS TOGETHER IN THE FIELD WITH 3/8" X 6" LAG SCREWS AT 32" O.C. ALTERNATE DIRECTIONS

REFERENCE: ATTACHED CALC PAGE 24, sect 6

SEE FOUNDATION DESIGN FOR COLUMN/JACKPOST DESIGN, SIZE, AND SPACING. SEE FT101-103

GROUND LEVEL VAPOR BARRIER TO BE INSTALL BY OTHERS



- NOTES:
1. ALL FINISH MATERIAL TO HAVE CLASS "C" FIRE RATING.
 2. ALL PENETRATIONS THROUGH FLOOR OR CEILING FIRE STOPPED
 3. SEE FOUNDATION PLAN FOR SUPPORT AND THE DOWN REQUIREMENTS.

PFS CORPORATION
Approval Limited to Factory Built Portion Only
North Carolina
Signature: *Tim Swade*
Staff Plan Reviewer
Date: 8/18/21



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE:
OFF FRAME
CROSS SECTION

MODEL:
23-3276-16 061720
30'-4" x 76'-0" 3 BEDROOM 3 BATH

DATE: 10/7/03

SCALE: 1/8" = 1'-0"

DRAWN BY: JPT

REVISIONS: 04-13-04

CDB: ADDED DORMER INFORMATION

SFA: ADDED P-TRAP RODENT PROOF

SHEET NO:

SE-101


PAGE:

FOUNDATION VENT TO PROVIDE 1st OF VENT PER EACH 150sf OF CRAWL SPACE AREA
 2305 SF / 150 SF = 15.4
 8"x16" (TYP) VENT = APPROX. 5 SF
 15.4 / .5 = APPROX. 31 VENTS

- NOTES:
1. SPLICES IN MATE LINE GIRDERS MUST FALL ON A SUPPORT PIER.
 2. PIERS OR POSTS TO BE SPACED PER CHART AND LOCATED UNDER OPENING COLUMN SUPPORTS WHEN OPENING WIDTH IS 4' OR GREATER.
 3. FOR SEISMIC DESIGN CATEGORY D0, D1 & D2 FOUNDATION DESIGNED BY OTHERS

OFF FRAME LIFTING NOTES:

1. IF LIFTING POINTS ARE MORE THAN 32 FEET APART (TYPICAL OF UNIT LENGTHS GREATER THAN 64'), A THIRD AND FOURTH LIFTING POINT IS REQUIRED. THIRD AND FOURTH LIFTING POINT IS TO BE BETWEEN OUTER LIFTING POINTS AND MEET THE REQUIREMENTS OF NOTE 2.
2. PICK UP POINT MUST NOT BE LOCATED UNDER A WALL OPENING. IF AN OPENING CANNOT BE AVOIDED, A TEMPORARY WALL MUST BE INSTALLED.



NOTE:
 1" ADDED TO OVERALL WIDTH TO ACCOMMODATE LIFT STRAPS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Tim B. Swalle*
 Title: Staff Plan Reviewer
 Date: 8/18/21

TITLE:	PERIMETER FOUNDATION PLAN
MODEL:	23-3276-16 061720
	30'-4" x 76'-0" 3 BEDROOM 3 BATH
DATE:	8-17-20
SCALE:	NTS
DRAWN BY:	TT
REVISIONS:	
SHEET NO.:	F-101
PAGE:	


PROJECT

CHAMPION


4055 HWY. 401 SOUTH LILLINGTON, NC 27546




SECTION A-A BLOCK WALL



SECTION A-A BRICK VENEER WALL



SECTION A-A PIER & CURTAIN WALL



SECTION A-A CONTINUOUS 8" MASONRY WALL

C:\Users\jtyndal\Desktop\23-3276-16 061720.dwg, 8/9/21 07:30 AM

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: **North Carolina**

Signature: *Tim Swade*
Staff Plan Reviewer

Date: 8/18/21

TYPICAL FOUNDATION NOTES :

- Foundation and its structural elements shall be capable of accommodating all superimposed live, dead, and other loads in accordance with applicable codes and all lateral loads in accordance with accepted design practices.
- Lots shall be provided with adequate drainage and shall be graded so as to drain surface water away from foundation walls - by lot owner.
- Materials shall conform to applicable standards and codes.
- Concrete subject to weathering shall have a minimum compressive strength and air content in accordance with code - 2500 psi concrete minimum.
- All exterior walls, bearing walls, columns, and piers shall be supported on continuous solid concrete footings which shall be of sufficient design to support safely the loads imposed as determined from the character of the soil, and shall in all cases, extend below the frost line. Top surface shall be level and bottom not exceeding 1 in 40 slope. Footings shall be not less than shown on drawings for 2000 psf soil.
- Foundation walls shall be constructed in accordance with the code and not less than as shown on the Drawings.
- Foundations shall extend not less than 12 inches below the finished natural grade or engineered fill and in no case less than the frost line depth. Footings on soil with a lower allowable soil pressure shall be designed in accordance with accepted engineering practice. However, where there is evidence that the groundwater table can rise to within 6 inches of the finished grade at the building perimeter or where there is evidence that the surface water does not readily drain from the building site, the building official may require that the grade in the under-floor space be as high as the outside finished grade, unless an approved drainage system is provided. Termite shields and/or protection shall be provided as per code. Local and state requirements for footings may exceed that shown on drawings. If there are any questions, contact your local building inspections department.
- Crawl space ventilation and access space shall be by openings in the foundation walls {cross-ventilation as required by code and/or as follows}. Provide 1 sq. Ft. of ventilation area for each 150 sq. Ft. of crawl space floor area. Use 8"x16" foundation vents with corrosion resistant wire mesh (1/8" mesh) or equal.
- Mortar shall be type "m" or "s".
- Minimum soil bearing capacity shall be 2000 psf.
- Anchorbolt length to be: masonry wall-20",
- Poured concrete footing w/two #5 rebar (120 & 130 only) continuous w/ a minimum 25" lap. Place bars 3" from bottom.
- This foundation plan is provided for reference as a typical. Actual foundation conditions must be evaluated for applicability if this plan is to be used. Alternate foundation plans may be designed by others in accordance with the requirements of the jurisdiction having authority.


* Vertical wall reinforcement or continuous anchorage is as follows:

- Sidewall anchor bolt spacing see F-101
- Endwall anchor bolt spacing see F-101


PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: **North Carolina**
Signature: *Tim B. Wade*
Title: **Staff Plan Reviewer**
Date: **8/18/21**

There shall be a minimum of (2) bolts per sill plate section, with one bolt located not more than 12" from each end of the plate section.



**SECTION B-B
BASEMENT WALL**



SECTION B-B

**PIER & CURTAIN WALL, BLOCK WALL
& BRICK VENEER WALL**
(where required on module mate lines)



4055 HWY. 401 SOUTH LILLINGTON, NC 27546

PROJECT

TITLE:
PERIMETER
FOUNDATION
DETAILS

MODEL:
23-3276-16 061720
37'-4" x 7'-0" BEDROOM 3 BATH
DATE: 6/17/20
SCALE: NTS
DRAWN BY: TT
REVISED:
REVISIONS

SHEET NO:
F-103

PAGE:

BUILDER MUST FINISH APPENDIX, FACTORY DONE MARKED IN RED

APPENDIX E

(E-1 THROUGH E-4)

RESIDENTIAL REQUIREMENTS FOR ENERGY CONSERVATION

This appendix is a North Carolina addition and not part of the 2015 International Residential Code.

There will be no underlined text.

(The provisions contained in this appendix are adopted as part of this code.)

APPENDIX E-1 Energy Efficiency Certificate (Section N1101.14)

ENERGY EFFICIENCY CERTIFICATE (N1101.14)

Builder, Permit Holder or Registered Design Professional	Print Name:	
	Signature:	
Property Address:	Signature:	<i>Jim Duvall</i>
	Title:	Staff Plan Reviewer
	Date:	8/18/21


Insulation Rating – List the value covering largest area to all that apply		R-38
Ceiling/roof:		R-18
Wall:		R-30
Floor:		
Closed crawl space wall:		
Closed crawl space floor:		
Slab:		
Basement wall:		
Fenestration:		
U-Factor		0.34
Solar Heat Gain Coefficient (SHGC)		0.29
Building Air Leakage		
<input type="checkbox"/> Visually inspected according to N1102.4.2.1 OR		
<input type="checkbox"/> Building air leakage test results		
(Sec. N1102.4.2.2) ACH50 [Target: 5.0] or CFM50/SFSA [Target: 0.30]		
Name of Tester/Company:		
Date:		
Phone:		
Ducts:		
Insulation		
Total duct leakage test result (Sect. N1103.3.3)		
Circle one:		
Total duct leakage test (CFM25 Total/100SF) [Target: 5] or Duct leakage to the outside test (CFM25 Total/100SF) [Target: 4]		
Name of Tester or Company:		
Date:		
Phone:		

Certificate to be displayed permanently

APPENDIX E-2
INSULATION AND AIR SEALING DETAILS


APPENDIX E-2.1

N1102.2.1 Ceilings with attic spaces: Exception for fully enclosed attic floor systems



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Jim Drake*
 Title: Staff Plan Reviewer
 Date: 8/18/21




N1102.2.11 Closed crawl space walls. Insulation illustrations

APPENDIX E-2.2


APPENDIX E-2.3

N1102.2.14 Framed cavity walls. Insulation enclosure—1. Tubs



FACTORY COMPLETED

N1102.2.14 Framed cavity walls. Insulation enclosure—2. Showers



FACTORY COMPLETED


PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tom Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

PFS CORPORATION
Approval Limited to Factory Built Portion Only


State: North Carolina
Signature: *Jim Clarke*
Title: Staff Plan Reviewer
Date: 8/18/21

SECTION VIEW OF INTERIOR STAIRCASE FOR WALL (OPTION 2)



N1102.2.14 Framed cavity walls. Insulation enclosure—3. Stairs

SECTION VIEW OF INTERIOR STAIRCASE ON EXTERIOR WALL (OPTION 1)




N1102.2.14 Framed cavity walls. Insulation enclosure—3. Stairs

FACTORY COMPLETED, IF APPLICABLE

N/A BY FACTORY

N1102.2.14 Framed cavity wall. Insulation enclosure—4. Direct vent gas fireplace



PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

2018 NORTH CAROLINA RESIDENTIAL CODE

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). Order Number #10066317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with ICC. No further reproduction or distribution authorized. Single user only, copying and networking prohibited. ANY UNAUTHORIZED REPRODUCTION OR DISTRIBUTION IS A VIOLATION OF THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

N1102.2.15 Framed cavity walls. Insulation enclosure—5. Walls that adjoin attic spaces


N/A BY FACTORY



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21


ISOMETRIC VIEW OF DIMENSIONAL LUMBER FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems N/A BY FACTORY

APPENDIX E-2.4


SECTION VIEW OF WALL ADJOINING ATTIC SPACE WITH TRUSS ROOF



N/A BY FACTORY


N1102.2.15 Framed cavity walls. Insulation enclosure.—5. Walls that adjoin attic spaces

ISOMETRIC VIEW OF I-JOIST FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems N/A BY FACTORY


ISOMETRIC VIEW OF WOOD TRUSS FLOOR/CEILING SYSTEM ABOVE COMMON WALL BETWEEN UNCONDITIONED AND CONDITIONED SPACE



N1102.4.1 Building thermal envelope.—1. Block and seal floor/ceiling systems N/A BY FACTORY

N1102.4.1 Building thermal envelope—2. Cap and seal shafts and chases

BY OTHERS IF APPLICABLE



SECTION VIEWS OF DUCT PENETRATING INTO ATTIC

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 Jim Clarke
 Staff Plan Reviewer
 Date: 8/18/21


2018 NORTH CAROLINA RESIDENTIAL CODE

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). (-) Order Number #10069317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
Signature: *Tim Duerke*
Title: Staff Plan Reviewer
Date: 8/18/21

SECTION VIEW OF SOFFIT OVER CABINET




N1102.4.1 Building thermal envelope.—3. Cap and seal soffit or dropped ceiling. N/A


N1102.4.1 Building thermal envelope.—4. Seal HVAC boot penetration—floor




PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
Jim Currie
 Staff Plan Reviewer
 8/18/21
Title: HVAC SUPPLY
Date:

N1102.4.1 Building thermal envelope.—4. Seal HVAC boot penetration—ceiling





N1102.4.1 Building thermal envelope.—5. Sealed exterior air barrier with sheathing



N1102.4.1 Building thermal envelope.—5. Sealed exterior air barrier with housewrap


Follow manufacturer's instructions for sealing air barrier-rated housewrap, including choice of materials, to provide an exterior air barrier at the following locations:

MUST BE INSPECTED ON SITE BY OTHERS FOR TEARS


2018 NORTH CAROLINA RESIDENTIAL CODE

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tom Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21



N1102.4.2.1 Visual inspection option. — Table N1102.4.2 Seal ceiling electrical box penetrations **FACTORY COMPLETED**



N1102.4.2.1 Visual inspection option. — Table N1102.4.2 Seal ceiling mechanical box penetrations **FACTORY COMPLETED**

MUST BE COMPLETED BY BUILDER ON SITE

APPENDIX E

APPENDIX E-3: SAMPLE WORKSHEETS FOR RESIDENTIAL AIR AND DUCT LEAKAGE TESTING

APPENDIX E-3A

AIR SEALING: VISUAL INSPECTION OPTION (Section N1102.4.2.1)

SAMPLE WORKSHEET

air sealing in Section N1102.2.15 and air sealing in Section N1102.4.1 are addressed and when the items listed in Table N1102.4.2, applicable to the method of construction, are certified by the builder, permit holder or registered design professional via the certificate in Appendix E-1.

N1102.4.2 Air sealing. Building envelope air tightness shall be demonstrated by Section N1102.4.2.1 or N1102.4.2.2. N1102.4.2.1 Visual inspection option. Building envelope tightness shall be considered acceptable when items providing insulation enclosure in Section N1102.2.14 and enclosure and

**TABLE N1102.4.2
AIR BARRIER INSPECTION**

COMPONENT	CRITERIA
Ceiling/attic	factory done Sealants or gaskets provide a continuous air barrier system joining the top plate of framed walls with either the ceiling drywall or the top edge of wall drywall to prevent air leakage. Top plate penetrations are sealed. For ceiling finishes that are not air barrier systems such as tongue-and-groove planks, air barrier systems (for example, taped house wrap), shall be used above the finish. Note: It is acceptable that sealants or gaskets applied as part of the application of the drywall will not be observable by the code official.
Walls	Sill plate is gasketed or sealed to subfloor or slab. factory done
Windows and doors	Space between window and exterior door jambs and framing is sealed. factory done
Floors (including above-garage and cantilevered floors)	Air barrier system is installed at any exposed edge of insulation. factory done
Penetrations	Utility penetrations through the building thermal envelope, including those for plumbing, electrical wiring, ductwork, security and fire alarm wiring, and control wiring, shall be sealed. factory done
Garage separation	Air sealing is provided between the garage and conditioned spaces. An air barrier system shall be installed between the ceiling system above the garage and the ceiling system of interior spaces.
Ceiling penetrations	Ceiling electrical box penetrations and ceiling mechanical boxes shall be caulked, gasketed, or sealed at the penetration of the ceiling finish. See Appendix E-2.4. factory done Exception: Ceiling electrical boxes and ceiling mechanical boxes not penetrating the building thermal envelope
Recessed lighting	Recessed light fixtures are air tight, IC rated, and sealed to drywall. factory done Exception: Fixtures in conditioned space.

Attic Access insulated and weatherstripped per N1102.2.2.4

Property Address:

N1102.4.2.1 Visual Inspection Option. The inspection information including tester name, date, and contact shall be included on the certificate described in Section N1101.14.

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Date: _____
Signature: *Jim Dumble*
Title: Staff Plan Reviewer
Date: 8/18/21

Signature

2018 NORTH CAROLINA RESIDENTIAL CODE

INTERNATIONAL CODE COUNCIL

Copyright © 2018 ICC. ALL RIGHTS RESERVED. Accessed by Ryan Duke (Rduke@championhomes.com). (-) Order Number #10066317 on Jan 3, 2019 12:08:36 PM pursuant to License Agreement with ICC. No further reproduction or distribution authorized. Single user only, copying and networking prohibited. ANY UNAUTHORIZED REPRODUCTION OR DISTRIBUTION IS A VIOLATION OF THE FEDERAL COPYRIGHT ACT AND THE LICENSE AGREEMENT, AND SUBJECT TO CIVIL AND CRIMINAL PENALTIES THEREUNDER.

MUST BE COMPLETED BY BUILDER ON SITE

APPENDIX E-3B

Air sealing: Testing option (Section N1102.4.2.2)

Sample Worksheet

tor, a North Carolina licensed HVAC contractor, a North Carolina licensed Home Inspector, a registered design professional, a certified BPI Envelope Professional or a certified HERS rater.

During testing:

1. Exterior windows and doors, fireplace and stove doors shall be closed, but not sealed;

2. Dampers shall be closed, but not sealed, including exhaust, backdraft, and flue dampers;

3. Interior doors shall be open;

4. Exterior openings for continuous ventilation systems, air intake ducted to the return side of the conditioning system, and energy or heat recovery ventilators shall be closed and sealed;

5. Heating and cooling system(s) shall be turned off; and

6. Supply and return registers shall not be sealed.

The air leakage information, including building air leakage result, tester name, date, and contact information, shall be included on the certificate described in Section N1101.14.

N1102.4.2 Air sealing. Building envelope air tightness shall be demonstrated by Section N1102.4.2.1 or N1102.4.2.2:

N1102.4.2.2 Testing option. Building envelope tightness shall be considered acceptable when items providing insulation enclosure in Section N1102.2.14 and enclosure and air sealing in Section N1102.2.15 and air sealing in Section N1102.4.1 are addressed and when tested air leakage is less than or equal to one of the two following performance measurements:

- 1. 0.30 CFM50/Square Foot of Surface Area (SFA) or 2. Five (5) air changes per hour (ACH50) or

When tested with a blower door fan assembly, at a pressure of 33.5 psf (50 Pa). A single point depressurization, not temperature corrected, test is sufficient to comply with this provision, provided that the blower door fan assembly has been certified by the manufacturer to be capable of conducting tests in accordance with ASTM E779-03. Testing shall occur after rough in and after installation of penetrations of the building envelope, including penetrations for utilities, plumbing, electrical, ventilation and combustion appliances. Testing shall be reported by the permit holder, a North Carolina licensed general contractor

For Test Criteria 1 in this section, the report shall be produced in the following manner: Perform the blower door test and record the CFM50. Calculate the total square feet of surface area for the building thermal envelope, all floors, cell-ings, and walls (this includes windows and doors) and record the area. Divide CFM50 by the total square feet and record the result below. If the result is less than or equal to [0.30 CFM50/SFA] the envelope tightness is acceptable; or For Test Criteria 2, the report shall be produced in the following manner: Perform a blower door test and record the CFM50. Multiply the CFM50 by 60 minutes to create CFHour50 and record. Then calculate the total conditioned volume of the home and record. Divide the CFHour50 by the total volume and record the result below. If the result is less than or equal to [5 ACH50] the envelope tightness is acceptable.

Property Address: _____
Fan attachment location _____
Company Name _____
Contact Information: _____
Signature of Tester _____
Date _____

Permit Holder, NC Licensed General Contractor,
NC Licensed Home Inspector, Registered
Certified BPI Envelope Professional, or
Approved HERS Rater
PFS CORPORATION
Approved Limited to Factory Built Portion Only

State: North Carolina
Signature: [Handwritten Signature]
Title: Staff Plan Reviewer
Date: 8/18/21

**APPENDIX E-3C
Duct sealing. Duct air leakage test (Section N1103.2.2 & Section N1103.3.3)**

Sample Worksheet

N1103.3.2 Sealing (Mandatory Requirements). Ducts, air handlers, filter boxes, and building cavities used as ducts shall be sealed. Joints and seams shall comply with either the *International Mechanical Code* or *International Residential Code*, as applicable.

N1103.3.3 Duct leakage (Prescriptive) and duct testing (Mandatory). Duct testing and duct leakage shall be verified by compliance with either Section N1103.3.3.1 or N1103.3.3.2. Duct testing shall be verified using one of the two following methods:

N1103.3.3.1 Total duct leakage. Total duct leakage shall be less than or equal to 5 CFM (12 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, including the manufacturer's air handler enclosure.

N1103.3.3.2 Duct leakage to the outside. Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leaks. Duct leakage to the outside shall be less than or equal to 4 CFM (12 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.

N1103.3.3.2 Duct leakage to the outside. Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leaks. Duct leakage to the outside shall be less than or equal to 4 CFM (12 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.

N1103.3.3.2 Duct leakage to the outside. Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leaks. Duct leakage to the outside shall be less than or equal to 4 CFM (12 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.

N1103.3.3.2 Duct leakage to the outside. Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leaks. Duct leakage to the outside shall be less than or equal to 4 CFM (12 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.

4. Supply boots or registers and return boxes or grilles shall be taped, plugged, or otherwise sealed air tight or as tight as possible.
5. The hose for measuring the 25 Pascals of pressure differential shall be inserted into the boot of the supply that is nominally closest to the air handler.
6. Open all interconnecting doors in the building, close dampers for fireplaces and other operable dampers.
7. Set up an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door, following the manufacturer's prescribed procedure.
8. Specific instructions from the duct testing equipment manufacturer shall be followed to reach duct test pressure and measure duct air leakage used in combination with a blower door. Typical steps are as follows:

- a. Depressurize the ductwork system to 25 Pa using the measurement hose in Step 5 above.
- b. Depressurize the house to 25 Pa using an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door.
- c. Correct the duct pressure to measure 0 Pa of pressure differential between the house and the ductwork system.
- d. Read the CFM of duct leakage using the procedures for the specific equipment being used. (Note that most automatically calculating pressure gauges cannot compute the CFM25 automatically with a duct-to-house difference in pressure of 0 Pa, so the gauge setting should be set to read CFM instead of CFM25).

Testing shall be performed and reported by the permit holder, a North Carolina licensed general contractor, a North Carolina licensed HVAC contractor, a North Carolina licensed Home Inspector, a registered design professional, a certified BPI Envelope Professional or a certified HRRS rater. A single point depressurization, not temperature corrected, test is sufficient to comply with this provision, provided that the duct testing fan assembly(s) has been certified by the manufacturer to be capable of conducting tests in accordance with ASTM E1554-07.

PFS CORPORATION, including duct leakage information, shall be included on the report and contact information shall be included on the report as required in Section N1101.14.

For the Test Criteria, the report shall provide the following manner: per [Signature] and record the CFM of conditioned Floor Area (CFA) and Multiply CFM25 by 100, divide the result by the CFA and Date: 8/18/21

State: North Carolina
Signature: [Signature]
Title: Staff Plan Reviewer
Date: 8/18/21

MUST BE COMPLETED BY BUILDER ON SITE

record the result. If the result is less than or equal to 5 CFM25/100SF for the "Total duct leakage test" or less than or equal to 4 CFM25/100SF for the "Duct leakage to the outside" test, then the HVAC system air tightness is acceptable.

Complete one duct leakage report for each HVAC system serving the home:

Property Address: _____

Test Performed: Total duct leakage or Duct leakage to the outside (circle one)

HVAC System Number: _____ Describe area of home served: _____

CFM25 Total _____ Conditioned Floor Area (CFA) served by system: _____ s.f.
CFM25 × 100 divided by CFA = _____ CFM25/100SF (e.g. 100 CFM25 × 100/2,000 CFA = 5 CFM25/100SF)

Fan attachment location _____

Company Name _____

Contact Information: _____

Signature of Tester _____
Date _____

Permit Holder, NC Licensed General Contractor, NC Licensed HVAC Contractor,
NC Licensed Home Inspector, Registered Design Professional,
Certified BPI Envelope Professional, or Certified HERS Rater
(circle one)

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Duvall*
Title: Staff Plan Reviewer
Date: 8/18/21

2018 NORTH CAROLINA RESIDENTIAL CODE

E-4D.2
DUCT SEALING, Duct air leakage test
(Section N1103.3.3)
Sample Worksheet for Alternative Residential
Energy Code for Higher Efficiency

N1103.3.3 Duct leakage (Prescriptive) and duct testing (Mandatory). Duct testing and duct leakage shall be verified by compliance with either Section N1103.3.3.1 or N1103.3.3.2. Duct testing shall be performed and reported by the permit holder, a NC licensed general contractor, a NC licensed HVAC contractor, a NC licensed Home Inspector, a registered design professional, a certified BPI Envelope Professional or a certified HERS rater. A single point depressurization, not temperature corrected, test is sufficient to comply with this provision, provided that the duct testing fan assembly(s) has been certified by the manufacturer to be capable of conducting tests in accordance with ASTM E1554-07.

The duct leakage information, including duct leakage test selected and result, tester name, date, and contact information, shall be included on the certificate described in Section N1101.3.

For the Test Criteria, the report shall be produced in the following manner: perform the HVAC system air leakage test and record the CFM25. Calculate the total square feet of conditioned Floor Area (CFA) served by that system. Multiply CFM25 by 100, divide the result by the CFA and record the result. If the result is less than or equal to 4 CFM25/100SF for the "Total duct leakage test or less than or equal to 3 CFM25/100SF for the Duct leakage to the outside" test, then the HVAC system air tightness is acceptable.

Exceptions to testing requirements:

1. Duct systems or portions thereof inside the building thermal envelope shall not be required to be leak tested.
2. Installation of a partial system as part of replacement, renovation or addition does not require a duct leakage test.

1103.3.3.1 Total duct leakage. Total duct leakage less than or equal to 4 CFM (113 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, including the manufacturer's air handler enclosure. During testing:

1. Block, if present, ventilation air duct(s) connected to the conditioning system.
2. The duct air leakage testing equipment shall be attached to the largest return in the system or to the air handler.
3. The filter shall be removed and the air handler power shall be turned off.
4. Supply boots or registers and return boxes or grilles shall be taped, plugged, or otherwise sealed air tight.
5. The hose for measuring the 25 Pascals of pressure differential shall be inserted into the boot of the supply that is nominally closest to the air handler.

6. Specific instructions from the duct testing equipment manufacturer shall be followed to reach duct test pressure and measure duct air leakage.
- 1103.3.3.2 Duct leakage to the outside.** Conduct the test using fan pressurization of distribution system and building at a fixed reference pressure for combined supply and return leak. Duct leakage to the outside shall be less than or equal to 3 CFM (85 L/min) per 100 ft² (9.29 m²) of conditioned floor area served by that system when tested at a pressure differential of 0.1 inches w.g. (25 Pa) across the entire system, relative to the outside, including the manufacturer's air handler enclosure.
- During testing:
1. Block, if present, the ventilation air duct(s) connected to the conditioning system.
 2. The duct air leakage testing equipment shall be attached to the largest return in the system or to the air handler.
 3. The filter shall be removed and the air handler power shall be turned off.
 4. Supply boots or registers and return boxes or grilles shall be taped, plugged, or otherwise sealed air tight or as tight as possible.
 5. The hose for measuring the 25 Pascals of pressure differential shall be inserted into the boot of the supply that is nominally closest to the air handler.
 6. Open all interconnecting doors in the building, close dampers for fireplaces and other operable dampers.
 7. Set up an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door, following the manufacturer's prescribed procedure.
 8. Specific instructions from the duct testing equipment manufacturer shall be followed to reach duct test pressure and measure duct air leakage used in combination with a blower door. Typical steps are as follows:

- a. Depressurize the ductwork system to 25 Pa using the measurement hose in Step 5 above.
- b. Depressurize the house to 25 Pa using an envelope air moving/flow-regulating/flow measurement assembly, such as a blower door.
- c. Correct the duct pressure to measure 0 Pa of pressure differential between the house and the ductwork system.
- d. Read the CFM of duct leakage using the procedure for the manufacturer's equipment being used. (Note that most automatically calculating pressure gauges cannot compute the CFM25 automatically with a duct-to-house difference in pressure of 0 Pa, so the final step, manual set to read

PFS CORPORATION
Approval Limited to Factory Built Potholes Only

State: North Carolina
Signature: Jim D'Amico
Title: Staff Plan Reviewer
Date: 8/18/21

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Permit Holder, NC Licensed General Contractor, NC Licensed HVAC Contractor, NC Licensed Home Inspector, Registered Design Professional, Certified BPI Envelope Professional, or Certified HERs Rater
 (circle one)

Property Address: _____
 HVAC System Number: _____ Describe area of home served: _____
 CFM25 Total _____ Conditioned Floor Area (CFA) served by system: _____ s.f.
 CFM25 x 100 divided by CFA = _____ CFM25/100 SF
 (e.g. 50 CFM25 x 100/2,000 CFA = 2.5 CFM25/100SF)
 Fan attachment location _____
 Company Name _____
 Contact Information: _____

 Signature of Tester _____
 Date _____

Complete one duct leakage report for each HVAC system serving the home:

APPENDIX E

MUST BE COMPLETED BY BUILDER ON SITE

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 North Carolina
 State:
 Signature: *Tom Dussle*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Code can be found at R806.2 in the NC Residential and the IRC

Ventilation in House

874	sq. in.
576	sq. in.
8	pc.

32 ft. of Ridge Vent
 52.05% through Ridge Vent

Soffit Ventilation in house:
 Ridge Ventilation in house:
 Number of Ridge Vents in house:

House Required Ventilation

1106.56	sq. in.
553.28	sq. in.
553.28	sq. in.
7.684444	pc.

30.73778 ft. of Ridge Vent

Required Ventilation for House:
 Inches Required for Soffit Ventilation:
 Inches Required for Ridge Ventilation:
 Number of Ridge Vents Required:

Floor Type: 28 Wide 32 Wide Triple Wide T-Ranch Check if pod

Manufacturer Specifications
 Ridge Vent: 18 sq. in. per ft.
 Soffit Vent: 5.89 sq. in. per ft.

Model Number: 23-3276-16
 Floor Length: 76 ft.
Required Ventilation

PFS CORPORATION
Approval Limited to Factory Built Portion Only




State: North Carolina
Signature: *Jim D'Amico*
Title: Staff Plan Reviewer
Date: 8/18/21

Front Sidelwall	USE PG. 55	71	% of Sheathing
Rear Sidelwall	USE PG. 55	59	% of Sheathing
Right Endwall	USE PG 41	71	% of Sheathing
Left Endwall	USE PG 38	90	% of Sheathing

House meets all applicability limits.
(Calculation sheet referenced to structural package)
USE 26.417 FOR 28 WIDES
USE 32.083 FOR 32 WIDES

a) House Mean Roof Height	20'	Max. Mean Roof Height = 33'-0"
b) Number of Stores	1	Max. Number of Stores = 3
c) House Length	76	Max. Length = 80'-0"
d) House Width	30.3	Min. Width = Mean Roof Height
e) House Aspect Ratio		Min. Ratio = 1:4
f) House Vertical Offset		
g) Floor Diaphragm Aspect Ratio = L / W	2.508251	
h) House Floor Diaphragm Opening Width	0	Max. = 12'-0"
House Floor Diaphragm Opening Length	0	Max. = 12'-0"
i) Max. Shearwall Plan Offset	0	(If wall offset is more than 4'-0", count as 2 different shear walls)
j) Min. Shearwall Segment = h/3.5	2.571429	
k) Wall Height	9	Max. Wall Height = 10'
l) Roof Diaphragm Aspect Ratio	2.508251	Max. Ratio = 4:1
m) Roof Slope	5/12	Min. 0/12 Max. 12/12

07/22/19



- P1 - P3
- P4 - P5
- P6
- P7 - P12
- P13
- P14
- P15
- P16
- P17
- P18
- P19 - P58

- TRUSS HM773855
- UFP TRUSS SHEET (FOR REFERENCE ONLY)
- TRUSS CONNECTIONS
- TRUSS LOAD SUMMARY
- EXTERIOR WALL STUDS
- EXTERIOR WALL HEADER / JACKSTUDS
- MATING WALL STUDS
- MATING WALL HEADER / JACKSTUDS
- PERIMETER BANDS
- FLOOR JOISTS
- CENTER GIRDER
- SHEARWALL CALCULATIONS


SECTION 6

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Job	89373	Truss	HM773855	HINGE MONO	Qty	1	Ply	1	Champion Homes 315 NC
Ref. #	3157316								

Universal Forest Products Inc., Grand Rapids, MI 49525, Weston Gorby 8.030 e Apr 8 2017 Mitek Industries, Inc. Fri Sep 22 13:38:30 2017 Page 1 of 2

Copyright © 2017 Universal Forest Products, Inc. All Rights Reserved



SPACING: 2-0-0	LOADING (psf)	23.1	TCLL	34.7	Plate Grip DOL	1.15	TC	0.90	DEFL.	in (loc)	8-9	>808	240	MT20	197/144
SPACING: 1-4-0	LOADING (psf)	(Ground Snow=30.0)	(Ground Snow=45.0)	Lumber DOL	1.15	BC	0.85	Vert(L)	Horz(CT)	in (loc)	8-9	>442	180	MT18HS	197/144
SPACING: 10.0	TCDL	10.0	TCDL	15.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	in (loc)	8	n/a	n/a		
BCLL	BCLL	0.0	BCLL	0.0	Code IBC2015/TP12014		Matrx-R								
BCLD	BCLD	10.0	BCLD	15.0	IBC2012/TP12007										
Weight: 83 lb	FT = 0%														


LUMBER-
 TOP CHORD 2x4 SP No.1 *Except*
 T2: 2x6 SP No.1 or 2x6 SPF No.2, T3: 2x4 SPF No.2
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.2 *Except*

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-2-10 oc bracing.
 JOINTS 1 Brace at Jt(s): 11, 13

REACTIONS. (lb/size) 2=72/10-3-8 (min. 0-1-8), 8=622/Mechanical, 7=0/Mechanical
 Max Horiz 2=419(LC 9), 7=-62(LC 14)
 Max Uplift 2=-392(LC 9), 8=-497(LC 9)
 Max Grav 2=752(LC 14), 8=733(LC 14)
FORCES. (lb) - Maximum Compression/Maximum Tension
 1-2=0/21, 2-15=-1319/623, 3-15=-1219/625, 3-16=-326/0, 16-17=-322/0, 4-17=-318/0, 4-14=-338/22
 1-2=0/21, 2-15=-111/49, 6-7=-70/57, 8-11=-404/414
 2-10=-960/1108, 9-10=-960/1108, 8-9=-960/1108
 3-10=0/330, 3-13=-973/825, 8-13=-975/815, 5-11=-433/443, 9-13=0/76
REQUIRED FIELD JOINT CONNECTIONS - Maximum Compression (lb)/ Tension (lb)/ Shear (lb)/ Moment (lb-in)
 6=86/55/38/0, 11=433/443/157/0

NOTES-
 1) Dado: 0-2-10 length x 0-0-12 deep dado, 0-2-4 to right edge from joint 4 on the top face.
 2) Wind: ASCE 7-10; Vult=150mph (3-second gust) Vasd=119mph @24in o.c.; TCDL=4.0psf; BCDL=4.0psf; (Alt. 180mph @ 16in o.c.; TCDL=6.0psf; BCDL=6.0psf); h=30ft; Cat. II; Exp C; enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60

WARNING - Verify design parameters and READ NOTES
 Universal Forest Products, Inc. 2801 EAST BELTLINE RD, NE GRAND RAPIDS, MI 49525
 PHONE (616)-364-6161 FAX (616)-365-0060




Job	89373	Truss	HM773855	HINGE MONO	Qty	1	Ply	1	Champion Homes 315 NC
									Ref. #3157316

Universal Forest Products Inc., Grand Rapids, MI 49525, Weston Gorby 8.030 e Apr 8 2017 MITek Industries, Inc. Fri Sep 22 13:38:30 2017 Page 2 of 2

Copyright © 2017 Universal Forest Products, Inc. All Rights Reserved

- 3) TLL: ASCE 7-10; Pg=30.0 psf (ground snow); Ps=23.1 psf (roof snow); Category II; Exp C; Partially Exp.; Ct=1.1
- 4) Root design snow load has been reduced to account for slope.
- 5) Unbalanced snow loads have been considered for this design.
- 6) This truss has been designed for greater or min roof live load of 19.0 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
- 7) All plates are MT20 plates unless otherwise indicated.
- 8) See HINGE PLATE DETAILS for plate placement.
- 9) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
- 10) All additional member connections shall be provided by others for forces as indicated.
- 11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 392 lb uplift at joint 8.
- 13) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TP1 1.
- 14) This truss is designed in accordance with the 2012 IBC Sec 2306.1 and referenced standard ANSI/TP1 1.
- 15) Take precaution to keep the chords in plane, any bending or twisting of the hinge plate must be repaired before the building is put into service.
- 16) The field-installed members are an integral part of the truss design. Retain a design professional to specify final field connections and temporary supports. All field-installed members must be properly fastened prior to applying any loading to the truss. This design anticipates the final set position.
- 17) Based on: HM773854
- 18) Revision: IBC2015/2012 Version



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Jim Duvall*

Title: Staff Plan Reviewer

Date: 8/18/21

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

WARNING - Verify design parameters and READ NOTES
 Universal Forest Products, Inc. 2801 EAST BELTLINE RD, NE GRAND RAPIDS, MI 49525
 PHONE (616)-364-6161 FAX (616)-365-0060



Truss shall not be cut or modified without approval of the truss design engineer. Construction and lifting forces have not been considered. The builder is responsible for lifting methods and system design. Builder responsibilities are defined under TP1. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult BCSI 1-06 from the Wood Truss Council of America and Truss Plate Institute Recommendation available from WTCA, 6300 Enterprise LN, Madison, WI 53719. J:\support\Mittek\suppl templates\trp;pe

Corporate Engineering
 2801 East Beltline, NE Grand Rapids, MI 49525-9736 (616) 364-6161 Fax (616) 365-0060
 SECTION 6/ pp. 3
 ufpi.com

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim D'Amico*
 Title: Staff Plan Reviewer
 Date: 8/18/21



Professional Engineers & Surveyors
 License No. 25801, Expiration Date: 10/30/2025
 By the Board of Professional Engineers & Surveyors
 of the State of Maryland
 I hereby certify that
 these documents were prepared or approved
 by me and that I am duly licensed or registered
 as a Professional Engineer under the laws of Maryland
 License No. 25801, Expiration Date: 10/30/2025

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

Job	89373	HM773855	315	CHAMPION HOMES
		Truss	MFG	Customer

Universal Forest Products




TRUSS CALCULATIONS

CHAMPION HOMES OF NC

TRUSS CONNECTIONS

TRUSS NUMBER : HM773855
 PROJECT NUMBER : 190127
 TRUSS PITCH : 5/12
 TRUSS SPAN : 15'-2"
 UNIT WIDTH : 30'-4"



UPLIFT CONNECTIONS (MWFRS LOADS):

CONDITION "A" - EXTERIOR WALL:	UPLIFT (lbs)	CASE	WIND	CD	1 1/2" x 26ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	16 ga STRAPLE	QTY / END	QTY / END	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
150 / 119 mph	392	CD	1.6	OK	OK	3	4	1 1/2" x 20 ga STRAP	2	4	OK	2	4	SIMPSON H8 TWIST STRAP	4	OK	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
ALTERNATE: (5) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				
ALTERNATE: (1) SIMPSON SDWC15600 SCREW																				
ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION																				
CONDITION "B" - MATING WALL (PER SIDE):	UPLIFT (lbs) / PER SIDE)	CASE	WIND	CD	1 1/2" x 26ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	16 ga STRAPLE	QTY / END	QTY / END	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
130 / 104 mph (ADJUSTED)	497	CD	1.6	NO GOOD	NO GOOD	N/A	N/A	1 1/2" x 20 ga STRAP	2	5	OK	2	5	SIMPSON CS20 STRAP	5	OK	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
ALTERNATE: (6) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (4) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				
ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				
CONDITION "A" - EXTERIOR WALL:	UPLIFT (lbs)	CASE	WIND	CD	1 1/2" x 26ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	16 ga STRAPLE	QTY / END	QTY / END	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
115 / 90 mph (ADJUSTED)	294	CD	1.6	OK	OK	2	3	1 1/2" x 20 ga STRAP	2	3	OK	2	3	SIMPSON H3 TWIST STRAP	3	OK	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				
ALTERNATE: (1) SIMPSON SDWC15600 SCREW																				
ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION																				
CONDITION "B" - MATING WALL (PER SIDE):	UPLIFT (lbs) / PER SIDE)	CASE	WIND	CD	1 1/2" x 26ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	16 ga STRAPLE	QTY / END	QTY / END	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
115 / 90 mph (ADJUSTED)	231	CD	1.6	OK	OK	2	3	1 1/2" x 20 ga STRAP	2	3	OK	2	3	SIMPSON H3 TWIST STRAP	3	OK	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
ALTERNATE: (3) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (2) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				
ALTERNATE: (1) SIMPSON SDWC15600 SCREW																				
ALTERNATE: (2) #10 x 5" WOOD SCREW WITH MINIMUM 2 in PENETRATION																				
CONDITION "B" - MATING WALL (PER SIDE):	UPLIFT (lbs) / PER SIDE)	CASE	WIND	CD	1 1/2" x 26ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAPLE	16 ga STRAPLE	QTY / END	QTY / END	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
292	292	CD	1.6	OK	OK	2	3	1 1/2" x 20 ga STRAP	2	3	OK	2	3	SIMPSON H3 TWIST STRAP	3	OK	QTY / END	QTY / END	CHECK ALT. STRAP	CHECK ALT. STRAP
ALTERNATE: (4) 16 d NAILS TOENAILED THROUGH BC INTO BAND PLUS (3) 16 d NAILS THROUGH SHEATHING INTO BAND AND STUD																				

PFS CORPORATION
 Approval Limited to Factory Built Portion Only


State: North Carolina
 Signature: *Tim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Jim Duvall*
Title: Staff Plan Reviewer
Date: 8/18/21

CONDITION "C" - KNEEWALL TO WEB MEMBER:									
1 1/2" x 26ga STRAP	10 d NAILS	1 1/2" x 20 ga STRAP	10 d NAILS	16 ga STRAP	16 ga STRAP	10 d NAILS	10 d NAILS	16 ga STRAP	10 d NAILS
CD	OK	OK	4	5	OK	2	5	OK	5
QTY / END	CHECK STRAP	QTY / END	CHECK ALT. STRAP	QTY / END	CHECK ALT. STRAP	QTY / END	CHECK ALT. STRAP	QTY / END	CHECK ALT. STRAP
443	TENSION (lbs)	443	TENSION (lbs)	443	TENSION (lbs)	443	TENSION (lbs)	443	TENSION (lbs)
1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE
SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD
157	TENSION (lbs)	157	TENSION (lbs)	157	TENSION (lbs)	157	TENSION (lbs)	157	TENSION (lbs)
1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE
SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD
CONDITION "D" - TOP CHORD FLIP:									
USE (2) 6 d NAILS THROUGH SHEATHING EACH SIDE	USE (2) 16 ga STRAP THROUGH SHEATHING EACH SIDE	USE (2) 16 d NAILS TOENAILLED EACH END PLUS USE 10 d NAILS AT 24 in O.C. THROUGH PLATES							
55	TENSION (lbs)	55	TENSION (lbs)	55	TENSION (lbs)	55	TENSION (lbs)	55	TENSION (lbs)
1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE
SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD
38	TENSION (lbs)	38	TENSION (lbs)	38	TENSION (lbs)	38	TENSION (lbs)	38	TENSION (lbs)
1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE	1.15	CASE
SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD	SNOW	CD

MAXIMUM OF DL + LL + 30 psf GSL & 150 / 119 mph WIND



TRUSS NUMBER : HMT73855
 PROJECT NUMBER : 190127
 TRUSS PITCH : 5/12
 TRUSS SPAN : 15'-2"
 UNIT WIDTH : 30'-4"

TRUSS CONNECTIONS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tom Duncanson*
Title: Staff Plan Reviewer
Date: 8/18/21

LOCATION	1	2	3	4
UPLIFT (0.6) DEAD LOAD	105	103	223	196
150 / 119 mph UPLIFT	196	249	-	-53
130 / 101 mph UPLIFT	147	187	-	-
115 / 90 mph UPLIFT	116	146	-	-

C & C UPLIFT

LOCATION	1	2	3	4
DEAD LOAD	175	171	371	327
LIVE LOAD	201	196	505	500
TOTAL LOAD	376	367	876	827

30 psf GROUND SNOW (MATING WALL LOADS ARE PER SIDE OF LINE)

COMPONENT LOADS (lbs/ft)


TRUSS HM773855, 5/12 PITCH, 15'-2" WIDTH

LOCATION 1 = EXT. WALL HEADER & EXT. WALL STUD
LOCATION 2 = M. WALL HEADER & M. WALL STUD
LOCATION 3 = PERIMETER BAND
LOCATION 4 = CENTER GIRDER
LOCATIONS 3 & 4 MAY BE USED TO GENERATE FOUNDATION LOADS

EXTERIOR WALL DEAD LOAD =	12	psf	x	10	ft	=	120	plf
MATING WALL DEAD LOAD =	8	psf	x	10	ft	=	80	plf
FLOOR DEAD LOAD =	10	psf	x	15.16	ft / 2	=	75.8	plf
FLOOR LIVE LOAD =	40	psf	x	15.16	ft / 2	=	303.2	plf
CEILING DEAD LOAD =	5	psf	x	15.16	ft / 2	=	37.9	plf

COMPONENT LOAD SUMMARY

* CROSS SECTION IS FOR REFERENCE ONLY
 AND MAY NOT REFLECT ACTUAL TRUSS



EXTERIOR WALL STUD TABLES

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Swade*
Title: Staff Plan Reviewer
Date: 8/18/21

CHAMPION HOMES of NC

101/130 mph WIND, 5/12 PITCH, FIELD PRESSURE (27.47 psf)

HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)							
8 ft	2 x 4 SPF STUD GRADE	12	755	0.227	9 ft	2 x 4 SPF STUD GRADE	12	295	0.372	10 ft	2 x 4 SPF STUD GRADE	12	660	0.495							
		16	295	0.303			16	**NG**	16			**NG**	-								
		19.2	295	0.364			19.2	**NG**	19.2			**NG**	-								
	2 x 4 SPF #2	24	**NG**	-		2 x 4 SPF #2	24	**NG**	-		2 x 4 SPF #2	24	**NG**	-	24	**NG**	-				
			12	1565				0.195	12				1035	0.319		12	660	0.495			
			16	1265				0.26	16				740	0.426		16	**NG**	-			
		2 x 4 SYP #2	19.2	1035			0.312	2 x 4 SYP #2	19.2			**NG**	-	2 x 4 SYP #2	19.2	**NG**	-	19.2	**NG**	-	
				24			685					0.39	24			**NG**	-		24	**NG**	-
				12			1395					0.195	12			865	0.319		12	490	0.495
	2 x 4 SYP #2	16	1045	0.26		2 x 4 SYP #2	16	510	0.426		2 x 4 SYP #2	16	**NG**	-	2 x 4 SYP #2	16	**NG**	-			
			19.2	765				0.312	19.2				**NG**	-			19.2	**NG**	-		
			24	320				0.39	24				**NG**	-			24	**NG**	-		
2 x 6 SPF STUD GRADE		12	4790	0.059	2 x 6 SPF STUD GRADE		12	3605	0.096	2 x 6 SPF STUD GRADE		12	2610	0.149		12	1915	0.198			
			16	4180				0.078	16				2940	0.128			16	1340	0.238		
			19.2	3705				0.094	19.2				2420	0.154			19.2	375	0.298		
2 x 6 SPF #2	24	2995	0.117	2 x 6 SPF #2	24	1605	0.192	2 x 6 SPF #2	24	4275	0.128	24	2685	0.255							
		12	7380			0.05	12			5625	0.082		12	4075	0.128						
		16	6810			0.067	16			5055	0.11		16	3720	0.17						
	2 x 6 SYP #2	19.2	6380		0.08	2 x 6 SYP #2	19.2		4625	0.132	2 x 6 SYP #2		19.2	3300	0.204	19.2	2980	0.204			
			24		5770				0.1	24				4010	0.164		24	2685	0.255		
			12		7285				0.05	12				5450	0.082		12	4075	0.128		
2 x 6 SYP #2	16	6635	0.067	2 x 6 SYP #2	16	4815	0.11	2 x 6 SYP #2	16	3455	0.17	16	3455	0.17							
		19.2	6150			0.08	19.2			4330	0.132		19.2	2980	0.204						
		24	5455			0.1	24			3635	0.164		24	2275	0.255						

P:\2019\190284\HMT\738551EXVALLS

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
 EVEN IF RATIO MEETS CODE REQUIREMENTS

190284

BARLOW ENGINEERING, P.C.
 6312 SIX FORKS RD., SUITE 203-B
 RALEIGH, NC 27615
 SECTION 6/ pp. 9

EXTERIOR WALL STUD TABLES



PFS CORPORATION

Approval Limited to Factory Built Portion Only

State:

North Carolina

Signature:

Tim Swade

Title:

Staff Plan Reviewer

Date:

8/18/21

CHAMPION HOMES of NC

101/130 mph WIND, 5/12 PITCH, EDGE PRESSURE (33.35 psf)

HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)				
8 ft	2 x 4 SPF STUD GRADE	12	470	0.276	9 ft	2 x 4 SPF STUD GRADE	12	**NG**	-	10 ft	2 x 4 SPF STUD GRADE	12	**NG**	-				
		16	295	0.368			16	**NG**	-			16	**NG**	-				
		19.2	**NG**	-			19.2	**NG**	-			19.2	**NG**	-				
	2 x 4 SPF #2	24	**NG**	-		2 x 4 SPF #2	24	**NG**	-		2 x 4 SPF #2	24	**NG**	-	2 x 4 SPF #2	24	**NG**	-
		12	1370	0.237			12	845	0.387			12	**NG**	-		12	**NG**	-
		16	1020	0.316			16	**NG**	-			16	**NG**	-		16	**NG**	-
	2 x 4 SYP #2	19.2	735	0.379		2 x 4 SYP #2	19.2	**NG**	-		2 x 4 SYP #2	19.2	**NG**	-	2 x 4 SYP #2	19.2	**NG**	-
		24	**NG**	-			24	**NG**	-			24	**NG**	-		24	**NG**	-
		12	1170	0.237			12	640	0.387			12	**NG**	-		12	**NG**	-
	2 x 4 SYP #2	16	745	0.316		2 x 4 SYP #2	16	**NG**	-		2 x 4 SYP #2	16	**NG**	-	2 x 4 SYP #2	16	**NG**	-
		19.2	385	0.379			19.2	**NG**	-			19.2	**NG**	-		19.2	**NG**	-
		24	**NG**	-			24	**NG**	-			24	**NG**	-		24	**NG**	-
2 x 6 SPF STUD GRADE	2 x 6 SPF STUD GRADE	12	4395	0.071	2 x 6 SPF #2	2 x 6 SPF STUD GRADE	12	3175	0.116	2 x 6 SPF #2	2 x 6 SPF STUD GRADE	12	2160	0.181				
		16	3670	0.095			16	2380	0.155			16	1300	0.241				
		19.2	3095	0.114			19.2	1725	0.186			19.2	530	0.289				
	2 x 6 SPF #2	24	2205	0.142		2 x 6 SPF #2	24	625	0.233		2 x 6 SPF #2	24	295	0.361	2 x 6 SPF #2	24	295	0.361
		12	7005	0.061			12	5250	0.1			12	3915	0.155		12	3915	0.155
		16	6350	0.081			16	4595	0.133			16	3265	0.206		16	3265	0.206
2 x 6 SYP #2	19.2	5855	0.098	2 x 6 SYP #2	19.2	4095	0.16	2 x 6 SYP #2	19.2	2770	0.248	2 x 6 SYP #2	19.2	2770	0.248			
	24	5140	0.122		24	3370	0.2		24	2025	0.31		24	2025	0.31			
	12	6860	0.061		12	5035	0.1		12	3670	0.155		12	3670	0.155			
2 x 6 SYP #2	16	6115	0.081	2 x 6 SYP #2	16	4300	0.133	2 x 6 SYP #2	16	2945	0.206	2 x 6 SYP #2	16	2945	0.206			
	19.2	5555	0.098		19.2	3735	0.16		19.2	2375	0.248		19.2	2375	0.248			
	24	4740	0.122		24	2900	0.2		24	1505	0.31		24	1505	0.31			

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS

EVEN IF RATIO MEETS CODE REQUIREMENTS

EXTERIOR WALL HEADER - 1 STORY (LOCATION 1)

2x3 FOR (1) MEMBER HEADERS
2x4 FOR (2) MEMBER HEADERS
2x6 FOR (3) MEMBER HEADERS

TRUSS HM773855

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

MEMBER	QUANTITY	HEADER	TL (pft)	HEADER	MAXIMUM	SPAN	LIMITED BY	DEFLECTION (in)	MID-SPAN	MIN. NUMBER OF JACKSTUDS REQ'D EACH END	SYP #2	SYP #2	SPF STUD	UPLIFT (pft)	REACTION (lbs)
2x4 SPF #2	1	378	201	2'-10"	LB	4'-0"	0.206	0.075	0.206	2	2	2	2	196	280
1.5x5.5 LVL	1	378	201	6'-2"	LB	6'-2"	0.304	0.1	0.304	2	2	2	2	196	409
2x6 SPF #2	1	378	201	4'-2"	LB	5'-3"	0.088	0.088	0.088	2	2	2	2	196	518
2x8 SPF #2	1	378	201	5'-3"	LB	6'-5"	0.107	0.107	0.107	2	2	2	2	196	633
2x4 SYP #2	1	378	201	2'-7"	LB	7'-5"	0.053	0.108	0.053	1	1	1	2	196	734
2x6 SYP #2	1	378	201	3'-10"	LB	4'-11"	0.066	0.078	0.066	2	2	2	2	196	833
2x8 SYP #2	1	378	201	4'-11"	LB	5'-10"	0.078	0.078	0.078	2	2	2	2	196	877
2x10 SYP #2	1	378	201	5'-10"	LB	7'-1"	0.09	0.074	0.09	2	2	2	2	196	972
1.5x3.5 LVL	1	378	201	4'-0"	LB	4'-0"	0.206	0.206	0.206	2	2	2	2	196	983
1.5x5.5 LVL	1	378	201	6'-2"	LB	6'-2"	0.304	0.304	0.304	2	2	2	2	196	1009
1.5x7.25 LVL	1	378	201	8'-1"	LB	8'-1"	0.387	0.387	0.387	2	2	2	2	196	1077
1.5x9.25 LVL	1	378	201	10'-3"	LB	10'-3"	0.479	0.479	0.479	3	3	3	3	196	1217
1.5x11.25 LVL	1	378	201	12'-4"	LB	12'-4"	0.568	0.568	0.568	3	3	3	3	196	1295
1.5x12 LVL	1	378	201	13'-2"	LB	13'-2"	0.6	0.6	0.6	3	3	3	3	196	1503
1.5x14 LVL	1	378	201	15'-4"	LB	15'-4"	0.687	0.687	0.687	3	3	3	3	196	1711
1.5x16 LVL	1	378	201	17'-5"	LB	17'-5"	0.771	0.771	0.771	3	3	3	3	196	1917
1.5x18 LVL	1	378	201	19'-6"	LB	19'-6"	0.854	0.854	0.854	3	3	3	3	196	2123
1.5x20 LVL	1	378	201	21'-7"	LB	21'-7"	0.936	0.936	0.936	3	3	3	3	196	2328
1.5x22 LVL	1	378	201	23'-7"	LB	23'-7"	1.017	1.017	1.017	3	3	3	3	196	2532
1.5x24 LVL	1	378	201	25'-7"	LB	25'-7"	1.097	1.097	1.097	3	3	3	3	196	2736
2x4 SPF #2	2	378	201	4'-10"	LB	5'-10"	0.177	0.177	0.177	1	1	1	1	196	396
2x6 SPF #2	2	378	201	6'-10"	LB	7'-10"	0.27	0.27	0.27	1	1	1	1	196	578
2x8 SPF #2	2	378	201	7'-5"	LB	8'-5"	0.214	0.214	0.214	1	1	1	1	196	733
2x10 SPF #2	2	378	201	9'-1"	LB	10'-1"	0.215	0.215	0.215	1	1	1	1	196	896
2x12 SPF #2	2	378	201	10'-1"	LB	11'-1"	0.215	0.215	0.215	1	1	1	1	196	1039
2x4 SYP #2	2	378	201	3'-8"	LB	3'-8"	0.106	0.106	0.106	2	2	2	2	196	362
2x6 SYP #2	2	378	201	5'-6"	LB	5'-6"	0.136	0.136	0.136	2	2	2	2	196	542
2x8 SYP #2	2	378	201	7'-0"	LB	7'-0"	0.155	0.155	0.155	2	2	2	2	196	688
2x10 SYP #2	2	378	201	8'-3"	LB	8'-3"	0.148	0.148	0.148	2	2	2	2	196	817
2x12 SYP #2	2	378	201	10'-1"	LB	10'-1"	0.18	0.18	0.18	2	2	2	2	196	993
1.5x3.5 LVL	2	378	201	6'-9"	LB	6'-9"	0.609	0.609	0.609	1	1	1	1	196	556
1.5x5.5 LVL	2	378	201	8'-9"	LB	8'-9"	0.775	0.775	0.775	1	1	1	1	196	861
1.5x7.25 LVL	2	378	201	11'-5"	LB	11'-5"	0.957	0.957	0.957	1	1	1	1	196	1125
1.5x9.25 LVL	2	378	201	14'-6"	LB	14'-6"	1.135	1.135	1.135	1	1	1	1	196	1424
1.5x11.25 LVL	2	378	201	17'-6"	LB	17'-6"	1.373	1.373	1.373	1	1	1	1	196	1831
1.5x12 LVL	2	378	201	18'-8"	LB	18'-8"	1.2	1.2	1.2	2	2	2	2	196	2126
1.5x14 LVL	2	378	201	21'-8"	LB	21'-8"	1.542	1.542	1.542	2	2	2	2	196	2419
1.5x16 LVL	2	378	201	24'-8"	LB	24'-8"	1.708	1.708	1.708	2	2	2	2	196	2711
1.5x18 LVL	2	378	201	27'-7"	LB	27'-7"	1.872	1.872	1.872	2	2	2	2	196	3002
1.5x20 LVL	2	378	201	30'-7"	LB	30'-7"	2.034	2.034	2.034	2	2	2	2	196	3292
1.5x22 LVL	2	378	201	33'-7"	LB	33'-7"	2.194	2.194	2.194	2	2	2	2	196	3581
2x4 SPF #2	3	378	201	4'-11"	LB	4'-11"	0.226	0.226	0.226	1	1	1	1	196	485
2x6 SPF #2	3	378	201	7'-2"	LB	7'-2"	0.265	0.265	0.265	1	1	1	1	196	708
2x8 SPF #2	3	378	201	9'-1"	LB	9'-1"	0.3	0.3	0.3	1	1	1	1	196	898
2x10 SPF #2	3	378	201	11'-2"	LB	11'-2"	0.321	0.321	0.321	1	1	1	1	196	1097
2x12 SPF #2	3	378	201	12'-11"	LB	12'-11"	0.323	0.323	0.323	1	1	1	1	196	1272
2x4 SYP #2	3	378	201	4'-6"	LB	4'-6"	0.159	0.159	0.159	1	1	1	1	196	444
2x6 SYP #2	3	378	201	6'-9"	LB	6'-9"	0.205	0.205	0.205	1	1	1	1	196	664
2x8 SYP #2	3	378	201	8'-7"	LB	8'-7"	0.233	0.233	0.233	1	1	1	1	196	843
2x10 SYP #2	3	378	201	10'-2"	LB	10'-2"	0.222	0.222	0.222	1	1	1	1	196	1000
2x12 SYP #2	3	378	201	12'-4"	LB	12'-4"	0.27	0.27	0.27	1	1	1	1	196	1216
1.5x3.5 LVL	3	378	201	6'-11"	LB	6'-11"	0.617	0.617	0.617	1	1	1	1	196	681
1.5x5.5 LVL	3	378	201	10'-9"	LB	10'-9"	0.913	0.913	0.913	1	1	1	1	196	1054
1.5x7.25 LVL	3	378	201	14'-0"	LB	14'-0"	1.162	1.162	1.162	1	1	1	1	196	1378
1.5x9.25 LVL	3	378	201	17'-9"	LB	17'-9"	1.436	1.436	1.436	1	1	1	1	196	1744
1.5x11.25 LVL	3	378	201	21'-6"	LB	21'-6"	1.703	1.703	1.703	1	1	1	1	196	2107
1.5x12 LVL	3	378	201	22'-10"	LB	22'-10"	1.801	1.801	1.801	1	1	1	1	196	2243
1.5x14 LVL	3	378	201	26'-6"	LB	26'-6"	2.06	2.06	2.06	1	1	1	1	196	2604
1.5x16 LVL	3	378	201	30'-2"	LB	30'-2"	2.313	2.313	2.313	1	1	1	1	196	2963
1.5x18 LVL	3	378	201	33'-10"	LB	33'-10"	2.561	2.561	2.561	1	1	1	1	196	3320
1.5x20 LVL	3	378	201	37'-6"	LB	37'-6"	2.808	2.808	2.808	2	2	2	2	196	3677
1.5x22 LVL	3	378	201	41'-1"	LB	41'-1"	3.052	3.052	3.052	2	2	2	2	196	4032
1.5x24 LVL	3	378	201	44'-9"	LB	44'-9"	3.291	3.291	3.291	2	2	2	2	196	4386

PFS CORPORATION
Approval Limited to Factory Built Portion Only
State: North Carolina
Signature: Jim Diwanke
Title: Staff Plan Reviewer
Date: 8/18/21

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
EVEN IF RATIO MEETS CODE REQUIREMENTS
190284
BARLOW ENGINEERING, P.C.
6512 SIX FORKS RD., SUITE 203-B
RALEIGH, NC 27615
SECTION 6/ pp. 13

MATING WALL STUDS

PFS CORPORATION
 Approval Limited to Factory Built Portion Only

CHAMPION HOMES OF NC

State: North Carolina
Signature: *Tim Swade*
Title: Staff Plan Reviewer

ALL WINDS, ALL PITCHES, LATERAL PRESSURE (5 psf)

HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)	HEIGHT	SIZE	SPACING	LOAD (lbs)	DEF. (in)
8 ft	2 x 3 SPF STUD GRADE	12	610	0.114	9 ft	2 x 3 SPF STUD GRADE	12	435	0.186	10 ft	2 x 3 SPF STUD GRADE	12	310	0.288
		16	540	0.151			16	370	0.248			16	295	0.385
		19.2	490	0.182			19.2	320	0.298			19.2	295	0.461
2 x 3 SPF #2	2 x 3 SPF #2	12	830	0.097	2 x 3 SPF #2	2 x 3 SPF #2	12	615	0.159	2 x 3 SPF #2	2 x 3 SPF #2	12	465	0.247
		16	775	0.13			16	565	0.213			16	415	0.33
		19.2	735	0.156			19.2	525	0.255			19.2	385	0.395
2 x 3 SYP #2	2 x 3 SYP #2	12	800	0.097	2 x 3 SYP #2	2 x 3 SYP #2	12	475	0.319	2 x 3 SYP #2	2 x 3 SYP #2	12	335	0.494
		16	740	0.13			16	585	0.159			16	435	0.247
		19.2	695	0.156			19.2	530	0.213			19.2	385	0.33
2 x 4 SPF STUD GRADE	2 x 4 SPF STUD GRADE	12	1920	0.041	2 x 4 SPF STUD GRADE	2 x 4 SPF STUD GRADE	12	1450	0.068	2 x 4 SPF STUD GRADE	2 x 4 SPF STUD GRADE	12	1110	0.105
		16	1810	0.055			16	1345	0.09			16	1010	0.14
		19.2	1725	0.066			19.2	1265	0.108			19.2	940	0.168
2 x 4 SPF #2	2 x 4 SPF #2	12	2495	0.035	2 x 4 SPF #2	2 x 4 SPF #2	12	1905	0.058	2 x 4 SPF #2	2 x 4 SPF #2	12	1485	0.09
		16	2400	0.047			16	1815	0.077			16	1400	0.12
		19.2	2330	0.057			19.2	1750	0.093			19.2	1340	0.144
2 x 4 SYP #2	2 x 4 SYP #2	12	2230	0.071	2 x 4 SYP #2	2 x 4 SYP #2	12	1660	0.116	2 x 4 SYP #2	2 x 4 SYP #2	12	1255	0.18
		16	2450	0.035			16	1855	0.058			16	1440	0.09
		19.2	2340	0.047			19.2	1755	0.077			19.2	1345	0.12
2 x 6 SPF STUD GRADE	2 x 6 SPF STUD GRADE	12	6495	0.011	2 x 6 SPF STUD GRADE	2 x 6 SPF STUD GRADE	12	5520	0.017	2 x 6 SPF STUD GRADE	2 x 6 SPF STUD GRADE	12	4600	0.027
		16	6345	0.014			16	5340	0.023			16	4405	0.036
		19.2	6230	0.017			19.2	5205	0.028			19.2	4260	0.043
2 x 6 SPF #2	2 x 6 SPF #2	12	9150	0.009	2 x 6 SPF #2	2 x 6 SPF #2	12	7445	0.015	2 x 6 SPF #2	2 x 6 SPF #2	12	6055	0.023
		16	8980	0.012			16	7260	0.02			16	5870	0.031
		19.2	8855	0.015			19.2	7125	0.024			19.2	5735	0.037
2 x 6 SYP #2	2 x 6 SYP #2	12	8670	0.018	2 x 6 SYP #2	2 x 6 SYP #2	12	6935	0.03	2 x 6 SYP #2	2 x 6 SYP #2	12	5545	0.046
		16	9325	0.009			16	7490	0.015			16	6040	0.023
		19.2	8970	0.015			19.2	7125	0.024			19.2	5685	0.037
24	2 x 6 SYP #2	12	8760	0.018	24	2 x 6 SYP #2	12	6910	0.03	24	2 x 6 SYP #2	12	5480	0.046
		16	9125	0.012			16	7280	0.02			16	5835	0.031
19.2	8970	0.015	19.2	7125	0.024	19.2	5685	0.037	19.2	5685	0.037			
24	8760	0.018	24	6910	0.03	24	5480	0.046	24	5480	0.046			

*** LOADS AND QUANTITIES ARE PER SIDE OF MATING WALL

MATING WALL HEADER - 1 STORY (LOCATION 2)

2x3 FOR (1) MEMBER HEADERS
 2x4 FOR (2) MEMBER HEADERS
 2x6 FOR (3) MEMBER HEADERS

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

MEMBER	QUANTITY	HEADER LL (plf)	HEADER TL (plf)	SPAN	LIMITED BY	DEFLECTION (in)	MID-SPAN	MIN. NUMBER OF JACKSTUDS REQ'D EACH END	SYP #2	SYP #2	SFP STUD	UPLIFT (plf)	UPLIFT REACTION (lbs)
2 x 4 SPF #2	1	198	367	2' - 10"	LB	0.078	0.078	1	1	1	249	249	361
2 x 6 SPF #2	1	198	367	4' - 2"	LB	0.091	0.091	2	2	2	249	249	527
2 x 8 SPF #2	1	198	367	5' - 4"	LB	0.103	0.103	2	2	2	249	249	668
2 x 10 SPF #2	1	198	367	6' - 6"	LB	0.111	0.111	2	2	2	249	249	816
2 x 4 SYP #2	1	198	367	2' - 7"	LB	0.055	0.055	1	1	1	249	249	330
2 x 6 SYP #2	1	198	367	3' - 11"	LB	0.07	0.07	2	2	2	249	249	494
2 x 8 SYP #2	1	198	367	5' - 0"	LB	0.08	0.08	2	2	2	249	249	627
2 x 10 SYP #2	1	198	367	5' - 11"	LB	0.076	0.076	2	2	2	249	249	744
2 x 12 SYP #2	1	198	367	7' - 3"	LB	0.093	0.093	2	2	2	249	249	905
1.5 x 3.5 LVL	1	198	367	4' - 0"	LB	0.212	0.212	2	2	2	249	249	507
1.5 x 5.5 LVL	1	198	367	6' - 3"	LB	0.314	0.314	2	2	2	249	249	785
1.5 x 7.25 LVL	1	198	367	8' - 2"	LB	0.399	0.399	2	2	2	249	249	1025
1.5 x 9.25 LVL	1	198	367	10' - 5"	LB	0.493	0.493	2	2	2	249	249	1298
1.5 x 11.25 LVL	1	198	367	12' - 7"	LB	0.585	0.585	3	3	3	249	249	1569
1.5 x 12 LVL	1	198	367	13' - 4"	LB	0.618	0.618	3	3	3	249	249	1670
1.5 x 14 LVL	1	198	367	15' - 6"	LB	0.707	0.707	3	3	3	249	249	1938
1.5 x 16 LVL	1	198	367	17' - 8"	LB	0.794	0.794	3	3	3	249	249	2205
1.5 x 18 LVL	1	198	367	19' - 10"	LB	0.879	0.879	3	3	3	249	249	2471
1.5 x 20 LVL	1	198	367	21' - 11"	LB	0.964	0.964	3	3	3	249	249	2737
1.5 x 22 LVL	1	198	367	24' - 1"	LB	1.048	1.048	3	3	3	249	249	3001
1.5 x 24 LVL	1	198	367	26' - 2"	LB	1.13	1.13	3	3	3	249	249	3265
2 x 4 SPF #2	2	198	367	4' - 1"	LB	0.155	0.155	1	1	1	249	249	510
2 x 6 SPF #2	2	198	367	5' - 11"	LB	0.182	0.182	1	1	1	249	249	745
2 x 8 SPF #2	2	198	367	7' - 7"	LB	0.206	0.206	1	1	1	249	249	945
2 x 10 SPF #2	2	198	367	9' - 3"	LB	0.221	0.221	1	1	1	249	249	1155
2 x 12 SPF #2	2	198	367	10' - 9"	LB	0.222	0.222	2	2	2	249	249	1339
2 x 4 SYP #2	2	198	367	3' - 9"	LB	0.109	0.109	1	1	1	249	249	467
2 x 6 SYP #2	2	198	367	5' - 7"	LB	0.141	0.141	1	1	1	249	249	699
2 x 8 SYP #2	2	198	367	7' - 1"	LB	0.16	0.16	1	1	1	249	249	887
2 x 10 SYP #2	2	198	367	8' - 5"	LB	0.152	0.152	1	1	1	249	249	1053
2 x 12 SYP #2	2	198	367	10' - 3"	LB	0.185	0.185	1	1	1	249	249	1280
1.5 x 3.5 LVL	2	198	367	5' - 9"	LB	0.423	0.423	1	1	1	249	249	717
1.5 x 5.5 LVL	2	198	367	8' - 10"	LB	0.627	0.627	1	1	1	249	249	1110
1.5 x 7.25 LVL	2	198	367	11' - 7"	LB	0.798	0.798	2	2	2	249	249	1450
1.5 x 9.25 LVL	2	198	367	14' - 8"	LB	0.986	0.986	2	2	2	249	249	1836
1.5 x 11.25 LVL	2	198	367	17' - 9"	LB	1.169	1.169	2	2	2	249	249	2218
1.5 x 12 LVL	2	198	367	18' - 11"	LB	1.236	1.236	2	2	2	249	249	2361
1.5 x 14 LVL	2	198	367	22' - 0"	LB	1.474	1.474	3	3	3	249	249	2741
1.5 x 16 LVL	2	198	367	25' - 0"	LB	1.588	1.588	3	3	3	249	249	3119
1.5 x 18 LVL	2	198	367	28' - 0"	LB	1.759	1.759	3	3	3	249	249	3495
1.5 x 20 LVL	2	198	367	31' - 1"	LB	1.928	1.928	3	3	3	249	249	3870
1.5 x 22 LVL	2	198	367	34' - 1"	LB	2.095	2.095	3	3	3	249	249	4245
1.5 x 24 LVL	2	198	367	37' - 1"	LB	2.26	2.26	3	3	3	249	249	4617
2 x 4 SPF #2	3	198	367	5' - 0"	LB	0.273	0.273	1	1	1	249	249	625
2 x 6 SPF #2	3	198	367	7' - 3"	LB	0.309	0.309	1	1	1	249	249	913
2 x 8 SPF #2	3	198	367	9' - 3"	LB	0.331	0.331	1	1	1	249	249	1158
2 x 10 SPF #2	3	198	367	11' - 4"	LB	0.333	0.333	1	1	1	249	249	1414
2 x 12 SPF #2	3	198	367	13' - 2"	LB	0.333	0.333	1	1	1	249	249	1640
2 x 4 SYP #2	3	198	367	4' - 7"	LB	0.164	0.164	1	1	1	249	249	572
2 x 6 SYP #2	3	198	367	6' - 10"	LB	0.211	0.211	1	1	1	249	249	856
2 x 8 SYP #2	3	198	367	8' - 8"	LB	0.24	0.24	1	1	1	249	249	1087
2 x 10 SYP #2	3	198	367	10' - 4"	LB	0.229	0.229	1	1	1	249	249	1289
2 x 12 SYP #2	3	198	367	12' - 7"	LB	0.278	0.278	1	1	1	249	249	1568
1.5 x 3.5 LVL	3	198	367	7' - 0"	LB	0.635	0.635	1	1	1	249	249	878
1.5 x 5.5 LVL	3	198	367	10' - 11"	LB	0.941	0.941	1	1	1	249	249	1359
1.5 x 7.25 LVL	3	198	367	14' - 3"	LB	1.197	1.197	1	1	1	249	249	1776
1.5 x 9.25 LVL	3	198	367	18' - 0"	LB	1.479	1.479	1	1	1	249	249	2248
1.5 x 11.25 LVL	3	198	367	21' - 9"	LB	1.754	1.754	1	1	1	249	249	2717
1.5 x 12 LVL	3	198	367	23' - 2"	LB	1.855	1.855	1	1	1	249	249	2892
1.5 x 14 LVL	3	198	367	26' - 11"	LB	2.121	2.121	1	1	1	249	249	3357
1.5 x 16 LVL	3	198	367	30' - 8"	LB	2.382	2.382	1	1	1	249	249	3820
1.5 x 18 LVL	3	198	367	34' - 4"	LB	2.638	2.638	1	1	1	249	249	4281
1.5 x 20 LVL	3	198	367	38' - 0"	LB	2.892	2.892	2	2	2	249	249	4740
1.5 x 22 LVL	3	198	367	41' - 9"	LB	3.143	3.143	2	2	2	249	249	5198
1.5 x 24 LVL	3	198	367	45' - 5"	LB	3.39	3.39	2	2	2	249	249	5655

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: Jim B...
 Title: Staff Plan Reviewer
 Date: 8/18/21

***LOADS AND QUANTITIES ARE PER SIDE OF MATING LINE

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS

EVEN IF RATIO MEETS CODE REQUIREMENTS

190284

PERIMETER BAND - 1 STORY (LOCATION 3)

TRUSS HM773855

5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD

MEMBER	QUANTITY	HEADER LT (plf)	HEADER TL (plf)	MAXIMUM SPAN	LIMITED BY	MID-SPAN DEFLECTION (in)	UPLIFT (plf)	REACTION (lbs)
2 x 8 SPF #2	1	505	878	3'-5"	Lb	0.043	0	0
2 x 10 SPF #2	1	505	878	4'-2"	Lb	0.046	0	0
2 x 12 SPF #2	1	505	878	4'-11"	Lb	0.046	0	0
2 x 8 SYP #2	1	505	878	3'-3"	Lb	0.033	0	0
2 x 10 SYP #2	1	505	878	3'-10"	Lb	0.032	0	0
2 x 12 SYP #2	1	505	878	4'-8"	Lb	0.039	0	0
1.5 x 7.25 LVL	1	505	878	5'-3"	Lb	0.167	0	0
1.5 x 9.25 LVL	1	505	878	6'-8"	Lb	0.206	0	0
1.5 x 11.25 LVL	1	505	878	8'-1"	Lb	0.244	0	0
2 x 8 SPF #2	2	505	878	4'-10"	Lb	0.086	0	0
2 x 10 SPF #2	2	505	878	5'-11"	Lb	0.092	0	0
2 x 12 SPF #2	2	505	878	6'-11"	Lb	0.093	0	0
2 x 8 SYP #2	2	505	878	4'-7"	Lb	0.067	0	0
2 x 10 SYP #2	2	505	878	5'-5"	Lb	0.064	0	0
2 x 12 SYP #2	2	505	878	6'-7"	Lb	0.077	0	0
1.5 x 7.25 LVL	2	505	878	7'-6"	Lb	0.333	0	0
1.5 x 9.25 LVL	2	505	878	9'-6"	Lb	0.412	0	0
1.5 x 11.25 LVL	2	505	878	11'-6"	Lb	0.489	0	0
2 x 8 SPF #2	3	505	878	6'-0"	Lb	0.129	0	0
2 x 10 SPF #2	3	505	878	7'-4"	Lb	0.138	0	0
2 x 12 SPF #2	3	505	878	8'-6"	Lb	0.139	0	0
2 x 8 SYP #2	3	505	878	5'-7"	Lb	0.1	0	0
2 x 10 SYP #2	3	505	878	6'-8"	Lb	0.096	0	0
2 x 12 SYP #2	3	505	878	8'-1"	Lb	0.116	0	0
1.5 x 7.25 LVL	3	505	878	9'-2"	Lb	0.5	0	0
1.5 x 9.25 LVL	3	505	878	11'-8"	Lb	0.618	0	0
1.5 x 11.25 LVL	3	505	878	14'-1"	Lb	0.733	0	0

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Duncanson*
Title: Staff Plan Reviewer
Date: 8/18/21

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
EVEN IF RATIO MEETS CODE REQUIREMENTS
190284
SECTION 6/ pp. 16
RALEIGH, NC 27615
6512 SIX FORKS RD., SUITE 203-B
BARROW ENGINEERING, P.C.

**CENTER GIRDER - 1 STORY (LOCATION 4)
TRUSS HM778355
5/12 PITCH, 30.33 ft UNIT WIDTH, 30 psf GROUND SNOW LOAD**

MEMBER	QUANTITY	HEADER LL (plf)	HEADER TL (plf)	MAXIMUM SPAN	LIMITED BY	MID-SPAN DEFLECTION (in)	UPLIFT (plf)	REACTION (lbs)
2 x 8 SPF #2	1	500	827	3'-6"	Lb	0.046	53	95
2 x 10 SPF #2	1	500	827	4'-4"	Lb	0.049	53	116
2 x 12 SPF #2	1	500	827	5'-0"	Lb	0.049	53	134
2 x 8 SYP #2	1	500	827	3'-4"	Lb	0.035	53	89
2 x 10 SYP #2	1	500	827	3'-11"	Lb	0.034	53	106
2 x 12 SYP #2	1	500	827	4'-10"	Lb	0.041	53	128
1.5 x 7.25 LVL	1	500	827	5'-5"	Lb	0.177	53	145
1.5 x 9.25 LVL	1	500	827	6'-11"	Lb	0.219	53	184
1.5 x 11.25 LVL	1	500	827	8'-4"	Lb	0.259	53	222
2 x 8 SPF #2	2	500	827	5'-0"	Lb	0.091	53	134
2 x 10 SPF #2	2	500	827	6'-2"	Lb	0.098	53	164
2 x 12 SPF #2	2	500	827	7'-1"	Lb	0.098	53	190
2 x 8 SYP #2	2	500	827	4'-8"	Lb	0.071	53	126
2 x 10 SYP #2	2	500	827	5'-7"	Lb	0.068	53	149
2 x 12 SYP #2	2	500	827	6'-10"	Lb	0.082	53	182
1.5 x 7.25 LVL	2	500	827	7'-9"	Lb	0.354	53	206
1.5 x 9.25 LVL	2	500	827	9'-9"	Lb	0.438	53	260
1.5 x 11.25 LVL	2	500	827	11'-10"	Lb	0.519	53	315
2 x 8 SPF #2	3	500	827	6'-2"	Lb	0.137	53	164
2 x 10 SPF #2	3	500	827	7'-6"	Lb	0.147	53	201
2 x 12 SPF #2	3	500	827	8'-9"	Lb	0.148	53	233
2 x 8 SYP #2	3	500	827	5'-9"	Lb	0.106	53	154
2 x 10 SYP #2	3	500	827	6'-10"	Lb	0.101	53	183
2 x 12 SYP #2	3	500	827	8'-4"	Lb	0.123	53	222
1.5 x 7.25 LVL	3	500	827	9'-6"	Lb	0.531	53	252
1.5 x 9.25 LVL	3	500	827	12'-0"	Lb	0.656	53	319
1.5 x 11.25 LVL	3	500	827	14'-6"	Lb	0.778	53	385


*** LOADS AND QUANTITIES ARE PER SIDE OF MATING LINE

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tom Dwork*
Title: Staff Plan Reviewer
Date: 8/18/21

THE DESIGNER IS TO DETERMINE IF ACTUAL DEFLECTION IS WITHIN ACCEPTABLE LIMITS
EVEN IF RATIO MEETS CODE REQUIREMENTS
190284
SECTION 6/ pp. 18
RALEIGH, NC 27615
6512 SIX FORKS RD., SUITE 203-B
BAYVIEW ENGINEERING, P.C.

DESIGN INFORMATION:		MEETS LIMITATIONS OF WFCM:		WIND:		EXPOSURE:		WALL HEIGHT:		FLOOR DEAD LOAD (FDL):		WALL DEAD LOAD (WDL):		ROOF & CEILING ASSEMBLY DEAD LOAD =	
TRUSS BOTTOM CHORD TO TOP PLATE CONNECTION:		V _{max} =		1605		18		18		1873		16		15	
AT 30 ft SIDEWALL LENGTH:		SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		72		72		72		72		72		72	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 35 ft SIDEWALL LENGTH:		17		17		17		17		17		17	
AT 30 ft SIDEWALL LENGTH:		OR SPACING OF (1) SIMPSON LTP4 PLATE		2013		2013		2013		2013		2013		2013	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 35 ft SIDEWALL LENGTH:		15		15		15		15		15		15	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 40 ft SIDEWALL LENGTH:		2140		2140		2140		2140		2140		2140	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 40 ft SIDEWALL LENGTH:		14		14		14		14		14		14	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 45 ft SIDEWALL LENGTH:		2408		2408		2408		2408		2408		2408	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 45 ft SIDEWALL LENGTH:		12		12		12		12		12		12	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 50 ft SIDEWALL LENGTH:		2675		2675		2675		2675		2675		2675	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 50 ft SIDEWALL LENGTH:		11		11		11		11		11		11	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 55 ft SIDEWALL LENGTH:		2943		2943		2943		2943		2943		2943	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 55 ft SIDEWALL LENGTH:		10		10		10		10		10		10	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 60 ft SIDEWALL LENGTH:		3210		3210		3210		3210		3210		3210	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 60 ft SIDEWALL LENGTH:		9		9		9		9		9		9	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 65 ft SIDEWALL LENGTH:		3478		3478		3478		3478		3478		3478	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 65 ft SIDEWALL LENGTH:		8		8		8		8		8		8	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 70 ft SIDEWALL LENGTH:		3745		3745		3745		3745		3745		3745	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 70 ft SIDEWALL LENGTH:		8		8		8		8		8		8	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 75 ft SIDEWALL LENGTH:		4013		4013		4013		4013		4013		4013	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 75 ft SIDEWALL LENGTH:		7		7		7		7		7		7	
OR SPACING OF (1) SIMPSON LTP4 PLATE		AT 80 ft SIDEWALL LENGTH:		4280		4280		4280		4280		4280		4280	
SPACING OF 0.131" x 2.5" COMMON NAIL (TOENAIL):		AT 80 ft SIDEWALL LENGTH:		7		7		7		7		7		7	
OR SPACING OF (1) SIMPSON LTP4 PLATE		4600		4600		4600		4600		4600		4600		4600	
6		6		6		6		6		6		6		6	
45		45		45		45		45		45		45		45	
lbs AT 30 ft LENGTH		2265		1725		1725		1725		1725		1725		1725	
lbs AT 35 ft LENGTH		2643		2013		2013		2013		2013		2013		2013	
lbs AT 40 ft LENGTH		3020		2300		2300		2300		2300		2300		2300	
lbs AT 45 ft LENGTH		3398		2588		2588		2588		2588		2588		2588	
lbs AT 50 ft LENGTH		3775		2875		2875		2875		2875		2875		2875	
lbs AT 55 ft LENGTH		4153		3163		3163		3163		3163		3163		3163	
lbs AT 60 ft LENGTH		4530		3450		3450		3450		3450		3450		3450	
lbs AT 65 ft LENGTH		4908		3738		3738		3738		3738		3738		3738	
lbs AT 70 ft LENGTH		5285		4025		4025		4025		4025		4025		4025	
lbs AT 75 ft LENGTH		5663		4313		4313		4313		4313		4313		4313	
lbs AT 80 ft LENGTH		6040		4600		4600		4600		4600		4600		4600	
mpH		YES		YES		YES		YES		YES		YES		YES	
ft		150		130		130		130		130		130		130	
psf		9		9		9		9		9		9		9	
psf		10		10		10		10		10		10		10	
psf		12		12		12		12		12		12		12	
psf		15		15		15		15		15		15		15	
5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH	



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Tim D'Amico*

Title: Staff Plan Reviewer

Date: 8/18/21



PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: **North Carolina**

Signature: *Tim Duerle*

Title: **Staff Plan Reviewer**

Date: **8/18/21**

DESIGN INFORMATION:		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH		5/12 PITCH, 30.33 ft WIDTH	
MEETS LIMITATIONS OF WFCM:	YES	YES	YES	YES	YES	YES	YES
WIND:	115	130	130	130	130	130	130
EXPOSURE:	C	C	C	C	C	C	C
WALL HEIGHT:	9	9	9	9	9	9	9
FLOOR DEAD LOAD (FDL):	10	10	10	10	10	10	10
WALL DEAD LOAD (WDL):	12	12	12	12	12	12	12
ROOF & CEILING ASSEMBLY DEAD LOAD =	15	15	15	15	15	15	15
SILL PLATE TO FOUNDATION CONNECTION: V _{max} =							
SPACING OF 1/2" ANCHOR BOLTS, AT 30 ft LENGTH:	3878	4617	4617	4617	4617	4617	4617
SPACING OF 5/8" ANCHOR BOLTS, AT 35 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 1/2" ANCHOR BOLTS, AT 35 ft LENGTH:	4525	5387	5387	5387	5387	5387	5387
SPACING OF 1/2" ANCHOR BOLTS, AT 40 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 5/8" ANCHOR BOLTS, AT 40 ft LENGTH:	5170	6155	6155	6155	6155	6155	6155
SPACING OF 1/2" ANCHOR BOLTS, AT 45 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 5/8" ANCHOR BOLTS, AT 45 ft LENGTH:	5817	6925	6925	6925	6925	6925	6925
SPACING OF 1/2" ANCHOR BOLTS, AT 50 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 5/8" ANCHOR BOLTS, AT 50 ft LENGTH:	6463	7694	7694	7694	7694	7694	7694
SPACING OF 1/2" ANCHOR BOLTS, AT 55 ft LENGTH:	7110	8464	8464	8464	8464	8464	8464
SPACING OF 5/8" ANCHOR BOLTS, AT 55 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 1/2" ANCHOR BOLTS, AT 60 ft LENGTH:	7755	9233	9233	9233	9233	9233	9233
SPACING OF 5/8" ANCHOR BOLTS, AT 60 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 1/2" ANCHOR BOLTS, AT 65 ft LENGTH:	8402	10003	10003	10003	10003	10003	10003
SPACING OF 5/8" ANCHOR BOLTS, AT 65 ft LENGTH:	67	67	67	67	67	67	67
SPACING OF 1/2" ANCHOR BOLTS, AT 70 ft LENGTH:	9048	10772	10772	10772	10772	10772	10772
SPACING OF 5/8" ANCHOR BOLTS, AT 70 ft LENGTH:	67	67	67	67	67	67	67
SPACING OF 1/2" ANCHOR BOLTS, AT 75 ft LENGTH:	9695	11542	11542	11542	11542	11542	11542
SPACING OF 5/8" ANCHOR BOLTS, AT 75 ft LENGTH:	56	56	56	56	56	56	56
SPACING OF 1/2" ANCHOR BOLTS, AT 80 ft LENGTH:	10340	12310	12310	12310	12310	12310	12310
SPACING OF 5/8" ANCHOR BOLTS, AT 80 ft LENGTH:	56	48	48	48	48	48	48
SPACING OF 1/2" ANCHOR BOLTS, AT 85 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 85 ft LENGTH:	33	33	33	33	33	33	33
SPACING OF 1/2" ANCHOR BOLTS, AT 90 ft LENGTH:	6113	6113	6113	6113	6113	6113	6113
SPACING OF 5/8" ANCHOR BOLTS, AT 90 ft LENGTH:	67	67	67	67	67	67	67
SPACING OF 1/2" ANCHOR BOLTS, AT 95 ft LENGTH:	7132	7132	7132	7132	7132	7132	7132
SPACING OF 5/8" ANCHOR BOLTS, AT 95 ft LENGTH:	56	56	56	56	56	56	56
SPACING OF 1/2" ANCHOR BOLTS, AT 100 ft LENGTH:	72	72	72	72	72	72	72
SPACING OF 5/8" ANCHOR BOLTS, AT 100 ft LENGTH:	8150	8150	8150	8150	8150	8150	8150
SPACING OF 1/2" ANCHOR BOLTS, AT 105 ft LENGTH:	48	48	48	48	48	48	48
SPACING OF 5/8" ANCHOR BOLTS, AT 105 ft LENGTH:	9170	9170	9170	9170	9170	9170	9170
SPACING OF 1/2" ANCHOR BOLTS, AT 110 ft LENGTH:	56	56	56	56	56	56	56
SPACING OF 5/8" ANCHOR BOLTS, AT 110 ft LENGTH:	10198	10198	10198	10198	10198	10198	10198
SPACING OF 1/2" ANCHOR BOLTS, AT 115 ft LENGTH:	37	37	37	37	37	37	37
SPACING OF 5/8" ANCHOR BOLTS, AT 115 ft LENGTH:	56	56	56	56	56	56	56
SPACING OF 1/2" ANCHOR BOLTS, AT 120 ft LENGTH:	11207	11207	11207	11207	11207	11207	11207
SPACING OF 5/8" ANCHOR BOLTS, AT 120 ft LENGTH:	33	33	33	33	33	33	33
SPACING OF 1/2" ANCHOR BOLTS, AT 125 ft LENGTH:	12225	12225	12225	12225	12225	12225	12225
SPACING OF 5/8" ANCHOR BOLTS, AT 125 ft LENGTH:	48	48	48	48	48	48	48
SPACING OF 1/2" ANCHOR BOLTS, AT 130 ft LENGTH:	12225	12225	12225	12225	12225	12225	12225
SPACING OF 5/8" ANCHOR BOLTS, AT 130 ft LENGTH:	30	30	30	30	30	30	30
SPACING OF 1/2" ANCHOR BOLTS, AT 135 ft LENGTH:	13245	13245	13245	13245	13245	13245	13245
SPACING OF 5/8" ANCHOR BOLTS, AT 135 ft LENGTH:	42	42	42	42	42	42	42
SPACING OF 1/2" ANCHOR BOLTS, AT 140 ft LENGTH:	14263	14263	14263	14263	14263	14263	14263
SPACING OF 5/8" ANCHOR BOLTS, AT 140 ft LENGTH:	28	28	28	28	28	28	28
SPACING OF 1/2" ANCHOR BOLTS, AT 145 ft LENGTH:	14263	14263	14263	14263	14263	14263	14263
SPACING OF 5/8" ANCHOR BOLTS, AT 145 ft LENGTH:	26	26	26	26	26	26	26
SPACING OF 1/2" ANCHOR BOLTS, AT 150 ft LENGTH:	15282	15282	15282	15282	15282	15282	15282
SPACING OF 5/8" ANCHOR BOLTS, AT 150 ft LENGTH:	24	24	24	24	24	24	24
SPACING OF 1/2" ANCHOR BOLTS, AT 155 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 155 ft LENGTH:	22	22	22	22	22	22	22
SPACING OF 1/2" ANCHOR BOLTS, AT 160 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 160 ft LENGTH:	33	33	33	33	33	33	33
SPACING OF 1/2" ANCHOR BOLTS, AT 165 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 165 ft LENGTH:	22	22	22	22	22	22	22
SPACING OF 1/2" ANCHOR BOLTS, AT 170 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 170 ft LENGTH:	33	33	33	33	33	33	33
SPACING OF 1/2" ANCHOR BOLTS, AT 175 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 175 ft LENGTH:	22	22	22	22	22	22	22
SPACING OF 1/2" ANCHOR BOLTS, AT 180 ft LENGTH:	16300	16300	16300	16300	16300	16300	16300
SPACING OF 5/8" ANCHOR BOLTS, AT 180 ft LENGTH:	33	33	33	33	33	33	33

DESIGN INFORMATION:	MEETS LIMITATIONS OF WFCM:	WIND:	115	5/12 PITCH, 30.33 ft WIDTH
WALL HEIGHT: FLOOR DEAD LOAD (FDL): WALL DEAD LOAD (WDL): ROOF & CEILING ASSEMBLY DEAD LOAD =	YES 115 10 12 15	C 9 10 12 15	115 10 12 15	5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH
FIRST FLOOR CORNER HOLDDOWN CORNER STUD CONNECTION: ENDWALL:	YES 1873 2013 2300 2588 2875 3163 3450 3738 4025 4313 4600	C 9 10 12 15	1873 2013 2300 2588 2875 3163 3450 3738 4025 4313 4600	5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH
SHEARWALL REACTION (Rend): DEAD LOAD REACTION (DL): SHEARWALL REACTION (Rend): DEAD LOAD REACTION (DL):	1605 1873 2140 2408 2675 2943 3210 3478 3745 4013 4280 4548	C 9 10 12 15	1605 1873 2140 2408 2675 2943 3210 3478 3745 4013 4280 4548	5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH
AT 30 ft SIDEWALL LENGTH: AT 35 ft SIDEWALL LENGTH: AT 40 ft SIDEWALL LENGTH: AT 45 ft SIDEWALL LENGTH: AT 50 ft SIDEWALL LENGTH: AT 55 ft SIDEWALL LENGTH: AT 60 ft SIDEWALL LENGTH: AT 65 ft SIDEWALL LENGTH: AT 70 ft SIDEWALL LENGTH: AT 75 ft SIDEWALL LENGTH: AT 80 ft SIDEWALL LENGTH:	1996 2328 2661 2993 3326 3659 3991 4324 4656 4989 5322	C 9 10 12 15	1996 2328 2661 2993 3326 3659 3991 4324 4656 4989 5322	5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH 5/12 PITCH, 30.33 ft WIDTH

PFS CORPORATION
Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Tim Duvall*

Title: Staff Plan Reviewer

Date: 8/18/21



Load Short For...

Entire House

AMS Of Indiana, In



PFS CORPORATION

Approval Limited to Factory Built Portion Only

Job: 23-3276-16 061720

Date: 8/5/21

By: AMS of Indiana, Inc.

North Carolina

Signature: *Jim D... [Signature]*

Title: Staff Plan Reviewer

8/18/21

Project Information

3933 East Jackson Blvd., Elkhart, IN 46516

For: Champion Home Builders
Lillington, NC

Design Information

Outside db (°F)	10	Method	Infiltration
Inside db (°F)	70	Construction quality	
Design TD (°F)	61	Fireplaces	
Daily range	-		
Inside humidity (%)	50		
Moisture difference (gr/lb)	49		

HEATING EQUIPMENT

COOLING EQUIPMENT

Make	Generic	Make	Generic
Trade		Trade	
Model	AFUE 100	Cond	SEER 14.0
AHRI ref		Coil	
Efficiency	100 AFUE	AHRI ref	
Heating input	11.6 kW	Efficiency	12.2 EER, 14 SEER
Heating output	39658 Btuh	Sensible cooling	23454 Btuh
Temperature rise	31 °F	Latent cooling	10052 Btuh
Actual air flow	1191 cfm	Total cooling	33505 Btuh
Air flow factor	0.034 cfm/Btuh	Actual air flow	1191 cfm
Static pressure	0.50 in H2O	Air flow factor	0.056 cfm/Btuh
Space thermostat		Static pressure	0.50 in H2O
		Load sensible heat ratio	0.75

ROOM NAME	Area (ft²)	Htg load (Btuh)	Cig load (Btuh)	Htg AVF (cfm)	Cig AVF (cfm)
B4	158	3788	1953	130	108
C4	49	0	0	0	0
BA3	45	691	292	24	16
DEN	154	3744	2635	128	146
H	126	0	0	0	0
DRKLT	476	5961	3842	204	213
U	140	3266	1251	112	69
BA1	138	2942	1154	101	64
LR	324	4417	3247	151	180
B2	160	2086	1678	71	93
BA2	48	742	271	25	15
B3	160	3282	1946	112	108
C1	70	837	311	29	17
B1	244	3083	2878	105	160

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



Right-Suite@ Universal 2021 21.0.03 RSU02009

...llington NC 02323-3276-16 061720(MOD-floor).rup Calc = MJ8 Front Door faces: W



Calculations approved by ACGA to meet all requirements of Manual J 8th Ed.

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Jim Duvall*
 Title: Staff Plan Reviewer
 Date: 8/18/21

1191	1191	21456	34839	2291	2291	Entire House
1191	1191	1697	4819			Other equip loads
		23453				Equip. @ 1.01 RSM
		7801				Latent cooling
1191	1191	31254	39658	2291	2291	TOTALS

Job: 23-3276-16 061720
 Date: 8/5/21
 By: AMS of Indiana, Inc.

Project Summary
Entire House
 AMS Of Indiana, Inc.



3933 East Jackson Blvd., Elkhart, IN 46516

PFS CORPORATION		Project Information	
Approval Limited to Factory Built Portion Only		For:	Champion Home Builders Lillington, NC
State:	North Carolina	Notes:	
Signature:	<i>Tom Duvall</i>		
Title:	Staff Plan Reviewer		
Date:	8/18/21		

Summer Design Conditions

Outside db	96 °F
Inside db	75 °F
Design TD	21 °F
Daily range	M
Relative humidity	50 %
Moisture difference	51 gr/lb

Sensible Cooling Equipment Load Sizing

Structure	19861 Btuh
Ducts	1594 Btuh
Central vent (75 cfm)	1697 Btuh
Outside air	0 Btuh
Blower	0 Btuh
Use manufacturer's data	1.01 n
Rate/swing multiplier	23453 Btuh
Equipment sensible load	23453 Btuh

Latent Cooling Equipment Load Sizing

Structure	3259 Btuh
Ducts	2006 Btuh
Central vent (75 cfm)	2536 Btuh
Outside air	7801 Btuh
Equipment latent load	7801 Btuh
Equipment Total Load (Sen+Lat)	31254 Btuh
Req. total capacity at 0.70 SHR	2.8 ton

Cooling Equipment Summary

Make	Generic
Trade	Generic
Cond	SEER 14.0
AHRI ref	
Efficiency	12.2 EER, 14 SEER
Sensible cooling	23454 Btuh
Latent cooling	10052 Btuh
Total cooling	33505 Btuh
Actual air flow	1191 cfm
Air flow factor	0.056 cfm/Btuh
Static pressure	0.50 in H2O
Load sensible heat ratio	0.75

Winter Design Conditions

Outside db	10 °F
Inside db	70 °F
Design TD	61 °F

Heating Summary

Structure	31459 Btuh
Ducts	3380 Btuh
Central vent (75 cfm)	4819 Btuh
Outside air	0 Btuh
Humidification	0 Btuh
Piping	0 Btuh
Equipment load	39658 Btuh

Infiltration

Method	Simplified
Construction quality	1 (Average)
Area (ft ²)	2291
Volume (ft ³)	20623
Air changes/hour	0.38
Equip. AVF (cfm)	130

Heating Equipment Summary


Make	Generic
Trade	Generic
Model	AFUE 100
AHRI ref	
Efficiency	100 AFUE
Heating input	11.6 kW
Heating output	39658 Btuh
Temperature rise	31 °F
Actual air flow	1191 cfm
Air flow factor	0.034 cfm/Btuh
Static pressure	0.50 in H2O
Space thermostat	

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

Job #: 23-3276-16 061720
 Performed by AMS of Indiana, Inc. for:
 Champion Home Builders
 Lillington, NC

AMS Of Indiana, Inc.
 3933 East Jackson Blvd.
 Elkhart, IN 46516

Scale: 1 : 131
 Page 1
 Right-Suite@ Universal 2021
 21.0.03 RSU02009
 2021-Aug-05 16:54:36
 ...23-3276-16 061720(MOD-floor).rup



Sheet 1



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
 Signature: *Tim Duerke*
 Title: Staff Plan Reviewer
 Date: 8/18/21

Project Information

For: Champion Home Builders
 Lillington, NC

External static pressure	0.50 in H2O	0.50 in H2O
Pressure losses	0.26 in H2O	0.26 in H2O
Available static pressure	0.24 in H2O	0.24 in H2O
Supply / return available pressure	0.170 / 0.070 in H2O	0.170 / 0.070 in H2O
Lowest friction rate	0.079 in/100ft	0.079 in/100ft
Actual air flow	1191 cfm	1191 cfm
Total effective length (TEL)	303 ft	303 ft

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Cig (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Fig.Eqv Ln (ft)	Trunk
B1	1439	53	80	0.094	6.0	0x0	VIFX	56.5	125.0	st1A
B1-A	1439	53	80	0.106	6.0	0x0	VIFX	46.3	115.0	st1
B2	1678	71	93	0.105	6.0	0x0	VIFX	16.5	145.0	st1
B3	3282	112	108	0.107	6.0	0x0	VIFX	23.5	135.0	st2A
B4	3788	130	108	0.112	8.0	0x0	VIFX	26.8	125.0	st2A
BA1	2942	101	64	0.083	6.0	0x0	VIFX	55.8	150.0	st1B
BA2	742	25	15	0.110	6.0	0x0	VIFX	14.5	140.0	st2A
BA3	691	24	16	0.109	6.0	0x0	VIFX	11.0	145.0	st2A
C1-A	837	29	17	0.088	6.0	0x0	VIFX	57.3	135.0	st1B
DEN	1318	64	73	0.104	6.0	0x0	VIFX	18.5	145.0	st1
DEN-A	1318	64	73	0.099	6.0	0x0	VIFX	27.8	145.0	st1
DRKVT	1281	68	71	0.100	6.0	0x0	VIFX	30.8	140.0	st1
DRKVT-A	1281	68	71	0.100	6.0	0x0	VIFX	40.5	130.0	st1
DRKVT-B	1281	68	71	0.092	6.0	0x0	VIFX	49.0	135.0	st1A
LR	1623	76	90	0.104	6.0	0x0	VIFX	28.5	135.0	st1
LR-A	1623	76	90	0.104	6.0	0x0	VIFX	38.3	125.0	st1
U	3266	112	69	0.079	6.0	0x0	VIFX	69.8	145.0	st1B

PFS CORPORATION
 Approval Limited to Factory Built Portion Only
 State: North Carolina
 Signature: *Tom Duncanson*
 Title: Staff Plan Reviewer
 Date: 8/18/21



Bold/italic values have been manually overridden

PFS CORPORATION

Approval Limited to Factory Built Portion Only

State: North Carolina

Signature: *Jim Duvall*

Title: Staff Plan Reviewer


Date: 8/18/21

Name	Grille Size (in)	Htg (cfm)	Cig (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb2	0x0	565	562	88.1	0.079	529	14.0	0x0		VIFx	
rb1	0x0	626	629	61.8	0.113	589	14.0	0x0		VIFx	

Return Branch Detail Table

Name	Trunk Type	Htg (cfm)	Cig (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
st2A	Peak AVF	291	248	0.107	872	9.0	8 x 6	RectFbg	st2
st1A	Peak AVF	362	302	0.079	620	10.4	14 x 6	RectFbg	st1
st1B	Peak AVF	241	151	0.079	723	8.9	8 x 6	RectFbg	st1A
st1	Peak AVF	900	944	0.079	1132	14.9	20 x 6	RectFbg	
st2	Peak AVF	291	248	0.107	436	9.0	16 x 6	RectFbg	

Supply Trunk Detail Table



PFS CORPORATION
 Approval Limited to Factory Built Portion Only

State: North Carolina
Signature: *Tim Swacke*
Title: Staff Plan Reviewer
Date: 8/18/21

	CUSTOMER: CHAMPION HOME BUILDER
MODEL: 23-3276-16	SCALE:
DRAWN: BPW	DATE: 8/5/21
CAD FILENAME: DS\CHAMPION LILLINGTON	



PFS Corporation d/b/a PFS TECO

An Employee-Owned Company

August 18, 2021

Mr. Mike Hamm, P.E.
Chief Building Code Consultant
North Carolina Department of Insurance - OSFM
325 North Salisbury Street
Raleigh, NC 27603

RE: Champion Home Builders #23
Lillington, NC
Model: 23-3276-16 (061720)

Dear Mr. Hamm:

Enclosed is one set of PFS accepted documents for the above referenced manufacturer. PFS has reviewed these documents and to the best of our knowledge have found them to conform to the North Carolina codes:

2018 NC Residential Code w/Amendments (includes plumbing, mechanical, & energy codes – Chapter 11)
2017 NC Electrical Code w/Amendments

If you have any questions, please contact us.

Sincerely,

A handwritten signature in black ink, appearing to read 'Ian Lehrer'.

Ian Lehrer, P.E.
Agency Engineer

Enclosure: As Stated

cc: Ryan Duke
File

Mr. Mike Hamm, P.E.
August 18, 2021
Page Two

PFS Corporation has reviewed and approved the above referenced material and to the best of our knowledge these documents conform to the referenced codes.



Construction Review
Ian Lehrer, P.E.



Structural Review
Ian Lehrer, P.E.



Plumbing Review
Ian Lehrer, P.E.



Mechanical Review
Ian Lehrer, P.E.



Electrical Review
Ian Lehrer, P.E.

N//A

Quality Control Review
Ian Lehrer, P.E.



Date Received at PFS: 8-10-2021
 IBC Transmittal No. (by PFS): _____
 Project No. (by PFS): 21005336

ADDITIONAL OR MODIFIED ACCEPTANCE (MODULARS/PANELIZED)

This form is to be used only when the manufacturer is seeking acceptance of an additional model, modified model or model name change which uses a previously accepted building system.

Current PFS Building System Acceptance #: _____
 Model Name/ No. 23-3276-16 061720
 Manufacturer's Name: CHAMPION HOME BUILDERS
 Plant(s) at which model will be produced PLANT #23 LILLINGTON, NC

Check One: Y NEW MODEL _____ Revised Model*

TECHNICAL DATA		Conforms		
		Yes	No	N/A
Floor Plan Showing:				
Braced Wall Method or Shearwalls		Y		
Building Size (LxW Dimensions)		Y		
Room Sizes, Light & Ventilation Schedule		Y		
Exit Requirements		Y		
Electrical Outlet Spacing & Smoke Detector		Y		
Location of Labels & Data Plates		Y		
Use Group, Type Const., Total Sq.Ft. Area		Y		
Plumbing System Design or Reference No. (<u>PROVIDED ON PP-101</u>)		Y		
Heat Loss Calculations or Reference No. (<u>PROVIDED ON RS-101</u>)		Y		
HVAC/Furnace Size/Model No. (<u>BY OTHERS</u>)		Y		
Thermal Performance Calculations or Reference No. (<u>PROVIDED ON RS-101</u>)		Y		
Electrical Load Calculations or Reference No. (<u>PROVIDED ON EP-101</u>)		Y		
Service Size and Location (<u>200A/UTILITY</u>)		Y		
Applicable Building Codes <u>SEE GE-101</u>		Y		
Submit model to the following states: <u>NC</u>				
*Description of Modification: _____				
Requested by: <u>JON TYNDALL</u> Date: <u>8-9-21</u>				
(designer)				

For PFS Use

Staff Plan Reviewer Tim Busche Certification #: B5002446-R3 Date: 8-18-2021

Structural Calculation(s) Reviewed By: _____ P.E. #: _____ Date: _____

Remarks: _____

**** (1) copy sent to IBC within 15 days of approval.**

VERBAL APPROVAL GIVEN By Whom: _____ To Whom: _____ Date: _____

MODEL WAS DEVIATED Revision Number: _____

THIS FORM SHALL BE FILLED OUT COMPLETELY WITH EACH MODEL ACCEPTANCE OR MODIFICATION PRIOR TO SUBMITTAL TO PFS.

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 1 of 3

revised May 2011

Manufacturer CHAMPION HOME BUILDERS

Model number/name 23-3276-16 061720

3rd Party PFS Corporation

Review Date

Reviewer

Plan Sheet Page # and NOTES

QC MANUAL (current and complete)

APPROVED ON 2-28-12

APPENDIX B (required and attached)

N/A

PLAN SHEETS

Each plan sheet third-party stamped with approver's name

Each plan sheets is numbered and/or indexed

GENERAL (cover sheet)

Code References

GE-101

Statement regarding connection to public utilities

GE-101

Statement regarding bathrooms if not included

N/A

Construction type

GE-101

Occupancy classification

GE-101

Fire resistance ratings (if required)

GE-101

Floor live load

GE-101

Roof live load

GE-101

Design wind velocity

GE-101

Seismic information (commercial projects)

GE-101

Thermal zones

RS-101/GE-101 UNDER GENERAL NOTES

Notice to inspections department regarding items to be site inspected

GE-101

FLOOR PLANS

Interior and exterior wall layouts

AP-101

Door and window schedule

AP-101

Light and Ventilation requirements

AP-101

Attic access (size and location)

AP-101

Non-prescriptive headers

AP-101, SECTION 9, PAGES 1-12

Safety glazing requirements

AP-101

Fire rating of Exterior walls (if applicable)

N/A

EXTERIOR ELEVATIONS

Exterior materials

EV-101-104/SE-101

Attic ventilation requirements

SE-101/AP-101/ WORKSHEET 1

PLUMBING

Plan

PP-101/WP-101

All fixtures furnished by mfg. shown on plans

PP-101/WP-101/GE-101(REFERENCE TO COMPLIANCE)

Materials (water supply & distribution, DWV, storm drainage)

PP-101/WP-101

Supply and waste risers, including DWV system (generic) beneath the building.

PP-101/WP-101

Water heater (type and capacity)

QA MANUAL 04.01.01

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 2 of 3

revised May 2011

Plan Sheet Page # and NOTES

MECHANICAL

Design calculations	BY OTHERS
Installed unit capacity	BY OTHERS
Supply and returns (locations and sizes)	AP-101 (RETURNS BY MANUFACTURER)
Duct sizes	BY OTHERS
Specifications (units, ducts)	BY OTHERS
All appliances furnished by mfg. shown on plans	QA MANUAL 04.01.01

ELECTRICAL

Plan	EP-101
Location of all electrical boxes	EP-101
Electrical panel location	EP-101
Note regarding main disconnect (if applicable)	GE-101
Exterior lighting and receptacles	EP-101
Ground level receptacles (if applicable)	BY OTHERS
Smoke detector location(s)	EP-101
Electrical load calculations	EP-101
Electrical panel layout (breaker and wire sizes, circuit schedule)	EP-101
Panel and service entrance sizes	GE-101/EP-101
All fixtures furnished by mfg. shown on plans	EP-101

ACCESSIBILITY

(for other than 1 & 2 family dwellings)

Entrances and means of egress	N/A
Doors, doorways, and door hardware	N/A
Stairs and handrails	N/A
Toilet rooms, plumbing fixtures, grab bars, etc	N/A
Bathrooms and shower rooms	N/A
Occupancy specific requirements	N/A
Multi-family dwellings: Type A and B units	N/A

FLOOR X-SECTION

Joists and beam sizes and spacing	SE-101/ STRUCT. MANUAL SECTION 20 PGS 1-2
Materials species and grade	SE-101 STRUCT. MANUAL SECTION 20 PGS 1-2
Sheathing, decking, and concrete as applicable	SE-101
Fastening instructions	SE-101/ STRUCT. MANUAL SECTION 20 PGS 1-2
Insulation	SE-101
Details as required for clarification	SE-101

WALL X-SECTION

Stud and column sizes and spacing	SE-101
Materials species and grade	SE-101
Sheathing and bracing	AP-101/SE-101
Headers and lintels	AP-101/SE-101
Finishes	SE-101
Fastening instructions	SE-101/SEE AP-101 FOR SHEARWALL SECTION-PAGE REFERENCE
Insulation	SE-101
Details as required for clarification	SE-101

NORTH CAROLINA
MODULAR PLANS REVIEW CHECKLIST

PAGE 3 of 3

revised May 2011

Plan Sheet Page # and NOTES

CEILING / ROOF X-SECTION

Truss, rafter, and beam spacing	AP-101/SE-101/ STRUCT. MANUAL SECTION 3 PAGES 1-38
Lumber species and grade	SE-101/ STRUCT. MANUAL SECTION 3 PAGES 1-38
Sheathing and decking	SE-101/ STRUCT. MANUAL SECTION 4 PAGES 1-36
Finishes	SE-101
Fastening instructions	SE-101/ STRUCT. MANUAL SECTION 4 PAGES 1-36
Insulation	SE-101
Details including NC sealed truss designs or manual reference	STRUCT. MANUAL SECTION 3 PAGES 1-38

FOUNDATION PLAN

Footings, pier, and curtain wall locations and specifications	F-101
X-sections with dimensions	F-101
Anchorage - sill plate to piers and curtain wall	F-102-103
Anchorage - building to sill plate	F-102-103
Anchorage - tie downs (lateral and longitudinal)	N/A
Soil bearing capacity	F-103
Minimum concrete compressive strength	F-103
Mortar type	F-103
Ventilation requirements (with and without vapor barrier)	F-101
Crawl space access requirements	F-101

ENERGY COMPLIANCE

Demonstrated compliance	RS-101
-------------------------	--------

SET-UP INSTRUCTIONS

Floor and ceiling connections	GE-101/SE-101/SETUP MANUAL PAGES 12-13
Marriage wall connections	N/A
Roof set-up and connection	GE-101/SE-101/SETUP MANUAL PAGES 12-13
Plumbing connections	GE-101/SE-101/SETUP MANUAL PAGES 23-24
Mechanical connections	GE-101/SE-101/SETUP MANUAL PAGES 21,25,28,29
Electrical connections	GE-101/SE-101/SETUP MANUAL PAGES 25-28
Fire stopping	GE-101/SE-101/SETUP MANUAL
Air infiltration elimination	GE-101/SE-101/SETUP MANUAL PAGE 11
Notice to inspections department attachment if set-up instructions are by attachment	GE-101/SE-101

ITEMS NOT INSPECTED IN PLANT

List of items not inspected by 3rd. Party	GE-101
Notice to inspections department	GE-101