Harnett County Department of Public Health

Improvement Permit


A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 1754 Sheriff Johnson Rd. (SR 1516) ISSUED TO: J David Avrette SUBDIVISION EXPANSION REPAIR | Site Improvements required prior to Construction Authorization Issuance: Type of Structure: 26x32(1bed/1ba) Proposed Wastewater System Type: 25% Reduction Sys. 2-Bedroom (240GPD) State Min - Residential Projected Daily Flow: 240 Number of bedrooms: 2 Number of Occupants: 4 Basement Yes ☐ No May be required based on final location and elevations of facilities Type of Water Supply: Community Public Well Distance from well NA feet Five years Permit valid for Permit conditions: ■ No expiration 05/16/2022 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules . 1950, . 1952, . 1954, . 1955, . 1956, . 1957, . 1958, and . 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: J David Avrette PROPERTY LOCATION: 1754 Sheriff Johnson Rd. (SR 1516) SUBDIVISION Facility Type: 26x32(1bed/1ba) Expansion Basement? Yes X No Basement Fixtures? Yes Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 240 (See note below, if applicable) 25% Reduction Sys. Number of trenches 2 Installation Requirements/Conditions Septic Tank Size 1000 gallons Exact length of each trench 90 Trench Spacing: 9 Feet on Center Pump Tank Size _____ Trenches shall be installed on contour at a Soil Cover: 6 Maximum Trench Depth of: 18 (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ft. TDH vs. __ NA inches below pipe Aggregate Depth: NA inches above pipe Conditions: inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: 1 understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: Date: Construction Authorization Expiration Date: ANDREW CURIN

Harnett County Department of Public Health Site Sketch

Property Location: 1754 Sheri Issued To: J David Avrette	Subdivision	Lot #
Authorized State Agent:	AND TENS LONGIN	e: <u>05/16/202</u>
* STOTIEN	FLACUED GNOTE	
* INSTALL	NO HIGH UPHILL AS CONTON ALLOW	
* LINE 1	SHOULD END APPROX SOFT FROM EXT PAT	41

EXT FARMED

FIZLS



This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.