



Permit Inspections Harnett County

Permit Number: **BRES2207-0018**

Description: **24 x 24 attached garage**

Applied: **7/8/2022**

Approved: **7/22/2022**

Site Address: **155 BLUE PINE DR**

Issued: **7/22/2022**

Finalized: **10/18/2023**

City, State Zip Code: **SPRING LAKE, NC 28390**

Status: **FINALED**

Applicant: **Autry Danny**

Parent Permit:

Owner: **FERGUSON ROSE**

Parent Project:

Contractor: **FERGUSON ROSE**

Details:

LIST OF INSPECTIONS

SEQ ID	SCHEDULED DATE	COMPLETED DATE	TYPE	INSPECTOR	RESULT	REMARKS
	8/1/2022	8/1/2022	FOOTING	John B Kokoszka	DISAPPROVED	

Notes:
 Scheduled by Jeff Autry
 Footing had water in it. The bottom of the footing need to be at frost level 12' below grade. Pipe sleeve need to be 2 sizes bigger and Annular space need to be filled. Cannot use corrugated pipe

	8/4/2022	8/4/2022	FOOTING	Steven Gazlay	DISAPPROVED	eTRAKiT Inspection Request
--	----------	----------	---------	---------------	-------------	----------------------------

Notes:
 8/2/2022 10:39 AM Danny Autry Sr
 Contact Name: Danny Autry Sr
 Site Address: 155 BLUE PINE DR
 Phone: 9192621867
 e-Mail: danny.autry@yahoo.com
 Inspector JTH changed the inspection assignment from JTH to SPG
 Footing must be continuous across garage door opening. Dowel into existing footing.

	8/5/2022	8/5/2022	FOOTING	James T Hall	APPROVED	eTRAKiT Inspection Request
--	----------	----------	---------	--------------	----------	----------------------------

Notes:

	9/7/2022	9/7/2022	FOUNDATION	James T Hall	APPROVED	
--	----------	----------	------------	--------------	----------	--

Notes:
 Please call Rose Ferguson (owner) before going out at (910)578-3688.

	9/25/2023	9/25/2023	FINAL**	Steven Gazlay	DISAPPROVED	
--	-----------	-----------	---------	---------------	-------------	--

Notes:
 Missing section of railing by roof.

	10/18/2023	10/18/2023	FINAL**	Daniel L Floyd	APPROVED	
--	------------	------------	---------	----------------	----------	--

Notes:





Permit Inspections Harnett County

20	10/6/2022	10/6/2022	FOUNDATION SURVEY	Donna Johnson	APPROVED	
Notes:						
30	11/14/2022	11/14/2022	ROUGH IN	James T Hall	DISAPPROVED	
Notes: 1.No truss docs on site for inspection 2.Nail garage door header every 12" per docs 3.Fire caulk all wires at top plate per code 4.Missing stud under top plate joint to left and 2 places to right of window 5.Need to strap top plate joint to left of window over window and to right of window joint less than 24" 6.Missing 2 king studs each side of window in garage 7.Missing stud under top plate joint on back wall 8.Need to install junction box with access on old wires for garage lights on right side of garage 9.Fire block crack at top plate where wall joins house 10.Need to anchor load bearing wall against house with anchor bolts per code 11.Stud under top plate joint over man door 12.Need to flash roof where it joins house and need access to see roof 13.Need engineer letter for design of roof /floor						
30	12/7/2022	12/7/2022	ROUGH IN REINSPECT	James T Hall	FAIL W/ PENALTY	
Notes: Items #1, 4, 5, 7, 8, 11, 12 & 13 were not corrected						
30	4/20/2023	4/20/2023	ROUGH IN REINSPECT	James T Hall	DISAPPROVED	
Notes: Waiting on engineer third party letter or the picture of the 2x4 vertical in floor trusses per engineers repair letter						
30	4/21/2023	4/21/2023	ROUGH IN REINSPECT	James T Hall	APPROVED	per eng letter
Notes:						

