



Window must meet egress

Must have min. 3x3 landing with 6'8" headroom at top and bottom of stairs

Receptacles must be spaced per code. All circuits shall be AFCI

NOTICE TO CONTRACTOR
 All construction shall comply with current IBC Building Codes and is subject to field inspection and verification.

APPROVED
 Limited liability only review
 Project number: 2022-010 for full compliance with the code

11/07/2022



