

**Donna Johnson**

---

**From:** Sarah Arbour  
**Sent:** Monday, January 23, 2023 4:26 PM  
**To:** Donna Johnson  
**Subject:** RA-30 Single Section Manufactured Homes

Hi Donna,

See below!

**RA-30 Zoning District**

All requirements or conditions shall be met prior to issuance of a Certificate of Occupancy (CO) for the home.

- A. The structure shall be built to the HUD code for manufactured homes.
- B. The structure shall have an a-pitched roof that is covered with material commonly used in standard residential roofing construction. Said material shall be installed properly and be consistent in appearance.
- C. The structure shall have underpinning consisting of a brick curtain wall or have galvanized metal sheeting, ABS, or PVC plastic color skirting with interlocking edges, installed around the perimeter of the home. Skirting shall be consistent in appearance, in good condition, continuous, permanent, and unpierced except for ventilation and access.
  - 1. In cases where the proposed home is located in Flood Zone AE, the home shall be located on a masonry foundation only, with approved flood vents or breakaway skirting. See "Flood Damage Prevention" Section of this Ordinance for more information.
- D. The exterior siding shall consist predominantly of vinyl, aluminum, wood or hardboard; and shall be comparable in composition, appearance, and durability to the exterior siding commonly used in standard residential construction. Said exterior siding shall be in good condition, complete, and not damaged or loose.
- E. The tongue or towing device shall be removed or landscaped.

**Sarah Arbour | Planner II**

Harnett County Development Services

Ph. (910) 814-6414

420 McKinney Pkwy. Lillington, NC 27546

[Check the Status of a Project](#) | [Submit a Project for Review](#)

