

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: J0922-4862
Cash/Pope Pool House/Harnett

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: I56920091 thru I56920096

My license renewal date for the state of North Carolina is December 31, 2023.

North Carolina COA: C-0844



March 1, 2023

Gilbert, Eric


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Cash/Pope Pool House/Harnett	156920091
J0922-4862	A1	GABLE	1	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:37:55 2023 Page 1

ID:yV9QGRqHsD60luO9w0vqPAzfNST-ck66LHdn1hrSqsq_aWjJ7s5PQI3mRTPnCMIT4FzJYQ



Scale = 1:43.3





Plate Offsets (X,Y)--	[2:0-1-3,0-2-2], [12:0-1-3,0-2-2]				
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.41	Vert(LL) -0.14 16-17 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.42	Vert(CT) -0.28 16-17 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.43	Horz(CT) -0.24 12 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.32 17-18 >901 240	Weight: 161 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-5-0 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 4-1-15 oc bracing.
WEBS 2x4 SP No.2	JOINTS 1 Brace at Jt(s): 21, 23
OTHERS 2x4 SP No.2	

REACTIONS. (size) 2=0-3-8, 12=0-3-8
 Max Horz 2=129(LC 12)
 Max Uplift 2=-272(LC 9), 12=-272(LC 8)
 Max Grav 2=1000(LC 1), 12=1000(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3033/3964, 3-4=-2905/3891, 4-5=-2367/2883, 5-6=-2328/2837, 6-7=-2304/2901,
 7-8=-2304/2902, 8-9=-2328/2837, 9-10=-2367/2883, 10-11=-2905/3896,
 11-12=-3033/3969
 BOT CHORD 2-20=-3423/2680, 19-20=-3360/2681, 18-19=-3299/2676, 17-18=-3257/2705,
 16-17=-3264/2705, 15-16=-3305/2676, 14-15=-3367/2681, 12-14=-3430/2680
 WEBS 7-17=-2336/1740, 17-23=-611/1013, 23-24=-612/1013, 10-24=-611/1014, 4-22=-611/1015,
 21-22=-611/1014, 17-21=-611/1014

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 4) All plates are 2x4 MT20 unless otherwise indicated.
 - 5) Gable studs spaced at 2-0-0 oc.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 8) Bearing at joint(s) 2, 12 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=272, 12=272.
 - 10) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.




March 1, 2023

Job	Truss	Truss Type	Qty	Ply	Cash/Pope Pool House/Harnett	156920092
J0922-4862	A2	SCISSORS	4	1		

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:37:57 2023 Page 1
 ID:yV9QGRqHsD60luO9w0vqPazfNST-YjEtmzf2YJ5A3A_MhxlnDHAIY6k0vMZ3fgEa97zfJYO



Scale = 1:43.3




Plate Offsets (X,Y)-- [2:0-1-1,0-2-10], [6:0-1-1,0-2-10]

LOADING (psf)	SPACING-	2-0-10	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.43	Vert(LL)	-0.14	8-9	>999	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.43	Vert(CT)	-0.29	8-9	>971		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.45	Horz(CT)	-0.23	6	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.31	8-9	>907		
								Weight: 151 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-2-7 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 4-2-5 oc bracing.
WEBS 2x4 SP No.2	

REACTIONS. (size) 2=0-3-8, 6=0-3-8
 Max Horz 2=83(LC 11)
 Max Uplift 2=-213(LC 9), 6=-213(LC 8)
 Max Grav 2=1000(LC 1), 6=1000(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-3126/3695, 3-4=-2384/2621, 4-5=-2384/2619, 5-6=-3126/3697
 BOT CHORD 2-10=-3220/2778, 9-10=-3077/2792, 8-9=-3081/2792, 6-8=-3224/2778
 WEBS 4-9=-2089/1680, 5-9=-698/1027, 5-8=-454/225, 3-9=-698/1028, 3-10=-454/225

NOTES-

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 12-0-0, Exterior(2) 12-0-0 to 16-4-13, Interior(1) 16-4-13 to 24-8-10 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=213, 6=213.
- See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 1, 2023

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



Job	Truss	Truss Type	Qty	Ply	Cash/Pope Pool House/Harnett	156920093
J0922-4862	A3	ROOF SPECIAL	1	1		

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:37:59 2023 Page 1

ID:yV9QGRqHsD60luO9w0vqPAzfNSt-U5MdBfgl4wLuiU8lpMoFliG8ZvVHNK8M7_jhD0zfJYM

Job Reference (optional)

0-10-8	6-3-8	12-1-12	18-0-0	23-10-4	29-8-8	36-0-0	36-10-8
0-10-8	6-3-8	5-10-4	5-10-4	5-10-4	5-10-4	6-3-8	0-10-8

Scale: 3/16"=1'




Plate Offsets (X,Y)--	[12:0-3-0,0-3-8], [16:0-3-0,0-3-8]				
LOADING (psf)	SPACING 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.21	Vert(LL) -0.03 14 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.13	Vert(CT) -0.05 13-14 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.25	Horz(CT) 0.03 12 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.02 2-16 >999 240	Weight: 306 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.2	
OTHERS 2x4 SP No.2	

REACTIONS. All bearings 0-3-8.
 (lb) - Max Horz 2=189(LC 16)
 Max Uplift All uplift 100 lb or less at joint(s) except 2=112(LC 8), 16=342(LC 12), 10=106(LC 8), 12=273(LC 13)
 Max Grav All reactions 250 lb or less at joint(s) 2, 10 except 16=1385(LC 1), 12=1385(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-146/417, 3-5=-829/320, 5-6=-919/347, 6-7=-919/347, 7-9=-829/320, 9-10=-68/417
 BOT CHORD 2-16=-277/140, 15-16=-359/170, 14-15=-125/708, 13-14=-26/708, 12-13=-359/171, 10-12=-277/129
 WEBS 6-14=-82/434, 7-13=-435/187, 9-13=-166/1026, 9-12=-1150/473, 5-15=-435/187, 3-15=-167/1026, 3-16=-1150/471

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 112 lb uplift at joint 2, 342 lb uplift at joint 16, 106 lb uplift at joint 10 and 273 lb uplift at joint 12.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 1, 2023

Job	Truss	Truss Type	Qty	Ply	Cash/Pope Pool House/Harnett	156920094
J0922-4862	A4	ROOF SPECIAL	3	1		

Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:38:01 2023 Page 1

ID:yV9QGRqHsD60luO9w0vqPAzfNST-QUTNblYcXbbYnl7wnqjN7LTQj7OrANfaHCnluzfJK

Job Reference (optional)

0-10-8	6-3-8	12-1-12	18-0-0	23-10-4	29-8-8	36-0-0	36-10-8
0-10-8	6-3-8	5-10-4	5-10-4	5-10-4	5-10-4	6-3-8	0-10-8

Scale: 3/16"=1'





Plate Offsets (X,Y)--	[2:0-1-4,0-1-7], [10:0-1-4,0-1-7], [12:0-3-0,0-3-8], [16:0-3-0,0-3-8]				
LOADING (psf)	SPACING 2-0-0	CSI	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.31	Vert(LL) -0.12 14 >999 360	MT20	244/190
TCDL 10.0	Lumber DOL 1.15	BC 0.34	Vert(CT) -0.25 13-14 >999 240		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.46	Horz(CT) 0.14 10 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-S	Wind(LL) 0.26 13-14 >999 240	Weight: 251 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-6-7 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 4-9-3 oc bracing.
WEBS 2x4 SP No.2	WEBS T-Brace: 2x4 SPF No.2 - 6-14
	Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c., with 3in minimum end distance.
	Brace must cover 90% of web length.

REACTIONS. (size) 2=0-3-8, 10=0-3-8
 Max Horz 2=-122(LC 10)
 Max Uplift 2=-319(LC 9), 10=-319(LC 8)
 Max Grav 2=1480(LC 1), 10=1480(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2604/2842, 3-5=-2898/3306, 5-6=-2559/2862, 6-7=-2559/2860, 7-9=-2898/3304, 9-10=-2604/2842
 BOT CHORD 2-16=-2391/2215, 15-16=-2417/2301, 14-15=-2646/2639, 13-14=-2651/2639, 12-13=-2414/2301, 10-12=-2387/2215
 WEBS 6-14=-2342/1876, 7-14=-438/586, 7-13=-312/115, 9-13=-401/337, 9-12=-512/384, 5-14=-438/587, 5-15=-311/115, 3-15=-400/337, 3-16=-512/384

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCCL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 18-0-0, Exterior(2) 18-0-0 to 22-4-13, Interior(1) 22-4-13 to 36-8-10 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 319 lb uplift at joint 2 and 319 lb uplift at joint 10.
 - 6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 7) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.




March 1, 2023

Job J0922-4862	Truss A5	Truss Type COMMON	Qty 3	Ply 1	Cash/Pope Pool House/Harnett Job Reference (optional)	156920095
-------------------	-------------	----------------------	----------	----------	--	-----------


Comtech, Inc. Fayetteville, NC - 28314,

8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:38:02 2023 Page 1

ID:yV9QGRqHsD60luO9w0vqPazfNST-ug1mpgjANrjS9xtKUULywLtd77OmaeTopxyLqLzJYJ



Scale = 1:67.0




LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.38	Vert(LL)	-0.25 10-13	>999	360	MT20	244/190
TCDL 10.0	Lumber DOL	1.15	BC 0.65	Vert(CT)	-0.34 10-13	>999	240		
BCLL 0.0 *	Rep Stress Incr	YES	WB 0.41	Horz(CT)	0.07 8	n/a	n/a		
BCDL 10.0	Code IRC2015/TPI2014		Matrix-S	Wind(LL)	0.28 2-13	>999	240	Weight: 230 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-4-7 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 6-1-3 oc bracing.
WEBS 2x4 SP No.2	WEBS 1 Row at midpt 5-10, 5-13

REACTIONS. (size) 2=0-3-8, 8=0-3-8
 Max Horz 2=122(LC 11)
 Max Uplift 2=-319(LC 9), 8=-319(LC 8)
 Max Grav 2=1544(LC 2), 8=1544(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-2639/1718, 3-5=-2416/1744, 5-7=-2416/1744, 7-8=-2639/1718
 BOT CHORD 2-13=-1400/2271, 10-13=-833/1541, 8-10=-1403/2271
 WEBS 5-10=-772/1008, 7-10=-517/312, 5-13=-772/1008, 3-13=-517/312

- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 18-0-0, Exterior(2) 18-0-0 to 22-4-13, Interior(1) 22-4-13 to 36-8-10 zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 4) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 319 lb uplift at joint 2 and 319 lb uplift at joint 8.
 - 6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 1, 2023

Job	Truss	Truss Type	Qty	Ply	Cash/Pope Pool House/Harnett	156920096
J0922-4862	A6	GABLE	1	1	Job Reference (optional)	

Comtech, Inc. Fayetteville, NC - 28314,


8.430 s Jan 6 2022 MiTek Industries, Inc. Wed Mar 1 10:38:04 2023 Page 1

ID:VY9QRqHsD60luO9w0vqPAzfNST-r39WEMkRvSzAPF0ibvNQ?mzznw7N2ZF5GFRRvDzJYH

-0-10-8 9-5-2 18-0-0 26-6-14 36-0-0 36-10-8
 0-10-8 9-5-2 8-6-14 8-6-14 9-5-2 0-10-8

5x12 ||

Scale = 1:69.2



12-3-7 23-8-9 36-0-0
 12-3-7 11-5-3 12-3-7

Plate Offsets (X, Y)-- [2:0-1-4,0-1-7], [9:0-3-3,0-2-0], [17:0-3-3,0-2-0], [24:0-1-4,0-1-7], [32:0-4-0,0-4-8], [36:0-4-0,0-4-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.31	Vert(LL) -0.07	32	>999	360	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.15	BC 0.39	Vert(CT) -0.15	28	>999	240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.32	Horz(CT) 0.06	24	n/a	n/a		
BCDL 10.0	Rep Stress Incr YES	Matrix-S	Wind(LL) 0.13	28	>999	240		
	Code IRC2015/TPI2014						Weight: 343 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x6 SP No.1	TOP CHORD Structural wood sheathing directly applied or 4-11-11 oc purlins.
BOT CHORD 2x6 SP No.1	BOT CHORD Rigid ceiling directly applied or 5-10-0 oc bracing.
WEBS 2x4 SP No.2	JOINTS 1 Brace at Jt(s): 43, 44, 47, 48
OTHERS 2x4 SP No.2	

REACTIONS. (size) 2=0-3-8, 24=0-3-8
 Max Horz 2=188(LC 16)
 Max Uplift 2=406(LC 9), 24=407(LC 8)
 Max Grav 2=1480(LC 1), 24=1480(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2478/2100, 3-4=-2366/2058, 4-5=-2321/2074, 5-6=-2299/2109, 6-7=-2216/2069,
 7-8=-2131/2016, 8-10=-2043/1936, 10-11=-2059/2011, 11-12=-2018/2027,
 12-13=-1999/2060, 13-14=-1971/2031, 14-15=-2014/2023, 15-16=-2058/2010,
 16-18=-2042/1936, 18-19=-2131/2016, 19-20=-2216/2069, 20-21=-2299/2110,
 21-22=-2321/2074, 22-23=-2366/2058, 23-24=-2478/2100
BOT CHORD 2-42=-1706/2057, 41-42=-1706/2057, 40-41=-1706/2057, 39-40=-1706/2057,
 38-39=-1706/2057, 37-38=-1706/2057, 36-37=-1013/1417, 35-36=-1013/1417,
 34-35=-1013/1417, 33-34=-1015/1419, 32-33=-1015/1419, 31-32=-1015/1419,
 30-31=-1708/2057, 29-30=-1708/2057, 28-29=-1708/2057, 27-28=-1708/2057,
 26-27=-1708/2057, 24-26=-1708/2057
WEBS 13-47=-739/735, 47-48=-736/729, 31-48=-767/762, 31-49=-649/675, 49-50=-506/552,
 19-50=-508/546, 37-44=-774/762, 43-44=-742/730, 13-43=-801/790, 7-46=-509/544,
 45-46=-506/550, 37-45=-648/674

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-10; Vult=130mph Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; porch left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - All plates are 2x4 MT20 unless otherwise indicated.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 406 lb uplift at joint 2 and 407 lb uplift at joint 24.
 - See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.




March 1, 2023

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601


ENGINEERING BY
TRENCO
 A MiTek Affiliate
 818 Soundside Road
 Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TFP 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing, Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TFP 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TFP 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TFP 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TFP 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.