

12 FT + Double band with 2x8 Girder
 on each end with 9' 6" 2x6 Joist
 on 12" center 4x4 Post with 5/8 thick
 Galvanized Bolts-washer+nuts. Post set on
 4 Solid Block embed 12" Deep post go thru
 Deck to Block. Step Irads are 4" Irads wide
 The Post Gate Stops are 48" apart also
 Set in on Solid Block. Handrails 36" High
 with picket 3 1/2 apart All nails are Galvanized

10 FT

