

## Description of Work

**To be performed by Mr. Smokestack Chimney Service:**

Installation of a gas line for the outdoor fireplace.

Removal of the center post where the fireplace will be set, cutting back the railings to make room for the 5ft. wide brick structure.

Installation of a masonry foundation wall, from the concrete slab to the patio floor, to support the structure in full.

Installation of framing for the fireplace & chimney.

Pour a concrete foundation slab to support your Fire-Rock fireplace.

Installation only of the Fire-Rock fireplace into the framing

Installation only of class "A" chimney piping from the top of the Fire-Rock fireplace to the top of the chimney, with a cap & chase cover

Installation of a brick veneer over the chimney structure in full.

Installation of a Pennsylvania Bluestone hearth & mantel shelf.

**To be performed by Harte Electric:**

Installation of an electrical outlet installed above the fireplace

Cheryl Schumacher  
479 D.L. Phillips Ln  
Broadway, NC 27505