

A Groundworks' Company

Scope of Work for: 272 Lambert Ln Fuquay-Varina NC 27526

The following will be performed as Crawl Space Moisture Remediation:

*20 ml Vapor Barrier installed wall to wall with 100% floor coverage. All sections of liner will be overlapped a minimum of 1' and will be seamed together, attached with Christmas Tree fasteners, and caulked.

*Wrap all existing CMU/Brick Piers 20 ml Vapor Barrier. Contractor will leave a termite inspection gap at the top of each pier. The liner will be fastened to the pier and the top edge of the liner will be sealed with caulking.

*All Vents will be sealed from inside the crawl space.

*AprilAire E100 Dehumidifier install - specifications on page 2

*Electrical - Installation of new dedicated 120vac/20amp electrical circuit/s and electrical outlet/s (WP-GFCI) to supply sump pump and /or dehumidifier in crawl space (basement).

Davis Dunlap Electrical LLC 210 Timberland Dr Angier NC 27501 919-669-0768 davisdunlapelectric@yahoo.com License #27056-L

*Install WallSeal on basement walls to help prevent water vapor and moisture intrusion as well as direct wall leakage to the waterproofing system. (12 ml Vapor Barrier on Walls)



A Groundworks' Company

SPECIFICATIONS		
Capacity		
	@ 80°F/60% RH	100 ppd
	@ 73°F/60% RH	85 ppd
Energy Factor		
	@ 80°F/60% RH	2.6 L/kW-h
	@ 73°F/60% RH	2.35 L/kW-h
Airflow @ varying (external static p	E.S.P. ressure - dry coil)	
	0.0" w.c.	280 CFM
	0.2" w.c.	245 CFM
	0.4" w.c.	210 CFM
Voltage, phase, frequency		120VAC, 1 phase, 60 Hz
Current draw ⁽¹⁾		6.9 Amps
Noise		55 dBA ducted
		Width: 14"
Dimensions: (cabinet only)(2)		Height: 15"
(cabillet ollly)		Length: 26"
Unit Weight		64 lbs.
Shipping Weight		82 lbs.
Inlet air operating	g conditions during	
-Dehumidification:		50°F-104°F, 40°F
		dew point min.
-Ventilation:		40°F-140°F, 0%-99% RH
		(non-condensing)

⁽⁹⁾Rated capacity, energy factor and current draw measured at 80°F/60% RH inlet air at 0.0 ESP.
⁽²⁾Height does not include adjustable feet. The width excludes the filter doors and length excludes the duct collars.

