

A Groundworks' Company

Scope of Work for: 405 N 14th St Erwin NC 28339

The following will be performed as Crawl Space Closed Encapsulation:

*2" Spray Foam R-19 Insulation on walls of crawlspace

*20 ml Vapor Barrier installed wall to wall with 100% floor coverage. All sections of liner will be overlapped a minimum of 1' and will be seamed together, attached with Christmas Tree fasteners, and caulked.

*All Vents will be sealed from inside the crawl space with R-10 Rigid 2" Foam Sheathing.

*Wrap all existing CMU/Brick Piers 20 ml Vapor Barrier. Contractor will leave a termite inspection gap at the top of each pier. The liner will be fastened to the pier and the top edge of the liner will be sealed with caulking.

*R-19 Insulation installed in the rim joist cavities

*Electrical - Installation of new dedicated 120vac/20amp electrical circuit/s and electrical outlet/s (WP-GFCI) to supply sump pump and /or dehumidifier in crawl space (basement).

Davis Dunlap Electrical LLC
210 Timberland Dr
Angier NC 27501
919-669-0768
davisdunlapelectric@yahoo.com
License #27056-L

*AprilAire E100 Dehumidifier install - specifications on page 2



A Groundworks' Company

SPECIFICATIONS	
Capacity	
@ 80°F/60% RH	100 ppd
@ 73°F/60% RH	85 ppd
Energy Factor	
@ 80°F/60% RH	2.6 L/kW-h
@ 73°F/60% RH	2.35 L/kW-h
Airflow @ varying E.S.P. (external static pressure - dry coil))
0.0" w.c.	280 CFM
0.2" w.c.	245 CFM
0.4" w.c.	210 CFM
Voltage, phase, frequency	120VAC, 1 phase, 60 Hz
Current draw ⁽¹⁾	6.9 Amps
Noise	55 dBA ducted
	Width: 14"
Dimensions: (cabinet only) ⁽²⁾	Height: 15"
(Cabillet Olly)	Length: 26"
Unit Weight	64 lbs.
Shipping Weight	82 lbs.
Inlet air operating conditions duri	ng
-Dehumidification:	50°F-104°F, 40°F
	dew point min.
-Ventilation:	40°F-140°F, 0%-99% RH
	(non-condensing)

⁽P) Rated capacity, energy factor and current draw measured at 80°F/60% RH inlet air at 0.0 ESP.
(P) Height does not include adjustable feet. The width excludes the filter doors and length excludes the duct collars.

