

Rogers Property
3-Bedroom Septic Proposal
330 Mabry Road Argue NC 275M
Harnett County PIN: 0682-37-3530

*Not a Survey Sketched from a plot plan supplied by owner

Stephenson Builders Fric PN 8125123

GRAPHIC SCALE 1" = 100"



System: Pump to D-Box Lines: 1-4 (260') 0.4 LTAR 18" Max Trench Bottom Accepted Status System Repair: Pressure Manifold Lines: 5-6 (195') 0.4 LTAR 16" Max Trench Bottom T&J Panel Block - 50% reduction

**1000 Gallon Septic and Pump Tanks
Tank and trenches to be located minimum of 10'
from any property line and minimum of 5'
from any building foundation.

*Do Not Cut, Fill, or Alter Drainfield or Repair Area

*Comply with all setbacks

*Contact local health dept. and/or Alex Adams prior to or during installation with any questions or concerns.

Adams
Soil Consulting
919-414-6761
Job #1776