



A Groundworks' Company

Scope of Work for: 56 Turtle Point Dr Fuquay-Varina NC 27526

The following will be performed as crawlspace closed encapsulation:

- *All Vents will be sealed from inside the crawl space with R-10 Rigid 2" Foam Sheathing.
- *Wrap all existing CMU/Brick Piers 20 ml Vapor Barrier. Contractor will leave a termite inspection gap at the top of each pier. The liner will be fastened to the pier and the top edge of the liner will be sealed with caulking.
- *20 ml Vapor Barrier installed wall to wall with 100% floor coverage. All sections of liner will be overlapped a minimum of 1' and will be seamed together, attached with Christmas Tree fasteners, and caulked.
- *R-19 Insulation installed in the rim joist cavities.
- *R-10 Rigid 2" Foam Sheathing Wall Insulation installed with a 3-4" termite inspection reveal left at the top of the foundation wall. All vents will be sealed from the inside.
- *AprilAire E100 Dehumidifier install unit specifications on page 2 using existing electrical



A Groundworks' Company

SPECIFICATIONS	
Capacity	
@ 80°F/60% RH	100 ppd
@ 73°F/60% RH	85 ppd
Energy Factor	
@ 80°F/60% RH	2.6 L/kW-h
@ 73°F/60% RH	2.35 L/kW-h
Airflow @ varying E.S.P. (external static pressure - dry coil))
0.0" w.c.	280 CFM
0.2" w.c.	245 CFM
0.4" w.c.	210 CFM
Voltage, phase, frequency	120VAC, 1 phase, 60 Hz
Current draw ⁽¹⁾	6.9 Amps
Noise	55 dBA ducted
	Width: 14"
Dimensions: (cabinet only) ⁽²⁾	Height: 15"
(Cabillet Olly)	Length: 26"
Unit Weight	64 lbs.
Shipping Weight	82 lbs.
Inlet air operating conditions duri	ng
-Dehumidification:	50°F-104°F, 40°F
	dew point min.
-Ventilation:	40°F-140°F, 0%-99% RH
	(non-condensing)

⁽P) Rated capacity, energy factor and current draw measured at 80°F/60% RH inlet air at 0.0 ESP.
(P) Height does not include adjustable feet. The width excludes the filter doors and length excludes the duct collars.

