



May 29, 2024

Leo Guadarrama
301 Cortez Morrison Rd.
Lillington, NC
C.O. Victor Carera
919-995-8199
Leogadarrama707@gmail.com

Reference: Engineering Services
301 Cortez Morrison Rd.
Lillington, NC
Project No.: DRB2301-0408-A

As requested by the client, a representative of Tyndall Engineering & Design, PA (TE&D) has reviewed the following item(s):

- 1) Temporary office container on site set up.

The following conclusions and recommendations were noted:

Based on our worst-case analyses, of a Connex type shipping container the existing structure is adequate as constructed to support the anticipated loading conditions of a temporary embroidery shop. However, TE&D recommends that a tie down strap with a 30-in steel-painted mobile home anchor with a minimum uplift capacity of 3,150 lb be installed at each of the 4 exterior corners.

We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,
Tyndall Engineering & Design

Sean M. Holmes
SMH/ DRB2301-0408-A

Prentice A. Tyndall Jr., P.E





