

1-Canyon Drift Dryer Vent

Alside Supply Center
3545 Gillespie St.
Fayetteville, NC 28306
(910) 426-0265

2-Canyon Drift Receptacle
Box
1-Canyon Drift large box
for AC disconnect

Alside Supply Center
4205 Global Street
Raleigh, NC 27610
(919) 250-0000
Bryan Urrutia
HSC129@ALSIDE.com


J-Channel Alside
Monterey Sand 300'

4 exterior Corners Alside
Monterey Sand

Aluminum Coil-Alside
Monterey Sand (160ft²)

6-Pcs 0.75x1.5" Canyon Drift
Finish trim


AMPAD™



Design based on plans and/or revisions dated
No Date
 Plans and/or revisions received on
04/03/24

**THIS LAYOUT IS TO BE USED AS A TRUSS PLACEMENT GUIDE ONLY.
 PLEASE REFER TO BUILDING PLANS FOR BUILDING CONSTRUCTION AND DETAILS,
 SUCH AS PLUMBING OR DUCT DROPS.**

**PROPOSED DESIGN-
 NOT FOR
 CONSTRUCTION**



Notes:
 1. Exterior dimensions shown are assumed to be:
 Out-to-out of stud
 Out-to-out of sheathing
 Out-to-out of
 2. Adjust truss locations as needed for plumbing and mechanical clearance. Unless otherwise noted, trusses may be shifted as long as O.C. spacing shown is not exceeded.
 3. Do not cut, drill, or otherwise damage any part of any truss without prior approval from Peak Truss.
 4. Do not approve drawings if any information herein is unclear. Once ordered trusses will be fabricated as approved.
 5. Please contact Peak Truss Builders with any questions. We are available to help any way we can. We can be reached at 919-545-5555 or sales@peaktruss.com

Roof Truss Loading specified by building designer on Residential jobs
 Top Chord Live Load 20.0 lb/ft²
 Top Chord Dead Load 10.0 lb/ft²
 Bottom Chord Live Load 0.0 lb/ft²
 Bottom Chord Dead Load 10.0 lb/ft²

Trusses are designed for additional storage load wherever a 42"x24" box will fit between the webs.

Floor Truss Loading specified by building designer on Residential jobs
 Top Chord Live Load 40.0 lb/ft²
 Top Chord Dead Load 10.0 lb/ft²
 Bottom Chord Live Load 0.0 lb/ft²
 Bottom Chord Dead Load 5.0 lb/ft²
 Floor Live Load deflection limit L/480
 Roof Live Load deflection limit L/240

This layout has been designed using the IRC2015 building code.
 Model created using a wind speed of 120 mph specified for Harnett County.

△ - This symbol denotes left end of truss as shown on truss drawings
 ● - Approximate location of toilet drop. Builder please confirm.
 Truss connections by others:
 N - Nailed
 L - Ledger

Roof Trusses	
Overhang:	12"
Depth:	NA
Spacing:	16" OC
Wall Types	
	Load Bearing
	Non Load Bearing

Job # **Q-2400849**

Crech Storage
 256 Oakhaven Dr
 Holly Springs NC 27540
 UNIT / Lot:

Layout Creation Date: **4/3/2024**

Valued Customer

Peak Truss Builders, LLC
 PO Box 340, New Hill, NC 27562

Sales: Le Greene - Design: Robert Rogers


Job Q-2400849-1	Truss T1GE	Truss Type Common Supported Gable	Qty 2	Ply 1	Creech Storage-Roof Job Reference (optional)
--------------------	---------------	--------------------------------------	----------	----------	---

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Sep 21 2023 Print: 8.720 S Sep 21 2023 MiTek Industries, Inc. Wed Apr 03 11:41:33

Page: 1

ID:80CPcU4eHw53jamXibu_W_zUSK0-7tryYgD2q?G4qdDM0Y2Gf65LB1LT?VXgybVrFOzUSHG



Scale = 1:40.8

Plate Offsets (X, Y): [21:0-2-8,0-3-0]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	Vert(CT)	n/a	-	n/a	999		
BCLL	0.0*	Rep Stress Incr	YES	WB	Horz(CT)	0.00	26	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							Weight: 101 lb FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 OTHERS 2x4 SP No.3

BRACING

TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS All bearings 19-11-0.

- (lb) - Max Horiz 2=54 (LC 10), 23=54 (LC 10)
- Max Uplift All uplift 100 (lb) or less at joint(s) 2, 12, 14, 15, 16, 17, 19, 20, 21, 22, 23, 26
- Max Grav All reactions 250 (lb) or less at joint(s) 2, 12, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 26

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Corner (3) 1-0-0 to 1-11-8, Exterior (2) 1-11-8 to 9-11-8, Corner (3) 9-11-8 to 12-11-8, Exterior (2) 12-11-8 to 20-11-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- All plates are 2x4 MT20 unless otherwise indicated.
- Gable requires continuous bottom chord bearing.
- Gable studs spaced at 2-0-0 oc.
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 19, 20, 21, 22, 17, 16, 15, 14, 12, 2, 12.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job Q-2400849-1	Truss T1	Truss Type Common	Qty 22	Ply 1	Creech Storage-Roof Job Reference (optional)
--------------------	-------------	----------------------	-----------	----------	---

Peak Truss Builders LLC, New Hill, user

Run: 8.72 S Sep 21 2023 Print: 8.720 S Sep 21 2023 MiTek Industries, Inc. Wed Apr 03 11:41:33

Page: 1

ID: gqf10840WczC5QBL9tNI_nzUSK1-?tryYgD2q?G4qdM0Y2Gf65Ju1Gq?TWgybVrF0zUSHG



Scale = 1:40.7

Plate Offsets (X, Y): [8:0-4-0,0-3-0]

Loading	(psf)	Spacing	1-4-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.03	8-11	>999	240	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.33	Vert(CT)	-0.13	8-11	>999	180		
BCLL	0.0*	Rep Stress Incr	YES	WB	0.16	Horz(CT)	0.02	6	n/a	n/a		
BCDL	10.0	Code	IRC2015/TPI2014	Matrix-MS							Weight: 89 lb	FT = 20%

LUMBER

TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.3

BRACING

TOP CHORD
 BOT CHORD

Structural wood sheathing directly applied or 6-0-0 oc purlins.
 Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS (lb/size) 2=571/0-3-8, (min. 0-1-8), 6=571/0-3-8, (min. 0-1-8)
 Max Horiz 2=54 (LC 10)
 Max Uplift 2=-89 (LC 11), 6=-89 (LC 11)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-15=-895/129, 3-15=-877/144, 3-16=-672/91, 4-16=-622/102, 4-17=-622/102, 5-17=-672/91, 5-18=-877/144, 6-18=-895/129
 BOT CHORD 2-8=-72/785, 6-8=-72/785
 WEBS 4-8=-15/390, 5-8=-266/102, 3-8=-266/102

NOTES

- Unbalanced roof live loads have been considered for this design.
- Wind: ASCE 7-10; Vult=120mph (3-second gust) Vasd=95mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; B=20ft; L=20ft; eave=4ft; Cat. II; Exp B; Enclosed; MWFRS (directional) and C-C Exterior (2) -1-0-0 to 2-0-0, Interior (1) 2-0-0 to 9-11-8, Exterior (2) 9-11-8 to 12-11-8, Interior (1) 12-11-8 to 20-11-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
- Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 89 lb uplift at joint 2 and 89 lb uplift at joint 6.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard