


Reoz

28'

11'-6"



168'

Ramp

SEE REVISION

12'

30'-0"

Foundation Layout

Crawlspace


FOUNDATION VEN

Front


107 Person Court
Spring Lake

The information in these documents is provided for informational purposes only. It is not intended to be used as a basis for any legal action. The Designer is not responsible for any errors or omissions in this drawing. The Designer is not responsible for any construction or other work that may be done in reliance on this drawing. The Designer is not responsible for any construction or other work that may be done in reliance on this drawing. The Designer is not responsible for any construction or other work that may be done in reliance on this drawing.

NOTICE TO CONTRACTOR
 APPROVED
 02/27/2024
 HARNETT COUNTY
 WOOD BRIDGE



Left Elevation
 Scale: 1/8" = 1'0"



Right Elevation
 Scale: 1/8" = 1'0"



Rear Elevation
 Scale: 1/8" = 1'0"

I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH 64H AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL 2018 NC BUILDING CODE/ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS/MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.

APPROVAL BY	DATE
 FRAZIER DESIGNS MEMBER A I B D AMERICAN INSTITUTE OF BUILDING DESIGN	
Frazier Designs A Residential Design Company (910) 818-9413 www.frazierplans.com	
Project: Sutton Addition 107 Person Ct, Spring Lake, NC 28390 MODEL: FD-632 BUILDER:	
DATE PRINTED: Oct. 2023 DRAWN BY: RTF	
Elevations	
SHEET 1	

**Plans Designed to the
2018 NORTH CAROLINA STATE
RESIDENTIAL BUILDING CODE**

CLIMATE ZONE	ZONE 3	ZONE 4	ZONE 5
FENESTRATION U-FACTOR	0.35	0.35	0.35
SKYLIGHT U-FACTOR	0.65	0.65	0.60
GLAZED FENESTRATION SHGC	0.30	0.30	0.30
CEILING R-VALUE	30	38	38
WALL R-VALUE	13	15	19
FLOOR R-VALUE	19	19	30
**BASEMENT WALL R-VALUE	10/13	10/13	10/13
**SLAB R-VALUE	0	0	10
* CRAWLSPACE WALL R-VALUE	5/13	10/13	10/13

** 10/13 Means R-13 Sheathing Insulation or R-13 Cavity Insulation
 ** Insulation Depth with Monolithic Slab 18" or From Inspection Gap to bottom of Footing; Insulation Depth with Stem Wall Slab 24" or to bottom of Foundation Wall
 DESIGNED FOR WIND SPEED OF 120 MPH, 3 SECOND GUST (93 FASTEST MILE) EXPOSURE 'B'

**DESIGN PRESSURES FOR DOORS AND WINDOWS
POSITIVE AND NEGATIVE IN PSF**

VELOCITY (MPH)	MEAN ROOF HEIGHT (FT)		
	15	25	35
115	15	17	19
120	20	23	25
130	25	29	32

ASSUMED MEAN ROOF HEIGHT 9'3"

Roof Truss Requirements

TRUSS DESIGN.

Trusses, if used, to be designed and engineered in accordance with these drawings. Any variation with these drawings must be brought to Frazier Designs attention before construction begins.

KNEE WALL AND CEILING HEIGHTS.

All Finished knee wall heights and ceiling heights are shown turned down 10' from roof decking for insulation. If for any reason the truss manufacturer fails to meet or exceed designated heel heights, finished knee wall heights, or finished ceiling heights shown on these drawings the finished square footage may vary. Any discrepancy must be brought to Frazier Designs Attention, so that a suitable solution can be reached before construction begins. Any variation due to these conditions not being met is the responsibility of the truss manufacturer.

ANCHORAGE.

All required anchors for trusses due to uplift or bearing shall meet the requirements as specified on the truss schematics.

Bearing.

All trusses shall be designed for bearing on SPF # 2 Plates or Ledgers unless noted otherwise.

Plate Heights and Floor Systems.

See Elevation page(s) for plate heights and floor system thicknesses.

ROOF VENTILATION

Section R806

R806.1 Ventilation required.

Enclosed Attics and enclosed rafter spaces formed where ceilings are applied directly to the underside of the roof rafters shall have a cross ventilation for each separate space by ventilating openings protected against the entrance of rain or snow. Ventilation openings shall have a least dimension of 1/16 inch (1.6mm) minimum and 1/4 inch (6.4 mm) maximum. Ventilation openings having a least dimension larger than 1/4" inch (6.4mm) shall be provided with corrosion-resistant wire cloth screening, hardware cloth, or similar material with openings having a least dimension of 1/16 inch (1.6mm) minimum and 1/4 inch (6.4mm) maximum. Openings in roof framing members shall conform to the requirements of Section R802.7.

R806.2 Minimum Area.

The Total net free ventilating area shall not be less than 1/150 of the area of the space ventilated except that reduction of the total area to 1/300 is permitted provided that at least 50 percent and not more than 80 percent of the required ventilating area is provided by ventilators located in the upper portion of the space to be ventilated at least 3 feet (914mm) above the eave or cornice vents with the balance of the required ventilation provided by eave or cornice vents. As an alternative, the net free cross-ventilation area may be reduced to 1/300 when a Class I or II vapor retarder is installed on the warm-in-winter side of the ceiling.

Exceptions:

1. Enclosed attic/rafter spaces requiring less than 1 square foot (0.0929 m²) of ventilation may be vented with continuous soffit ventilation only.
2. Enclosed attic/rafter spaces over unconditioned space may be vented with continuous soffit vent only.

Square footage of roof to be vented = 1201

Net-Free Cross Ventilation Needed:

Without 50% to 80% of Venting 30" above Eave= 8.01

With 80% to 80% of Venting 30" above eave; or with Class I or II

Vapor Retarder on Warm-in-Winter Side of Ceiling: 4.00

STRUCTURAL NOTES

All construction shall conform to the latest requirements of the 2018 North Carolina Residential Building Code, plus all local codes and regulations. This document in no way shall be construed to supersede the code.

Job Site Practices And Safety:

Frazier Designs assumes no liability for contractors practices and procedures or safety program. Frazier Designs takes no responsibility for the contractor's failure to carry out the construction work in accordance with the contract documents. All members shall be framed, anchored, and braced in accordance with good construction practice and the building code.

Design Loads	Live Load Dead Load Deflection		
	USE (PSF)	(PSF)	(LL)
Attics without storage	10	10	L/240
Attics with Limited storage	20	10	L/360
Attics with fixed stairs	40	10	L/360
Balconies and Decks	40	10	L/360
Fire Escapes	40	10	L/360
Guardrails and Handrails	200	--	--
Guardrail In-fill components	50	--	--
Passenger vehicle garages	50	10	L/360
Rooms other than sleeping	40	10	L/360
Sleeping rooms	30	10	L/360
Stairs	40	--	L/360
Snow	20	--	--

Framing Lumber:

All non treated framing lumber shall be SPF # 2 (Fb=875 PSI) or SYP # 2 (Fb= 750 PSI) and all treated lumber shall be SYP # 2 (Fb= 750 PSI) unless noted otherwise.

Engineered Wood Beams:

Laminated lumber (LL) = Fb= 2800 PSI, Fv=285 PSI, E=1.8x10⁶ PSI
 Parallel strand lumber (PSL) = Fb= 2900 PSI, Fv= 290 PSI, E= 2.0x10⁶ PSI
 Laminated Strand Lumber (LSL) = Fb= 2250 PSI, Fv= 400 PSI, E = 1.55 x 10⁶ PSI
 Install All connections per Manufacturers Instructions

Truss And I -Joist Members:

All Roof Truss and I-Joist Layouts shall be prepared in accordance with this document. Trusses and I-Joists shall be installed according to the Manufacturers specifications. Any Change in Truss or I-Joist Layout shall be coordinated with Frazier Designs.

Lintels:

Brick Lintels Shall be 3 1/2" x 3 1/2" x 1/4" Steel angle for up to 60" Span and 6" x 4" x 5/16" Steel angle with 6" leg vertical for spans up to 90" Unless noted otherwise.

Concrete and Soils:

See Foundation Notes.

Foundation Structural Notes

120 MPH wind zone (1 1/2 to 2 1/2 story)

Continuous Footing:

16" wide and 8" thick minimum. 20" wide minimum at brick veneer. Must extend 2" to either side of supported wall.

Girders:

(2) 2x8 girder unless noted otherwise.

Piers:

6" x 16" piers with 6" solid masonry cap on 16" x 24" x 6" concrete footing with maximum pier height of 64" with hollow masonry and 160" with solid masonry unless otherwise noted.

Point Loads:

 designates significant point load and should have solid blocking to pier, girder or foundation wall.

Anchor Bolts:

1/2" diameter anchor bolts embedded minimum 7" maximum 60" on center, within 12" of plate ends, and minimum two anchor bolts per plate.

Concrete:

Concrete shall have a minimum 28 day strength of 3000 psi and maximum 5" slump. Air entrained in Table 402.2. All concrete shall be in accordance with ACI standards. All samples for pumping shall be taken from the exit end of the pump.

Lug Footings:

Lug Footings shall be 20" wide x 10" depth and shall run continuously underneath any wall that is deemed to be load bearing. See Detail for specs.

Soils:

Allowable soil bearing pressure assumed to be 2000 PSF. The Contractor must contact a geotechnical engineer and a structural engineer if unsatisfactory subsurface conditions are encountered. The surface area adjacent to be foundation wall shall be provided with adequate drainage, and shall be graded so as to drain surface water away from foundation walls.

AIR LEAKAGE

Section N1102.4

N1102.4.1 Building Thermal Envelope.

The Building Thermal Envelope shall be durably sealed with an Air Barrier System to limit infiltration. The sealing methods between dissimilar materials shall allow for differential expansion and contraction. For all homes, where present, the following shall be caulked, gasketed, weatherstripped or otherwise sealed with an air barrier material or solid material consistent with Appendix E-4.1 of this code:

1. Blocking and sealing floor/ceiling systems and under knee walls open to unconditioned or exterior space.
2. Capping and sealing shafts or chases, including flue shafts.
3. Capping and sealing soffit or dropped ceiling areas.

"I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH IAH AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL (2018 RESIDENTIAL NC BUILDING CODE), ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS, MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.

The information on these documents was prepared by Frazier Designs, Inc. It is provided for your information only. It is not intended to be a substitute for professional engineering or architectural services. Frazier Designs, Inc. is not responsible for any errors or omissions in this document. Frazier Designs, Inc. is not responsible for any consequences arising from the use of this information. Frazier Designs, Inc. is not responsible for any damages, including consequential damages, arising from the use of this information. Frazier Designs, Inc. is not responsible for any claims, damages, or liabilities arising from the use of this information. Frazier Designs, Inc. is not responsible for any claims, damages, or liabilities arising from the use of this information.

APPROVED BY	DATE



Frazier Designs
 Residential Design Company
 (910) 818-9413
 www.frazierplans.com


Project: Sutton Addition
 107 Person Ct, Spring Lake, NC 28390
 MODEL: FD-632
 BUILDER:

DATE PRINTED:
 Oct.30.25
 DRAWN BY:
 RIT

Notes

"I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH IAH AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL (2018 NC BUILDING CODE), ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS, MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.

SHEET
2




Overhang Detail - Siding


Not to Scale
 ***If Roof is to be Slick Built, See Structural Engineers Details for Specifications**

NOTE THAT "CORNER" BYLLS (SHINGLES/ROOF SQUARE) VENTS MUST BE PROVIDED IN ADDITION TO ONE IN LINE OF ABOVE VENTS INDICATED.


SEE 3x 3x 3 FT. UNCOVERED + BULKY VENTILATION AREA BELOW



RIDGE VENT




ROOF JACKS AND VENTS



Exterior Wall Detail Siding - 4" Brick/4" Block

Not to Scale
 Use Grout Stop to ensure Full embedding of Anchor bolt.



2-2X10 Girder 8X16 Pier

Not to Scale

I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH IAH AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL (2018 NC BUILDING CODE/ENERGY CONSERVATION STANDARDS) OF THE 30th COUNCIL OF AMERICAN BUILDING OFFICIALS/MORE ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.

APPROVAL BY: DATE:



MEMBER
AI
BD
 AMERICAN INSTITUTE OF BUILDING DESIGN

Frazier Designs
 A Residential Design Company
 (910) 818-9413
 www.frazierplans.com

Project: Sutton Addition
 107 Person Ct, Spring Lake, NC 28390
 MODEL: FD-532
 BUILDER:

DATE PRINTED: Oct. 2023
 DRAWN BY: RTF

Details

SHEET
3

THIS DRAWING IS THE PROPERTY OF FRAZIER DESIGNS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FRAZIER DESIGNS, INC. ANY UNAUTHORIZED REPRODUCTION OR TRANSMISSION IS STRICTLY PROHIBITED AND WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.



MEMBER
A I B D
AMERICAN INSTITUTE OF BUILDING DESIGN


Frazier Designs
A Residential Design Company
(910) 818-9413
www.frazierplans.com

Project: Sutton Addition
107 Person Ct, Spring Lake, NC 28390
MODEL: FD-532
BUILDER:

DWG PRINTED:
Oct. 2025
DRAWN BY:
RTT


Crawspace
Layout

SHEET
4




Foundation Layout
Crawspace
Scale: 1/4" = 1'0"
Existing

FOUNDATION VENTILATION:
653 S.F. / 150 = 4.35 S.F. VENTILATION REQ'D




Exterior Wall Detail
Siding - 4" Brick/4" Block
Not to Scale
Use Grout Stop to ensure Full embedding of Anchor bolt.



2-2X10 Girder
8X16 Pier
Not to Scale

"I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH IAH AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL 2018 NC BUILDING CODE/ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS, MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.



Electrical Drawn as Approximation
See Electrical Contractor for
Exact Layout and Specs.

ELECTRICAL LEGEND		
ELECTRICAL	COUNT	SYMBOL
ceiling fan globe 01	2	
exterior light 02	1	
Exhaust fan w light	2	
4 prong 240V Outlet	1	
light	7	
outlet	15	
outlet gfi	2	
switch	2	
switch double	2	
switch quad	2	
switch triple	1	
wall mounted 01 2 lights	2	

Layout Existing_New

Scale: 1/4" = 1'0"



Ceiling Ht to match Existing
532 S.F. New Addition
(Includes, Laundry, office, Bedroom
Bathroom and Closet)
181S.F. New Therapy Room
127 S.F. Wood Deck
(Includes Ramp)

"I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH RAH AND VA FIREARM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL (2018) NC BUILDING CODE/ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS/MODEL ENERGY CODES AND THE REQUIREMENT FOR LEAD-FREE PIPING.

APPROVED BY: DATE:



MEMBER
A I B D
ASSOCIATION OF RESIDENTIAL BUILDING DESIGNERS

Frazier Designs
Residential Design Company
(910) 818-2413
www.frazierplans.com





Project: Sutton Addition
107 Person Ct, Spring Lake, NC 28390
MODEL: FD-532

DATE PRINTED: Oct. 2023
DRAWN BY: RTT


Layout

SHEET


5




RAMP DETAIL
 SCALE: 1/2" = 10"
 *Slope for ramps to not exceed 5% or 1:19 Pitch from grade to platform**
 ** Due to the Nature of Pressure Treated Wood to swell or shrink depending on Weather Conditions, Ramps are to be built at 62" Minimum so as to meet or exceed 42" Minimum OAH Requirement for distance between handrails.




Unobstructed Reach Range For Electrical
 Scale: 1/4" = 1"




TOILET CLEARANCES




Toilet Side
 Scale: 1/4" = 1"



Toilet Plan View
 Scale: 1/4" = 1"




Toilet Front
 Scale: 1/4" = 1"




Window Control Ht. Detail
 Scale: 1/2" = 1"



Depth of Roll Under Area



Wall Mounted Sink
 Scale: 1/4" = 1"



Roll in "No Lip" Shower
 Scale: 1/4" = 1"

THESE PLANS AND SPECIFICATIONS ARE THE PROPERTY OF FRAZIER DESIGNS. THEY ARE TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. ANY REUSE OR REPRODUCTION OF THESE PLANS WITHOUT THE WRITTEN PERMISSION OF FRAZIER DESIGNS IS STRICTLY PROHIBITED. FRAZIER DESIGNS ASSUMES NO LIABILITY FOR ANY DAMAGE, LOSS, OR INJURY RESULTING FROM THE USE OF THESE PLANS. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND REGULATORY APPROVALS. FRAZIER DESIGNS IS NOT RESPONSIBLE FOR ANY CONSTRUCTION DEFECTS OR OMISSIONS. THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND REGULATORY APPROVALS. FRAZIER DESIGNS IS NOT RESPONSIBLE FOR ANY CONSTRUCTION DEFECTS OR OMISSIONS.

APPROVED BY:	DATE:



MEMBER
A I B D
 AMERICAN INSTITUTE OF BUILDING DESIGNERS

Frazier Designs
 A Residential Design Company
 (910) 818-8413
 www.frazierplans.com

Project: Sutton Addition
 107 Person Ct, Spring Lake, NC 28390
 MODEL: FD-532
 BUILDER:


DATE PRINTED:
 03.2025
 DRAWN BY:
 RTT

SAH
Details

SHEET

6

I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH SAH AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL 2018 NC BUILDING CODE/ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS/MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.



= Thickened Slab
 Detail $\frac{1}{2}$

Foundation Layout
Stemwall Slab
 Scale: 1/4" = 1'0"




I DO HEREBY CERTIFY THAT THIS DRAWING OR PLAN AND RELATED SPECIFICATIONS MEET ALL LOCAL REQUIREMENTS AND ARE IN SUBSTANTIAL CONFORMITY WITH BOTH S&H AND VA MINIMUM PROPERTY REQUIREMENTS INCLUDING THE INTERNATIONAL BUILDING CODE COUNCIL 2018 NC BUILDING CODE/ENERGY CONSERVATION STANDARDS OF THE 2018 COUNCIL OF AMERICAN BUILDING OFFICIALS/MODEL ENERGY CODE AND THE REQUIREMENT FOR LEAD-FREE PIPING.


This drawing was prepared by the Designer in accordance with the provisions of the International Building Code, 2018 Edition, and the Virginia State Building Code, 2018 Edition. The Designer is not responsible for the accuracy of the information provided by the client. The Designer is not responsible for the accuracy of the information provided by the client. The Designer is not responsible for the accuracy of the information provided by the client.

MEMBER A I BD <small>AMERICAN INSTITUTE OF BUILDING DESIGNERS</small>	
Project: Sutton Addition 107 Person Ct, Spring Lake, NC 28390 MODEL: FD-532 BUILDER:	
DATE:	APPROVED BY:
SHEET 4	Frazier Designs A Residential Design Company (910) 818-9413 www.frazierdesigns.com

4" CONCRETE SLAB 3000 P.S.I. - CONCRETE COMPRESSION, TENSILE, AND FLEXURAL STRENGTH ARE INCREASED W/ THE ADDITION OF 1.5 LBS. PER CU. YD. OF FIBER MESH. REFERENCE F.E.D. REPORT #1



Raised Slab Detail W/Brick




Overhang Detail - Siding



3/4" = 1'-0"

DETAIL AT THICKENED SLAB



WOOD STUDS @ 16" O.C.

POWER DRIVEN ANCHORS @ 8" O.C. THROUGH TRID. PL.

6x6-w1.4xw1.4 w.w.f. AT CENTER OF SLAB (TYP.)

WIRE REINFORCING (4'-0" WIDE) IN THICKENED CONC. SLAB

(2) #4'S CONT.


8"

1'-6"

8"

8"

4"



L