


Jeffrey Stewart
 3-Bedroom Septic system repair/relocation
 9665 NC 27 E - Benson (Harnett County)
 Harnett County PIN#: 1529-47-5372
 2-13-24



System: Pressure Manifold
 Lines: 1-6 (330')
 0.35 LTAR
 15" Trench Bottom
 Accepted Status

New System

- **1000 Gallon Septic and Pump Tanks
- Tank and trenches to be located minimum of 10' from any property line and minimum of 5' from any building foundation.
- *Do Not Cut, Fill, or Alter Drainfield or Repair Area
- *Comply with all setbacks

 Areas contain soils with 24 inches or more of useable material and have potential for conventional, modified conventional, LPP or ultra-shallow conventional septic systems.

*System flagged by Alex Adams on property. If flags are missing at time of installation contact Alex Adams to reflag.
 Pre construction meeting required with Alex Adams and installer prior to installation.

GRAPHIC SCALE
 1" = 60'



Adams
 Soil Consulting
 919-414-6761
 Project #1868