

8x8x9' PT posts Simpson Strong Tie anchor to concrete.  
(3) 2x12 header with mechanical fastener to posts.  
2x8 Rafters 16"OC with mechanical rafter ties.  
End wall beams supported on 8x8x9' posts.  
1/2" sheathing on roof, 30lb felt, architectural shingles.

