

т 919 773-1200 = г 919 773-9658

250 Shipwash Drive, Suite 104 - Garner North Carolina - 27529

www.tyndallengineering.com

April 24, 2024

Joe Ski c/o Clean Slate Contracting 229 Cherry Bark Loop Clayton, NC 27527 Email: info@cleanslaterdu.com

Reference: Engineering Services

865 Coachman Way Sanford, NC 27332

TE&D Project No.: 2401-020288

To Whom It May Concern;

As requested by the client, a representative of Tyndall Engineering & Design, PA (TE&D) is providing analysis for the following framing issue(s):

1) We understand the existing rear deck is to be removed and replaced with a new 3-Season Room. We are providing an analysis of the framing for the proposed space.

The following conclusions and recommendations were noted:

 We understand the existing deck framing and foundation is to be removed and replaced per the plan provided by the client and included with this report. Based on our understanding and analysis, the proposed deck framing and foundation is adequate to support the anticipated loading conditions.

We understand the walls and roof of the sunroom are to be framed per the plans provided by the client and included with this report. Based on our observations and analysis, we recommend the following:

- A) The proposed wall headers are to consist of minimum (2) 2 x 12 headers.
- B) The aluminum posts are to be connected to each of the top brackets with a total of (4) 1/2" TEC screws (1 screw from each side of the post). The brackets are to be attached to the top beams with (4) 6" long Fastenmaster Timberlok screws.
- C) The aluminum posts are to be connected to each of the bottom brackets with a total of (4) 1/2" TEC screws (1 screw from each side of the post). The brackets at the bottom of the posts are to be fastened to the beam below with (2) 6" long Fastenmaster Timberlok screws per side.
- D) The aluminum tracks securing the posts to the beams above and below are to be installed with 6" long Fastenmaster Timberlok screws installed at 24" o.c. and within 12" of corners.



т 919 773-1200 = F 919 773-9658 250 Shipwash Drive, Suite 104 = Garner = North Carolina = 27529

E) New rafters and ceiling joists are to consist of minimum 2 x 8 at 16" o.c. rafters/joists. Rafters/joists are to bear on the existing home with new 2 x 8 bands attached to the existing wall framing with (3) 2" SDS screws at 16" o.c. (i.e. every stud).

Upon completion, the new deck framing and new 3-Season Room framing will provide the required support for the anticipated loading conditions. We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,

Tyndall Engineering & Design

Tripp Amos


PT III | 2401-020288

Triggs Amos


Prentice Tyndall Jr., P.E.

DASE OZASE


τ 919 773-1200 * F 919 773-9658 250 Shipwash Drive, Suite 104 * Garner * North Carolina * 27529 www.tyndallengineering.com



т 919 773-1200 = в 919 773-9658 250 Shipwash Drive, Suite 104 = Garner = North Carolina = 27529 www.tyndallengineering.com



т 919 773-1200 = £ 919 773-9658 250 Shipwash Drive, Suite 104 = Garner = North Carolina = 27529 www.tyndallengineering.com



т 919 773-1200 = F 919 773-9658 250 Shipwash Drive, Suite 104 = Garner = North Carolina = 27529 www.tyndallengineering.com

