



~~NOA~~ NO NOA

IN GROUND POOL QUOTE SHEET

DATE: 5-4-2024

NAME: Ken + Val Seagraves

PRIMARY PHONE: (K) 919-270-1962 ALT PHONE: (V) 919-271-4602 (*)

ADDRESS: 33 Joel Way

CITY: Hillington STATE: NC ZIP: 27546

SUB DIVISION: NA COUNTY PERMIT: Hannett

SEWER/SEPTIC SYSTEM: Septic

PRIMARY EMAIL: KVKKSEA@AOL.COM

VINYL FIBERGLASS MANUFACTURER: Latham

MODEL: DASIS DESIGN: Rectangle SIZE: 18' X 36' X 5'

INTERIOR FINISH: _____

BASIC POOL PRICE: (INCLUDES STANDARD EQUIPMENT AND CONCRETE): 62,990.00

PUMP TYPE: Pentair Superflo VS PRICE: included

FILTER TYPE: Pentair SD 70 sand PRICE: included

SANITIZER TYPE: NA PRICE: NA

MINERAL SPRINGS SALT WATER CHEMICAL PACKAGE: PRICE: NA

LIGHTING TYPE: NA PRICE: NA

STEP TYPE: White Thermoplastic PRICE: included

LADDER TYPE: Stainless Steel PRICE: included

RAIL TYPE: Stainless Steel PRICE: included

AUTOMATIC CLEANER TYPE: NA PRICE: NA

SLIDE TYPE: NA PRICE: NA

DIVING BOARD:	<u>NA</u>	PRICE:	<u>NA</u>
HEATER:	<u>NA</u>	PRICE:	<u>NA</u>
WATER FEATURE:	<u>NA</u>	PRICE:	<u>NA</u>
CANTILEVER COPING:	<u>Standard Bullnose</u> ^{NO Bander}	PRICE:	<u>2750.00</u>
STONE FOUNDATION:	<u>NA</u>	PRICE:	<u>NA</u>
STONE BACKFILL:	<u>NA</u>	PRICE:	<u>NA</u>
ADDITIONAL ELECTRICAL:	<u>?</u>	PRICE:	<u>?</u>
FENCING:	<u>NA</u>	PRICE:	<u>NA</u>
FENCE GATE:	<u>NA</u>	PRICE:	<u>NA</u>
ADDITIONAL CONCRETE:	<u>NA</u>	PRICE:	<u>NA</u>
COVER:	<u>NA</u>	PRICE:	<u>NA</u>
RETAINING WALL:	<u>?</u>	PRICE:	<u> </u>
ACCESSORIES TOTAL:	<u>2750.00</u>	TAXES:	<u>192.50</u>
PERMITTING AND INSPECTION:	<u>Standard -</u>	PRICE:	<u>250.00</u>
TOTAL ESTIMATED PRICE:	<u>\$66,182.50</u>		

Does not include any additional ground prep, retaining walls, Drainage systems, ground water control, unseen obstacles below ground, or additions requested by customer during layout.

Note* Estimated prices are subject to change based on materials availability and manufacturers pricing at time of signing of final contract.

CUSTOMERS SIGNATURE: Val Seagraves

PARNELL REPRESENTATIVE: my J Barry



Expected time line for building a new IG Pool

Building your new IG pool takes, on average, between 5-6 weeks from start to finish.

Factors that affect the build time are:

1. Weather conditions (Rain, muddy conditions, power loss due to storms, ETC)
2. Site conditions (Ground water, sub-strata conditions, IE sand, Rocks, Stumps, ETC)
3. Availability of materials (Special orders, Vendor inventory, Shipping, ECT)
4. Labor issues (Build crew days lost to illness, injury, Ect)

Phases of the Pool Build:

- | | | |
|----------------|---|-----------|
| 1. Phase one | Digging, setting, leveling, and starting water | 5-10 days |
| 2. Phase two | Plumbing, electrical, bonding and electrical inspection | 1-2 weeks |
| 3. Phase Three | Backfill, forming and laying decking, dirt haul | 5-10 days |
| 4. Phase three | Curing of deck, final cleanup, indoctrination on pool operation | 5-10 days |

Fencing, if included in contract, will begin 1-2 weeks after completion of pool.

I, the undersigned, understand that build time for my IG Pool as listed above is a general time line and is subject to change based on building conditions.

Date: _____

Customer Signature _____ Print _____

Customer Signature _____ Print _____

Parnell Representative _____