



**North Carolina Onsite Wastewater Contractor Inspector Certification Board  
Authorized Onsite Wastewater Evaluator Permit Option for Non-Engineered Systems  
Notice of Intent (NOI) to Construct**

New     Expansion     Repair     Relocation     Relocation of Repair Area

Owner or Legal Representative Information:  
 Name: Katherine Wilkinson  
 Mailing address: 25 Corner Ln City: Cameron State: NC Zip: 28326  
 Phone: 803-468-5165 Email: wilkinsonwayne12@yahoo.com

Authorized Onsite Wastewater Evaluator Information:  
 Name: Hal Owen Certification #: 10036E  
 Mailing address: PO Box 400 City: Lillington State: NC Zip: 27546  
 Phone: 910-893-8743 Email: hal@halowensoil.com

Site Location Information:  
 Site address: 25 Corner Ln, Cameron, NC  
 Tax parcel identification number or subdivision lot, block number of property: \_\_\_\_\_  
PIN 9565-78-6778.000 County: Harnett

System Information:  
 Wastewater System Type: IIIb  
 Daily Design Flow: 480 gpd  
 Saprolite System:  Yes  No    Subsurface Operator Required:  Yes  No  
 Water Supply Type:  Private Well  Public Water Supply  Spring  Other: \_\_\_\_\_

Facility Type:  
 Residential 4 # Bedrooms 8 Maximum # of Occupants \_\_\_\_\_  
 Business    Type of Business and Basis for Flow: \_\_\_\_\_  
 Public Assembly    Type of Public Assembly and Basis for Flow: \_\_\_\_\_

Required Attachments:  
 Plat or Site Plan  
 Evaluation of Soil and Site Features by Licensed Soil Scientist


Attest: On this the 19 day of December, 2024 by signature below I hereby attest that the information required to be included with this NOI to Construct is accurate and complete to the best of my knowledge. Furthermore, I hereby attest that I have adhered to the laws and rules governing onsite wastewater systems in the state of North Carolina.  
 This NOI shall expire on 19 day of December, 2029.  
 Signature of Authorized Onsite Wastewater Evaluator: Hal Owen  
 Signature of Owner or Legal Representative: \_\_\_\_\_

Disclosure: The owner may apply for a building permit for the project upon submitting a complete NOI to Construct and the fee required (if any) to the local health department. An onsite wastewater system authorized by an authorized onsite wastewater evaluator shall be transferable to a new owner with the consent of the authorized onsite wastewater evaluator.

Local Health Department Receipt Acknowledgement:  
 Signature of Local Health Department Representative: \_\_\_\_\_ Date: \_\_\_\_\_



sa Road



**Legend**

- House
- Driveway
- Distances

Hal Owen & Associates Inc.  
PO Box 400, Lillington, NC 27546  
www.halowensoil.com  
919-893-8743

0 40 80 ft

For reference only. Not a survey.

25 Corner Ln  
Harnett Co., NC  
16 December 2024

Site Plan

**AOWE EVALUATION**

HAL OWEN ASSOCIATES  
www.halowensoil.com

# HOA-AOWE-2412-04

Issue date **12/19/2024**

Expiration **12/19/2029**

**APPLICANT INFORMATION**

Name	Katherine Wilkinson		
Mailing Address	25 Corner Ln, Cameron, NC 28326		
E-mail Address	<a href="mailto:wilkinsonwayne12@yahoo.com">wilkinsonwayne12@yahoo.com</a>	Telephone Number	803-468-5165

**PROPERTY IDENTIFIERS**

County	Harnett	PIN	9565-78-6778.000
Size (Acre)	0.72	County PID	
Site Address	25 Corner Ln, Cameron, NC 28326		
S/D Name and Lot#			

**PROJECT INFORMATION**

Wastewater System	New	.0403 Eng Low Flow	No
Wastewater Strength	Domestic	Effluent Standard	DSE
Facility Type	Residential	Water Supply	Public Water
Design Wastewater Flow	480 gpd	gal/unit	120
Basis for Flow	4 bedrooms	max occupancy	8
Basement	No	Fixtures in basement?	No
Crawl Space	Yes	Slab Foundation	No

**CONSULTANT INFORMATION**

Company Name	Hal Owen & Associates, Inc.		
Mailing Address	PO Box 400, Lillington, NC 27546		
E-mail Address	<a href="mailto:hal@halowensoil.com">hal@halowensoil.com</a>	Telephone Number	910-893-8743
Licensed Soil Scientist	Britt Wilson, LSS#1351	AOWE	Hal Owen, #10036E

A soil and site evaluation has been conducted for the referenced property for the purpose of permitting a subsurface wastewater system. This evaluation was prepared based on information provided by the applicant to include the basis for design flow, proposed structure location(s), and property boundaries. Any false, inaccurate, or incomplete information provided by the applicant, owner, or legal representatives may result in denial or revocation of applications, approvals, or permits.

This AOWE Evaluation is being submitted pursuant to and meets the requirements of G.S.130A-336.2. This evaluation includes a soil and site evaluation, specifications, plans, and reports for the site layout and construction of a proposed onsite wastewater system by an Authorized On-Site Wastewater Evaluator (AOWE). The evaluation of soil conditions and site features is provided in accordance with G.S. 130A-335(e), the Rules for "Wastewater Treatment and Dispersal Systems", 15A NCAC 18E, and local septic regulations (if any). This report represents my professional opinion as a Licensed Soil Scientist and Authorized Onsite Wastewater Evaluator.

*Britt Wilson*

*Hal Owen*



**WASTEWATER SYSTEM DESIGN SPECIFICATIONS**

Permit # **HOA-AOWE-2412-04**

Proposed Design Daily Flow	480	gpd
Septic Tank Size (minimum)	1000	gallons
Pump Tank Size (minimum)	1000	gallons, if required

Drainfield Meets Requirements:

.0508 Available Space	Yes
.0601 Setbacks	Yes

**Initial System**

System Type	Illbe – Pump to PPBPS system		
Pump Required	Yes	10.17	ft TDH at 25.0 GPM
Trenches:	PPBPS, horizontal		
Design LTAR	0.90	gal/day/ft <sup>2</sup>	Saprolite System <u>No</u>
Total Trench/ Bed Length	89	feet	Fill System <u>No</u>
Trench Spacing	9	ft on center	
Usable soil depth to LC	47	inches	
Maximum Trench Depth	21	inches, not to exceed 3" off contour	
Minimum Soil Cover	6	inches	
Artificial Drainage Required	No		

**Repair System**

System Type:	Illbe – Pump to PPBPS system		
Pump Required	Yes		
Trenches:	PPBPS, horizontal		
Design LTAR	0.90	gal/day/ft <sup>2</sup>	Saprolite System <u>No</u>
Total Trench/ Bed Length	89	feet	Fill System <u>No</u>
Trench Spacing	9	ft on center	
Usable soil depth to LC	47	inches	
Maximum Trench Depth of	21	inches, not to exceed 6" off contour	
Minimum Soil Cover	6	inches	

Potential Drainlines flagged at site on 9-ft centers.

Line #	Color	Rel Elev. (ft)	Relative Elev(ft)	Drainline Length(ft)	Field Length(ft)	
		Roadside				
1	Y	99.50	99.37	44	44	} Repair Initial
2	B	99.48	99.26	45	44	
3	W	99.22	99.52	44	44	
4	R	99.41	98.93	45	44	
<b>Septic Tank:</b>		99.42				
<b>Pump Tank:</b>		99.42				
<b>Reference Elev:</b>		<b>100.00</b>				

Notes:

- \*No grading or removal of soil in initial or repair areas
- \*Property lines per owner
- \*Trench bottoms shall be level to +/- 1/4" in 10ft
- \*All parts of septic system must meet minimum setbacks

# **HOA-AOWE-2412-04****PERMIT CONDITIONS**

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met.

System shall be installed in accordance with the attached Wastewater System Design Specifications. See attached SYSTEM LAYOUT for wastewater system design and location.

Any changes to the site plan or intended use must be approved by Hal Owen & Associates. Permit modification and resubmittal to the LHD may be necessary to ensure regulatory compliance.

Conformance to ALL regulatory setbacks shall be maintained. Local regulations (such as County, well, or riparian ordinances) may require more stringent setbacks than specified in the State septic regulations.

Minimum soil cover of six inches shall be established over dispersal field. Soil cover above the original grade shall be placed at a uniform depth over the entire dispersal field and shall extend laterally five feet beyond the dispersal trench. Site shall be graded to shed water away from field and a vegetative cover established to prevent erosion.

The dispersal field and repair area shall not be subject to vehicular traffic. Vehicular traffic can damage soils, pipes, and valve boxes. Do not use septic areas for parking.

Do not allow underground utilities, water lines, or sprinkler systems to be installed in the septic areas. Damage to the septic areas could result in the septic permit being revoked.

The wastewater system shall not be covered until inspected by Hal Owen & Associates and shall not be placed into use until an Authorization to Operate is issued.

**SPECIFIC REQUIREMENTS**

A pre-construction conference with the septic contractor is required prior to installation.

Call Hal Owen & Associates at least five days in advance to schedule 910-893-8743

The inlet and outlet of all tanks shall be equipped with an approved pipe penetration boot.

The pump tank may be eliminated if gravity distribution can be demonstrated.

Multiple existing septic systems were located on this property,

The existing septic tanks must be properly abandoned

Drainlines in the initial system shall be installed off contour, not to exceed 3 inch.

Drainlines in the repair system shall be installed off contour, not to exceed 6 inch.

Notes:  
 \*No grading or removal of soil in initial or repair areas  
 \*Property lines per owner  
 \*Trench bottoms shall be level to +/- 1/4" in 10ft

### Legend


- House
- Driveway
- Distances
- Reference Elevation

#### Septic Components

- Septic Tank
- Pressure Manifold
- Pump Tank
- Existing Septic Tank

#### Drainlines

- Initial
- Repair
- Supply Line



Design Daily Flow: 480 gpd

Initial System:  
 PM to 89' (x3ft) Lines 1-2  
 Horizontal PPBPS (50% reduction system)  
 Installed off contour, NTE 3", MTD 21"  
 LTAR 0.9 gal/day/sqft

Repair System:  
 PM to 89' (x3ft) Lines 3-4  
 Horizontal PPBPS (50% reduction system)  
 Installed off contour, NTE 6", MTD 21"  
 LTAR 0.9 gal/day/sqft



Hal Owen & Associates Inc.  
 PO Box 400, Lillington, NC 27546  
 www.halowensoil.com  
 919-893-8743

0 50 100 ft

For reference only. Not a survey.

25 Corner Ln  
 Harnett Co., NC  
 19 December 2024

Septic Layout

**INITIAL WASTEWATER SYSTEM**

Permit # HOA-AOWE-2412-04

**DESIGN DAILY FLOW** 480 gallons/day **SOIL LTAR:** 0.90 gpd/ft<sup>2</sup>  
**TANKS (minimum)** Septic Tank 1000 gallons Pump Tank 1000 gallons  
**SUPPLY LINE** Length (ft): 95 Diameter: 2 " sch 40 pvc  
 Min total flow (gpm) to maintain 2 fps scour velocity = 20.89

**TRENCHES** Drainline Type: PPBPS, horizontal  
 Maximum Trench Depth of 21 inches, measured on low side of trench  
 Trench width: 3 feet Effective Trench Width: 6 ft  
 Absorption Area: 267 ft<sup>2</sup> Minimum Linear Length: 89 ft  
 ÷ 4.33 ft per panel : 21 panels

**PRESSURE MANIFOLD**

# Taps 2 Tap Configuration: 6in. spacing, 1 side of manifold  
 Length (ft): 2.5 Diameter: 4" sch 80 pvc Elevation: 100.5

**TAP CHART**

Tap #	Line #	Color	Elevation (ft)	Drainline Length(ft)	Number of Panels	Tap Size/ Schedule	Flow/tap (gpm)	LTAR (gpd/ft <sup>2</sup> )
1	1	Y	99.5	44	10	3/4"sch 40	12.50	1.818
2	2	B	99.48	45	11	3/4"sch 40	12.50	1.778
			Totals:	89	21	Total Flow:	25.00	

Target LTAR\*: 1.80  
 LTAR + 5%: 1.890

**Pump Calculations:**

Number of Panels: 21  
 Dose Volume: 75.6 gallons # of panels \* 3.6 gallons/ panel  
 Dose Pump Run Time: 3.02 minutes Dose volume/total flow  
 Daily Pump Run Time: 19.20 minutes Daily Flow/total flow  
 Drawdown (in.): 76 gallons ÷ 20.25 gal/ inch = 3.73 inches  
 Pump Tank Elevation (ft): 99.42 Pump Elevation (ft): 94.42  
 Friction Head: 2.09 \*Hazen Williams Formula (use supply line length+70' for fittings in pump tank)  
 Elevation Head: 6.08 Design Head: 2.0 Total Head: 10.17 feet  
 Pump to Deliver: **25.00** gpm @ **10.17** ft head

NEMA 4X Simplex Control Panel with elapsed time meter, event counter, audible and visible alarm (w/ silence button), hand-off-automatic (HOA) switch, pump run light, and pump on separate circuits is required. Control panel bottom shall be mounted a minimum of 24 in. above finished grade within 50 ft of pump tank. A septic tank filter is required. Floats to be determined by type of pump tank used.

Possible Septic Tank: Brantley 1000 STB-502 Septic Filter: \_\_\_\_\_  
 Possible Pump Tank: Brantley 1000\_PT-237 Vol(gal): 1000 GPI: 20.25  
 Possible Pump: \_\_\_\_\_ pump height (in) = 14  
 Possible Control Panel: \_\_\_\_\_




**INITIAL WASTEWATER SYSTEM**

Permit # HOA-AOWE-2412-04

**Pressure Manifold Diagram**

Tap#	1	2
Manifold	4" SCH 80 PVC	
tap size	3/4" sch 40	3/4" sch 40
flow (gpm)	12.50	12.50
line length (ft)	44	45




INITIAL WASTEWATER SYSTEM

Permit # HOA-AOWE-2412-04


Typical Septic Tank

1000 GALLON SEPTIC TANK, minimum



Typical Pump Tank

1000 GALLON PUMP TANK, minimum



**INITIAL WASTEWATER SYSTEM**

Permit # **HOA-AOWE-2412-04**

**Pump Tank Calculations:**

Possible pump tank: Brantley 1000\_PT-237

Possible Pump: \_\_\_\_\_


tank GPI (gal/in): 20.25 calculated

height: 14 inches

tank volume (gal): 1000 per manufacturer

tank height (in): 50.0 per manufacturer


minimum emergency storage: 240 gal



Drawing N.T.S.

**Supply Line Profile:**

	Distance	Elevation
Pump	0	94.42
pump tank	1	99.42
Pressure manifold	95	100.5
4)		
5)		



**REPAIR WASTEWATER SYSTEM**

Permit # HOA-AOWE-2412-04

**DESIGN DAILY FLOW** 480 gallons/day **SOIL LTAR:** 0.90 gpd/ft<sup>2</sup>  
**TANKS (minimum)** Septic Tank 1000 gallons Pump Tank 1000 gallons  
**SUPPLY LINE** Length (ft): 80 Diameter: 2 " sch 40 pvc  
 Min total flow (gpm) to maintain 2 fps scour velocity = 20.89

**TRENCHES** Drainline Type: PPBPS, horizontal  
 Maximum Trench Depth of 21 inches, measured on low side of trench  
 Trench width: 3 feet Effective Trench Width: 6 ft  
 Absorption Area: 267 ft<sup>2</sup> Minimum Linear Length: 89 ft  
 ÷ 4.33 ft per panel : 21 panels

**PRESSURE MANIFOLD**

# Taps 2 Tap Configuration: 6in. spacing, 1 side of manifold  
 Length (ft): 2.5 Diameter: 4" sch 80 pvc Elevation: 100.52

**TAP CHART**

Tap #	Line #	Color	Elevation (ft)	Drainline Length(ft)	Number of Panels	Tap Size/ Schedule	Flow/tap (gpm)	LTAR (gpd/ft <sup>2</sup> )
1	3	W	99.52	44	10	3/4"sch 40	12.50	1.818
2	4	R	98.93	45	11	3/4"sch 40	12.50	1.778
			Totals:	89	21	Total Flow:	25.00	


Target LTAR\*: 1.80  
 LTAR + 5%: 1.890

**Pump Calculations:**

Number of Panels: 21  
 Dose Volume: 75.6 gallons # of panels \* 3.6 gallons/ panel  
 Dose Pump Run Time: 3.02 minutes Dose volume/total flow  
 Daily Pump Run Time: 19.20 minutes Daily Flow/total flow  
 Drawdown (in.): 76 gallons ÷ 20.25 gal/ inch = 3.73 inches  
 Pump Tank Elevation (ft): 99.42 Pump Elevation (ft): 94.42  
 Friction Head: 1.90 \*Hazen Williams Formula (use supply line length+70' for fittings in pump tank)  
 Elevation Head: 6.1 Design Head: 2.0 Total Head: 10.00 feet  
 Pump to Deliver: **25.00** gpm @ **10.00** ft head

NEMA 4X Simplex Control Panel with elapsed time meter, event counter, audible and visible alarm (w/ silence button), hand-off-automatic (HOA) switch, pump run light, and pump on separate circuits is required. Control panel bottom shall be mounted a minimum of 24 in. above finished grade within 50 ft of pump tank. A septic tank filter is required. Floats to be determined by type of pump tank used.

Possible Septic Tank: Brantley 1000 STB-502 Septic Filter: \_\_\_\_\_  
 Possible Pump Tank: Brantley 1000\_PT-237 Vol(gal): 1000 GPI: 20.25  
 Possible Pump: \_\_\_\_\_ pump height (in) = 14  
 Possible Control Panel: \_\_\_\_\_



Hal Owen & Associates Inc.  
 PO Box 400, Lillington, NC 27546  
 www.halowensoil.com  
 919-893-8743

0 50 100 ft



For reference only. Not a survey.



25 Corner Ln  
 Harnett Co., NC

16 December 2024

Soil Map for Septic Suitability

# AOWE EVALUATION

HAL OWEN ASSOCIATES  
www.halowensoil.com

Permit # HOA-AOWE-2412-04

## SOIL/SITE EVALUATION FORM FOR ON-SITE WASTEWATER SYSTEM

OWNER NAME: Katherine Wilkinson  
 PROPOSED FACILITY: Residential DESIGN DAILY FLOW: 480 WATER SUPPLY Public Water  
 LOCATION OF SITE: 25 Corner Ln, Cameron, NC 28326 PIN: 9565-78-6778.000  
 WASTEWATER TYPE: Domestic COUNTY: Harnett  
 EVALUATION METHOD: AUGER BORING  PIT  CUT   
 EVALUATED BY: Britt Wilson, LSS#1351 DATE EVALUATED: 12/13/24

	INITIAL SYSTEM	REPAIR SYSTEM
AVAILABLE SPACE	267 ft <sup>2</sup> trench bottom	267 ft <sup>2</sup> trench bottom
SYSTEM TYPE	PPBPS, horizontal	PPBPS, horizontal
SITE LTAR	0.90 gpd/ft <sup>2</sup>	0.90 gpd/ft <sup>2</sup>
MAX TRENCH DEPTH	21 inches (measured on downhill side)	21 inches (measured on downhill side)
SITE CLASSIFICATION	<u>Suitable</u>	OTHER FACTORS _____

COMMENTS:

### PROFILE 1

HORIZON DEPTH	COLOR	CONSI TENCE	TEXTURE	STRUCTURE	MINERA LOGY	OTHER PROFILE FACTORS	
0-4	10YR 4/2	VFR	LS	GR	SEXP	LANDSCAPE POSITION	
4-15	10YR 5/3	VFR	LS	GR	SEXP	SOIL WETNESS DEPTH	47"
15-40	2.5Y 6/4	VFR	LS	GR	SEXP	SOIL WETNESS COLOR	2.5Y 7/2
40-48+	2.5Y 6/6	FR	SL	SBK	SEXP	SOIL DEPTH	48"
						SAPROLITE CLASS	NA
						RESTRICTIVE HORIZON	NA
						SLOPE %	2
PROFILE CLASSIFICATION			<b>Suitable</b>	LTAR gpd/ft <sup>2</sup>	<b>0.9</b>	SLOPE CORRECTION (IN)	0.7
COMMENT: Max trench depth of 21 inches due to existing drainlines buried deeper in soil profile.							

**SOIL/SITE EVALUATION FORM FOR ON-SITE WASTEWATER SYSTEM**

**LEGEND OF ABBREVIATIONS**

<b>LANDSCAPE POSITION</b>	<b>TEXTURE GROUP</b>	<b>TEXTURE CLASS</b>	<b>LTAR (gal/day/sqft)</b>
CC - Concave Slope	I	S - Sand	1.2-0.8
CV - Convex Slope		LS - Loamy Sand	
DS - Debris Slump	II	SL - Sandy Loam	0.8 – 0.6
D - Depression		L - Loam	
DW - Drainage Way			
FP - Flood Plain	III	SCL - Sandy Clay Loam	0.6 – 0.3
FS - Foot Slope		CL - Clay Loam	
H - Head Slope		SiL - Silt Loam	
L - Linear Slope		Si - Silt	
N - Nose Slope		SiCL - Silt Clay Loam	
R - Ridge	IV	SC - Sandy Clay	0.4 – 0.1
S - Shoulder Slope		C - Clay	
T - Terrace		SiC - Silty Clay	
TS - Toe Slope		O - Organic	
<b>STRUCTURE</b>	<b>MOIST CONSISTENCE</b>	<b>WET CONSISTENCE</b>	
G - Single Grain	VFR - Very Friable	NS - Non Stick	
M - Massive	FR - Friable	SS - Slightly Sticky	
CR - Crumb	FI - Firm	MS - Moderately Stick	
GR - Granular	VFI - Very Firm	VS - Very Sticky	
SBK - Subangular Blocky	EFI - Extremely Firm	NP - Non Plastic	
ABK - Angular Blocky		SP - Slightly Plastic	
PL - Platy	<b>MINERALOGY</b>	MP - Moderately Plastic	
PR - Prismatic	SEXP - Slightly Expansive	VP - Very Plastic	
	EXP - Expansive		
<b>MOTTLES</b>	f – few	1 - fine	F - Faint
	c – common	2 - medium	D - Distinct
	m – many	3 - coarse	P - Prominent

Give Horizon Depth in inches below natural soil surface and Fill Depth in inches above land surface.

Depth to Soil Wetness: inches below land surface to free water or to soil colors with chroma 2 or less.

Classification:           S – Suitable                           U – Unsuitable

All soil characteristics were described in accordance with the USDA Field Book for Describing and Sampling Soils. The soils were evaluated under moist soil conditions. This evaluation included observations of topography and landscape position, soil morphology (texture, structure, clay mineralogy, organics), soil wetness, soil depth, and restrictive horizons.

## TERMS AND CONDITIONS

This AOWE Evaluation is intended to file a Notice of Intent to construct a wastewater system with the Local Health Department and shall expire in five years. This evaluation is not a permit to develop. The owner and subcontractors will need to abide by all state and local rules and regulations pertaining to planning, zoning, and land use development.

Notice of Intent to Construct – Prior to commencing or assisting in the construction, siting, relocation, or repair of a wastewater system, a complete Notice of Intent (NOI) to Construct a wastewater system using an AOWE must be submitted to the Local Health Department (LHD). The owner may apply for a building permit for the project upon submitting a complete NOI and the required fee.

Plan Alterations – If there are any changes in the site plan that can impact the wastewater system, such as moving the house or driveway, site alterations, or if the applicant chooses to change the design daily flow prior to wastewater system construction, a new NOI shall be submitted to the LHD. The applicant shall request in writing that the PE or AOWE invalidate the prior NOI with a signed and sealed letter sent to the applicant and LHD.

Site Alterations – The applicant shall be responsible for preventing modifications or alterations of the site for the wastewater system and the system repair area before, during, and after any construction activities for the facility, unless approved by the AOWE.

On-Site Wastewater System Contractor – The AOWE shall assist the owner in the selection of a certified on-site wastewater system contractor who shall be under contractual obligation to the owner and have sufficient errors and omissions, liability, or other insurance for the system constructed.

Inspections, Construction Observations, and Reports – The AOWE shall make periodic visits to the site to observe the progress and quality of the construction of the wastewater system.

Authorization to Operate (ATO) – Upon determining that the wastewater system has been properly installed and is capable of being operated in accordance with the conditions of the permit, the AOWE shall provide the owner with a report that includes inspection reports, a written operation and management program, any special reports, and an Authorization to Operate. The owner shall sign confirming acceptance and receipt of the report, and then provide a copy to the LHD who will issue the certificate of occupancy for the facility.

Operation and Management – The owner shall be responsible for continued adherence to the operations and management program established by the AOWE. This permit shall in no way be taken as a guarantee or implied warranty that the septic system will function satisfactorily for any given period of time.

Change in System Ownership – An authorized wastewater system shall be transferrable to a new owner with the consent of the AOWE. The new owner and the AOWE shall enter a contract for the wastewater system.

Revocation – The AOWE permit is subject to revocation if the site plan, plat, or the intended use changes. This permit is subject to compliance with the provisions of the laws and Rules for Wastewater Treatment and Dispersal Systems and to the conditions of this permit.

Repair of Malfunctioning Systems – The owner may apply for an Improvement Permit and a Construction Authorization from the LHD or obtain a NOI from an AOWE to repair a malfunctioning wastewater system.