

Notes

- 2x8 double bands
- 2x10 double drop girder
- 3x6 joist 16" on center
- 2x4 Ledger 4 galvanize nails
- under each joist
- 5/8" x 8" carriage bolts thru
- knockst post
- 4x8x16 solid block under
- post 16" below ground level
- 2x4 railing
- 2x2 balusters 3 1/2" apart
- 2x1/2 step stringers no more than
- 7" rise
- Steps 40" wide

