

We will be completing the following:

1. HVAC Changeout

- a. Like for like change out of the existing system with a 2-ton split heat pump system

2. Duct Replacement

- a. Replacement of the flexible duct work in the crawlspace.

3. Encapsulation of the crawlspace

- a. Removal of the floor insulation
- b. Sealing of the crawlspace with foam board
- c. Installation of a vapor barrier
- d. Installation of a dehumidifier

4. Installation of a dedicated circuit/GFI for the dehumidifier

- a. Running a new circuit from the panel box to the crawlspace.