

Building Plan:
205 Sneed Lane
Fuquay Varina, NC 27526

- Covered Screened patio
- Final covered area is 14'x14'

- Footings: Footings included in monolithic slab. Footing location will be dug out 18" deep. Slab reinforced with wire mesh and poured on 5" compacted ABC base

- Posts: 6x6 posts notched to receive beam, attached to footing using Simpson Strongtie 6x6 footing bracket

- Post height: 8'

- Beams: 2ply 2x10 beam

- 2x6 rafters, 16" o.c.. Rafters attached with rafter ties to ridge beam.

Roof:

-Radiant barrier 7/16" roof sheathing

- Total height: 10'-3 7/16"

- 3/12 pitch roof

