



Scope of Work for:

**385 Evelyn Lane
Dunn, NC 28334**

*CrawlSeal System to include the following:

-20 ml Vapor Barrier installed wall to wall with 100% floor coverage. All sections of liner will be overlapped a minimum of 1' and will be seamed together, attached with Christmas Tree fasteners, and caulked.

-Install WallSeal on basement walls to help prevent water vapor and moisture intrusion as well as direct wall leakage to the waterproofing system. (12 ml Vapor Barrier on Walls)

-Wrap all existing CMU/Brick Piers 20 ml Vapor Barrier. Contractor will leave a termite inspection gap at the top of each pier. The liner will be fastened to the pier and the top edge of the liner will be sealed with caulking.

-All Vents will be sealed from inside the crawl space with R-10 Rigid 2" Foam Sheathing.

*AprilAire E100 Dehumidifier install - unit specifications on page 2

*Existing R-19 insulation will remain in the floor system.

*Electrical - Installation of new dedicated 120vac/20amp electrical circuit/s and electrical outlet/s (WP-GFCI) to supply sump pump and /or dehumidifier in crawl space (basement).

Touchstone Electric

8601 Six Forks Road

Unit 400

Raleigh, NC 27601

(919) 670-4015

dispatch@touchstoneelectric.com

License # U.37073

TARHEEL™

BASEMENT SYSTEMS










A Groundworks Company


SPECIFICATIONS		
Capacity		
	@ 80°F/60% RH	100 ppd
	@ 73°F/60% RH	85 ppd
Energy Factor		
	@ 80°F/60% RH	2.6 L/kW-h
	@ 73°F/60% RH	2.35 L/kW-h
Airflow @ varying E.S.P. (external static pressure - dry coil)		
	0.0" w.c.	280 CFM
	0.2" w.c.	245 CFM
	0.4" w.c.	210 CFM
Voltage, phase, frequency	120VAC, 1 phase, 60 Hz	
Current draw⁽¹⁾	6.9 Amps	
Noise	55 dBA ducted	
Dimensions: (cabinet only)⁽²⁾	Width: 14" Height: 15" Length: 26"	
Unit Weight	64 lbs.	
Shipping Weight	82 lbs.	
Inlet air operating conditions during		
-Dehumidification:	50°F-104°F, 40°F dew point min.	
-Ventilation:	40°F-140°F, 0%-99% RH (non-condensing)	
<small>⁽¹⁾Rated capacity, energy factor and current draw measured at 80°F/60% RH inlet air at 0.0 ESP.</small>		
<small>⁽²⁾Height does not include adjustable feet. The width excludes the filter doors and length excludes the duct collars.</small>		

Tar Heel Basement Systems
 Certified Foundation and Waterproofing Inspector
 Jordan Williams
 910.919.1748
 jordan.williams@tarheelbasementsystems.com

Signature: *J. Williams*

Ashley Ennis
 C#244076
 385 Evelyn Ln. Dunn NC 28334

-  Discharge Line
-  Crawl Drain
-  AquaStop Sump Pump
-  AquaStop Air System
-  Electric Outlet
-  Crawl Seal
-  X-block
-  Biocide spray w/ insulation pull
-  20-Mil Vapor Barrier



FRONT