



Existing Storage Room

Closet Framed with 2"X4"s  
Drywalled with 1/2 Drywall

5' Closet Doors (Double Hung) 

**General Notes:**

1. REFER TO SHEET 01.1 FOR GENERAL NOTES.
2. ALL SECOND FLOOR CEILINGS TO BE 9'-11" ABOVE SUBFLOOR UNLESS OTHERWISE NOTED.
3. FRAME TOP OF ALL WINDOWS AT 4" BELOW TOP OF PLATE UNLESS OTHERWISE NOTED.
4. ALL DROPPED INTERIOR HEADERS (FALLS AND BEAMS) ARE DROPPED 1" FROM CEILING.
5. ALL SECTION SHIMS FOR FLOORING MATERIAL PRIOR TO CONSTRUCTING SHIMS TO DETERMINE RISE & FALLS.
6. REFER TO SHEET 2.025 FOR STRUCTURAL INFORMATION.

**Key Notes:**

- 202A 2x4 BALLOON FRAMED WALL AT STAIRS - SEE SHEET 2.025 FOR MORE INFO
- 202B 18" HIGH WALL SCOTED WITH STAIR SPRINGER
- 202D 18" HIGH WALL
- 202G FRAME TOP OF WINDOW AT 10'-0" BELOW TOP PLATE
- 202H FRAME TOP OF WINDOWS AT 10'-0" BELOW TOP OF PLATE
- 202A SEE DETAIL N02.1 FOR WALL AT RIC ACCESS DETAILS
- 202P FULL DOWN ATTIC ACCESS STAIRS (25'-11/2" x 5'-4") WITH LIGHT AND OUTLET

Space for Architect Seal



The Drees Company  
12/15/2022 12:21:17 PM

RESIDENCE FOR:  
**ROSE**  
70 Comfort Court  
SERENITY - 50'

Job Number: **ST15-0040-00** Drawing Date: **12/19/22** Coord Name: **GREG PIER** Coord Release: **859-578-4355**  
Revised Name: Drawing Scale: 1/8" = 1'-0"

the HAVEN II

Room on Date: 08/11/22 CD: Drawn By: CLM Plan No.: PLAN\_NIM



Sheet Information  
**2.02F**  
Second Floor Framing Plan  
Elevation "B"

