

1. All post thru-bolted
2. 6" x 6" will be on outer dble band. 10' High.
3. 4" x 6" will be under deck posts. 8' - 10' High
4. 12" cemented under grade. To Code
1. Outside band will be 2" x 12" > thru-bolted
2. Inside band will be 2" x 10"
1. All Joists will be 2" x 10" w/ joist hangers.
1. Band on Foundation will be thru bolted.
1. 4' x 4' posts for railing every 5' thru-bolted
2. SS wire according to Code installed
3. 2" x 4" ~~trex~~ treated inbetween posts with square edge 1" x 6" Trex on top.
1. Steps will be 5' wide with 3x5 step risers. Square edge trex will go over treated steps.
1. 14' x 16' decking to Right side of house will be covered x 23/32" x 4' x 8' Treated plywood.

* All Work Performed to Code.