



ELEVATIONS SHOWN ON THIS PAGE REPRESENT BASIC COMPONENTS AND ARE NOT INTENDED TO BE ALL INCLUSIVE, NOR DO THESE ELEVATIONS DETAIL EVERY CODE REQUIRED ASPECT OF THIS BUILDING. SITE BUILT STOOPS, STEPS, DECKS, PORCHES, HANDRAILS AND/OR SIMILAR ITEMS MUST BE PROVIDED BY OTHERS ON SITE FOR COMPLIANCE WITH APPLICABLE CODES. COMPLIANCE WITH ALL APPLICABLE CODES PER LOCAL AUTHORITY HAVING JURISDICTION, WHETHER DETAILED IN THIS SET OR NOT, MUST BE MET.


Note: Window fall protection must be provided on-site where required in accordance with applicable code.




FRONT VIEW



REAR VIEW



RIGHT VIEW



LEFT VIEW

-NOTES-


1. FOUNDATION SHALL BE DESIGNED AND CONSTRUCTED BY OTHERS WHERE "OTHERS" REFERS TO THE DEALER BUILDER.
2. GUTTERS AND LEADERS SHALL BE INSTALLED BY OTHERS.
3. TYPICAL 12" OR 15" VINYL SHUTTERS PROVIDED BY MANUFACTURERS.
4. ALL FOOTINGS, RAILINGS AND STEPS SHALL BE FIELD INSTALLED IN COMPLIANCE WITH APPLICABLE STATE AND LOCAL CODES.
5. SIDING SHALL BE VINYL SIDING WITH VINYL TRIM, AND MAY BE PARTIALLY INSTALLED ON SITE.
6. EXTERIOR LIGHTS MAY BE SHIPPED LOOSE FOR INSTALLATION ON SITE.
7. ROOFING SHINGLES MAY BE PARTIALLY SITE INSTALLED.
8. PORCH RAILINGS ARE PVC. TREATED LUMBER PORCH POSTS MAY BE COVERED WITH VINYL. PORCH DECKING SHALL BE TREATED.
9. ALL EXTERIOR COVERINGS SHALL BE WEATHER AND DECAY RESISTIVE TO PROVIDE PROPER PROTECTION FOR UNTREATED MATERIALS.

NOTE:
HOMES WITH ATTIC SPACE QUALIFYING AS HABITABLE, MUST BE EQUIPPED WITH EMERGENCY ESCAPE AND RESCUE OPENINGS REGARDLESS OF WHETHER ATTIC AREA IS FINISHED OR UNFINISHED. OPENINGS MAY OCCUR AT END WALL OF ATTIC AND/OR AT ROOF DORMERS IN WHATEVER ARRANGEMENT NECESSARY TO INSURE THAT ANY SLEEPING ROOM HAS AT LEAST ONE EGRESS OPENING.



Builder: TCC VANDERBUILT	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: N.T.S.	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
		Drawn By: NE	Reference: 2R2010-R	Dir: HBV	S/N: 44850	Pg.: EL	Run:	

ALL SITE CONSTRUCTION TO MEET 2018 ED. OF THE IBC RESIDENTIAL BUILDING CODE, SUBJECT TO LOCAL JURISDICTION INSPECTION AND APPROVAL.
ALL FASTENING NOT SPECIFIED TO MEET THE IBC. RESIDENTIAL BUILDING CODE.



CUSTOMER	CITY	COUNTY	VARIOUS
STATE	NC	STATE	NC
WIND SPEED	110	WIND LOAD	32.4
SNOW LOAD	20	SNOW LOAD	20
CUST. NO.	DRAWING NAME		

DATE:	7/08/08	BY:	BRB	NOTE:
REVISION:	CR12	BY:	CR12	NOTE:

SHED PORCH DETAIL

DATE: 7/08/08 BY: BRB

REVISION: CR12

FILE: T:\MISCELLANEOUS\SHED PORCH 2012.DWG

HOMES BY VANDERBUILT

3300 JEFFERSON DAVIS HWY
SANFORD, NC 27332
PHONE: (919) 718-2760
FAX: (919) 718-2799

BEAM SIZING CHART

GROUND SNOW LOAD (psf) 30

HEADER SIZE	MAX. SPAN
2-2x8	7'-4"
2-2x10	9'-0"
3-2x8	9'-3"
3-2x10	11'-4"

VALUES DERIVED FROM TABLE R502.5(1) NCRC INTERPOLATED TO 16' BUILDING WIDTH.

DESIGN APPLICABLE FOR UNITS UP TO 130 MPH, EXP. C.

Footing size (in.)	Footing max. load (lbs.) for 8" x16" pier		
	1500 PSF	2000 PSF	2500 PSF
*16x16x6	2.5K	3.4K	4.3K
*20x20x6	4.0K	5.3K	6.7K
24x24x8	5.6K	7.6K	9.6K
30x30x10	8.5K	11.7K	14.8K
36x36x12	12.4K	16.7K	20.7K
42x42x14	16.5K	22.4K	28.2K
48x48x14	21.2K	N/A	N/A
* = A 4" thick pre-cast footer of equivalent width and length may be used in place of a 6" thick cast in place footer.			
Footer size must be designed by others to site conditions if noted kip load exceeds capacities listed above			

COLUMNS & FOOTINGS
MUST BE RATED TO
MEET THE CENTER
LINE LOADS LISTED

GROUND SNOW LOAD


20
PSF

Kip loads noted are based on allowable stress design (ASD).
Capacity of supports (columns, footings, etc.) must exceed noted Kip loads.
Any changes to this plan that effect the foundation in any way will be the sole responsibility of the builder/dealer.

SELF-WEIGHT ON FOOTERS NOT INCLUDED IN LOADS SHOWN.
♦ IF APPLICABLE, REPRESENTS TIE DOWN LOADS FROM BRACE WALLS
TO FOUNDATION. TO BE DESIGNED ON SITE BY OTHERS.

FOR CONNECTION OF THE HOME TO FOUNDATION AT BRACING WALLS, REFER TO "BRACED WALLS-CALCULATED" PAGE, IF APPLICABLE. WHEN THIS PAGE IS PRESENT, HORIZONTAL AND OVERTURNING (RACKING) LOADS AT BRACING WALL LOCATIONS ARE INDICATED FOR THESE FOUNDATION CONNECTIONS. THESE LOADS MAY BE RECALCULATED AND REDESIGNED PER LOCAL CODES TO CONFORM TO SITE CONDITIONS AS REQUIRED. REFER TO CHAPTER 3 (3.9 TIE DOWN TO FOUNDATION) OF THE "MODULAR HOME INSTALLATION MANUAL" FOR ADDITIONAL INFORMATION. REFER TO APPLICABLE CODES FOR CONNECTION OF HOME TO FOUNDATION WHEN "BRACED WALLS-PRESCRIPTIVE" PAGE IS APPLICABLE.


FOUNDATION SHOWN MUST BE DESIGNED BY OTHERS TO THE SITE CONDITIONS. THIS INCLUDES SEISMIC DESIGN AND ATTACHING THE HOME TO THE FOUNDATION, ALONG WITH RESISTANCE TO LATERAL, LONGITUDINAL SHEAR, UPLIFT AND DOWNLIFT FORCES IN BOTH DIRECTIONS.



- 2X10 OR TRUSS FLOOR NOTES -
- FOUNDATION LAYOUT IS APPLICABLE TO NOTED MAXIMUM SNOW LOADING AND MINIMUM SOIL BEARING PRESSURE. REFER TO INSTALLATION MANUAL FOR OTHER APPLICABLE INFORMATION. CONSULT LOCAL OFFICIALS AND THE APPLICABLE LOCAL CODES FOR OTHER REQUIREMENTS (I.E. DRAINAGE, DAMP-PROOFING, BACKFILL SUPPORT, ETC.).
 - WIDTH DIMENSIONS SHOWN INCLUDE A 3/4" ALLOWANCE PER HOME SECTION FOR HOMES WITH FACTORY-INSTALLED O.S.B. ON THE MARRIAGE WALL MATE LINE. THIS ALLOWANCE TAKES INTO ACCOUNT THE 7/16" O.S.B. MATERIAL INSTALLED ON EACH MARRIAGE WALL PLUS ALLOWANCE DUE TO OTHER FACTORS. IF HOME DOES NOT INCLUDE O.S.B. ON THE MARRIAGE WALL MATE LINE, FOUNDATION WIDTH IS TO BE SIZED EQUAL TO ACTUAL MANUFACTURED FLOOR WIDTH. LESSER DIMENSION, IF SHOWN, INDICATES ACTUAL FLOOR WIDTH. THESE DIMENSIONS DO NOT ALLOW FOR ANY VARIANCE THAT MAY OCCUR IN SITE INSTALLATION SUCH AS GAPPING, OFF CENTER SET OR OTHER FIELD-ENCOUNTERED VARIABLES. ANY ADJUSTMENTS NEEDED IN FOUNDATION WIDTH DUE TO SUCH VARIANCES ARE AT THE DISCRETION OF THE INSTALLER.
 - FOR DEVIATIONS &/OR OTHER FOUNDATION DESIGNS CONSULT A LOCAL PROFESSIONAL ENGINEER & YOUR LOCAL BUILDING OFFICIAL.
 - SILL PLATE FASTENING TO BE PER INSTALLATION MANUAL AND/OR LOCAL CODES. SILL FASTENING REQUIREMENT IS PER APPLICABLE WIND SPEED AND SEISMIC ZONES. SEE YOUR HOME DATA PLATE FOR APPLICABLE ZONES.
 - CONCRETE COMPRESSIVE STRENGTH (FC'): 2500 PSI MINIMUM.
 - CENTERLINE LINE SUPPORTS AND SPACING ARE BASED ON (2) 2X10'S SPF#2 ON EACH HALF (4-2X10'S TOTAL).
 - CRAWLSPACE VENTILATION IS NOT REQUIRED WHEN INSULATION IS APPLIED TO CRAWLSPACE WALLS AS REQUIRED BY RESCHECK (CONDITIONED AIR). INSTALLATION OF VENTS IN CRAWLSPACE WALLS WOULD MANDATE INSULATING THE FLOOR SYSTEM PER APPLICABLE THERMAL CALCULATIONS. REFER TO APPLICABLE PRESCRIPTIVE CODES & GUIDELINES. WHEN REQUIRED, ONE VENT SHALL BE PROVIDED WITHIN 3 FEET OF EACH CORNER.
 - FOUNDATION CONSTRUCTION AND TIE DOWN REQUIREMENTS FOR HOMES LOCATED IN 90 MPH OR LESS WIND ZONES MAY USE APPLICABLE PRESCRIPTIVE CODES & GUIDELINES UNLESS NOTED OTHERWISE.


Builder: TCC VANDERBUILT LLC.	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 1/8" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code:	Number:	Order/Plan Number:
					Dir: HBV	D9	42763B	2025-1003370
		Drawn By: NE	Reference: 2R2010-R	S/N: 44850	Pg.: FD20#	Run:		
Title: Foundation 2x10 Marriage Line without Stair								

N.C. Foundation Cross Section- 90 to 130 Mph 1-1/2, 2, OR 2-1/2 STORY




Applicable to Seismic Zone C with minimum soil bearing capacity of 1500 PSF. Concrete 2500-PSI min. Wind speed up to 130 Mph Exp. C. Refer to Chapter 4 in the North Carolina Residential Code for specific foundation application or CMU Construction. Refer to the wind bracing pages for additional tie down and braced wall requirements.

N.C. High Wind Foundation Cross Section- 140 to 150 Mph 1-1/2, 2, OR 2-1/2 STORY



Applicable to Seismic Zone C, D0, D1 with minimum soil bearing capacity of 2500 PSF. Concrete-2500 PSI min. Wind speed up to 130 Mph maximum. Refer to wind bracing pages for additional tie down requirements at braced wall locations. Refer to Chapters 4 & 45 in the North Carolina Residential Code for specific foundation application or CMU Construction. REFER TO FIGURE R4504.2(B) FOUNDATION WALL WITH UPLIFT ANCHOR BOLTS FROM FOOTING TO SILL PLATE


N.C. Pier Cross Section- All Zones- UP TO 3 STORIES



R404.1.5.4 Piers.

The unsupported height of masonry piers shall not exceed 10 times their least dimension. When structural clay tile or hollow concrete masonry units are used for isolated piers to support beams and girders, the cellular spaces shall be filled solidly with concrete or Type M or S mortar, except that unfilled hollow piers may be used if their unsupported height is not more than four times their least dimension. When hollow masonry units are solidly filled with concrete or Type M or S mortar, the allowable compressive stress may be increased as provided in Table 606.9.

N.C. 800# HOLD DOWN STRAP DEVICE



Applicable to Seismic Zone C with minimum soil bearing capacity of 2500 PSF. Concrete 2500-PSI min. Wind speed up to 110 Mph Exp. C. Refer to Chapter 4 in the North Carolina Residential Code for specific foundation application or CMU Construction. Refer to the wind bracing pages for additional tie down and braced wall requirements.

CUSTOMER		ALL HOMES		COUNTY	ALL
CITY	STATE	NC	SNOW LOAD	20	
WIND SPEED	110	WIND LOAD	150	CUST. NO.	
DRAWING NAME		PIER DETAILS 2021.DWG			

TYP FOUNDATION DETAILS		NOTE:
DATE:	REVISION:	BY:
11/18/18	1/30/19	2018 CODE UPDATES

HOMES BY VANDERBUILT

3300 JEFFERSON DAVIS HWY
SANFORD, NC 27332
PHONE: (919) 718-2760
FAX: (919) 718-2799

June 9, 2025

Mr. Shane Phelps
State of North Carolina
Department of Insurance
Manufactured Building Division
322 Chapanoke Road
Suite 200
Raleigh, NC 27603

RE : Cavco-Crouse
Model: 2025-1003370-NC

Dear Mr. Phelps,

Enclosed, you will find one (1) copy of the above mentioned project for your files.

Should you have any questions or comments, please contact me at your earliest convenience.

Sincerely,

Joe Shultz

Joe Shultz
Account Manager
ICC NTA, LLC

Enclosures



A MEMBER OF THE ICC FAMILY OF SOLUTIONS

Adopted Codes: State of North Carolina

- 2018 North Carolina Residential Code
- 2017 North Carolina Electrical Code (2017 NEC)
- 2018 North Carolina Energy Code
- 2018 North Carolina Mechanical Code
- 2018 North Carolina Plumbing Code
- 2018 North Carolina Fuel Gas Code
- .
- .
- .

Project Location:

TBD Baptist Grove Rd
Fuquay-Varina, NC 27526
HARNETT County

Occupancy:

Occupancy:IRC - Single Family Dwelling
Construction Type:5B (Wood Frame - Unprotected)
Number of Stories:One Story Cape

Design Load:

Floor Area:2433 Sq.Ft.

Floor Live Load:40 psf

Ground Snow Load:20 psf

Floor Dead Load:10 psf

Top Chord Dead Load:10 psf

Bottom Chord Live Load: See Truss Diagram

Ultimate Wind Speed: 120 mph

Wind Exposure Category:B

Seismic Design Category: ...C

IECC Geographical Code:4


Insulation

Reference RESCheck for Requirements.

Attention Local Inspection Departments:

- Set-up instructions for this modular unit are included by attachment to these plans. Any plans set that does not include an attachment entitled "MODULAR HOME INSTALLATION MANUAL" is incomplete.
- The following items are not completed by the home manufacturer, are not inspected by in-factory third party inspectors, and are not certified by the modular compliance label: (A) Components or connections for heating or air conditioning systems which are NOT part of the factory installation. (B) Below floor ducts. (C) Electrical service disconnect. (D) Foundation designs and attachments. In order to verify that all required systems connections are complete, refer to the "Inspection Check Sheet" in the manufacturer's modular home installation manual. Regardless of factory or site installation, the furnace, water heater, and all elements of heating system must be per applicable codes, (refer to ResCheck if applicable). (E) The following items are omitted: furnace, heat ducts, and ceiling room to room return air jumpers.
- Site installed furnace must meet IECC Energy Efficiency Certificate if applicable.
- This unit must be connected to a public water supply and sewer system if these are available.
- If this structure is in a thermal zone more stringent than that listed on these plans, is set on pilings, or is installed at a mountain region or coastal high hazard site such that wind or other design parameters are increased, the design must be determined to be adequate for actual site conditions. Alterations may be required to bring the home into compliance with the more stringent conditions.**
- Soffit materials for this unit assume that the building face will be 10 feet or greater from the property line when installed on site. Where the building face is less than 10 feet from the property line, underlayment materials and ventilation in accordance with **Section R302.1.1, NC Residential Code**, must be provided and installed at the site and inspected by the local jurisdiction.
- If after installation of this home, the lowest part of the clear opening of any window is more than 72" above the finished grade, guards will be required to be installed onsite in accordance with **Section R312**; subject to local inspection.
- Partial plumbing installation (stubbed in) requires full DWV testing in field. Testing of factory portion of DWV is not required unless partial testing is mandated by code.
- Smoke detectors required by code that are not shown on the plan will be site installed by others and are subject to inspection by the authority having jurisdiction.
- Where required, window protection designed and provided on site by others to meet applicable local codes.

Plan: 2025-1003370
Customer: BROWN, JEFFREY
Builder: HBV
Manufacturer:
530 Cavco-Crouse
235 Anthony Grove Rd.
Crouse, NC 28033




Drawing Index

Title	Page
Cover	CV
Floor Plan	FP
Proposed Cape Floor Plan	PCFP
Electrical Plan	EP
Schedules and General Notes	NG
Elevations	EL
Cross Section	XS
Cross Section 2	XS-2
Cross Section Tag	XS-TAG
Hot Water Lines	WH
Cold Water Lines	WC
DWV System	DL
DWV Notes	DN
Supply Air Ducts - Perimeter Registers	SP
Ceiling Return Air System	HR
Braced Walls-Prescriptive	BWP
Foundation 2x10 Marriage Line without Stair	FD20#
Manual J Calculations	ATTACHED
ResCheck	ATTACHED
UFP Rigid Collar Tie Connection Details	UFP-EB05-02
Truss Diagram	ATTACHED



Note: Window fall protection must be provided on-site where required in accordance with applicable code.




Note: Window fall protection must be provided on-site where required in accordance with applicable code.

Note:
* LVLs noted must extend past column on at least one end 24" minimum and be overlayed with OSB sheathing.

NOTES: 28' 12/12 cape

Proposed Second Floor:
All design materials and work to be the responsibility of the builders on site to local codes. Light, vent, egress, heating and plumbing are the responsibility of the builder.

Note: Window fall protection must be provided on-site in accordance with section R312 of the 2015 IRC as required.



Proposed Second Floor:
All design materials and work to be the responsibility of the builders on site to local codes. Light, vent, egress, heating and plumbing are the responsibility of the builder.

Area: 1575 sq. ft.

See Schedules and General Notes Page

⬡ = Column Support Location

⬢ = Attic Access

Notes:


1. Exterior opening headers and jack studs are SPF #2 unless otherwise noted.
2. Sidewall headers may use alternate construction per section B-10 of Systems Manual.
3. LVL's where specified to be minimum of 1 1/2" wide, M.O.E. = 2.0 and fb = 2900 PSI.
4. See C-10-45 for stair opening framing.
5. See C-10-105 for dormer opening framing.

NOTES: 28' TAG 12/12 cape

Engineer seal applies ONLY to FACTORY MANUFACTURED portions of the building. Seal does not apply to site installed elements or portions built on site such as, but not limited to; foundation, connections to foundation, exterior steps, smoke detectors, or other site works. Site work must be designed BY OTHERS for site conditions, under local jurisdiction. COMPLIANCE WITH ALL APPLICABLE CODES PER LOCAL AUTHORITY HAVING JURISDICTION, WHETHER DETAILED IN THIS SET OR NOT, MUST BE MET.

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 3/16" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
Title: Proposed Cape Floor Plan		Drawn By: NE	Reference: 2R2010-R		Dir: HBV	S/N: 44850	Pg.: PCFP	Run:

5300942763B2025-1003370



Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 3/16" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY Dir: HBV S/N: 44850	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
		Drawn By: NE	Reference: 2R2010-R			Pg.: EP		Run:	

5300942763B2025-1003370

Optional Method Load Calculation for One-Family Dwellings			Model # 2025-1003370	
1 General Lighting and Receptacle Loads 220.82(B)(1) <i>Do not include open porches, garages, or unused or unfinished spaces not adaptable for future use.</i>		3 x 4008 = (ft² using outside dimensions)	1	12024
2 Small-Appliance Branch Circuits 220.82(B)(2) <i>At least two small-appliance branch circuits must be included. 210.11(C)(1)</i>		1500 x 3 = (minimum of two)	2	4500
3 Laundry Branch Circuits (s) 220.82(B)(2) <i>At least one laundry branch circuit must be included. 210.11(C)(2)</i>		1500 x 1 = (minimum of one)	3	1500
4 Appliances 220.82(B)(3) and (4) <i>Do NOT include any heating or Use the nameplate rating of all A/C equipment in this section.</i>		Total volt-amperes of all app. LISTED BLEOW	4	34300
<i>appliances (fastened in place, permanently connected, or connected to a specific circuit),</i>		(1) Electric H ₂ O Heater 4.5 KVA	(4) Vent Fans 1.2 KVA	
<i>ranges, ovens, cooktops, motors, and clothes dryers. Convert any nameplate rating given in amperes to volt-amperes by multiplying the amperes by the rated voltage.</i>		(1) Electric Dryer 5.4 KVA	(1) Microwave 1.5 KVA	
		(1) Electric Range 14.2 KVA	(1) Dishwashe 1.5 KVA	
		(0) Electric Wal Oven (S) 0 KVA	(1) Freezer 1.5 KVA	
		(0) Electric Wal Oven (D) 0 KVA	(1) Refrigerato 1.5 KVA	
		(2) Bath Circ's 3 KVA		
5 Apply 220.82(B) demand factor to the total of lines 1 through 4. 52324 - 10,000 = 42324 x 40 % = 16930 + 10,000 = 26930 (total of lines 1-4)				
6 Heating or Air-Conditioning System 220.82(C). <i>Use the nameplate ratings in volt-amperes for all applicable systems in lines a through e.</i>		c) Supplemental electric heating equipment for heat-pump systems. Include the heat-pump compressor(s) at 100%. <i>If the heat-pump compressor is prevented from operating with the supplemental heat, omit the compressor.</i>		
a) Air-conditioning and cooling systems, including heat pumps without any supplemental electric heating: 6000 x 100 % = a) 6000		0 x 65 % = c) 0		
b) Electric thermal storage & other heating systems where the usual load is expected to be continuous at full nameplate value. <i>Systems qualifying under this selection shall not be figured under any other selection in 220.82(C).</i> 0 x 100 % = b) 0		d) Electric space-heating equipment, if fewer than four separately controlled units: 20000 x 65 % = d) 13000		
		e) Electric space-heating equipment, if four or more separately controlled units: 0 x 40 % = e) 0		
7 Total Volt-Ampere 13000 + 26930 = Demand Load: (Largest VA rating, 6a -6e) (Line 5)		7 39930		
8 Minimum Amperes <i>Divide the total volt-amperes by voltage.</i> 39930 ÷ 240 = 167 (line 7) (voltage) (min. amperes)		9 Minimum Size Service or Feeder 240.6(A) 200 Amps Installed		
10 Size the Service or Feeder Conductors. <i>Use 310.15(B)(6) to find the service conduct up to 400 amperes. Ratings in excess of 400 amperes shall comply w/ Table 310.16. 310.15(B)(6) also applies to feeder conductors serving as the main power feeder.</i>		10 Minimum Size Conductors 2/0 Copper OR 4/0 Aluminum		

REFER TO RESCHECK FOR DOOR AND WINDOW U-VALUES

WINDOW SCHEDULE										
AT LEAST ONE EGRESS WINDOW IS REQUIRED FOR EACH SLEEPING AREA WHERE NO EXTERIOR EXIT DOOR EXISTS.										
S SUFFIX DENOTES SAFETY GLAZING / E SUFFIX DENOTES EGRESS										
Label	Width R/O	Height R/O	R/O SF	Light	Vent	Room SF	U Value	Egress	Design Load	SHGC w/o Grids
(2)3036	61	36.5	15.46	11.09	5.28	132.00	0.34	No	+50/-50	0.23
(2)3668	73	68.5	34.73	28.01	13.84	346.00	0.34	Yes	+50/-50	0.23
(2)3668-E	73	68.5	34.73	28.01	13.84	346.00	0.34	Yes	+50/-50	0.23
(2)3668-S	73	68.5	34.73	28.01	13.84	346.00	0.34	Yes	+50/-50	0.23
3036	30.5	36.5	7.73	5.50	2.64	66.00	0.34	No	+50/-50	0.23
3036-S	30.5	36.5	7.73	5.50	2.64	66.00	0.34	No	+50/-50	0.23
3240GB	32.25	39.75	8.90	8.90	0.00	0.00	0.51	No	+58/-58	0.58
3612TRN	36.5	12.5	3.17	2.15	0.00	0.00	0.31	No	+50/-50	0.26
3658-S	36.5	58.5	14.83	11.76	5.76	144.00	0.34	Yes	+50/-50	0.23
3668-E	36.5	68.5	17.36	14.00	6.92	173.00	0.34	Yes	+50/-50	0.23
3668-E-S	36.5	68.5	17.36	14.00	6.92	173.00	0.34	Yes	+50/-50	0.23
3668-S	36.5	68.5	17.36	14.00	6.92	173.00	0.34	Yes	+50/-50	0.23
7112TRN	71.5	12.5	6.21	4.42	0.00	0.00	0.31	No	+50/-50	0.26

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: N.T.S.	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
Title: Schedules and General Notes		Drawn By: NE	Reference: 2R2010-R		Dir: HBV			
					S/N: 44850	Pg.: NG		Run: .

LEGEND			
=15 AMP RECEPT	=15 AMP FLOOR RECPT	=20 AMP RECEPT	=20 AMP FLOOR RECPT
=SWITCHED RECEPT	=220 VOLT RECEPT	WPR = WEATHERPROOF ENCLOSURE WITH WEATHE RESISTANT RECEPT	
=STD LIGHT	=RECESSED LIGHT		
			=PULL CHAIN LIGHT
=UNDER CABINET LIGHT / WALL LIGHT		=UNDER CABINET STEREO	
=SWITCH		=DIMMER SWITCH	=3-WAY SWITCH
=STANDARD VENT		=WIRE	=DOORBELL
=WHOLE HOUSE VENTILATION FAN		=MOTION LIGHT	=STANDARD FAN
=PHONE JACK		=DATA JACK	=TV JACK
=JUNCTION BOX		=HOSE BIBB	
GFI =GROUND FAULT CIRCUIT INTERRUPTER			
=BULLET		=PANEL BOX	
WP =WET LOCATION		=SPEAKER	=AV JACK
=IONIZATION SMOKE ALARM		=THERMOSTAT	=FIRE EXTINGUISHER
=SMOKE/CO ALARM		=PE = PHOTOELECTRIC SMOKE/CO ALARM	=CO ALARM

If an attached garage is to be added to this home, the entrance door to the home from the garage must be a self-closing fire rated door per applicable code. Clothes dryer vents may need to be completed to the exterior of the home on site. Refer to sections of applicable local codes and to Section 8 of the home installation manual for required completion of dryer ventilation as necessary.

Ventilation Requirements	
1.	Bathroom exhaust fans to be minimum 50 CFM per G-20-20
2.	Kitchen range hoods minimum 100 CFM and should exhaust to the outside or be an approved recirculating hood if adequate natural ventilation per G-20-30
3.	Whole house ventilation minimum 30 CFM per E-20-20 & E-20-20.1

FOR PERMANENTLY CONNECTED APPLIANCES RATED AT OVER 300 VOLT-AMPERES OR 1/8 HP, THE BRANCH CIRCUIT BREAKER SHALL BE PERMITTED TO SERVE AS THE DISCONNECTING MEANS WHERE THE CIRCUIT BREAKER IS WITHIN SIGHT FROM THE APPLIANCE OR IS CAPABLE OF BEING LOCKED IN THE OPEN POSITION. THE LOCKING MEANS SHALL REMAIN IN PLACE WITH OR WITHOUT THE LOCK INSTALLED. MAIN DISCONNECT SHALL BE LOCATED ON THE EXTERIOR OF THE HOME.



WINDOW SCHEDULE - PROPOSED CAPE										
AT LEAST ONE EGRESS WINDOW IS REQUIRED FOR EACH SLEEPING AREA WHERE NO EXTERIOR EXIT DOOR EXISTS.										
S SUFFIX DENOTES SAFETY GLAZING / E SUFFIX DENOTES EGRESS										
Label	Width R/O	Height R/O	R/O SF	Light	Vent	Room SF	U Value	Egress	Design Load	SHGC w/o Grids
(2)3036	61	36.5	15.46	11.09	5.28	132.00	0.34	No	+50/-50	0.23
3052-E	36.25	62	15.61	10.26	5.88	128.25	0.31	Yes	+50.13/-50.13	0.21
3658-E	36.5	58.5	14.83	11.76	5.76	144.00	0.34	Yes	+50/-50	0.23

CIRCUIT ID NO.	LOAD	AMPS	POLES REQ'D	WIRE SIZE
1-12	General Lighting/Receptacles	15	1	NM14-2/WG
13-16	Small Appliance	20	1	NM12-2/WG
17-18	Bath (GFCI)	20	1	NM12-2/WG
19	Smoke Alarms (AFCI)	15	1	NM14-2/WG
20	Laundry	20	1	NM12-2/WG
21	Electric Dryer	30	2	NM10-3/WG
22	Electric Range	50	2	NM6-3/WG
23	Electric Cooktop	40	2	NM8-3/WG
24	Electric Wall Oven	20	2	NM12-2/WG
	Electric Wall Oven	40	2	NM8-2/WG
25	Electric W/H	25	2	NM10-2/WG
25.1	Tankless W/H	20	1	NM12-2/WG
26	Gas Furnace	15	1	NM14-2/WG
27	Electric Furnace	60/30	4	NM4-2/WG
	Electric Furnace	60/60	4	NM4-2/WG
28-37	Electric BB Heat	20	2	NM12-2/WG
38	A/C	50	2	NM6-2/WG
39	Freezer	20	1	NM12-2/WG
40	Dishwasher	15	1	NM14-2/WG
41	Disposal (GFCI)	15	1	NM14-2/WG
42	Whirlpool Tub (GFCI)	20	1	NM12-2/WG
43	Microwave Oven	20	1	NM12-2/WG
44	Garage (GFCI)	20	1	NM12-2/WG
46	Exterior Receptacles	15 (Opt. 20)	1	NM14-2/WG (Opt. NM12-2/WG)
47	Refrigerator	20	1	NM12-2/WG

DOOR SCHEDULE					
Description	Label	R/O SF	Light	Vent	Design Load
7280 Sliding Patio Door	7280	40.00	32.88	16.06	+50/-50
3882 9 Lite Exterior Door	3882	21.70	5.12	20.76	+50/-50
3882 6 Panel Exterior Door	3882	21.70	0.00	20.76	+50/-50
28 Hinged Interior Door	28	17.29	0.00	0.00	NA
24 Hinged Interior Door	24	14.99	0.00	0.00	NA
30 Hinged Interior Door	30	18.44	0.00	0.00	NA
36 Hinged Interior Door	36	21.90	0.00	0.00	NA
STAIRWAYS RISER HEIGHT - 8 1/4" MAX. TREAD DEPTH - 9" MIN. HEAD ROOM 80" MIN. NOTE: THE STAIRWELL GEOMETRY IN THIS HOME HAS BEEN DESIGNED TO THE CRITERIA ABOVE. IF MORE STRINGENT STAIR GEOMETRY IS REQUIRED OR DESIRED, PLEASE CONTACT THE PLANT OF MANUFACTURE FOR PLAN ADJUSTMENTS.					

- ELECTRICAL PLAN NOTES BASED ON NEC 2017:
- ALL KITCHEN AND BATHROOM COUNTER RECEPTS TO BE GFCI PROTECTED.
 - ALL CLOSET LIGHTS TO BE ENCLOSED SURFACE MOUNT FIXTURES, 12" MIN. FROM STORAGE SPACE.
 - ALL RECEPTS TO BE GROUNDING TYPE, PER 406.4/NEC.
 - SPECS, WIRING, INSTALLATIONS, ETC. TO COMPLY WITH NEC REGULATIONS.
 - SERVICE PANEL MAY BE LOCATED IN GARAGE.
 - ALL SMOKE ALARMS TO HAVE BATTERY BACK-UP AND TO BE INTERCONNECTED WITH A 14 GA. MIN. INTERCONNECTION WIRE, 14-3 CABLE, OR EQUIVALENT PER MFG.S RECOMMENDATIONS.
 - EXTERIOR LIGHT AT GARAGE SIDE MAY BE REPLACED.
 - GAS APPLIANCES MAY BE SUBSTITUTED FOR ELECTRIC APPLIANCES WHERE APPLICABLE. WHEN GAS APPLIANCES ARE INSTALLED, ALL GAS PIPING, CONNECTIONS, HOOK-UPS, ETC. TO BE INSTALLED ON SITE BY OTHERS. THE OPTIONAL GARBAGE DISPOSAL CONNECTED TO INDEPENDENT RECEPTACLE AND WALL SWITCH.
 - 200 AMP PANEL BOX INSTALLED
 - ALL 120v GENERAL USE RECEPTS ARE TAMPER RESISTANT UNLESS MOUNTED AT LEAST 66" ABOVE FLOOR, OR ARE PART OF A LISTED LIGHT FIXTURE OR APPLIANCE, OR WHERE CORD & PLUG APPLIANCE IN DEDICATED SPACE IS NOT EASILY MOVED FOR USE.
 - ALL EXTERIOR RECEPTACLES ARE GFI, TAMPER RESISTANT AND LISTED FOR WET LOCATIONS.
 - COMBINATION TYPE AFCI BREAKERS ARE REQUIRED FOR ALL 120 V CIRCUITS EXCEPT THOSE SERVING BATHROOMS, GARAGE, LAUNDRY AREAS, KITCHENS, UNFINISHED BASEMENTS AND OUTDOORS.
 - ALL ELECTRICAL BOXES SUPPORTING LIGHTING FIXTURES MUST BE RATED @ 50# AND IDENTIFIED ON THE BOX.
 - WHIRLPOOL RECEPTACLES MUST BE GFCI, TAMPER RESISTANT AND READILY ACCESSIBLE PER NEC 680.71
 - A CIRCUIT BREAKER LOCKING DEVICE SHALL BE PROVIDED TO LOCK THE APPLICABLE BREAKERS IN THEIR "OFF" POSITION. THIS APPLIES TO CIRCUIT BREAKERS WHICH SERVE AS THE DISCONNECT FOR ELECTRIC WATER HEATERS, ELECTRIC BASEBOARD HEATERS, AND ANY APPLIANCE RATED OVER 300 WATTS OR 1/8 HORSEPOWER, WHICH ARE NOT LOCATED WITHIN CLEAR SIGHT OF THEIR DISCONNECT
 - A RECEPTACLE OUTLET IS REQUIRED FOR PORCHES, BALCONIES OR DECKS WHICH ARE ACCESSIBLE FROM THE INSIDE OF THE DWELLING UNIT REGARDLESS OF THE SIZE OF THE PORCH, BALCONY OR DECK.
 - NON-SWITCHED CIRCUIT NEUTRAL CONDUCTOR MUST BE PRESENT AT EACH WALL SWITCH. RE-IDENTIFIED CONDUCTORS WITH WHITE, GREY OR THREE STRIPE INSULATION MAY ONLY BE USED AS SUPPLY TO SWITCH AND NOT FOR HOT RETURN TO FIXTURE.
 - 120v 15 OR 20 AMP RECEPTS LOCATED WITHIN 6' FROM ANY DWELLING UNIT SINK MUST BE GFCI PROTECTED.
 - IF THE PERIMETERS OF THE AREAS OF THE ON-SITE INSTALLED STOOPS, PORCHES OR DECKS ARE NOT UNDER THE EXTERIOR ELECTRICAL RECEPTACLES SHOWN IN THE ELECTRICAL FLOOR PLAN, THEN ADDITIONAL RECEPTACLES SHALL BE SITE INSTALLED WITHIN THESE AREAS BY THE CONTRACTOR.


ELEVATIONS SHOWN ON THIS PAGE REPRESENT BASIC COMPONENTS AND ARE NOT INTENDED TO BE ALL INCLUSIVE, NOR DO THESE ELEVATIONS DETAIL EVERY CODE REQUIRED ASPECT OF THIS BUILDING. SITE BUILT STOOPS, STEPS, DECKS, PORCHES, HANDRAILS AND/OR SIMILAR ITEMS MUST BE PROVIDED BY OTHERS ON SITE FOR COMPLIANCE WITH APPLICABLE CODES. COMPLIANCE WITH ALL APPLICABLE CODES PER LOCAL AUTHORITY HAVING JURISDICTION, WHETHER DETAILED IN THIS SET OR NOT, MUST BE MET.

Note: Window fall protection must be provided on-site where required in accordance with applicable code.


NOTE:
HOMES WITH ATTIC SPACE QUALIFYING AS HABITABLE, MUST BE EQUIPPED WITH EMERGENCY ESCAPE AND RESCUE OPENINGS REGARDLESS OF WHETHER ATTIC AREA IS FINISHED OR UNFINISHED. OPENINGS MAY OCCUR AT END WALL OF ATTIC AND/OR AT ROOF DORMERS IN WHATEVER ARRANGEMENT NECESSARY TO INSURE THAT ANY SLEEPING ROOM HAS AT LEAST ONE EGRESS OPENING.




FRONT VIEW



REAR VIEW



RIGHT VIEW



LEFT VIEW

-NOTES-

1. FOUNDATION SHALL BE DESIGNED AND CONSTRUCTED BY OTHERS WHERE "OTHERS" REFERS TO THE DEALER BUILDER.
2. GUTTERS AND LEADERS SHALL BE INSTALLED BY OTHERS.
3. TYPICAL 12" OR 15" VINYL SHUTTERS PROVIDED BY MANUFACTURERS.
4. ALL FOOTINGS, RAILINGS AND STEPS SHALL BE FIELD INSTALLED IN COMPLIANCE WITH APPLICABLE STATE AND LOCAL CODES.
5. SIDING SHALL BE VINYL SIDING WITH VINYL TRIM, AND MAY BE PARTIALLY INSTALLED ON SITE.
6. EXTERIOR LIGHTS MAY BE SHIPPED LOOSE FOR INSTALLATION ON SITE.
7. ROOFING SHINGLES MAY BE PARTIALLY SITE INSTALLED.
8. PORCH RAILINGS ARE PVC. TREATED LUMBER PORCH POSTS MAY BE COVERED WITH VINYL. PORCH DECKING SHALL BE TREATED.
9. ALL EXTERIOR COVERINGS SHALL BE WEATHER AND DECAY RESISTIVE TO PROVIDE PROPER PROTECTION FOR UNTREATED MATERIALS.

APPROVED BY
NIA
6/9/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: N.T.S.	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
		Drawn By: NE	Reference: 2R2010-R			Pg.: EL			

Title: Elevations

- LEGEND
- 1 JACK POST, PIER OR CONCRETE FILLED POST THAT MEETS OR EXCEEDS REQUIRED SUPPORT CAPACITY PER FOUNDATION DESIGN.
 - 2 EXTERIOR WALL INSULATION (SEE INSULATION R-VALUES).
 - 3 2X6 #3 SPF EXTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
 - 4 2X6 #3 SPF SIDEWALL BOTTOM PLATE.
 - 5 7/16" RATED SHEATHING.
 - 6 VINYL OR HARDBOARD SIDING (RAN VERT. OR HORZ.) INSTALLED PER MFGR.'S INSTRUCTIONS.
 - 7 AIR INFILTRATION AND WATER RESISTANT BARRIER.
 - 8 2X4 #3 SPF SINGLE OR DOUBLE TOP PLATE.
 - 9 2X6 TREATED SILL PLATE. FASTENING OF SILL AND HOME TO FOUNDATION ON SITE PER CODES OR BY LOCAL ENGINEER WHEN APPLICABLE.
 - 10 2X4 #3 SPF INTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
 - 11 2X4 #3 SPF BOTTOM PLATE INTERIOR WALLS, TYP.
 - 12 ENGINEERED TRUSSES SPACED TO MEET DESIGNED GROUND LOAD SNOW LOAD.
 - 13 VAPOR BARRIER.
 - 14 CEILING BOARD 1/2" GYPSUM.
 - 15 7/16" 24/16 RATED ROOF DECKING MIN. TYP.
 - 16 2X4 #3 SPF MIN. VERT. RAIL CONT. ON BOTH SECTIONS OVER MATE WALL. USE APPLICABLE BEAM OVER OPEN SPANS (TYP.) PER PG'S C-10-10 OF SYSTEM DOCUMENT.
 - 17 RIDGE VENT TYP. 50% VENTILATION OF ROOF CAVITY (UPPER PORTION); INSTALLED PER CODE REQUIREMENTS.
 - 18 TYPICAL SHINGLES, INSTALLED PER MFGR'S INSTRUCTIONS.
 - 19 SHINGLE UNDERLAYMENT TYP.
 - 20 JOIST HANGERS AT MATELINE(S).
 - 21 1" MIN. SPACE FOR ATTIC VENTILATION.
 - 22 TYPICAL ICE BARRIER PER SECTION 905 OF APPLICABLE CODE.
 - 23 CEILING INSULATION TYP. (SEE INSULATION R-VALUES).
 - 24 23/32" (O.S.B.) BOARD DECKING.
 - 25 ALUM., VINYL OR HARDIE BOARD FACIA AND DRIP EDGE.
 - 26 FLOOR CAVITY OR PERIMETER WALL MUST BE INSULATED ON SITE OR AT THE FACTORY (SEE "INSULATION R-VALUES")
 - 27 PERIMETER RIM JOIST MUST BE INSULATED TO R-VALUE LISTED FOR EXTERIOR WALLS
 - 28 INSULATION INSTALLED ONSITE BY OTHERS PER THERMAL REQUIREMENTS AND/OR STATE AND LOCAL CODES
 - 29 VENTED SOFFIT 50% OF LOWER ROOF VENTILATION.
 - 30 BAFFLE REQUIRED
 - 31 DRIFT BLOCKER
 - 32 VAPOR RETARDER (AS REQUIRED PER CLIMATE ZONE).
 - 33 FLOOR DECKING RATED FOR 19.2" O.C. JOIST SPACING MAX.
 - 34 MIN. 2X10 #2 SPF FLOOR JOIST 16" O.C.
 - 35 2X6 #3 SPF DOUBLE TOP PLATE.
 - 36 WALL COVERING (MIN. 1/2" GYPSUM).


Truss Data			
Truss #	Spacing	Sidewall	Centerline
R28C12F	24	1146	985
R14C12T	24	668	0
R274G12F	24	1532	0

STUD O.C. SPACING
EXTERIOR WALL: 16"
INTERIOR WALL: 24"

INSULATION R-VALUES

CEILING: 38
CEILING (Between Knee Walls: 30
EXTERIOR WALLS (continuous): 0
EXTERIOR WALLS (cavity): 19
FLOOR: 30
FOUNDATION WALLS (continuous): 0
FOUNDATION WALLS (cavity): 0

SYSTEMS MANUAL REFERENCES
FLOOR CONSTRUCTION: A-10-10 & 20
SIDEWALL CONSTRUCTION: B-10-10
CENTER WALL UPLIFT DETAIL: B-20-10
COLUMN REQUIREMENTS: B-20-20, 21 & 30
INTERIOR WALLS: B-30-10 & 11
BEAMS: C-10-10 THRU C-10-30



APPROVED BY
NIA
6/9/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz

NOTES:
FOLLOW RECOMMENDED ATTACHMENTS FOR FASTENING OF HOME TO FOUNDATION.
FOUNDATIONS TO BE BUILT AND CONSTRUCTED BY OTHERS ON SITE.
FOUNDATIONS (BY OTHERS) MUST MEET ALL APPLICABLE CODES.
NOTES AND/OR ILLUSTRATIONS SHOWN ARE TYPICAL AND MAY NOT APPLY TO ALL HOMES CONSTRUCTED.
CONSTRUCTION & SPECIFICATIONS MAY VARY PER PLAN.
REFER TO INSTALLATION MANUAL FOR MODULE CONNECTIONS.
REFER TO INSTALLATION MANUAL AND TRUSS MFG. DIAGRAM FOR ROOF TRUSS BRACING.

TRIMLINE RIDGE VENT: ALLOWS 13" OF NET FREE AIR PER LINEAL FOOT
FULL LENGTH OF HOUSE AIR FLO SOFFIT: FULL VENTED 5.89 SQ IN PER LINEAL FOOT
FULL LENGTH OF HOUSE 2433/300 = 8.11 VENT REQUIRED

IMPORTANT!
MAIN LEVEL FLOORS, OVER ENCLOSED FOUNDATIONS, CONSTRUCTED WITH OPTIONAL ENGINEERED WEB FLOOR JOISTS (OPEN JOISTS) OR WITH JOISTS OF NOMINAL LUMBER LESS THAN 2X10, MAY BE SUBJECT TO SPECIAL FIRE PROTECTIVE REQUIREMENTS TO BE PERFORMED BY OTHERS ON SITE. CONSULT ADOPTED LOCAL CODES FOR COMPLIANCE WITH FIRE PROTECTION OF FLOORS. REFERENCE THE APPROVED SYSTEMS PACKAGE FOR ADDITIONAL AND SPECIFIC CROSS SECTION INFORMATION

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 1/4" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
Title: Cross Section		Drawn By: NE	Reference: 2R2010-R		Dir: HBV S/N: 44850	Pg.: XS		Run: .

LEGEND

- 1

EXTERIOR WALL INSULATION (SEE INSULATION R-VALUES).
- 2

2X6 #3 SPF EXTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
- 3

2X6 #3 SPF SIDEWALL BOTTOM PLATE.
- 4

7/16" RATED SHEATHING.
- 5

VINYL OR HARDBOARD SIDING (RAN VERT. OR HORZ.) INSTALLED PER MFGR.'S INSTRUCTIONS.
- 6

AIR INFILTRATION AND WATER RESISTANT BARRIER.
- 7

2X6 TREATED SILL PLATE. FASTENING OF SILL AND HOME TO FOUNDATION ON SITE PER CODES OR BY LOCAL ENGINEER WHEN APPLICABLE.
- 8

ENGINEERED TRUSSES SPACED TO MEET DESIGNED GROUND LOAD SNOW LOAD.
- 9

VAPOR BARRIER.
- 10

CEILING BOARD 1/2" GYPSUM.
- 11

7/16" 24/16 RATED ROOF DECKING MIN. TYP.
- 12

RIDGE VENT TYP. 50% VENTILATION OF ROOF CAVITY (UPPER PORTION), INSTALLED PER CODE REQUIREMENTS.
- 13

TYPICAL SHINGLES, INSTALLED PER MFGR'S INSTRUCTIONS.
- 14

SHINGLE UNDERLAYMENT TYP.
- 15

1" MIN. SPACE FOR ATTIC VENTILATION.
- 16

TYPICAL ICE BARRIER PER SECTION 905 OF APPLICABLE CODE.
- 17

CEILING INSULATION TYP. (SEE INSULATION R-VALUES).
- 18

ALUM., VINYL OR HARDIE BOARD FACIA AND DRIP EDGE.
- 19

FLOOR CAVITY OR PERIMETER WALL MUST BE INSULATED ON SITE OR AT THE FACTORY (SEE "INSULATION R-VALUES")
- 20

PERIMETER RIM JOIST MUST BE INSULATED TO R-VALUE LISTED FOR EXTERIOR WALLS
- 21

INSULATION INSTALLED ONSITE BY OTHERS PER THERMAL REQUIREMENTS AND/OR STATE AND LOCAL CODES
- 22

VENTED SOFFIT 50% OF LOWER ROOF VENTILATION.
- 23

BAFFLE REQUIRED
- 24

DRIFT BLOCKER
- 25

VAPOR RETARDER (AS REQUIRED PER CLIMATE ZONE).
- 26

FLOOR DECKING RATED FOR 19.2" O.C. JOIST SPACING MAX.
- 27

MIN. 2X10 #2 SPF FLOOR JOIST 16" O.C.
- 28

2X6 #3 SPF DOUBLE TOP PLATE.
- 29


WALL COVERING (MIN. 1/2" GYPSUM).

Truss Data			
Truss #	Spacing	Sidewall	Centerline
R28C12F	24	1146	985
R14C12T	24	668	0
R274G12F	24	1532	0

STUD O.C. SPACING
EXTERIOR WALL: 16"
INTERIOR WALL: 24"

INSULATION R-VALUES
CEILING: 38
CEILING (Between Knee Walls: 30
EXTERIOR WALLS (continuous): 0
EXTERIOR WALLS (cavity): 19
FLOOR: 30
FOUNDATION WALLS (continuous): 0
FOUNDATION WALLS (cavity): 0

SYSTEMS MANUAL REFERENCES
FLOOR CONSTRUCTION: A-10-10 & 20
SIDEWALL CONSTRUCTION: B-10-10
CENTER WALL UPLIFT DETAIL: B-20-10
COLUMN REQUIREMENTS: B-20-20, 21 & 30
INTERIOR WALLS: B-30-10 & 11
BEAMS: C-10-10 THRU C-10-30



NOTES:
FOLLOW RECOMMENDED ATTACHMENTS FOR FASTENING OF HOME TO FOUNDATION.
FOUNDATIONS TO BE BUILT AND CONSTRUCTED BY OTHERS ON SITE.
FOUNDATIONS (BY OTHERS) MUST MEET ALL APPLICABLE CODES.
NOTES AND/OR ILLUSTRATIONS SHOWN ARE TYPICAL AND MAY NOT APPLY TO ALL HOMES CONSTRUCTED.
CONSTRUCTION & SPECIFICATIONS MAY VARY PER PLAN.
REFER TO INSTALLATION MANUAL FOR MODULE CONNECTIONS.
REFER TO INSTALLATION MANUAL AND TRUSS MFG. DIAGRAM FOR ROOF TRUSS BRACING.



TRIMLINE RIDGE VENT: ALLOWS 13" OF NET FREE AIR PER LINEAL FOOT

FULL LENGTH OF HOUSE AIR FLO SOFFIT: FULL VENTED 5.89 SQ IN PER LINEAL FOOT

FULL LENGTH OF HOUSE 2433/300 = 8.11 VENT REQUIRED

IMPORTANT!
MAIN LEVEL FLOORS, OVER ENCLOSED FOUNDATIONS, CONSTRUCTED WITH OPTIONAL ENGINEERED WEB FLOOR JOISTS (OPEN JOISTS) OR WITH JOISTS OF NOMINAL LUMBER LESS THAN 2X10, MAY BE SUBJECT TO SPECIAL FIRE PROTECTIVE REQUIREMENTS TO BE PERFORMED BY OTHERS ON SITE. CONSULT ADOPTED LOCAL CODES FOR COMPLIANCE WITH FIRE PROTECTION OF FLOORS. REFERENCE THE APPROVED SYSTEMS PACKAGE FOR ADDITIONAL AND SPECIFIC CROSS SECTION INFORMATION

Builder: 530 Cavco-Crouse		Address: 235 Anthony Grove Rd. Crouse, NC 28033		Revisions	Scale: 3/8" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
Title: Cross Section 2				Drawn By: NE	Reference: 2R2010-R		Dir: HBV S/N: 44850	Pg.: XS-2		Run:	

LEGEND

- 1
- EXTERIOR WALL INSULATION (SEE INSULATION R-VALUES).
- 2
- 2X6 #3 SPF EXTERIOR WALL STUDS. (SEE STUD O.C. SPACING NOTE)
- 3
- 2X6 #3 SPF SIDEWALL BOTTOM PLATE.
- 4
- 7/16" RATED SHEATHING.
- 5
- VINYL OR HARDBOARD SIDING (RAN VERT. OR HORZ.) INSTALLED PER MFGR.'S INSTRUCTIONS.
- 6
- AIR INFILTRATION AND WATER RESISTANT BARRIER.
- 7
- 2X6 TREATED SILL PLATE. FASTENING OF SILL AND HOME TO FOUNDATION ON SITE PER CODES OR BY LOCAL ENGINEER WHEN APPLICABLE.
- 8
- ENGINEERED TRUSSES SPACED TO MEET DESIGNED GROUND LOAD SNOW LOAD.
- 9
- VAPOR BARRIER.
- 10
- CEILING BOARD 1/2" GYPSUM.
- 11
- 7/16" 24/16 RATED ROOF DECKING MIN. TYP.
- 12
- RIDGE VENT TYP. 50% VENTILATION OF ROOF CAVITY (UPPER PORTION), INSTALLED PER CODE REQUIREMENTS.
- 13
- TYPICAL SHINGLES, INSTALLED PER MFGR'S INSTRUCTIONS.
- 14
- SHINGLE UNDERLAYMENT TYP.
- 15
- 1" MIN. SPACE FOR ATTIC VENTILATION.
- 16
- TYPICAL ICE BARRIER PER SECTION 905 OF APPLICABLE CODE.
- 17
- CEILING INSULATION TYP. (SEE INSULATION R-VALUES).
- 18
- 23/32" (O.S.B.) BOARD DECKING.
- 19
- ALUM., VINYL OR HARDIE BOARD FACIA AND DRIP EDGE.
- 20
- FLOOR CAVITY OR PERIMETER WALL MUST BE INSULATED ON SITE OR AT THE FACTORY (SEE "INSULATION R-VALUES")
- 21
- PERIMETER RIM JOIST MUST BE INSULATED TO R-VALUE LISTED FOR EXTERIOR WALLS
- 22
- INSULATION INSTALLED ONSITE BY OTHERS PER THERMAL REQUIREMENTS AND/OR STATE AND LOCAL CODES
- 23
- VENTED SOFFIT 50% OF LOWER ROOF VENTILATION.
- 24
- BAFFLE REQUIRED
- 25
- DRIFT BLOCKER
- 26
- VAPOR RETARDER (AS REQUIRED PER CLIMATE ZONE).
- 27
- FLOOR DECKING RATED FOR 19.2" O.C. JOIST SPACING MAX.
- 28
- MIN. 2X10 #2 SPF FLOOR JOIST 16" O.C.
- 29
- 2X6 #3 SPF DOUBLE TOP PLATE.
- 30
- WALL COVERING (MIN. 1/2" GYPSUM).

APPROVED BY

NIA

6/9/2025


Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Truss Data			
Truss #	Spacing	Sidewall	Centerline
R28C12F	24	1146	985
R14C12T	24	668	0
R274G12F	24	1532	0

STUD O.C. SPACING
EXTERIOR WALL: 16"
INTERIOR WALL: 24"

INSULATION R-VALUES
CEILING: 38
CEILING (Between Knee Walls: 30
EXTERIOR WALLS (continuous): 0
EXTERIOR WALLS (cavity): 19
FLOOR: 30
FOUNDATION WALLS (continuous): 0
FOUNDATION WALLS (cavity): 0



SYSTEMS MANUAL REFERENCES
FLOOR CONSTRUCTION: A-10-10 & 20
SIDEWALL CONSTRUCTION: B-10-10
CENTER WALL UPLIFT DETAIL: B-20-10
COLUMN REQUIREMENTS: B-20-20, 21 & 30
INTERIOR WALLS: B-30-10 & 11
BEAMS: C-10-10 THRU C-10-30

NOTES:
FOLLOW RECOMMENDED ATTACHMENTS FOR FASTENING OF HOME TO FOUNDATION.
FOUNDATIONS TO BE BUILT AND CONSTRUCTED BY OTHERS ON SITE.
FOUNDATIONS (BY OTHERS) MUST MEET ALL APPLICABLE CODES.
NOTES AND/OR ILLUSTRATIONS SHOWN ARE TYPICAL AND MAY NOT APPLY TO ALL HOMES CONSTRUCTED.
CONSTRUCTION & SPECIFICATIONS MAY VARY PER PLAN.
REFER TO INSTALLATION MANUAL FOR MODULE CONNECTIONS.
REFER TO INSTALLATION MANUAL AND TRUSS MFG. DIAGRAM FOR ROOF TRUSS BRACING.

IMPORTANT!
MAIN LEVEL FLOORS, OVER ENCLOSED FOUNDATIONS, CONSTRUCTED WITH OPTIONAL ENGINEERED WEB FLOOR JOISTS (OPEN JOISTS) OR WITH JOISTS OF NOMINAL LUMBER LESS THAN 2X10, MAY BE SUBJECT TO SPECIAL FIRE PROTECTIVE REQUIREMENTS TO BE PERFORMED BY OTHERS ON SITE. CONSULT ADOPTED LOCAL CODES FOR COMPLIANCE WITH FIRE PROTECTION OF FLOORS. REFERENCE THE APPROVED SYSTEMS PACKAGE FOR ADDITIONAL AND SPECIFIC CROSS SECTION INFORMATION

TRIMLINE RIDGE VENT: ALLOWS 13" OF NET FREE AIR PER LINEAL FOOT

FULL LENGTH OF HOUSE AIR FLO SOFFIT: FULL VENTED 5.89 SQ IN PER LINEAL FOOT


FULL LENGTH OF HOUSE 2433/300 = 8.11 VENT REQUIRED

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 1/4" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
		Drawn By: NE	Reference: 2R2010-R	S/N: 44850	Pg.: XS-TAG	Run:			
Title: Cross Section Tag									

- NOTE:
- 1. 3/4" GALVANIZED, OR COPPER RELIEF DRAIN (NOT SHOWN) THRU FLOOR w/VISIBLE AIR GAP
 - 2. INLET WITH 1" CAP & CHAIN.
 - 3. DIMENSIONS EXPRESSED IN PARENTHESIS (A x B) INDICATE: (DIST. FROM REAR END OF HOME FLOOR x DIST. FROM HOME MATE LINE).
 - 4. ANTI-SCALD DEVICE ON ALL SHOWER, AND TUB/SHOWER COMBINATIONS.
 - 5. WATER-HAMMER ARRESTORS AT BATTERY OF FIXTURES INSTALLED WHEREVER THERE IS A QUICK-CLOSING VALVE CONFORMING TO ASSE 1010 & MANUFACTURER'S INSTRUCTIONS.
 - 6. SHUT-OFF VALVE IS REQUIRED AT EACH FIXTURE
 - 7. BATHROOMS WITH DOUBLE LAVS ARE FED FROM THE SAME RISER.
 - 8. ANY LINE NOT LABELED IS 1/2"
 - 9. WATER HEATER TEMPERATURE & PRESSURE RELIEF VALVE AND RELIEF DRAIN PIPE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 - 10. SHUT-OFF VALVE AT WATER HEATER IS FULL OPEN VALVE INSTALLED ON COLD WATER SUPPLY PIPE AT EACH WATER HEATER, PER CODE.
 - 11. FULLWAY SHUT-OFF VALVE WITH BLEED ORIFICE INSTALLED AT MAIN INLET SERVICE VALVE, INSTALLED ON-SITE, PER CODE.
 - 12. SEE SYSTEMS PACKAGE PLUMBING SECTION PAGES FOR ADDITIONAL PLUMBING NOTES AND DETAILS

SITE NOTES FOR DIAGRAM EXPLANATION:

- A. WHEN VERTICAL FIXTURE WATER SUPPLY RISERS ONLY ARE SHOWN ON THIS PLAN, RISERS ONLY ARE FACTORY INSTALLED AS SHOWN AND TERMINATED BELOW THE FLOOR AT THE INDICATED LOCATIONS. MATERIAL PROVISIONS, SYSTEM CONNECTIONS, TESTING, AND INSPECTION FOR ALL BELOW-FLOOR CONNECTIONS ARE ON SITE BY OTHERS IN ACCORDANCE WITH ALL STATE AND LOCAL CODES.
- B. WHEN BELOW-FLOOR SYSTEM CONNECTIONS TO RISERS ARE SHOWN ON PLAN BY SOLID LINES, THESE ARE COMPLETED, TESTED, AND INSPECTED IN THE FACTORY TO THE TERMINATION POINT SHOWN ON ILLUSTRATED PLAN.
- C. DOTTED LINES ON PLAN,(IF PRESENT), ARE INTENDED ONLY TO ILLUSTRATE TYPICAL ON-SITE CONNECTIONS. THESE ARE FOR ILLUSTRATION ONLY AND ARE NOT PROVIDED, INSTALLED, TESTED, OR INSPECTED BY THE FACTORY.
- D. ALL BELOW FLOOR WATER LINES MUST BE SIZED, INSTALLED, AND TESTED ON SITE PER APPLICABLE LOCAL AND STATE CODES.



LINE SIZED FOR
DISHWASHER

ELECTRIC WATER HEATER-RHEEM MODEL #82V40-2
ELECTRIC WATER HEATER-RHEEM MODEL #82V52-2
ELECTRIC WATER HEATER-RHEEM MODEL #83VR52-2
GAS WATER HEATER-RHEEM MODEL #22V40F1
GAS WATER HEATER-RHEEM MODEL #22V50F1

HANGER SPACING - PEX PIPE (SUPPLY)	
MAX HORIZONTAL SPACING (FT.)	MAX VERTICAL SPACING (FT.)
2'-8"	4'-0"

APPROVED BY
NIA
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz
6/9/2025

ALL DIMENSIONS FROM REAR
AND MARRIAGE EDGE

Builder: 530 Cavco-Crouse				Address: 235 Anthony Grove Rd. Crouse, NC 28033		Revisions	Scale: CUSTOM	Date: 06/03/2025	Cust: BROWN, JEFFREY		Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
Title: Hot Water Lines						Drawn By: NE	Reference: 2R2010-R		Dir: HBV		Pg.: WH	Run: .		


5300942763B2025-1003370

- NOTE:
- 1. 3/4" GALVANIZED, OR COPPER RELIEF DRAIN (NOT SHOWN) THRU FLOOR w/VISIBLE AIR GAP
 - 2. INLET WITH 1" CAP & CHAIN.
 - 3. DIMENSIONS EXPRESSED IN PARENTHESIS (A x B) INDICATE: (DIST. FROM REAR END OF HOME FLOOR x DIST. FROM HOME MATE LINE).
 - 4. ANTI-SCALD DEVICE ON ALL SHOWER, AND TUB/SHOWER COMBINATIONS.
 - 5. WATER-HAMMER ARRESTORS AT BATTERY OF FIXTURES INSTALLED WHEREVER THERE IS A QUICK-CLOSING VALVE CONFORMING TO ASSE 1010 & MANUFACTURER'S INSTRUCTIONS.
 - 6. SHUT-OFF VALVE IS REQUIRED AT EACH FIXTURE
 - 7. BATHROOMS WITH DOUBLE LAVS ARE FED FROM THE SAME RISER.
 - 8. ANY LINE NOT LABELED IS 1/2"
 - 9. WATER HEATER TEMPERATURE & PRESSURE RELIEF VALVE AND RELIEF DRAIN PIPE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 - 10. SHUT-OFF VALVE AT WATER HEATER IS FULL OPEN VALVE INSTALLED ON COLD WATER SUPPLY PIPE AT EACH WATER HEATER, PER CODE.
 - 11. FULLWAY SHUT-OFF VALVE WITH BLEED ORIFICE INSTALLED AT MAIN INLET SERVICE VALVE, INSTALLED ON-SITE, PER CODE.
 - 12. SEE SYSTEMS PACKAGE PLUMBING SECTION PAGES FOR ADDITIONAL PLUMBING NOTES AND DETAILS

SITE NOTES FOR DIAGRAM EXPLANATION:

- A. WHEN VERTICAL FIXTURE WATER SUPPLY RISERS ONLY ARE SHOWN ON THIS PLAN, RISERS ONLY ARE FACTORY INSTALLED AS SHOWN AND TERMINATED BELOW THE FLOOR AT THE INDICATED LOCATIONS. MATERIAL PROVISIONS, SYSTEM CONNECTIONS, TESTING, AND INSPECTION FOR ALL BELOW-FLOOR CONNECTIONS ARE ON SITE BY OTHERS IN ACCORDANCE WITH ALL STATE AND LOCAL CODES.
- B. WHEN BELOW-FLOOR SYSTEM CONNECTIONS TO RISERS ARE SHOWN ON PLAN BY SOLID LINES, THESE ARE COMPLETED, TESTED, AND INSPECTED IN THE FACTORY TO THE TERMINATION POINT SHOWN ON ILLUSTRATED PLAN.
- C. DOTTED LINES ON PLAN,(IF PRESENT), ARE INTENDED ONLY TO ILLUSTRATE TYPICAL ON-SITE CONNECTIONS. THESE ARE FOR ILLUSTRATION ONLY AND ARE NOT PROVIDED, INSTALLED, TESTED, OR INSPECTED BY THE FACTORY.
- D. ALL BELOW FLOOR WATER LINES MUST BE SIZED, INSTALLED, AND TESTED ON SITE PER APPLICABLE LOCAL AND STATE CODES.

ELECTRIC WATER HEATER-RHEEM MODEL #82V40-2
ELECTRIC WATER HEATER-RHEEM MODEL #82V52-2
ELECTRIC WATER HEATER-RHEEM MODEL #83VR52-2
GAS WATER HEATER-RHEEM MODEL #22V40F1
GAS WATER HEATER-RHEEM MODEL #22V50F1




APPROVED BY
NIA
6/9/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz

ALL DIMENSIONS FROM REAR
AND MARRIAGE EDGE

Builder: 530 Cavco-Crouse			Address: 235 Anthony Grove Rd. Crouse, NC 28033		Revisions	Scale: CUSTOM	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
Title: Cold Water Lines					Drawn By: NE	Reference: 2R2010-R	Dir: HBV	S/N: 44850	Pg.: WC	Run:	

5300942763B2025-1003370

NOTE:


1. ALL LINES 1/4" SLOPE/FOOT MINIMUM UNLESS OTHERWISE NOTED.
2.  DENOTES 1/8" SLOPE/FOOT.
3. ALL 2" DIA. LINES SHOWN FILLED (BOLD)
4. ALL LINES 1-1/2" DIA. MINIMUM OTHERWISE NOTED.
5. LINES SERVING STOOL ARE 3" DIA. CONTINUOUS TO OUTLET.
6. AIR ADMITTANCE VALVES SHOWN ARE IN ACCORDANCE w/ASSE 1051 & MANUFACTURER'S INSTRUCTIONS.
7. CONTINUOUS WASTE APPL. ON SINKS AND LAVATORIES WHERE SPACING DOES NOT EXCEED 30".
8. STACKS CLEANED THROUGH REMOVABLE FIXTURE P-TRAPS.
9. THE DISCHARGE LINE FROM THE DISHWASHER SHALL BE NOT LESS THAN 1/2 INCH NOMINAL SIZE AND SHALL EITHER BE LOOPED UP AND SECURELY FASTENED TO THE UNDERSIDE OF THE COUNTER OR BE CONNECTED TO A DECK-MOUNTED DISHWASHER AIR GAP FITTING THAT IS LISTED.

APPROVED BY

 6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz



ALL DIMENSIONS FROM REAR
AND MARRIAGE EDGE

HANGER SPACING - DRAIN PIPE (DWV)	
MAX HORIZONTAL SPACING (FT.)	VERTICAL SPACING
4'-0"	Vertical piping shall be supported at each story or floor level.

DWV FITTING IDENTIFICATION			
XLTL	LONG TURN 90° ELBOW	4X3CB	90° CLOSET ELBOW
XLSL	LONG TURN 90° STREET ELBOW	3-WAY-L	DOUBLE 90° ELBOW
45L	45° ELBOW	STY	SANITARY TEE
45SL	45° STREET ELBOW	LTTY	LONG RADIUS TY
22.5L	22 1/2° ELBOW	45 WYE	45° WYE
22.5SL	22 1/2° STREET ELBOW		

PLUMBING ABOVE THE FLOOR IS FACTORY INSTALLED. PLUMBING BELOW THE FLOOR INCLUDING CONNECTIONS SHALL BE INSTALLED ON SITE BY OTHERS ACCORDING TO SITE CONDITIONS, SUBJECT TO APPROVAL OF LOCAL INSPECTION. ON SITE PLUMBING SHOWN IS SUGGESTIVE ONLY.

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: CUSTOM	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
Title: DWV System		Drawn By: NE	Reference: 2R2010-R		Dlr: HBV			
					S/N: 44850	Pg.: DL		Run:

530D942763B2025-1003370

PIPE SUPPORT:

VERTICAL PIPING:



SUPPORTS AT 10' O.C. MAX.
OR BETWEEN FLOOR LEVELS.

HORIZONTAL PIPING:

SUPPORTS AT 4' O.C. MAX.
ENDS OF BRANCHES, AND
AT CHANGES IN ELEVATION
AND/OR DIRECTION.

TRAP ARMS:

SUPPORT LOCATED AS
CLOSE TO TRAP AS
POSSIBLE WHEN TRAP TO
VENT EXCEEDS 3'.




OPTIONAL GARBAGE DISPOSAL PLUMBING ILLINOIS MODELS ONLY - USE DETAIL ABOVE FOR OPTIONAL GARBAGE DISPOSAL.

APPROVED BY
NIA
6/9/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz

- NOTES:
- ALL BELOW FLOOR PLUMBING BY OTHERS. ALL FITTINGS BELOW BOTTOM CAN BE SHIPPED LOOSE.
 - ALL BELOW FLOOR PLUMBING ILLUSTRATIONS ARE RECOMMENDATIONS ONLY. ON-SITE CONDITIONS AND/OR RESTRICTIONS MAY REQUIRE SOME MODIFICATIONS.
 - OPT. GARBAGE DISPOSAL TO BE LOCATED ON KITCHEN SINK WASTE ASSEMBLY. ALL VENTS THRU ROOF TO BE 3", 12" MIN. ABOVE AND BELOW ROOF PENETRATION.
 - ALL P-TRAPS TO BE 1 1/2" UNLESS NOTED.
 - HORIZONTAL VENT SLOPE : 1/8" PER FOOT
 - HORIZONTAL DRAIN SLOPE: 1/4" PER FOOT
 - DRAIN, WASTE, AND VENT PLUMBING TO BE PVC PLASTIC OR EQUAL, APPROVED FOR DWV APPLICATIONS.
 - DRAIN AND DISCHARGE PIPES SERVING WATER HEATERS TO BE CPVC OR OTHER CODE APPROVED MATERIAL.
 - ANY TRANSITIONS TO MATERIALS, OTHER THAN THE SPECIFIED MATERIAL, MUST INCORPORATE AN APPROVED FITTING FOR CONNECTION.
 - ALL TUBS WITH WHIRLPOOL MUST BE PROVIDED WITH ACCESS TO MOTOR. ALL PLUMBING TO MEET OR EXCEED CURRENT ADOPTED PLUMBING CODES.
 - IN CONCEALED SPACES WHERE PIPING IS INSTALLED THRU HOLES OR NOTCHES IN STUDS, JOISTS, TRUSSES, OR SIMILAR MEMBERS LESS THAN 1 1/2" FROM NEAREST EDGE OF THE MEMBER, THE PIPE SHALL BE PROTECTED BY SHIELD PLATES.
 - PROTECTIVE SHIELD PLATES SHALL BE A MINIMUM OF 16 GA. STEEL. PLATES SHALL COVER AREA OF THE PIPE WHERE THE MEMBERS ARE NOTCHED OR BORED, AND SHALL EXTEND A MINIMUM OF 2" ABOVE SOLE PLATES AND BELOW TOP PLATES.
 - AIR ADMITTANCE VALVES MAY SUBSTITUTE ROOF VENTS AT VARIOUS LOCATIONS PER APPLICABLE STATE AND LOCAL PLUMBING CODES. THE 3" MAIN VENT MUST BE VENTED THRU THE ROOF AND CANNOT BE MECHANICALLY VENTED.
 - IN SEISMIC CATEGORIES D0, D1, D2 OR E STRAP UPPER THIRD AND LOWER THIRD OF WATER HEATER TO RESIST A HORIZONTAL FORCE OF 1/3 THE OPERATING WEIGHT OF THE WATER HEATER.

Builder: 530 Cavco-Crouse		Address: 235 Anthony Grove Rd. Crouse, NC 28033		Revisions	Scale: N.T.S.	Date: 06/03/2025	Cust: BROWN, JEFFREY		Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
Title: DWV Notes				Drawn By: NE	Reference: 2R2010-R		Dir: HBV		Pg.: DN	Run:		
							S/N: 44850					



FURNACE AND HEAT DUCTS ARE
OMITTED AND WILL BE INSTALLED
ON-SITE BY OTHERS


HVAC MUST BE INSTALLED BY A LICENSED HVAC
TECHNICIAN - PER CODE REQUIREMENTS

APPROVED BY
NIA 6/9/2025
Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws.
Joe Shultz

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 3/16" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY Dir: HBV S/N: 44850	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
		Drawn By: NE	Reference: 2R2010-R			Pg.: SP	Run:		

Title: Supply Air Ducts - Perimeter Registers

5300942763B2025-1003370



CEILING ROOM TO ROOM RETURN AIR JUMPERS ARE OMITTED
BUILDER RESPONSIBILITY ONSITE


APPROVED BY
NIA 6/9/2025
Joe Shultz

Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws.

RETURNS IN CEILING IN ADDITION TO AIR THRU GRILLES/OPENINGS

Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 3/16" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370
		Drawn By: NE	Reference: 2R2010-R		Dlr: HBV	S/N: 44850	Pg.: HR	Run:
Title: Ceiling Return Air System								

5300942763B2025-1003370



Footing size (in.)	Footing max. load (lbs.) for 8" x16" pier		
	1500 PSF	2000 PSF	2500 PSF
*16x16x6	2.5K	3.4K	4.3K
*20x20x6	4.0K	5.3K	6.7K
24x24x8	5.6K	7.6K	9.6K
30x30x10	8.5K	11.7K	14.8K
36x36x12	12.4K	16.7K	20.7K
42x42x14	16.5K	22.4K	28.2K
48x48x14	21.2K	N/A	N/A
* = A 4" thick pre-cast footer of equivalent width and length may be used in place of a 6" thick cast in place footer.			
Footer size must be designed by others to site conditions if noted kip load exceeds capacities listed above			

COLUMNS & FOOTINGS
MUST BE RATED TO
MEET THE CENTER
LINE LOADS LISTED

GROUND SNOW LOAD

20
PSF

Kip loads noted are based on allowable stress design (ASD).
Capacity of supports (columns, footings, etc.) must exceed noted Kip loads.
Any changes to this plan that effect the foundation in any way will be the sole responsibility of the builder/dealer.


SELF-WEIGHT ON FOOTERS NOT INCLUDED IN LOADS SHOWN.
♦ IF APPLICABLE, REPRESENTS TIE DOWN LOADS FROM BRACE WALLS TO FOUNDATION. TO BE DESIGNED ON SITE BY OTHERS.

FOR CONNECTION OF THE HOME TO FOUNDATION AT BRACING WALLS, REFER TO "BRACED WALLS-CALCULATED" PAGE, IF APPLICABLE. WHEN THIS PAGE IS PRESENT, HORIZONTAL AND OVERTURNING (RACKING) LOADS AT BRACING WALL LOCATIONS ARE INDICATED FOR THESE FOUNDATION CONNECTIONS. THESE LOADS MAY BE RECALCULATED AND REDESIGNED PER LOCAL CODES TO CONFORM TO SITE CONDITIONS AS REQUIRED. REFER TO CHAPTER 3 (3.9 TIE DOWN TO FOUNDATION) OF THE "MODULAR HOME INSTALLATION MANUAL" FOR ADDITIONAL INFORMATION. REFER TO APPLICABLE CODES FOR CONNECTION OF HOME TO FOUNDATION WHEN "BRACED WALLS-PRESCRIPTIVE" PAGE IS APPLICABLE.


FOUNDATION SHOWN MUST BE DESIGNED BY OTHERS TO THE SITE CONDITIONS. THIS INCLUDES SEISMIC DESIGN AND ATTACHING THE HOME TO THE FOUNDATION, ALONG WITH RESISTANCE TO LATERAL, LONGITUDINAL SHEAR, UPLIFT AND DOWNLIFT FORCES IN BOTH DIRECTIONS.



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz



- 2X10 OR TRUSS FLOOR NOTES -
1. FOUNDATION LAYOUT IS APPLICABLE TO NOTED MAXIMUM SNOW LOADING AND MINIMUM SOIL BEARING PRESSURE. REFER TO INSTALLATION MANUAL FOR OTHER APPLICABLE INFORMATION. CONSULT LOCAL OFFICIALS AND THE APPLICABLE LOCAL CODES FOR OTHER REQUIREMENTS (I.E. DRAINAGE, DAMP-PROOFING, BACKFILL SUPPORT, ETC.).
 2. WIDTH DIMENSIONS SHOWN INCLUDE A 3/4" ALLOWANCE PER HOME SECTION FOR HOMES WITH FACTORY-INSTALLED O.S.B. ON THE MARRIAGE WALL MATE LINE. THIS ALLOWANCE TAKES INTO ACCOUNT THE 7/16" O.S.B. MATERIAL INSTALLED ON EACH MARRIAGE WALL PLUS ALLOWANCE DUE TO OTHER FACTORS. IF HOME DOES NOT INCLUDE O.S.B. ON THE MARRIAGE WALL MATE LINE, FOUNDATION WIDTH IS TO BE SIZED EQUAL TO ACTUAL MANUFACTURED FLOOR WIDTH. LESSER DIMENSION, IF SHOWN, INDICATES ACTUAL FLOOR WIDTH. THESE DIMENSIONS DO NOT ALLOW FOR ANY VARIANCE THAT MAY OCCUR IN SITE INSTALLATION SUCH AS GAPPING, OFF CENTER SET OR OTHER FIELD-ENCOUNTERED VARIABLES. ANY ADJUSTMENTS NEEDED IN FOUNDATION WIDTH DUE TO SUCH VARIANCES ARE AT THE DISCRETION OF THE INSTALLER.
 3. FOR DEVIATIONS &/OR OTHER FOUNDATION DESIGNS CONSULT A LOCAL PROFESSIONAL ENGINEER & YOUR LOCAL BUILDING OFFICIAL.
 4. SILL PLATE FASTENING TO BE PER INSTALLATION MANUAL AND/OR LOCAL CODES. SILL FASTENING REQUIREMENT IS PER APPLICABLE WIND SPEED AND SEISMIC ZONES. SEE YOUR HOME DATA PLATE FOR APPLICABLE ZONES.
 5. CONCRETE COMPRESSIVE STRENGTH (FC'): 2500 PSI MINIMUM.
 6. CENTERLINE LINE SUPPORTS AND SPACING ARE BASED ON (2) 2X10's SPF#2 ON EACH HALF (4-2X10'S TOTAL).
 7. CRAWLSPACE VENTILATION IS NOT REQUIRED WHEN INSULATION IS APPLIED TO CRAWLSPACE WALLS AS REQUIRED BY RESCHECK (CONDITIONED AIR). INSTALLATION OF VENTS IN CRAWLSPACE WALLS WOULD MANDATE INSULATING THE FLOOR SYSTEM PER APPLICABLE THERMAL CALCULATIONS. REFER TO APPLICABLE PRESCRIPTIVE CODES & GUIDELINES. WHEN REQUIRED, ONE VENT SHALL BE PROVIDED WITHIN 3 FEET OF EACH CORNER.
 8. FOUNDATION CONSTRUCTION AND TIE DOWN REQUIREMENTS FOR HOMES LOCATED IN 90 MPH OR LESS WIND ZONES MAY USE APPLICABLE PRESCRIPTIVE CODES & GUIDELINES UNLESS NOTED OTHERWISE.



Builder: 530 Cavco-Crouse	Address: 235 Anthony Grove Rd. Crouse, NC 28033	Revisions	Scale: 1/8" = 1'-0"	Date: 06/03/2025	Cust: BROWN, JEFFREY Dir: HBV S/N: 44850	Prod. Code: D9	Number: 42763B	Order/Plan Number: 2025-1003370	
		Drawn By: NE	Reference: 2R2010-R			Pg.: FD20#		Run:	

Title: Foundation 2x10 Marriage Line without Stair

5300942763B2025-1003370



6-9-2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Project Information

For: The Commodore Corporation
 2025-1003370(NC)

Design Information

	Htg	Clg	Infiltration	
Outside db (°F)	10	99	Method	Simplified
Inside db (°F)	70	75	Construction quality	Average
Design TD (°F)	60	24	Fireplaces	0
Daily range	-	M		
Inside humidity (%)	50	50		
Moisture difference (gr/lb)	48	42		

HEATING EQUIPMENT

Make	Generic
Trade	
Model	AFUE 100
AHRI ref	
Efficiency	100 AFUE
Heating input	10.8 kW
Heating output	36899 Btuh
Temperature rise	26 °F
Actual air flow	1303 cfm
Air flow factor	0.040 cfm/Btuh
Static pressure	0.50 in H2O
Space thermostat	

COOLING EQUIPMENT

Make	Generic
Trade	
Cond	SEER 14.0
Coil	
AHRI ref	
Efficiency	12.2 EER, 14 SEER
Sensible cooling	26872 Btuh
Latent cooling	11516 Btuh
Total cooling	38388 Btuh
Actual air flow	1303 cfm
Air flow factor	0.054 cfm/Btuh
Static pressure	0.50 in H2O
Load sensible heat ratio	0.80

ROOM NAME	Area (ft²)	Htg load (Btuh)	Clg load (Btuh)	Htg AVF (cfm)	Clg AVF (cfm)
BA1	159	2701	1161	107	62
C1	80	770	324	30	17
G/R	407	4364	3229	173	174
KIT DR	411	5083	4803	201	259
pan	44	897	696	36	37
BA2	58	1157	835	46	45
UTL	83	2396	1322	95	71
B3	204	3541	2839	140	153
B2	173	2307	2504	91	135
FOYER	56	1308	549	52	30
MASTER BED	252	2511	1915	99	103
MEDIA	213	3489	2551	138	137
room 1	128	2387	1479	95	80
stair	52	0	0	0	0

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

H		92	0	0	0	0
Entire House	d	2412	32908	24207	1303	1303
Other equip loads			3991	1606		
Equip. @ 1.04 RSM				26872		
Latent cooling				6442		
TOTALS		2412	36899	33314	1303	1303

APPROVED BY

 6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

Project Information

For: The Commodore Corporation
 2025-1003370(NC)

Notes:

APPROVED BY



6/9/2025

Approval of this document does not authorize or
 approve any deviation or deviations from the
 requirements of applicable State Laws.

Joe Shultz

Design Information

Weather: Raleigh Executive, NC, US

Winter Design Conditions

Outside db 10 °F
 Inside db 70 °F
 Design TD 60 °F

Ventilation Method MJ8

Heating Summary

Structure 28001 Btuh
 Ducts (R-4.0) 4907 Btuh
 Central vent (61 cfm) 3991 Btuh
 Outside air
 Humidification 0 Btuh
 Piping 0 Btuh
 Equipment load 36899 Btuh

Infiltration

Method Simplified
 Construction quality Average
 Fireplaces 0

	Heating	Cooling
Area (ft²)	2412	2412
Volume (ft³)	19300	19300
Air changes/hour	0.32	0.16
Equiv. AVF (cfm)	103	51

Heating Equipment Summary

Make Generic
 Trade
 Model AFUE 100
 AHRI ref

Efficiency 100 AFUE
 Heating input 10.8 kW
 Heating output 36899 Btuh
 Temperature rise 26 °F
 Actual air flow 1303 cfm
 Air flow factor 0.040 cfm/Btuh
 Static pressure 0.50 in H2O
 Space thermostat

Summer Design Conditions

Outside db 99 °F
 Inside db 75 °F
 Design TD 24 °F
 Daily range M
 Relative humidity 50 %
 Moisture difference 42 gr/lb

Sensible Cooling Equipment Load Sizing

Structure 22046 Btuh
 Ducts (R-4.0) 2161 Btuh
 Central vent (61 cfm) 1606 Btuh
 Outside air
 Blower 0 Btuh
 Use manufacturer's data n
 Rate/swing multiplier 1.04
 Equipment sensible load 26872 Btuh

Latent Cooling Equipment Load Sizing

Structure 2441 Btuh
 Ducts 2291 Btuh
 Central vent (61 cfm) 1711 Btuh
 Outside air
 Equipment latent load 6442 Btuh

Equipment Total Load (Sen+Lat) 33314 Btuh
 Req. total capacity at 0.70 SHR 3.2 ton

Cooling Equipment Summary


Make Generic
 Trade
 Cond SEER 14.0
 Coil

AHRI ref
 Efficiency 12.2 EER, 14 SEER
 Sensible cooling 26872 Btuh
 Latent cooling 11516 Btuh
 Total cooling 38388 Btuh
 Actual air flow 1303 cfm
 Air flow factor 0.054 cfm/Btuh
 Static pressure 0.50 in H2O
 Load sensible heat ratio 0.80

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.



1ST FLOOR



APPROVED BY
NIA
6/9/2025

Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws.
Joe Shultz

Job #: 2025-1003370(NC)
Performed by AMS of Indiana, Inc. for:
The Commodore Corporation
2025-1003370(NC)

AMS of Indiana, Inc.
3933 E. Jackson Blvd.
Elkhart, IN 46516
Phone: 574-293-5526 Fax: 574-294-1366
eng-ams@comcast.net

Scale: 1 : 128
Page 1
Right-Suite@ Universal 2025
25.0.02 RSU56435
2025-Jun-04 09:33:14
...S:\Commodore\2025-1003370(NC)...

Project Information


For: The Commodore Corporation
 2025-1003370(NC)

	Heating	Cooling
External static pressure	0.50 in H2O	0.50 in H2O
Pressure losses	0.20 in H2O	0.20 in H2O
Available static pressure	0.30 in H2O	0.30 in H2O
Supply / return available pressure	0.150 / 0.150 in H2O	0.150 / 0.150 in H2O
Lowest friction rate	0 in/100ft	0 in/100ft
Actual air flow	1303 cfm	1303 cfm
Total effective length (TEL)		0 ft

Supply Branch Detail Table

Name	Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
B2-A	c 2504	91	135	0	0	0x0	VIFx	0	0	
B3	c 1420	70	76	0	0	0x0	VIFx	0	0	
B3-A	c 1420	70	76	0	0	0x0	VIFx	0	0	
BA1	h 1161	107	62	0	0	0x0	VIFx	0	0	
BA2	h 835	46	45	0	0	0x0	VIFx	0	0	
C1	h 324	30	17	0	0	0x0	VIFx	0	0	
FOYER	h 549	52	30	0	0	0x0	VIFx	0	0	
G/R	c 1076	58	58	0	0	0x0	VIFx	0	0	
G/R-A	c 1076	58	58	0	0	0x0	VIFx	0	0	
G/R-B	c 1076	58	58	0	0	0x0	VIFx	0	0	
KIT DR	c 1601	67	86	0	0	0x0	VIFx	0	0	
KIT DR-A	c 1601	67	86	0	0	0x0	VIFx	0	0	
KIT DR-B	c 1601	67	86	0	0	0x0	VIFx	0	0	
MASTER BED	c 957	50	52	0	0	0x0	VIFx	0	0	
MASTER BED-A	c 957	50	52	0	0	0x0	VIFx	0	0	
MEDIA	h 1276	69	69	0	0	0x0	VIFx	0	0	
MEDIA-A	h 1276	69	69	0	0	0x0	VIFx	0	0	
UTL	h 1322	95	71	0	0	0x0	VIFx	0	0	
pan	c 696	36	37	0	0	0x0	VIFx	0	0	
room 1	h 1479	95	80	0	0	0x0	VIFx	0	0	

APPROVED BY



6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb2	0x 0	1303	1303	0	0	0	0	0x 0		VIFx	

APPROVED BY

 6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz



Generated by REScheck-Web Software

Compliance Certificate

Project 2025-1003370

Energy Code: **2018 IECC**
Location: **Harnett County, North Carolina**
Construction Type: **Single-family**
Project Type: **New Construction**
Project SubType: **None**
Orientation: **Unspecified**
Conditioned Floor Area: **2,433 ft2**
Glazing Area: **11%**
Climate Zone: **4 (3499 HDD)**
Permit Date:
Permit Number:
All Electric: **false**
Is Renewable: **false**
Has Charger: **false**
Has Battery: **false**
Has Heat Pump: **false**

APPROVED BY



6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Construction Site:
Tbd Baptist Grove Rd
Fuquay-varina, North Carolina
27526

Owner/Agent:
BROWN, JEFFREY
HBV

Designer/Contractor:
Cavco-Crouse
235 Anthony Grove Rd.
Crouse, NC 28033

Compliance: Passes using UA trade-off

Compliance: **2.8% Better Than Code** Maximum UA: **426** Your UA: **414** Maximum SHGC: **0.40** Your SHGC: **0.24**

The % Better or Worse Than Code Index reflects how close to compliance the house is based on code trade-off rules.
It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home.

Slab-on-grade tradeoffs are no longer considered in the UA or performance compliance path in REScheck. Each slab-on-grade assembly in the specified climate zone must meet the minimum energy code insulation R-value and depth requirements.

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Ceiling 1: Flat Ceiling or Scissor Truss	1,141	38.0	0.0	0.030	0.026	34	30
Ceiling 2 [Between knee walls]: Flat Ceiling or Scissor Truss	1,292	30.0	0.0	0.035	0.026	45	34
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Right side	401	19.0	0.0	0.060	0.060	21	21
Window - Hy-Lite 3240 Glass Block {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.58 Orientation: Right side	9			0.510	0.320	5	3
Window - Lippert SH 3668 {Qty 2}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Right side	35			0.340	0.320	12	11

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Prop. U-Factor	Req. U-Factor	Prop. UA	Req. UA
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Left side	401	19.0	0.0	0.060	0.060	23	23
Door - Hinged - Exterior - 9 Lite {Qty 1}: null Orientation: Left side	22			0.290	0.320	6	7
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Back	743	19.0	0.0	0.060	0.060	37	37
Door - Sliding Patio {Qty 1}: null Orientation: Back	40			0.230	0.320	9	13
Window - Lippert 7112 Transom {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.26 Orientation: Back	6			0.310	0.320	2	2
Window - Lippert SH 3658 {Qty 2}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Back	30			0.340	0.320	10	10
Window - Lippert 3612 Transom {Qty 2}: Vinyl Frame:Double Pane with Low-E SHGC: 0.26 Orientation: Back	6			0.310	0.320	2	2
Window - (2) Lippert SH 3036 {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Back	15			0.340	0.320	5	5
Window - Lippert SH 3036 {Qty 3}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Back	23			0.340	0.320	8	7
Wall [1walls]: Wood Frame, 16" o.c. Orientation: Front	743	19.0	0.0	0.060	0.060	34	34
Door - Hinged - Exterior - 6 Panel {Qty 1}: Solid Orientation: Front	22			0.170	0.320	4	7
Window - (2) Lippert SH 3668 {Qty 4}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Front	139			0.340	0.320	47	44
Window - Lippert SH 3668 {Qty 1}: Vinyl Frame:Double Pane with Low-E SHGC: 0.23 Orientation: Front	17			0.340	0.320	6	5
Wall [Cape Close Off Kit]: Wood Frame, 24" o.c. Orientation: Unspecified	200	11.0	0.0	0.087	0.060	16	11
Attic Door: Solid Orientation: Unspecified	18			0.460	0.320	8	6
Floor 1: All-Wood Joist/Truss:Over Outside Air	2,433	30.0	0.0	0.033	0.047	80	114

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the 2018 IECC requirements in REScheck Version : REScheck-Web and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

N. Edwards - drafter

Name - Title

N. Edwards

Signature

6/3/2025

Date








Inspection Checklist

Energy Code: 2018 IECC

Requirements: 0.0% were addressed directly in the REScheck software

Text in the "Comments/Assumptions" column is provided by the user in the REScheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Pre-Inspection/Plan Review	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
103.1, 103.2 [PR1] ¹ 	Construction drawings and documentation demonstrate energy code compliance for the building envelope. Thermal envelope represented on construction documents.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
103.1, 103.2, 403.7 [PR3] ¹ 	Construction drawings and documentation demonstrate energy code compliance for lighting and mechanical systems. Systems serving multiple dwelling units must demonstrate compliance with the IECC Commercial Provisions.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
302.1, 403.7 [PR2] ² 	Heating and cooling equipment is sized per ACCA Manual S based on loads calculated per ACCA Manual J or other methods approved by the code official.	Heating: Btu/hr____ Cooling: Btu/hr____	Heating: Btu/hr____ Cooling: Btu/hr____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

APPROVED BY

6/9/2025



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

1 High Impact (Tier 1)

2 Medium Impact (Tier 2)

3 Low Impact (Tier 3)

Section # & Req.ID	Foundation Inspection	Complies?	Comments/Assumptions
303.2.1 [FO11] ² 	A protective covering is installed to protect exposed exterior insulation and extends a minimum of 6 in. below grade.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.9 [FO12] ² 	Snow- and ice-melting system controls installed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	













Additional Comments/Assumptions:

APPROVED BY

6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
402.1.1, 402.3.4 [FR1] ¹ 	Door U-factor.	U-____	U-____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Envelope Assemblies table for values.
402.1.1, 402.3.1, 402.3.3, 402.5 [FR2] ¹ 	Glazing U-factor (area-weighted average).	U-____	U-____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Envelope Assemblies table for values.
303.1.3 [FR4] ¹ 	U-factors of fenestration products are determined in accordance with the NFRC test procedure or taken from the default table.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.4.1.1 [FR23] ¹ 	Air barrier and thermal barrier installed per manufacturer's instructions.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.4.3 [FR20] ¹ 	Fenestration that is not site built is listed and labeled as meeting AAMA /WDMA/CSA 101/I.S.2/A440 or has infiltration rates per NFRC 400 that do not exceed code limits.	<div style="text-align: center;"> APPROVED BY  6/9/2025 </div>		<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.4.5 [FR16] ²	IC-rated recessed lighting fixtures sealed at housing/interior finish and labeled to indicate ≤2.0 cfm leakage at 75 Pa.	<div style="text-align: center;"> Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws. Joe Shultz </div>		<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.1 [FR12] ¹ 	Supply and return ducts in attics insulated ≥ R-8 where duct is ≥ 3 inches in diameter and ≥ R-6 where < 3 inches. Supply and return ducts in other portions of the building insulated ≥ R-6 for diameter ≥ 3 inches and R-4.2 for < 3 inches in diameter.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.2 [FR13] ¹ 	Ducts, air handlers and filter boxes are sealed with joints/seams compliant with International Mechanical Code or International Residential Code, as applicable.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.5 [FR15] ³ 	Building cavities are not used as ducts or plenums.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.4 [FR17] ² 	HVAC piping conveying fluids above 105 °F or chilled fluids below 55 °F are insulated to ≥R-3.	R-____	R-____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.4.1 [FR24] ¹ 	Protection of insulation on HVAC piping.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.3 [FR18] ² 	Hot water pipes are insulated to ≥R-3.	R-____	R-____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
403.6 [FR19] ²	Automatic or gravity dampers are installed on all outdoor air intakes and exhausts.			<div><input type="checkbox"/>Complies</div> <div><input type="checkbox"/>Does Not</div> <div><input type="checkbox"/>Not Observable</div> <div><input type="checkbox"/>Not Applicable</div>	





Additional Comments/Assumptions:

APPROVED BY

6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Section # & Req.ID	Insulation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
303.1 [IN13] ² 	All installed insulation is labeled or the installed R-values provided.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.1.1, 402.2.6 [IN1] ¹ 	Floor insulation R-value.	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Steel	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Steel	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Envelope Assemblies table for values.
303.2, 402.2.8 [IN2] ¹ 	Floor insulation installed per manufacturer's instructions and in substantial contact with the underside of the subfloor, or floor framing cavity insulation is in contact with the top side of sheathing, or continuous insulation is installed on the underside of floor framing and extends from the bottom to the top of all perimeter floor framing members.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.1.1, 402.2.5, 402.2.6 [IN3] ¹ 	Wall insulation R-value. If this is a mass wall with at least ½ of the wall insulation on the wall exterior, the exterior insulation requirement applies (FR10).	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Mass <input type="checkbox"/> Steel	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Mass <input type="checkbox"/> Steel	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Envelope Assemblies table for values.
303.2 [IN4] ¹	Wall insulation is installed per manufacturer's instructions.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:


APPROVED BY





6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
402.1.1, 402.2.1, 402.2.2, 402.2.6 [FI1] ¹	Ceiling insulation R-value.	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Steel	R-_____ <input type="checkbox"/> Wood <input type="checkbox"/> Steel	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	See the Envelope Assemblies table for values.
303.1.1.1, 303.2 [FI2] ¹	Ceiling insulation installed per manufacturer's instructions. Blown insulation marked every 300 ft ² .			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.2.3 [FI22] ²	Vented attics with air permeable insulation include baffle adjacent to soffit and eave vents that extends over insulation.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.2.4 [FI3] ¹	Attic access hatch and door insulation ≥ R-value of the adjacent assembly.	R-____	R-____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
402.4.1.2 [FI17] ¹	Blower door test @ 50 Pa. ≤=5 ach in Climate Zones 1-2, and ≤=3 ach in Climate Zones 3-8.	ACH 50 = ____	ACH 50 = ____	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.3 [FI27] ¹	Ducts are pressure tested to determine air leakage with either: Rough-in test: Total leakage measured with a pressure differential of 0.1 inch w.g. across the system including the manufacturer's air handler enclosure if installed at time of test. Postconstruction test: Total leakage measured with a pressure differential of 0.1 inch w.g. across the entire system including the manufacturer's air handler enclosure.	____ cfm/100 ft ²	____ cfm/100 ft ²	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.4 [FI4] ¹	Duct tightness test result of ≤=4 cfm/100 ft ² across the system or ≤=3 cfm/100 ft ² without air handler @ 25 Pa. For rough-in tests, verification may need to occur during Framing Inspection.	____ cfm/100 ft ²	____ cfm/100 ft ²	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.3.2.1 [FI24] ¹	Air handler leakage designated by manufacturer at ≤=2% of design air flow.	 <p>APPROVED BY</p> <p>6/9/2025</p> <p>Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.</p> <p>Joe Shultz</p>		<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.1.1 [FI9] ²	Programmable thermostats installed for control of primary heating and cooling systems and initially set by manufacturer to code specifications.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.1.2 [FI10] ²	Heat pump thermostat installed on heat pumps.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.1 [FI11] ²	Circulating service hot water systems have automatic or accessible manual controls.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

1 High Impact (Tier 1)	2 Medium Impact (Tier 2)	3 Low Impact (Tier 3)
------------------------	--------------------------	-----------------------

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
403.6.1 [FI25] ²	All mechanical ventilation system fans not part of tested and listed HVAC equipment meet efficacy and air flow limits per Table R403.6.1.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.2 [FI26] ²	Hot water boilers supplying heat through one- or two-pipe heating systems have outdoor setback control to lower boiler water temperature based on outdoor temperature.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.1.1 [FI28] ²	Heated water circulation systems have a circulation pump. The system return pipe is a dedicated return pipe or a cold water supply pipe. Gravity and thermosyphon circulation systems are not present. Controls for circulating hot water system pumps start the pump with signal for hot water demand within the occupancy. Controls automatically turn off the pump when water is in circulation loop is at set-point temperature and no demand for hot water exists.	<div style="text-align: center;"> <p>APPROVED BY</p>  <p>6/9/2025</p> <p>Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.</p> <p>Joe Shultz</p> </div>		<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.1.2 [FI29] ²	Electric heat trace systems comply with IEEE 515.1 or UL 515. Controls automatically adjust the energy input to the heat tracing to maintain the desired water temperature in the piping.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.2 [FI30] ²	Demand recirculation water systems have controls that manage operation of the pump and limit the temperature of the water entering the cold water piping to ≤ 104°F.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
403.5.4 [FI31] ²	Drain water heat recovery units tested in accordance with CSA B55.1. Potable water-side pressure loss of drain water heat recovery units < 3 psi for individual units connected to one or two showers. Potable water-side pressure loss of drain water heat recovery units < 2 psi for individual units connected to three or more showers.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
404.1 [FI6] ¹	90% or more of permanent fixtures have high efficacy lamps.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
404.1.1 [FI23] ³ 	Fuel gas lighting systems have no continuous pilot light.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
401.3 [FI7] ²	Compliance certificate posted.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Section # & Req.ID	Final Inspection Provisions	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
303.3 [FI18] ³	Manufacturer manuals for mechanical and water heating systems have been provided.			<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	

Additional Comments/Assumptions:

APPROVED BY

6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz



2018 IECC Energy Efficiency Certificate

Insulation Rating	R-Value
Above-Grade Wall	19.00
Below-Grade Wall	0.00
Floor	30.00
Ceiling / Roof	30.00
Ductwork (unconditioned spaces):	_____

Glass & Door Rating	U-Factor	SHGC
Window	0.34	0.23
Door	0.23	

Heating & Cooling Equipment	Efficiency
Heating System: _____	_____
Cooling System: _____	_____
Water Heater: _____	_____

Name: _____ Date: _____

Comments

APPROVED BY

NIA 6/9/2025


Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Job 32802	Truss A098601	Truss Type RIGID COLLAR TIE CONNECTION DETAILS 1	Qty	Ply	UFP ENGINEERING 1 Bulletin 05-02 REF # 2001092
--------------	------------------	---	-----	-----	--


Universal Forest Products Inc., Grand Rapids, MI 49525,

2x4 Collar Tie
Nailed to 2x6 Chord




Detail (A)

2x6 Collar Tie
Nailed to 2x6 Chord




Detail (B)

2x6 Collar Tie
Nailed to 2x8 Chord




Detail (C)

This Bulletin to be used only in conjunction with UFPI truss designs which specifically refer to this Bulletin by number for collar tie field fastening.




2x8 Collar Tie
Nailed to 2x6 Chord



Detail (D)


2x8 Collar Tie
Nailed to 2x8 Chord



Detail (E)

Acceptable Alternate Applications

See truss print for which detail is actually used



Section A-A

Section A-A

* FOR 1 PLY, OFFSET NAILS WITH RESPECT TO EACH FACE.

Power Driven Nails Rigid Collar Tie
Connection Details

- A) Side member shall be fastened with structural adhesive that meets the requirements of ASTM-2559. Maximum wood to wood gap = 1/16".
B) Bostitch .131" Dia. x 3" nails (or equal)



8.620 e Sep 22 2022 MiTek Industries, Inc. Tue Apr 4 07:13:30 2023 Page 1





UFP INDUSTRIES

Job	Truss	MFG	Customer
112915	CCB32621	315	COMMODORE

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



APPROVED BY


NIA

6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

Copyright © 2023 UFP Industries, Inc. All Rights Reserved



APPROVED BY
NTA
6/9/2025
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
Joe Shultz

Plate Offsets (X,Y)-- [1:0-4-4,Edge], [1:0-5-8,0-2-12], [2:0-0-4,0-0-0], [4:0-0-4,0-0-0], [5:0-5-8,0-2-12], [5:0-4-4,Edge]

SPACING-- 2-0-0 LOADING (psf) TCLL 17.8 (Ground Snow=30.0) TCDL 10.0 BCLL 0.0 * BCDL 10.0	SPACING-- 1-4-0 LOADING (psf) TCLL 26.7 (Ground Snow=45.0) TCDL 15.0 BCLL 0.0 * BCDL 15.0	SPACING-- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IBC2021/TPI2014	CSI. TC 0.70 BC 0.63 WB 0.00 Matrix-R	DEFL. in (loc) l/defl L/d Vert(LL) -0.19 1-5 >865 240 Vert(CT) -0.30 1-5 >545 180 Horz(CT) 0.00 5 n/a n/a	PLATES GRIP MT20 197/144 MT18HS 197/144 Weight: 115 lb FT = 0%
---	---	--	---	---	--

LUMBER--
TOP CHORD 2x10 SP No.2 or 2x10 SPF No.2 "Except" T2: 2x6 SP No.2 or 2x6 SPF No.2
BOT CHORD 2x10 SP No.2 or 2x10 SPF No.2
WEDGE Left: 2x4 SPF Stud , Right: 2x4 SPF Stud

BRACING--
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 8-10-10 oc bracing.

REACTIONS. (lb/size) 1=513/0-5-8 (min. 0-1-8), 5=513/0-5-8 (min. 0-1-8)
Max Horz 1=-359(LC 8)
Max Uplift 1=-303(LC 13), 5=-301(LC 12)
Max Grav 1=668(LC 3), 5=667(LC 4)

FORCES. (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-507/399, 2-8=-358/327, 8-9=-300/332, 3-9=-296/345, 3-10=-291/342, 10-11=-298/329, 4-11=-353/325, 4-5=-507/400
BOT CHORD 1-6=-133/276, 6-7=-133/276, 5-7=-133/276

REQUIRED FIELD JOINT CONNECTIONS - Maximum Compression (lb)/ Maximum Tension (lb)/ Maximum Shear (lb)/ Maximum Moment (lb-in)
3=246/349/358/0

- NOTES--
- 1) Wind: ASCE 7-16; Vult=150mph (3-second gust) Vasd=119mph @24in o.c.; TCDL=4.0psf; BCDL=4.0psf; (Alt. 180mph @16in o.c.; TCDL=6.0psf; BCDL=6.0psf); h=36ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-8 to 3-0-8, Interior(1) 3-0-8 to 3-9-4, Exterior(2R) 3-9-4 to 9-9-4, Interior(1) 9-9-4 to 10-7-8, Exterior(2E) 10-7-8 to 13-7-8 zone; cantilever left and right exposed ; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-16; Pg=30.0 psf; Ps=17.8 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=0.77; Ct=1.10
 - 3) Roof design snow load has been reduced to account for slope.
 - 4) Unbalanced snow loads have been considered for this design.
 - 5) All plates are MT20 plates unless otherwise indicated.
 - 6) See HINGE PLATE DETAILS for plate placement.
 - 7) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
 - 8) All additional member connections shall be provided by others for forces as indicated.
 - 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit b the bottom chord and any other members, with BCDL = 10.0psf.
 - 11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 303 lb uplift at joint 1 and 301 lb uplift at joint 1
 - 12) This truss is designed in accordance with the 2021 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 13) This truss is designed in accordance with the 2018 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 14) This truss is designed in accordance with the 2015 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
 - 15) Temporary supports are required to maintain the bottom chord in a level position during storage, transportation, and setup. Retain a design professional to specify all temporary bracing to support the truss until setup is complete. Temporary support(s) must not be removed until field connections are completed.
 - 16) Take precaution to keep the chords in plane, any bending or twisting of the hinge plate must be repaired before the building is put into service.
 - 17) The field-installed members are an integral part of the truss design. Retain a design professional to specify final field connections and temporary supports. All field-installed members must be properly fastened prior to applying any loading to the truss. This design anticipates the final position.
 - 18) Based on: P1595410. Changes: IBC 2021, 150mph wind, SP/SPF lower top chords.



The professional engineering seal indicates that a licensed professional engineer has designed the truss under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

3/30/2023

WARNING - Verify design parameters and READ NOTES

Truss shall not be cut or modified without approval of the truss design engineer.

This component has only been designed for the loads noted on this drawing. Construction and lifting forces have not been considered. The builder is responsible for lifting methods and system design. Builder responsibilities are defined under TPI1. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult BCSI 1-06 from the Wood Truss Council of America and Truss Plate Institute Recommendation available from WTCA, 6300 Enterprise LN, Madison, WI 53719 J:\support\MitekSupp\templates\ufp.tpe

UFP Industries, Inc.
PHONE (616)-364-6161

2801 EAST BELTLINE RD, NE
GRAND RAPIDS, MI 49525





UFP INDUSTRIES

Job	Truss	MFG	Customer
112830	P1595413	315	COMMODORE

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



APPROVED BY




6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

APPROVED BY
NTA 6/9/2025
Approval of this document does not author
approve any deviation or deviations from t
requirements of applicable State Laws.
Joe Shultz



SPACING:- 2-0-0 LOADING (psf)	SPACING:- 1-4-0 LOADING (psf)	SPACING- 2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IBC2021/TPI2014	CSI. TC 0.84 BC 0.88 WB 0.61 Matrix-R	DEFL. in (loc) l/defl L/d Vert(LL) 0.41 1-14 >804 240 Vert(CT) -0.39 12-14 >835 180 Horz(CT) 0.02 11 n/a n/a Attic -0.16 12-14 900 360	PLATES GRIP MT20 197/144 MT18HS 197/144 Weight: 203 lb FT = 0%
TCLL 17.8 (Ground Snow=30.0) TCDL 10.0 BCLL 0.0 * BCDL 10.0	TCLL 26.7 (Ground Snow=45.0) TCDL 15.0 BCLL 0.0 * BCDL 15.0				

REQUIRED FIELD JOINT CONNECTIONS - Max/Min Compression (lb)/ Maximum Tension (lb)/ Maximum Shear (lb)/ Maximum Moment (lb-in)
4=978/740/53/0, 5=353/191/215/0, 6=162/215/217/0, 7=352/188/217/0, 8=978/740/53/0, 12=386/793/0/0, 14=386/793/0/0

NOTES-

- 1) Wind: ASCE 7-16; Vult=150mph (3-second gust) Vasd=119mph @24in o.c.; TCDDL=4.0psf; BCDDL=4.0psf; (Alt. 180mph @16in o.c.; TCDDL=6.0psf; BCDDL=6.0psf); h=36ft; Cat. II; Exp C; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2E) 0-0-8 to 3-0-8, Interior(1) 3-0-8 to 10-7-4, Exterior(2R) 10-7-4 to 16-7-4, Interior(1) 16-7-4 to 24-3-8, Exterior(2E) 24-3-8 to 27-3-8 zone; cantilever left and right exposed ;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 2) TCLL: ASCE 7-16; Pg=30.0 psf; Ps=17.8 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat C; Partially Exp.; Ce=1.0; Cs=0.77; Ct=1.10
- 3) Roof design snow load has been reduced to account for slope.
- 4) Unbalanced snow loads have been considered for this design.
- 5) All plates are MT20 plates unless otherwise indicated.
- 6) See HINGE PLATE DETAILS for plate placement.
- 7) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
- 8) All additional member connections shall be provided by others for forces as indicated.
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit b the bottom chord and any other members, with BCDDL = 10.0psf.
- 11) Ceiling dead load (5.0 psf) on member(s). 3-4, 8-9, 4-8
- 12) Bottom chord live load (40.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 12-14
- 13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 573 lb uplift at joint 1 and 571 lb uplift at joint 14
- 14) Attic room checked for L/360 deflection.
- 15) This truss is designed in accordance with the 2021 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
- 16) This truss is designed in accordance with the 2018 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
- 17) This truss is designed in accordance with the 2015 IBC Sec 2306.1 and referenced standard ANSI/TPI 1
- 18) Take precaution to keep the chords in plane, any bending or twisting of the hinge plate must be repaired before the building is put into se
- 19) The field-installed members are an integral part of the truss design. Retain a design professional to specify final field connections and ten supports. All field-installed members must be properly fastened prior to applying any loading to the truss. This design anticipates the fina position.
- 20) Temporary supports are required to maintain the bottom chord in a level position during storage, transportation, and setup. Retain a design professional to specify all temporary bracing to support the truss until setup is complete. Temporary support(s) must not be removed until all field connections are completed.
- 21) The bottom chord must be laterally braced during shipment and setup to prevent damage to the splice plate.
- 22) Based on: CCB33030. Changes: IBC 2021.

The professional engineering seal indicates that a licensed professional engineer has designed the truss under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.

3/23/2023




WARNING - Verify design parameters and READ NOTES

Truss shall not be cut or modified without approval of the truss design engineer.

This component has only been designed for the loads noted on this drawing. Construction and lifting forces have not been considered. The builder is responsible for lifting methods and system design. Builder responsibilities are defined under TP11. This design is based only upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult BCS1-1-06 from the Wood Truss Council of America and Truss Plate Institute Recommendation available from WTCA, 6300 Enterprise LN, Madison, WI 53719 J:\support\MitekSupp\templates\ufp.tpe

UFP Industries, Inc.
PHONE (616)-364-6161

2801 EAST BELTLINE RD, NE
GRAND RAPIDS, MI 49525





UFP INDUSTRIES

Job	Truss	MFG	Customer
112740	CCB33046	315	COMMODORE

The professional engineering seal indicates that a licensed professional has reviewed the design under the standards referenced within this document, not necessarily the current state building code. The engineering seal is not an approval to use a design in a specific state. The final determination on whether a truss design is acceptable under the locally adopted building code rest with the building official or designated appointee.



APPROVED BY

NIA

6/9/2025

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

Joe Shultz

NORTH CAROLINA

MODULAR PLANS REVIEW CHECKLIST

PAGE 2 of 3

REVISED 1-30-2025

Plan Sheet Page # and NOTES

MECHANICAL

Design calculations
 Installed unit capacity
 Supply and returns (locations and sizes)
 Duct sizes
 Specifications (units, ducts)
 All appliances furnished by mfg. shown on plans

ELECTRICAL

Plan
 Location of all electrical boxes
 Electrical panel location
 Note regarding main disconnect (if applicable)
 Exterior lighting and receptacles
 Ground level receptacles (if applicable)
 Smoke detector location(s)
 Electrical load calculations
 Electrical panel layout (breaker and wire sizes, circuit schedule)
 Panel and service entrance sizes
 All fixtures furnished by mfg. shown on plans

ACCESSIBILITY

(for other than 1 & 2 family dwellings)

Entrances and means of egress
 Doors, doorways, and door hardware
 Stairs and handrails
 Toilet rooms, plumbing fixtures, grab bars, etc
 Bathrooms and shower rooms
 Occupancy specific requirements
 Multi-family dwellings: Type A and B units

FLOOR X-SECTION

Joists and beam sizes and spacing
 Materials species and grade
 Sheathing, decking, and concrete as applicable
 Fastening instructions
 Insulation
 Details as required for clarification

WALL X-SECTION

Stud and column sizes and spacing
 Materials species and grade
 Sheathing and bracing
 Headers and lintels
 Finishes
 Fastening instructions
 Insulation
 Details as required for clarification

<u>NORTH CAROLINA</u>		
<u>MODULAR PLANS REVIEW CHECKLIST</u>		
	PAGE 3 of 3	REVISED 1-30-2025
	Plan Sheet Page # and NOTES	
<u>CEILING / ROOF X-SECTION</u>		
	Truss, rafter, and beam spacing	
	Lumber species and grade	
	Sheathing and decking	
	Finishes	
	Fastening instructions	
	Insulation	
	Details including NC sealed truss designs or manual reference	
<u>FOUNDATION PLAN</u>		
	Footings, pier, and curtain wall locations and specifications	
	X-sections with dimensions	
	Anchorage - sill plate to piers and curtain wall	
	Anchorage - building to sill plate	
	Anchorage - tie downs (lateral and longitudinal)	
	Soil bearing capacity	
	Minimum concrete compressive strength	
	Mortar type	
	Ventilation requirements (with and without vapor barrier)	
	Crawl space access requirements	
<u>ENERGY COMPLIANCE</u>		
	Demonstrated compliance	
<u>SET-UP INSTRUCTIONS</u>		
	Floor and ceiling connections	
	Marriage wall connections	
	Roof set-up and connection	
	Plumbing connections	
	Mechanical connections	
	Electrical connections	
	Fire stopping	
	Air infiltration elimination	
	Notice to inspections department attachment if set-up instructions are by attachment	
<u>ITEMS NOT INSPECTED IN PLANT</u>		
	List of items not inspected by 3rd. Party	
	Notice to inspections department	