

OLD HICKORY BUILDINGS, LLC

P.O. BOX 331973
MURFREESBORO, TN 37133

GENERAL NOTES:

- 1. STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH THE 2018 NORTH CAROLINA RESIDENTIAL CODE (NCRC) AND THE 2018 NORTH CAROLINA BUILDING CODE (NCBC).
- 2. ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE ABOVE CODES AT THE TIME OF MANUFACTURE.
- 3. DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS.
- 4. STRUCTURES ARE CLASSIFIED AS "MINOR STORAGE FACILITIES" (RISK CATEGORY I) PER NCBC TABLE 1604.5 AND SHOULD NOT BE USED FOR HUMAN HABITATION.
- 5. WOOD FRAMING SHALL COMPLY WITH THE ANSI/AWC "NATIONAL DESIGN SPECIFICATION (NDS) FOR WOOD CONSTRUCTION", 2015.
- 6. ALL ROOFING IS TO BE 29 GA. METAL PANELS.
- 7. ALL EXTERIOR WALL SIDING IS TO BE 29 GA. METAL PANELS.
- 8. ALL FLOOR JOISTS ARE TO BE PRESSURE TREATED SYP #2, OR BETTER, UNLESS NOTED OTHERWISE. FLOOR JOISTS FOR 10' WIDE BUILDINGS ARE TO BE SYP #1, OR BETTER.
- 9. ALL UN-TREATED WOOD FRAMING IS TO BE SPF #2 OR BETTER.
- 10. ALL EXTERIOR NAILS ARE TO BE ZINC COATED.

- 11. ALL FLOOR DECKING IS TO BE 5/8" OR 3/4" PLYWOOD OR ENGINEERED FLOORING.
- 12. ALL SKIDS ARE TO BE 4x6 PRESSURE TREATED, RATED FOR GROUND CONTACT.
- 13. SECTIONS AND DETAILS SHOWN ARE INTENDED TO BE TYPICAL AND SHALL APPLY AT ALL SIMILAR LOCATIONS, UNLESS NOTED OTHERWISE.

ITEMS BY OTHERS:
THE FOLLOWING ITEMS ARE TO BE SUPPLIED AND INSTALLED BY OTHERS. THESE ITEMS MAY BE SUBJECT TO LOCAL JURISDICTION APPROVAL. OLD HICKORY BUILDINGS IS NOT RESPONSIBLE FOR THESE ITEMS.

- 1. THE COMPLETE FOUNDATION AND TIE-DOWN SYSTEM
- 2. RAMPS, STAIRS, AND GENERAL ACCESS
- 3. ELECTRICAL SERVICE HOOKUP

DESIGN CRITERIA:


- 1. RISK CATEGORY I
- 2. FLOOR LIVE LOAD: 40 PSF
- 3. ROOF LIVE LOAD: 20 PSF (REDUCIBLE PER NCBC 1607.12.2.1)
- 4. SNOW LOADS ARE BASED ON THE FOLLOWING:
GROUND SNOW LOAD, Pg = 20 PSF
FLAT ROOF SNOW LOAD, Pf = 14 PSF
EXPOSURE FACTOR, Ce = 1.0
IMPORTANCE FACTOR, I = 0.8
THERMAL FACTOR, Ct = 1.2
- 5. WIND LOADS ARE BASED ON THE FOLLOWING:
Vult = 115 MPH
RISK CATEGORY I
EXPOSURE CATEGORY B
INTERNAL PRESSURE COEFFICIENT:
GCpi = ±0.18
COMPONENTS & CLADDING:
ROOF-ZONE 1 = 10.0, -13.1 PSF
ROOF-ZONE 2 = 10.0, -22.7 PSF
ROOF-ZONE 3 = 10.0, -33.6 PSF
WALL-ZONE 4 = 14.3, -15.5 PSF
WALL-ZONE 5 = 14.3, -19.1 PSF

NOTE: C&C WIND PRESSURES SHOWN ARE FOR A 10 SQUARE FOOT EFFECTIVE AREA (Ae) AND MAY BE REDUCED FOR LARGER AREAS AS ALLOWED BY CODE.

PIERS (IF REQUIRED):

- 1. PIERS ARE NOT REQUIRED WHEN THE SKIDS CAN BE SUPPORTED ON FIRM, LEVEL GROUND. PIERS ALONG INTERIOR SKIDS SHALL BE ORIENTED WITH THE LONG SIDE PERPENDICULAR TO THE SKID. PIERS ALONG THE OUTSIDE SKIDS OF BUILDINGS WITH 4 SKIDS ARE PERMITTED TO BE ORIENTED WITH THE LONG SIDE PARALLEL TO THE SKID PROVIDED THAT THE PIERS ALONG THE INTERIOR SKID ARE ORIENTED PERPENDICULAR TO THE SKID.
- 2. PIERS SHALL TYPICALLY BE 8"x8"x16" OPEN CELL OR SOLID CONCRETE BLOCKS, DRY STACKED TO A MAXIMUM HEIGHT OF 36". THE BLOCK IN CONTACT WITH THE GROUND AT EACH PIER SHALL BE A 4"x8"x16" SOLID BLOCK. OPEN CELL BLOCKS AND 2" THICK SOLID BLOCKS ARE NOT TO BE USED AS THE BASE OF ANY PIERS. OPEN CELL BLOCKS ARE TO BE PLACED ON TOP OF SOLID BLOCKS AS NEEDED WITH THE OPEN CELLS RUNNING VERTICALLY AND MUST NOT BE PLACED ON THEIR SIDE.

CORNER PIERS OVER 20" TALL SHALL BE DOUBLE STACKED CONCRETE BLOCKS. TIE DOUBLE STACKED BLOCKS BY ALTERNATING THE DIRECTION OF BLOCKS ON EACH ROW.
- 3. OLD HICKORY BUILDINGS IS NOT RESPONSIBLE FOR THE PREPARATION OF THE PROPOSED SITE OR DETERMINATION OF THE SITE'S SUITABILITY TO SUPPORT THE PROPOSED STRUCTURE. IT IS THE PROPERTY OWNER'S RESPONSIBILITY TO DETERMINE IF SITE CONDITIONS ARE SUITABLE TO SUPPORT THE STRUCTURE.
- 4. PIERS SHOWN ON SHEET S-1 ARE CONCEPTUAL AND MAY NOT REFLECT ACTUAL CONDITIONS. THE PIER LAYOUT MAY BE ADJUSTED AS NEEDED BASED ON SITE CONDITIONS, PROVIDED THAT THE MAXIMUM SPACING SHOWN IS NOT EXCEEDED.




METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC



PROJECT NO:	SHEET NUMBER S-0 SCALE: NONE
DATE: 03-31-2022	
DRAWN BY: KLN	
CHECKED BY: KLN	
REVISION:	

PIER SPACING SCHEDULE	
BLDG WIDTH	MAX SPACING
8'-0"	6'-0"
10'-0"	6'-0"
12'-0"	7'-0"



BUILDING TIE-DOWN TO BE INSTALLED BY THE CUSTOMER. REFER TO NOTES ON S-0. THE QUANTITY OF TIE-DOWNS SHOWN ON THIS PLAN ARE CONCEPTUAL AND MAY NOT REFLECT THE ACTUAL REQUIRED QUANTITY. SEE THE SCHEDULE ON SHEET S-2 FOR THE REQUIRED TIE-DOWN QUANTITY AND LOAD RATING BASED ON THE BUILDING LENGTH (TYP)

FLOOR FRAMING PLAN

3-31-22

METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC



PROJECT NO:	
DATE:	03-31-2022
DRAWN BY:	KLN
CHECKED BY:	KLN
REVISION:	



SHEET NUMBER

S-1

SCALE: NOT TO SCALE

UPLIFT ANCHORAGE SCHEDULE						
BLDG LENGTH	8' WIDE BLDGS		10' WIDE BLDGS		12' WIDE BLDGS	
	NUMBER OF TIE-DOWNS	CAPACITY OF EACH ANCHOR	NUMBER OF TIE-DOWNS	CAPACITY OF EACH ANCHOR	NUMBER OF TIE-DOWNS	CAPACITY OF EACH ANCHOR
10'-0"	2	550#	2	550#	-	-
12'-0"	3	450#	3	450#	-	-
14'-0"	3	500#	3	550#	-	-
16'-0"	3	600#	3	600#	3	400#
18'-0"	-	-	4	500#	3	450#
20'-0"	-	-	4	550#	3	500#
22'-0"	-	-	-	-	3	550#
24'-0"	-	-	-	-	3	600#
26'-0"	-	-	-	-	4	500#
28'-0"	-	-	-	-	4	550#
30'-0"	-	-	-	-	4	550#
32'-0"	-	-	-	-	4	600#

- NOTES:
- 1) TIE-DOWNS AND ANCHORS ARE TO BE SUPPLIED AND INSTALLED BY THE CUSTOMER. OLD HICKORY BUILDINGS IS NOT RESPONSIBLE FOR THE TIE-DOWN SYSTEM. REFER TO NOTE SHEET S-0.
 - 2) THE SCHEDULE INDICATES THE RECOMMENDED NUMBER OF BUILDING TIE-DOWNS TO BE INSTALLED BY THE CUSTOMER. EACH TIE-DOWN SYSTEM SHALL HAVE AN ANCHOR AT EACH END. EACH TIE-DOWN COMPONENT IS TO BE RATED FOR AT LEAST THE CAPACITY SHOWN IN THE SCHEDULE.
 - 3) AT A MINIMUM, PROVIDE A TIE-DOWN NEAR EACH END OF THE BUILDING. REMAINING TIE-DOWNS (IF REQUIRED) SHOULD BE EVENLY SPACED ALONG THE ENTIRE LENGTH OF BUILDING.



METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC




PROJECT NO:	
DATE:	03-31-2022
DRAWN BY:	KLN
CHECKED BY:	KLN
REVISION:	


SHEET NUMBER

S-2

SCALE: NONE



8' WIDE




10' WIDE

- METAL PANEL NOTES:**
- 1) RIBS OF METAL PANELS RUN HORIZONTALLY.
 - 2) METAL PANELS ARE TO BE SCREWED TO WOOD FRAMING @ 9" O.C. (UNO).
 - 3) METAL PANELS ARE TO BE SCREWED TO RIM BOARDS @ 12" O.C.

- NOTES:**
1. PROVIDE A DOUBLE TOP PLATE ALONG THE SIDE WALLS WHEN THE RAFTER SPACING DOES NOT MATCH THE WALL STUD SPACING.
 2. ACTUAL SKID SPACING MAY VARY PROVIDED THAT THE CENTER TO CENTER SPACING IS WITHIN THE MAX/MIN SPACING STATED.
 3. 2x6 FRAMING MAY BE SUBSTITUTED FOR THE 2x4 FRAMING SHOWN. THE SPACING OF THE 2x6 FRAMING SHALL BE AS SHOWN FOR THE 2x4.

BUILDING SECTIONS



3-31-22

METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC




PROJECT NO:	
DATE:	03-31-2022
DRAWN BY:	KLN
CHECKED BY:	KLN
REVISION:	

SHEET NUMBER

S-3.0


SCALE: 1/4" = 1'-0"



- METAL PANEL NOTES:
- 1) RIBS OF METAL PANELS RUN HORIZONTALLY.
 - 2) METAL PANELS ARE TO BE SCREWED TO WOOD FRAMING @ 9" O.C. (UNO).
 - 3) METAL PANELS ARE TO BE SCREWED TO RIM BOARDS @ 12" O.C.

- NOTES:
1. PROVIDE A DOUBLE TOP PLATE ALONG THE SIDE WALLS WHEN THE RAFTER SPACING DOES NOT MATCH THE WALL STUD SPACING.
 2. ACTUAL SKID SPACING MAY VARY PROVIDED THAT THE CENTER TO CENTER SPACING IS WITHIN THE MAX/MIN SPACING STATED.
 3. 2x6 FRAMING MAY BE SUBSTITUTED FOR THE 2x4 FRAMING SHOWN. THE SPACING OF THE 2x6 FRAMING SHALL BE AS SHOWN FOR THE 2x4.

BUILDING SECTION



3-31-22

METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC



PROJECT NO:

DATE: 03-31-2022

DRAWN BY: KLN


CHECKED BY: KLN

REVISION:




SHEET NUMBER

S-3.1

SCALE: 1/4" = 1'-0"



<div></div>	<h1>METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC</h1>	<div></div> <div>OLD HICKORY — BUILDINGS —</div>	<div>PROJECT NO:</div> <div>DATE: 03-31-2022</div> <div>DRAWN BY: KLN</div> <div>CHECKED BY: KLN</div> <div>REVISION:</div>	<div>SHEET NUMBER</div> <div>S-4.0</div> <div>SCALE: 1"=1'-0</div>
-------------	---	---	---	---



METAL LOFTED BARN--NORTH CAROLINA--2018 NCBC



PROJECT NO:		SHEET NUMBER
DATE:	03-31-2022	S-4.1
DRAWN BY:	KLN	
CHECKED BY:	KLN	
REVISION:		SCALE: 1"=1'-0