

than lengths indicate.

*No grading septic area.

*No adding soil within septic area

*No rutting-up septic area

*No cuts of >2' within 15' of septic areas

196 Hook Drive Fuquay-Varina NC 27526

GRAPHIC SCALE 1" = 40'80 40

50' PUBLIC R/W & UTILITY

Initial System: Pressure Manifold Lines: 5-7, (325') Accepted Status System (25% reduction) 0.3 Soil LTAR

20" Trench Bottom on the downhill side


Repair System: Pressure Manifold

Lines: 1-4, (237')

T&J Panel Block System (horizontal)

0.3 Soil LTAR

20" Trench Bottom on the downhill side



Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569—6704 Fax (919)569—6703

4-Bedroom Septic Layout 360 gal/day per Engineered Flow-Reduction Lot 9, Cotton Farms Subdivision Harnett County, North Carolina

Job#: 4943 Drawn By: JR Date: 05/09/2024 Revision: 08/19/2024