

**ECS Southeast, LLC**

6151 Raeford Road, Suite A

Fayetteville, NC 28304

T 910.401.3288

F 910.323.0539

FIELD REPORT

Project **125 Boston Harbor Home**
 Location **Cameron, NC**
 Client **Mr. Clyde Knoll**
 Contractor **None Listed**

Project No. **33:7515**
 Report No. **2**
 Day & Date **Wednesday 9/17/2025**
 Weather **75 °/ Sunny**
 On-Site Time **1.00**
 Lab Time **0.00**
 Travel Time* **0.00**
 Total **1.00**
 Re Obs Time **0.00**

Remarks

Trip Charges*	Tolls/Parking*	Mileage*	Time of Arrival	Departure
Chargeable Items			12:00P	1:00P

* Travel time and mileage will be billed in accordance with the contract.

Summary of Services Performed (field test data, locations, elevations & depths are estimates) & Individuals Contacted.
--

The undersigned arrived on site, as requested, to observe conditions of porch pier excavations. A total of 10 excavations (planned depth was 3 feet below adjacent grade) were observed. Using a steel-tipped rod, the bottom of the excavations were probed to determine stability. Several excavations had standing water. Below are our observations of each location, also shown on the attached site plan:

Excavations 1 and 4 - pump out water prior to pouring concrete.

Excavations 2, 6, 7, and 10 - undercut 1 foot below bottom of planned foundation elevation and replace with 57 stone wrapped in non-woven geotextile fabric.

Excavations 3, 5, 8, and 9 - undercut 2 feet below bottom of planned foundation elevation and replace with 57 stone wrapped in non-woven geotextile fabric.

ECS will return for additional services

**ECS Southeast, LLC**

6151 Raeford Road, Suite A

Fayetteville, NC 28304

T 910.401.3288

F 910.323.0539

LETTER OF TRANSMITTAL

September 18, 2025

Mr. Clyde Knoll

Diberville, MS 39540

ATTN: Clyde Knoll

RE: **125 Boston Harbor Home**ECS Job # **33:7515**

Permits:

Location: **125 Boston Harbor
Cameron, NC 28326**☒

Field Reports

☒

For your use

☒

As requested

CC:

ENCL: Field Report # 2 9/17/2025

**SEP 18 2025**Jack Cowsert, P.E.
Office Manager

Robert T. Harrigan
Team Leader*Disclaimer*

1. This report (and any attachments) shall not be reproduced except in full without prior written approval of ECS.
2. The information in this report relates only to the activities performed on the report date.
3. Where appropriate, this report includes statements as to compliance with applicable project drawings, and specifications for the activities, performed on this report date.
4. Incomplete or non-conforming work will be reported for future resolution.
5. The results of samples and/or specimens obtained or prepared for subsequent laboratory testing will be presented in separate reports/documents.

1

3

5

7

9

2

4

6


8

10



Andrew Gomez
9/17/2025
125 Boston Harbor,
Cameron, NC 283261
Proj #: 7515
W/O # 87228

Key (NTS)
Probe Rod
Inpection



Test Location: