

Tobacco Road S/D - Lot #31
480 Gallons/Day - Septic Design
180 Looping Ct
Davidson Homes
Harnett County PIN: 0693-15-2416

*Not a Survey
Sketched from a plot plan supplied by owner

**1000 Gallon Septic Tank
Tank and trenches to be located minimum of 10'
from any property line and minimum of 5'
from any building foundation.
*Do Not Cut, Fill, or Alter Drainfield or Repair Area
*Comply with all setbacks
*Contact local health dept. and/or Alex Adams prior to
or during installation with any questions or concerns.

System: Pressure Manifold
Lines: 1-6 (300')
0.4 LTAR
18" Max Trench Bottom
Accepted Status System Repair:
Pressure Manifold Lines: 7-10
(200')
0.4 LTAR
18 Max Trench Bottom PPBPS -
50% Reduction System

Adams
Soil Consulting
919-414-6761
Job #1215
8-19-24

GRAPHIC SCALE
1" = 50'

