

Kim Sarrag
ms.kimsarrag@gmail.com
26 Boysenberry Ln
Bunnlevel
Lean-To 14x20

Bunnlevel

NOTES:

- 14x20 lean-to over existing concrete pad

- 4x6 post attachment using Simpson Strong-Tie bracket RPS2 ZMAX

- 2x8 ledger attached to roof over load bearing exterior wall

- 2x6 rafters 12oc SPF #2

- footers 12x12, 6'8" apart

OSB 7/16

Posts 4x6 (4)

Beam 2x8 (2)

Rafters 2x6x16 SPF #2 12oc. Table R 802.5 (1)

Footers (4)

14

13'

2x8 roof ledger

House

pitch shall be 3:12 min for shingles

16x16 minimum

16x16 min



20

6'8" 6'8" 6'8"