

- *6x6 Pier supports on 8x24 concrete piers, Simpson bracket.
- *2x10 floor joists 16"OC, double 2x12 rim joist.
- *3/4" OSB subfloor.
- *2x4 Wall framing, R19 insulation, vinyl exterior siding.
- *Double 2x10 headers.
- * 2x10 Rafters at 24"OC with collar ties, rafter ties.
- *R30 fiberglass insulation with baffles, ridge vent and vented soffit.
- *5/12 slope, 1/2" sheathing with shingles.

