

- \*6x6 Pier supports on 8x24 concrete piers, Simpson bracket.
- \*2x10 floor joists 16"OC, double 2x12 rim joist.
- \*3/4" OSB subfloor.
- \*2x4 Wall framing, R19 insulation, vinyl exterior siding.
- \*Double 2x10 headers.
- \* 2x10 Rafters at 24"OC with collar ties, rafter ties.
- \*R30 fiberglass insulation with baffles, ridge vent and vented soffit.
- \*5/12 slope, 1/2" sheathing with shingles.

