

HTE# 07-5-16820R

Harrill County Department of Public Health

23864

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: ROBERT MILLER

PROPERTY LOCATION: RAMBEAUX RD (SR1124)

SUBDIVISION SPRING LAKE CHURCH

LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: 40x100 CHURCH (120 MEMBERS w/ KITCHEN)

Proposed Wastewater System Type: CONVENTIONAL

Projected Daily Flow: 500 GPD

Number of bedrooms: — Number of Occupants: 120 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years

Permit conditions: EXISTING WELL MUST BE PROPERLY ABANDONED

No expiration

Authorized State Agent: _____

Date: 3/20/07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: ROBERT MILLER

PROPERTY LOCATION: RAMBEAUX RD (SR1124)

SUBDIVISION SPRING LAKE CHURCH

LOT # _____

Facility Type: 40x100 CHURCH (120 MEMBERS w/ KITCHEN) New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 500 GPD

(See note below, if applicable)

CONVENTIONAL (Repair)

Installation Requirements/Conditions

Septic Tank Size 1500 gallons

Pump Tank Size — gallons

5 TRENCHES

Exact length of each trench 100 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24 inches

(Trench bottoms shall be level to +/1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 12 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

Conditions: _____

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: _____

Date: 3/20/07

Construction Authorization Expiration Date: 3/20/12

HTE# 07-5-16820R

Permit # 23864

Harnett County Department of Public Health Site Sketch

ISSUED TO: ROBERT MILLER PROPERTY LOCATOR: RAMBEAUX RD (SR124)
 SUBDIVISION SPRING LAKE CH LOT # _____
 Authorized State Agent: [Signature] AS (GUYER TOLSON) Date: 3/20/07

JOINT RD

- TANK LOCATION REQUESTED BY APPLICANT. TANK MAY BE RELOCATED AS LONG AS MINIMUM FALL IS MAINTAINED
- ALL STRUCTURES EXISTING

