

Mailing: P. O. Box 370 Lillington, NC 27546
Physical: 200 North 13th Street, Suite 19
Erwin, NC 28339

910-893-7580

910-893-5025

APPLICATION FOR PLAN REVIEW

APPLICATION NUMBER: 08 - 500 199 27
TODAY'S DATE: 6/20/08 RECEIVED BY: [Signature]
SUBMITTED BY: Mark Wilson
NAME OF PROJECT: Dining Common Extension Project
PHYSICAL ADDRESS: 60 Whitefield Loop, Dunn NC
PHONE NUMBER: 919-820-1212-Cel EXT.:
CONTACT PERSON: Mark Wilson
MAILING ADDRESS: P.O. Box 1166, Dunn, NC 28335
PHONE NUMBER: 910-892-8761
CONTRACTOR'S NAME: Foundations Bible College, Inc.
MAILING ADDRESS: P.O. Box 1166, Dunn, NC 28335
PHONE NUMBER: 910-892-8761

Mark Wilson
Foundations Bible College
Dunn NC 28335-1166
mwilson@foundations.edu

NOTICE

PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS
POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7 - 10
WORKING DAYS.

5C



Harnett
COUNTY



Emergency Services Department

www.harnett.org

200 N. 13th Street
Suite 19
Erwin, NC 28339

Mailing Address:
PO Box 370
Lillington, NC 27546

ph: 910-893-7580
fax: 910-893-5025

Plan Review, Inspection and Permit Fees

Application Number 08 -- 50019927

\$100.00	_____	Explosive Materials (90 Days)
\$ 35.00	_____	Explosive Materials (48 Hrs)
\$ 25.00	_____	Fireworks Public Display
\$ 20.00	<u>1</u> _____	Final Inspection
\$ 25.00	_____	Fire Alarm Testing
\$ 25.00	_____	Fixed Fire Suppression
\$ 10.00	_____	Insecticide Fog/Fumigation
\$ 50.00	_____	Testing of Pipes/UST/AGST
\$ 50.00	<u>1</u> _____	Plans up to 5000 ft ²
\$100.00	_____	Plans 5001 ft ² to 10,000 ft ²
\$150.00	_____	Plans 10,001 ft ² to 25,000 ft ²
\$250.00	_____	Plans 25,001 ft ² and over
\$ 25.00	_____	Sprinkler Certification Test
\$ 25.00	_____	Standpipe Testing
\$ 25.00	_____	Special Assembly
\$ 10.00	_____	Temporary Kiosks/Displays
\$ 10.00	_____	Tents greater than 700 ft ²
\$ 50.00	_____	Tank Installation (charge for each tank)
\$ 50.00	_____	Tank Removal (charge for each tank)

\$ 70.⁰⁰/₁₀₀ Total

Michael B. Smith *DFM*
Code Enforcement Official

9/15/08
Date



Harnett
COUNTY
NORTH CAROLINA



Emergency Services Department

www.harnett.org

200 N. 13th Street
Suite 19
Erwin, NC 28339

Mailing Address:
PO Box 370
Lillington, NC 27546

ph: 910-893-7580
fax: 910-893-5025

September 15, 2008

Mark Wilson
Post Office Box 1166
Dunn, NC 28335

Foundations Bible College Dining Room Expansion
60 Whitefield Loop
Dunn, NC 28334

Application Number 08-50019927

Mr. Wilson,

Thank you for submitting the plans for the dining room extension project. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**

- Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
- The fire extinguishers provided shall have a minimum rating of 2A 10B: C and shall not be installed higher than 5 feet above the finished floor.

- **Fire Department Access**


- The fire department access shall extend to within 150 feet of all portions of the facility.
- The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less than 13 feet 6 inches.

- **506.1 Knox Box**
 - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency.
 - Knox Box ID stickers shall be placed on all exterior doors in which entry to the building may be gained.
 - The box shall be mounted not to exceed 48 – 60 inches in height.
 - An authorized order form is included with this letter (Choose any of the 3200 Series listed on the back of the order form).
- **505.1 Physical Address**
 - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
 - The numbers used to make up the physical address shall be at least 5 inches in height.
- **Duct Detectors**
 - As indicated on the plans, AHU-1 has an output of 2400 cfm's. this requires duct detector placement on the return side of the unit.
 - Each Detector shall have an audio/visual device acknowledging activation.
- **1004.1.2 Occupancy Load**
 - The occupancy load for the building must be posted at the time of the final inspection. The Fire Marshal's Office will provide the posting documents.

Thank you again for submitting the plans for the dining room extension project. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office

Again, thank you and we look forward to working with you during the construction period!

Sincerely,



Michael L. Martin
Deputy Fire Marshal