

HTE# 135-31792

Harnett County Department of Public Health Improvement Permit

27561

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Benson Pentecostal Holiness Church PROPERTY LOCATION: Hwy 27
 SUBDIVISION _____ LOT # _____
 NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:
 Type of Structure: Ex BUILD to CHURCH
 Proposed Wastewater System Type: 25% REDUCTION - Pressure Manifold
 Projected Daily Flow: 1150 GPD
 Number of bedrooms: _____ Number of Occupants: 230 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: Follow Consultants Design & Layout No expiration

Authorized State Agent: James E. Markham Date: 8-7-13 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Benson Pentecostal Holiness Church PROPERTY LOCATION: Hwy 27
 SUBDIVISION _____ LOT # _____
 Facility Type: Ex BUILD to CHURCH New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pressure Manifold to 25% RED (Initial) Wastewater Flow: 1150 GPD
 (See note below, if applicable Pressure Manifold to 25% (Repair) RED)

Installation Requirements/Conditions
 Septic Tank Size 2000 gallons
 Pump Tank Size 2000 gallons
 Number of trenches _____
 Exact length of each trench 900 TOTAL feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18" inches
 (Trench bottoms shall be level to +/- 1/4"
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Trench Spacing: 9 Feet on Center
 Soil Cover: 6 inches
 (Maximum soil cover shall not exceed
 36" above the trench bottom)
 Conditions: Follow Consultants DESIGN
and Layout - Meet on site prior to install
 Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markham Date: 8-7-13
 Construction Authorization Expiration Date: 8-7-18

HTE# 13-5-31792

Permit # 27561

Harnett County Department of Public Health
Site Sketch

ISSUED TO: Benson Holness Pentecostal Church PROPERTY LOCATOR: Aug 27
DIVISION _____ LOT # _____

Authorized State Agent James E. Manhart Date: 8-7-13

- * Follow Consultants Design + Layout.
- * Meet ON SITE prior to INSTALL.