



Plan Review, Inspection, and Permit Fees

Application Number : 15-50036489

\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		Total Cost	\$	100.00

Code Enforcement Official

D. Banks Wallace

8/1/2018



Application for Plan Review

HARNETT COUNTY EMERGENCY SERVICES
REVIEWED FOR CODE COMPLIANCE

Application # 15-50036489

D.B. WALLACE
CODE COMPLIANCE OFFICER
DATE 8-1-18

Date Received: 7/20/18 Received By: [Signature]

Name of Project: spout springs church

Physical Address of Project: 150 Martz Rd. Cameron
NC N.C.

Plans Submitted By: Ronnie Fish

Project Phone: (910) 890-4056

Contact Person/Address: STE. Bernesh contractor
P.O. 2364 N.C.

Contact Email: _____

Contact Phone: (____) - ____ - ____ (____) - ____ - ____

Contractor's Name/Info: _____

Contractor's Phone: (910) 890-4056

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://htweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.

HARNETT COUNTY EMERGENCY SERVICES
REVIEWED FOR CODE COMPLIANCE

DATE 3/1/12
CODE COMPLIANCE OFFICER [Signature]

10-112



Fire Marshal Division

August 1, 2018

Ronnie Fish
STE General Contractor
P.O. Box 2364

RE: Spout Springs Church
150 Marks Rd
Cameron, NC

Application Number – 15-50043489

Mr. Fish,

Thank you for submitting plans for the Church Addition. The plans have been reviewed by a qualified code enforcement official for compliance with the North Carolina Fire Prevention code and all other fire protection regulations. The following are items that will need to be addressed before a final inspection of this project can be completed. The items are listed and described below.

- **906.1 Fire Extinguishers**
 - Fire extinguishers shall be placed in approved locations and may be field verified on final inspection. The fire extinguishers provided shall have a minimum rating of 2A 10 B: C.
 - Fire extinguisher shall be installed not to exceed 75' distance of travel.

- **1006.1 / 1006.2 Emergency Illumination**
 - Emergency illumination is required to meet minimum foot candle illumination.

- **1011 Exit Signs**
 - Exit signs shall be installed at all required exits. Exit signs shall meet all provisions of chapter 10.

- **1004.3 Posting of occupant load.**
 - Every room or space that is an assembly occupancy shall have the *occupant load* of the room or space posted in a conspicuous place, near the *main exit* or *exit access doorway* from the room or space. Posted signs



shall be of an *approved* legible permanent design and shall be maintained by the owner or authorized agent.

- An occupant load certificate will be provided by the Fire Marshal's Office.
- **1008.1.10 Panic and fire exit hardware.**
 - Doors serving a Group H occupancy and doors serving rooms or spaces with an *occupant load* of 50 or more in a Group A or E occupancy shall not be provided with a latch or lock unless it is panic hardware or *fire exit hardware*.
- **Notes**
 - Please contact the Fire marshal's office to schedule fire final inspection when work is complete, 910-984-4003

Please review the plans and adhere to any notes and alterations that were made in addition to the original designed plans. These remarks are for the plans that were submitted and its original intent. If you have any questions please do not hesitate to contact me. We look forward to working with you during the construction period.

Sincerely,

D. Banks Wallace
Chief Deputy Fire Marshal