



## Plan Review, Inspection, and Permit Fees

Application Number : 18-50043695

<b>\$200.00</b>	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
<b>\$100.00</b>	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
<b>\$100.00</b>	<input type="checkbox"/>	Fireworks Public Display	\$	-
<b>\$50.00</b>	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
<b>\$35.00</b> + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
<b>\$35.00</b> + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
<b>\$75.00</b>	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
<b>\$100.00</b>	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
<b>\$50.00</b>	<input type="checkbox"/>	Plans up to 5000 sq ft	\$	-
<b>\$100.00</b>	<input checked="" type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	100.00
<b>\$150.00</b>	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
<b>\$250.00</b>	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
<b>\$35.00</b> + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
<b>\$50.00</b>	<input type="checkbox"/>	Standpipe Testing	\$	-
<b>\$50.00</b>	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
<b>\$75.00</b>	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
<b>\$100.00</b>	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
<b>\$100.00</b>	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		<b>Total Cost</b>	<b>\$</b>	<b>150.00</b>

Code Enforcement Official

Banks Wallace

5/2/2018



**Fire Marshal Division**

May 1, 2018

Mr. Pedro Nuñez  
2291 NC Hwy 55 E  
Dunn, NC 28334

**Re: Gospel Tabernacle Hispanic Church**  
**2291 Hwy 55 E**  
**Dunn, NC 28334**

**Application Number 18-50043695**

Mr. Nuñez,

Thank you for submitting the plans for the Gospel Tabernacle. The plans have been carefully reviewed by a qualified code enforcement official to examine for compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
  - Minimum of (1) 2A10:BC fire extinguisher shall be installed per 75' distance of travel.
  - All Fire extinguishers shall be properly mounted and tagged by a fire extinguisher company.
  
- **1008.1.10 Panic Hardware**
  - UL 305 listed panic hardware is required on exit doors serving a room/space with an occupant load >50, also indicated on Building code summary. Panic hardware is not included on door schedule sheet B8 of Drawings.
  
- **1004.3 Occupant Load Posting**
  - The occupant load posting shall be provided by the Fire Marshal's Office at fire final inspection.
  
- **1006.1 Means of Egress Illumination**



- The means of egress, including the exit discharge, shall be illuminated at all time the building space is served by the means of egress is occupied.
  - Means of egress consist of three separate and distinct parts: the exit access, the exit and the exit discharge.
- The means of egress illumination shall not be less than 1 foot-candle at the walking surface.
  
- **703.5 Rated Wall Identification**
  - Rated walls shall be permanently identified with signs or stenciling.
  - **Example: "1 Hour Fire Barrier Protect All Openings"**
  
- **Notes**
  - A final fire inspection is required.
  - Place key to building in existing Knox Box to allow access any locked doors
  - Schedule all fire inspections through the Fire Marshal's Office.  
(919)893-0743

Thank you again for submitting the plans for the Gospel Tabernacle. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Sincerely,



D. Banks Wallace  
Chief Deputy Fire Marshal



*File*

### Application for Plan Review

Application # 18-50043695

Date Received: 4.20.18 Received By: duownsm

Name of Project: Gospel Tabernacle Hispanic

Physical Address of Project: 2291 Hwy 55 E Church  
Dunn, NC

Plans Submitted By: Pedro Nuñez

Project Phone: (910)-658-3317

Contact Person/Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Contact Email: \_\_\_\_\_

Contact Phone: (\_\_\_\_) - \_\_\_\_ - \_\_\_\_ (\_\_\_\_) - \_\_\_\_ - \_\_\_\_

Contractor's Name/Info: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Contractor's Phone: (\_\_\_\_) - \_\_\_\_ - \_\_\_\_

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://htweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.