



## Fire Marshal Division

October 25, 2019

Nathan Benson  
490 Chesterfield Lake Rd.  
Lillington, NC 27546

**Re: Sorrell's Cabinet Shop**  
490 Chesterfield Lake Rd.  
Lillington, NC 27546

### **Application Number CAAC18-50043781**

To Whom It May Concern,

Thank you for submitting the plans for the renovation. The plans have been carefully reviewed by a qualified code enforcement official to examine for compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
  - Minimum of (1) 2A10:BC fire extinguisher shall be installed not to exceed 75' distance of travel.
  - All Fire extinguishers shall be properly mounted and tagged by a fire extinguisher company.
  
- **1006.1 Means of Egress Illumination**
  - The means of egress, including the exit discharge, shall be illuminated at all time the building space is served by the means of egress is occupied.
    - Means of egress consist of three separate and distinct parts: the exit access, the exit and the exit discharge.
  - The means of egress illumination shall not be less than 1 foot-candle at the walking surface.



- **901.2.1 State of Compliance.**
  - Before requesting final approval of the installation, where required by the fire code official, the installing contractor shall furnish a written statement to the fire code official that the subject fire protection system has been installed in accordance with the manufacture's specifications and the appropriate installation standard. Any deviations from the design standards shall be noted and copies of the approvals for such deviations shall be attached to the written statement.
  
- **703.5 Identification**
  - Walls and partitions required to have protected openings shall be permanently identified with signs or stencils. **(Example "2- hour Fire Barrier Protect All Openings")**
  
- **Notes**
  - A final fire inspection is required.
  - Schedule all fire inspections through the Fire Marshal's Office. (910) 893-0742

Thank you again for submitting the plans for the renovation. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Sincerely,



D. Banks Wallace  
Chief Deputy Fire Marshal