



## Application for Plan Review

Application # 18 - 50043826  
Date Received: 4/17/18 Received By: Beth  
Name of Project: Buffalo Lake Medical

Physical Address of Project: \_\_\_\_\_  
\_\_\_\_\_, NC \_\_\_\_\_

Plans Submitted By: Troy White

Project Phone: (919) 824-3325

Contact Person/Address: 2110 Cow Road St.  
DURHAM NC 27707

Contact Email: DRFT Contractors@gmail.com

Contact Phone: 919 824-3325 (\_\_\_\_) - \_\_\_\_ - \_\_\_\_

Contractor's Name/Info: Dents Right The First Time Contractors  
2110 Cow Road St. Durham NC 27707

Contractor's Phone: (919) 824-3325

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://hteweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.



## Fire Marshal Division

April 20, 2018

Troy White  
2110 Concord Street  
Durham, N.C. 27707

**Re: Buffalo Lake Medical**  
**85 Mattie Haddock Drive**  
**Cameron, NC 228326**

**Application Number 18-50043826**

Mr. White,

Thank you for submitting the plans for the Buffalo Lake Medical Upfit. The plans have been carefully reviewed by a qualified code enforcement official to examine for compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
  - Minimum of (1) 2A10:BC fire extinguisher shall be installed not to exceed 75' distance of travel.
  - All Fire extinguishers shall be properly mounted and tagged by a fire extinguisher company.
  
- **1006.1 Means of Egress Illumination**
  - The means of egress, including the exit discharge, shall be illuminated at all time the building space is served by the means of egress is occupied.
    - Means of egress consist of three separate and distinct parts: the exit access, the exit and the exit discharge.
  - The means of egress illumination shall not be less than 1 foot-candle at the walking surface.
  
- **105.7.1 Automatic fire-extinguishing systems.**



- A construction permit is required for the fire sprinkler system installation before any such work commences. Submit complete construction documents that include the hydraulic calculations for the system. The system shall also be designed consistent with the architectural design documents and specifications. Construction documents shall include detail as described in NFPA 13 standard for automatic sprinkler system installation. Contractor must obtain construction permit for the fire sprinkler system before commencement of any work.
  - A rough in inspection is required.
  - A final acceptance test is required.
- **901.2.1 State of Compliance.**
  - Before requesting final approval of the installation, where required by the fire code official, the installing contractor shall furnish a written statement to the fire code official that the subject fire protection system has been installed in accordance with the manufacturer's specifications and the appropriate installation standard. Any deviations from the design standards shall be noted and copies of the approvals for such deviations shall be attached to the written statement.
- **Notes**
  - A final fire inspection is required.
  - Schedule all fire inspections through the Fire Marshal's Office. (919)893-0743

Thank you again for submitting the plans for the upfit. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Sincerely,

Roger Sullivan  
Deputy Fire Marshal



## Plan Review, Inspection, and Permit Fees

Application Number : 18-50043826

\$100.00	<input type="checkbox"/>	DRB Major Sub Division Prelim Site Plans	\$	-
\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)		
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		<b>Total Cost</b>	<b>\$</b>	<b>100.00</b>

Code Enforcement Official

Roger Sullivan

4/20/2018

