

HTE D450010894R

16757

OPERATIONS PERMIT

Name: (owner) Walter & Valerie Moody New Installation Septic Tank
 Property Location: SR# NC 87 Repairs Nitrification Line
 Subdivision STARWOOD Lot # 32
 Tax ID # _____ Quadrant # _____
 Contractor: Terry Maples Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Pump to 25% Reduction system
 Size of tank: Septic Tank: existing gallons Pump Tank: 1000 gallons Infiltrator Quadrant 4 Chamber

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 70 ft. width of ditches 3 ft. depth of ditches 18.30 in.
 Chamber

French Drain Required: _____ Linear feet

Date: 01-19-05

Inspected by: [Signature]
Environmental Health Specialist

PERMIT NO. 21491

Hawker work place

