

HARNETT COUNTY DEPARTMENT OF PUBLIC HEALTH

Well Abandonment Permit

Permit Number: 26416 Application Number: 11-5-26019 Applicant Name: Michael & Celia Jones
Address: 1607 Cone Ave ,Apex N.C. 27502
Type of Well: Bored Total Dept: 35 Diameter: 24" Grouted: yes Static Water Level: 17
Directions to Site: SR 1403 Kipling RD

Agent of the State James E. Manhart Date: 2-24-11

Abandonment Procedure: Abandonment Procedure: 1. Remove all plumbing or piping into the well, along with any obstructions inside the well; 2. Remove as much of the well tile casing a possible, but no less than to a depth of three feet below land surface; 3. remove all soil or other subsurface material present down to the top of the remaining well casing, and extending to a width of at least 12 inches outside of the well casing on all sides; 4. Using 5 oz. of hypochlorite solution (such as HTH), disinfect the well in accordance with 15A NCAC 2C .0111 of this Subchapter. Do not use a common commercial household liquid bleach, as this is too weak a solution to ensure proper disinfection; 5. Fill the well up to the top of the remaining casing with cement grout, concrete grout, bentonite grout, dry clay, or material excavated during drilling of the well and then compacted in place; 6. Pour a one foot thick concrete grout or cement grout plug that fills the entire excavated area about the top of the casing, including the area extending on all sides of the casing out to a width of at least 12 inches on all sides; 7. Complete the abandonment process by filling the remainder of the well above the concrete or cement plug with additional concrete grout, cement grout, or soil.

Note: Contact Harnett County Environmental Health for appointment prior to beginning of well abandonment procedure.

Well must be abandoned by a Certified North Carolina well driller/contractor.

SEE ATTACHED SITE PLAN

Michael Jones
Property Owner's or Owners Legal Representative Signature Required

2/28/11
Date

NOTE:
 1. NO N.C. GRID MONUMENT FOUND WITHIN 2000'.

REFERENCES:
 1. PIN 0653-10-6149.000
 2. D.B. 2159 PG.892

N/F RYALS CATLAS SR.
 D.B. 908 PG. 830

N/F SUSAN VUNCANNON
 D.B. 2244 PG. 332

PICKET FENCE
 (OWNERSHIP UNKNOWN)

*1.28 0974
 3.88
 4.60
 2.21*

*2' 35" deep
 17' to water
 2' 17" deep
 17' to water*

COMPUTED POINT 2.3'
 FROM BENT EIP

25,103 SQ. FT.
 0.576 ACRES
 342 KIPLING ROAD

N/F JERRY VUNCANNON
 PIN 0653-10-7167

16.8' side yard set back

N 77°06'00" W
 200.09' (TIE)

KIPLING ROAD (S.R. 1403)
 60' R/W - PUBLIC

NAIL @ C.L. INTERSECTION
 KIPLING RD. & HWY. 401

BOUNDARY SURVEY FOR
CELIA P. JONES
 HARNETT COUNTY, NORTH CAROLINA

BAR SCALE: 1" = 40'

