

HTE# 14-5-34327

Harris County Department of Public Health

28063

See 06-5-15352
for home system layout
Penny Dupree**Improvement Permit**

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Christopher Hall

PROPERTY LOCATION: 8152 Winbury Rd
SUBDIVISION _____ LOT # _____NEW ☒ REPAIR ☐ EXPANSION ☐

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: Det Garage + 2 BR + Pool

Proposed Wastewater System Type: 25% RSTC system

Projected Daily Flow: 240 GPD

Number of bedrooms: 2 Number of Occupants: 4 max

Basement ☐ Yes ☒ NoPump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well _____ feetPermit valid for: ☒ Five years
☐ No expiration

Permit conditions: _____

Authorized State Agent: James E. Montanone

Date: 8-20-14

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Christopher Hall

PROPERTY LOCATION: 81502 Winbury Rd

SUBDIVISION _____ LOT # _____

Facility Type: Det Garage + 2 BR ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No

Type of Wastewater System** 25% RSTC system

(Initial) Wastewater Flow: 240 GPD

(See note below, if applicable ☐)

Pump to 25% RSTC system (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 2

Exact length of each trench 100 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24 max inches

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Trench Spacing: 8 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.**NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.******If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.**

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Montanone

Date: 8-20-14

Construction Authorization Expiration Date: 8-20-14

HTE# 14-5-34327

Permit # 28063

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATION: SR1502 Wimberty RD

ISSUED TO: Christopher Hall



SUBDIVISION

LOT #

Authorized State Agent:

James S. Montfort

Date: 8-20-14



SR1502 Wimberty RD