

08-5-19174R

HTE# ~~07510945~~

Harnett County Department of Public Health 24555

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Sam & Sandra Warnon PROPERTY LOCATION: SR 1115 Buffalo Lake
 NEW REPAIR EXPANSION SUBDIVISION Buffalo Lake LOT # 244
 Type of Structure: SFD 56X67 Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: pump to chamber system
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: [Signature] Date: 2/5/2008 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Sam & Sandra Warnon PROPERTY LOCATION: SR 1115
 Facility Type: SFD 56X67 New Expansion Repair SUBDIVISION Buffalo Lake LOT # 244
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** pump to chamber (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable)
Not needed due to age of property (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4x50 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6" min inches
 Maximum Trench Depth of: 36-12 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/-1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: _____ inches above pipe

Conditions: Drain lines to start at 36" run to 12" & step down to 20"
Contractor to meet on site prior to installing system & system area should not be disturbed

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: [Signature] Date: 2/5/2008 SEE ATTACHED SITE SKETCH
 Construction Authorization Expiration Date: 2/5/2013

HTE# 08-5-19174R

Permit # 24555

Harnett County Department of Public Health Site Sketch

ISSUED TO: Sant Sandra Wornom PROPERTY LOCATOR: SR 1115
SUBDIVISION Buffalo Lake LOT # 244

Authorized State Agent: Devin M. Smith, S. Date: 2/5/2008

* Tanks & Lines must be
15 Ft. from Foundation

* Each drain line to be
connected to each other
at start of line

