

HTE# 17-5-42614

Harnett County Department of Public Health

29772

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 2563 Oak Grove Ch. Rd. (NC 1532)

ISSUED TO: Tony Wimberly SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: 30'x30' Pool House

Proposed Wastewater System Type: Conv. Gravel Sys.

Projected Daily Flow: 100 GPD

Number of bedrooms: NA Number of Occupants: NA max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 50 feet (MIN) Permit valid for: Five years

Permit conditions: _____ No expiration

Authorized State Agent: [Signature] Date: 12/06/2017 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Tony Wimberly PROPERTY LOCATION: 2563 Oak Grove Ch. Rd. (NC 1532)

SUBDIVISION _____ LOT # _____

Facility Type: 30'x30' Pool House New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Conv. Gravel Sys. (Initial) Wastewater Flow: 100 GPD

(See note below, if applicable)

Conv. Gravel Sys. (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 2

Exact length of each trench 50 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18 inches

(Trench bottoms shall be level to +/-1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

Conditions: _____ 12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 12/06/2017

ANDREW CURRY

Construction Authorization Expiration Date: 12/06/2022

HTE# 17-5-42014

Permit # 29772

Harnett County Department of Public Health Site Sketch

ISSUED TO: Tony Wimberly PROPERTY LOCATOR: 2563 Oak Grove Ch. Rd. (Sec 1532)
SUBDIVISION _____ LOT # _____

Authorized State Agent: *Andrew Curran* Date: 12/06/2017
ANDREW CURRAN

- * Septic system shall be 50ft min from ext. irrigation well
- * Conv. gravel may be substituted for 25% reduction with 2 40ft lines
- * 25% reduction sys. must be installed by septic installer
- * Conv. gravel may be installed by homeowners with notarized waivers
- * 100 GPD min Pool House

